



EUROPEAN COMMISSION

Integrated Pollution Prevention and Control

Reference Document on

Best Available Techniques in the Slaughterhouses and Animal

By-products Industries

May 2005

This document is one of a series of foreseen documents as below (at the time of writing, not all documents have been drafted):

Full title	BREF code
Reference Document on Best Available Techniques for Intensive Rearing of Poultry and Pigs	ILF
Reference Document on the General Principles of Monitoring	MON
Reference Document on Best Available Techniques for the Tanning of Hides and Skins	TAN
Reference Document on Best Available Techniques in the Glass Manufacturing Industry	GLS
Reference Document on Best Available Techniques in the Pulp and Paper Industry	PP
Reference Document on Best Available Techniques on the Production of Iron and Steel	I&S
Reference Document on Best Available Techniques in the Cement and Lime Manufacturing Industries	CL
Reference Document on the Application of Best Available Techniques to Industrial Cooling Systems	CV
Reference Document on Best Available Techniques in the Chlor – Alkali Manufacturing Industry	CAK
Reference Document on Best Available Techniques in the Ferrous Metals Processing Industry	FMP
Reference Document on Best Available Techniques in the Non Ferrous Metals Industries	NFM
Reference Document on Best Available Techniques for the Textiles Industry	TXT
Reference Document on Best Available Techniques for Mineral Oil and Gas Refineries	REF
Reference Document on Best Available Techniques in the Large Volume Organic Chemical Industry	LVOC
Reference Document on Best Available Techniques in the Waste Water and Waste Gas Treatment/Management Systems in the Chemical Sector	CWW
Reference Document on Best Available Techniques in the Food, Drink and Milk Industry	FM
Reference Document on Best Available Techniques in the Smitheries and Foundries Industry	SF
Reference Document on Best Available Techniques on Emissions from Storage	ESB
Reference Document on Economics and Cross-Media Effects	ECM
Reference Document on Best Available Techniques for Large Combustion Plants	LCP
Reference Document on Best Available Techniques in the Slaughterhouses and Animals By-products Industries	SA
Reference Document on Best Available Techniques for Management of Tailings and Waste-Rock in Mining Activities	MTWR
Reference Document on Best Available Techniques for the Surface Treatment of Metals	STM
Reference Document on Best Available Techniques for the Waste Treatments Industries	WT
Reference Document on Best Available Techniques for the Manufacture of Large Volume Inorganic Chemicals (Ammonia, Acids and Fertilisers)	LVIC-AAF
Reference Document on Best Available Techniques for Waste Incineration	WI
Reference Document on Best Available Techniques for Manufacture of Polymers	POL
Reference Document on Energy Efficiency Techniques	ENE
Reference Document on Best Available Techniques for the Manufacture of Organic Fine Chemicals	OFC
Reference Document on Best Available Techniques for the Manufacture of Specialty Inorganic Chemicals	SIC
Reference Document on Best Available Techniques for Surface Treatment Using Solvents	STS
Reference Document on Best Available Techniques for the Manufacture of Large Volume Inorganic Chemicals (Solids and Others)	LVIC-S
Reference Document on Best Available Techniques in Ceramic Manufacturing Industry	CER

EXECUTIVE SUMMARY

Introduction

The BAT (Best Available Techniques) Reference Document (BREF) entitled ‘Best Available Techniques in the Slaughterhouses and Animal By-products Industries’ reflects an information exchange carried out under Article 16(2) of Council Directive 96/61/EC (IPPC Directive). This executive summary describes the main findings, a summary of the principal BAT conclusions and the associated consumption and emission levels. It should be read in conjunction with the preface, which explains this document’s objectives; how it is intended to be used and legal terms. It can be read and understood as a standalone document but, as a summary, it does not present all the complexities of this full document. It is therefore not intended as a substitute for this full document as a tool in BAT decision making.

Scope

This BREF covers the industrial activities specified in Annex I, paragraphs 6.4.(a) and 6.5. of the Directive, i.e.

6.4.(a) Slaughterhouses with a carcase production capacity greater than 50 tonnes per day

and

6.5. Installations for the disposal or recycling of animal carcasses and animal waste with a treatment capacity exceeding 10 tonnes per day

Some processes are in this document because they are associated activities of 6.4.(a) even though on first examination they would more obviously be 6.5. activities, but they fall below that threshold.

For large animals, such as cattle, sheep and pigs, the “slaughter” activity is considered to end with the making of standard cuts and for poultry, with the production of a clean whole saleable carcase. In recent years there has been a change in the terminology used to describe outputs from slaughterhouses. The term “by-product” is being used increasingly and it is widely used in this document. The word “waste” is only used when referring to disposal activities.

Animal by-products activities covered include the treatments for entire bodies or parts of animals and those for products of animal origin. These activities include the treatments of animal by-products both intended for and not intended for human consumption. A wide range of by-products activities are covered. These include fat melting; rendering; fish-meal and fish-oil production; bone processing; blood processing associated with slaughterhouses and to the degree where the blood becomes a material for use in the preparation of another product. The incineration of carcasses, parts thereof and animal meal and the burning of tallow, are covered principally as routes for disposal. Land spreading; land injection; biogas production; composting; the preservation of hides and skins for tannery use, in slaughterhouses and gelatine manufacture are also covered. Landfill is not covered, except when mentioned as a route for disposal.

General information (Chapter 1)

Slaughterhouses

The slaughtering industry throughout the EU is diverse with many different national characteristics. Some of these are due to different local end products, e.g. typical Italian cured products. Others depend on what market the products are destined for, e.g. longer shelf-lives may be required for meat destined for export than that to be sent to the local market. These characteristics reportedly affect some of the choices made about what techniques are used in some slaughterhouses.

Trends in the industries can influence environmental issues by, e.g. changing the amounts of water consumed or the amount of waste produced. There appears to be a trend towards fewer slaughterhouses with increasing average throughputs. It is reported that this trend towards larger units has not resulted in lower consumption levels, but that it is easier and cheaper to solve environmental problems at large plants. The increasing concern about food safety can result in more waste being produced as parts of animals are discarded, such as following the BSE crisis and in increased cleaning and sterilisation, which incur associated consumption of water, energy and chemicals. There are other trends based on environmental driving forces, such as odour prevention. The cooling of blood and other by-products, not only those parts destined for use, but also those destined for disposal is becoming more common. Refrigeration requires a considerable amount of energy, but does provide other advantages, such as better products and less air and water pollution.

Animal by-products installations

In the past, animal by-products provided a valuable source of slaughterhouse income, however, due to BSE, in recent years their value reduced substantially and much of the material which was previously used, is now disposed of as waste at a cost to the slaughterhouse operator.

The animal by-products industry handles all of the raw materials that are not directly destined for human consumption. The use and disposal routes permitted are governed by the *Regulation (EC) No 1774/2002 of the European Parliament and of the Council of 3 October 2002 laying down health rules concerning animal by-products not intended for human consumption*.

The continuing ban on the use of processed animal proteins in feed for animals farmed for food has led to the diversification of the animal by-products industry into incineration and to research into alternative ways of disposing of by-products and in particular TSE materials and SRM. The rendering industry still processes most of the animal by-products not intended for human consumption although some are stored frozen, for future incineration.

Key environmental issues in slaughterhouses


The most significant environmental issues associated with slaughterhouse operations are typically water consumption, emissions of high organic strength liquids to water and the energy consumption associated with refrigeration and heating water. Blood has the highest COD strength of any liquid effluent arising from both large animal and poultry slaughterhouses and its collection, storage and handling is a key issue for assessment and control. At most slaughterhouses, the refrigeration plant is the biggest consumer of electricity. It can constitute 45 - 90 % of the total site load during the working day and almost 100 % during non-production periods. Food and veterinary legislation requires potable water to be used in slaughterhouses, so there are virtually no opportunities for re-use of water. This has water consumption and contamination consequences and also energy consequences when the water is heated. The emission of odours from e.g. blood storage and handling and WWTPs, can be the most problematic day to day environmental issue. Noise from e.g. animal noises during unloading and marshalling and from compressors can also lead to local problems.

Key environmental issues in animal by-products installations

All animal by-products installations can potentially emit high organic strength liquids to water and cause significant local odour problems. If animal by-products are not treated quickly after slaughter and before decomposition causes odour and/or quality problems and downstream waste water problems, they may be refrigerated to minimise decomposition. This consumes energy. Odour is a key environmental issue during rendering and fish-meal and fish-oil production, even if fresh by-products are treated. Energy consumption is also a key issue for those installations undertaking drying activities, i.e. fat melting, rendering, fish-meal and fish-oil production, blood processing, gelatine manufacture and glue manufacture. Emissions of the gaseous products of combustion to air, is an issue for incinerators. Infectivity associated with the destruction of TSE risk material is an issue for rendering plants and for incinerators. Infectivity associated with the destruction of pathogens has to be considered for composting and where the by-product or waste produced by a treatment can be landfilled, land spread or land injected. Infestation by insects, rodents and birds can be an issue during animal by-products storage and use. Water consumption is significant for gelatine manufacture.

Applied processes and techniques (Chapter 2)

The relationships between slaughterhouses and their downstream activities are illustrated in a very simplified and general form in the figure below.



Relationships between slaughterhouses and their downstream activities (summary)

Individual unit operations in slaughterhouses are described first. This section is divided between the slaughter of large animals and the slaughter of poultry. The processes at individual types of animal by-products installations are then described. Some waste water treatment processes that are applied in the industries are then described, firstly for slaughterhouses and then for animal by-products installations.

Current consumption and emission levels (Chapter 3)

The average live weights of animals and carcase weights vary considerably between Member States. Consumption and emission data has, to a large extent, been reported either “per tonne of carcase produced” or “per tonne of by-product treated”. This reflects the terminology of the Directive and makes it easier to compare information from different sources. It also enables the relationships between the actual processes and consumption and emission levels to be examined, at the same time as avoiding misleading information based on, e.g. low concentrations, which may be achieved by the overconsumption of water.

Detailing the consumption and emission levels serves several purposes. Firstly, the ranges of levels for given processes and unit operations illustrate potential opportunities for improvement in environmental performance by those operating at the higher levels in the range. Secondly, the availability of data from unit operations also demonstrates that it is practicable to measure consumption and emission levels at that level and thus to monitor improvements. Thirdly, the information can also be used to identify priority unit operations which can be improved. Also, the availability of data at unit operation level makes it possible to compare techniques and determine BAT for those parts of processes where consumption and emission levels are significant and alternatives are available.

The data reported in the BREF illustrate a wide range of performances in the industries. For example, for pig slaughterhouses a total water consumption range of 1600 – 8300 litres per tonne of carcase produced is reported in Table 3.2. Water consumption levels, either in ranges or single values, were also provided for the following unit operations: loading and vehicle washing; lairage; slaughter; bleeding; scalding; hair and toenail removal; singeing; rind treatment; chilling; intestine washing and cleaning. Intestine washing was reported to use between 442 – 680 litres per tonne of carcase produced and to emit a BOD range of 0.98 - 3.25 kg per tonne of carcase and was therefore identified as a unit operation making a significant contribution to the pollution caused by the whole activity. Any contact between water and carcasses or animal by-products leads to water contamination, which is one of the key environmental issues for slaughterhouses. The issue of reducing water consumption and water contamination, during intestine washing is addressed later in this document. Techniques are described and BAT is identified in Section 5.2.1.

Some of the data provided for slaughterhouses show the breakdown of how water and energy are consumed for different operations in an installation, as percentage values. This method of presenting data can be useful for identifying overall priorities, but it is less useful for monitoring improvements in a single operation because others may also change. For example, if less water is used for scalding then the percentage used in cleaning may rise even if the actual consumption does not. Nevertheless, this information has been useful, for confirming that cleaning as a major consumer of water and that refrigeration as a major consumer of energy, in slaughterhouses. The issue of minimising the consumption of water, and therefore the associated reduced contamination of waste water and the energy consumed to heat the water, has been addressed in this document. Unfortunately very little information has been received about reducing the energy consumed by chilling and refrigeration.

Drying operations at animal by-products installations generally use most of the energy consumed. Information about consumption levels supports this. This issue has been addressed to some extent in the BREF and BAT has been identified for rendering.

Most of the information provided about odour is qualitative and the measurements received have been presented using several units, which has made quantitative comparison between the problems and potential solutions impossible. Nevertheless, odour associated with the storage and processing of animal by-products is addressed from both the preventive and abatement perspectives and BAT have been identified.

Most of the consumption and emission data provided for slaughterhouses and animal by-products installations relates to waste water, although unfortunately most of the data submissions were not accompanied by descriptions of the processes and throughput data or the waste water treatments applied. Nevertheless, sufficient information was received for the technical working group (TWG) to conclude that BAT is to subject the effluent from slaughterhouses and animal by-products installations to a biological treatment process. BAT associated levels based on the expert judgment of the TWG are given in chapter 5 and are shown in the table below.

For incineration, data on air emissions and ash analysis is reported both in this chapter and in the chapter 4. The TWG has agreed to BAT associated levels and these are reported in chapter 5 and are shown in the table below.

For some animal by-products activities, little or no consumption and emission level data was provided, however, qualitative information is included in the document.

The collection of data at the unit operation level, using comparable monitoring techniques and accompanied with detailed descriptions of the technique and the operating conditions, would be very useful for the revision of the BREF.

Techniques to consider in the determination of BAT (Chapter 4)

Chapter 4 contains the detailed information used by the TWG to determine BAT for the slaughterhouses and animal by-products industries.

About 250 techniques are described. They are described under the standard headings Description, Achieved environmental benefits, Cross-media effects, Operational data, Applicability, Economics, Driving force for implementation, Example plants and Reference literature. The TWG has aimed to include enough information to assess the applicability of the techniques in general or specific cases. The standard structure assists the comparison of techniques both qualitatively and quantitatively. The information in this chapter is essential to the determination of BAT.

Those techniques which the TWG has judged to be BAT, are also cross-referenced from chapter 5. Permit writers and installation operators are thus directed to the discussion of the technique associated with the BAT conclusions, which can assist them when they are determining the BAT-based conditions of IPPC permits.

This chapter includes both “process-integrated” and “end-of-pipe” techniques, thus covering both pollution prevention and pollution control measures, respectively. Some of the techniques are very technical and others are good operating practices, including management techniques.

The chapter is structured so that techniques which are generally applicable to all slaughterhouses and animal by-products installations are described first. These include general training, maintenance and operational good practice, considered as general techniques as they can be applied to virtually all activities. Others are more technical, but apply to the provision and use of utilities and services that are also applied in most industrial activities, such as providing lighting, or cleaning the installation. There are some techniques in this section which are more directly related to slaughterhouses and animal by-products installations, including several dealing with the storage of animal by-products and in particular the prevention of odour. Techniques associated with preventing the accidental release of large volumes of liquids and especially blood, are also included. General waste water treatment techniques are also included in this section.

Techniques which apply to all slaughterhouses are then described. These deal with issues such as the cleaning of lorries delivering live animals; minimisation of water consumption and contamination on slaughter-lines; blood collection and the minimisation of water and energy use in knife sterilisation.

The next 2 main sections contain techniques dealing with the slaughter of large animals and poultry, respectively. These include viscera and hide treatments undertaken at large animal slaughterhouses. The techniques address potential consumption and emission issues at the unit operation level, i.e. they are inherently “process-integrated” pollution prevention and control techniques. Some are technical and some are operational. Many of them address the key environmental issue of minimisation of water consumption and the associated contamination of waste water. In many cases there are energy considerations too, due to water being heated. They also address the minimisation of waste, e.g. associated with the trimming of hides.

The final section on slaughterhouses includes techniques for cleaning, waste water treatment and waste treatment. Throughout the chapter there is an ongoing theme about preventing waste water contamination and the segregation of by-products to maximise their usability and minimise cross contamination and waste.

When the animal by-products industries are addressed there is an emphasis on minimising waste and odour problems. Where the individual processes are addressed one by one, techniques particular to the process in question are addressed, although in many cases the same environmental issues are discussed. For example, several of the techniques address energy saving for drying processes. Many of the techniques deal with “end-of-pipe” odour abatement and waste water treatment.


The section on the incineration of animal by-products addresses those issues specific to the incineration of animal by-products, starting from their delivery to the site. Techniques which have no special relevance to animal by-products are not covered because they come within the scope of the “Waste Incineration” BREF. Issues such as flue gas treatment come within the scope of the “Waste Incineration” BREF whereas the main issues addressed by the techniques in this BREF are either directly or indirectly related to prevention of odour arising from animal by-products and the destruction of TSE risk material.

Finally, 3 integrated same-site activities are described and the environmental advantages of, e.g. reduced energy consumption by re-using heat and odour destruction by on-site incinerators are described.

Best available techniques (Chapter 5)

The way the BAT conclusions are presented in chapter 5 is shown in the figure below. In the figure, the BAT conclusions are presented in tiers. The top tier shows the Sections listing BAT for all slaughterhouses and animal by-products installations; the second is divided between additional BAT for slaughterhouses and BAT for animal by-products installations and the third is divided further showing the Sections listing additional BAT for individual types of slaughterhouse and animal by-products installation.

The conclusions represent what the TWG considered to be BAT in a general sense for the slaughterhouses and animal by-products industries based upon the information in chapter 4 and taking account of the Article 2(11) definition of “best available techniques” and the considerations listed in Annex IV to the Directive. This chapter does not set emission limit values but suggests emission levels that are associated with the use of BAT.



How the BAT conclusions are presented for slaughterhouses and animal by-products installations

BAT addressing the main environmental issues for slaughterhouses and animal by-products installations have been identified, to the extent that the information provided during the information exchange has allowed. The assessment of techniques is dependent on the information provided and assessed by the TWG. For many techniques there is only limited technical and economic data available. For some key environmental issues very little information was provided.

For slaughterhouses, the key environmental issues are generally water consumption; the emission of high organic strength liquids to water and the energy consumption associated with refrigeration and heating water. For animal by-products installations, the main issues are related to the energy consumption associated with drying animal by-products; the emission of high strength organic liquids to water; infectivity, especially related to the controlling, the handling and the destruction of TSE material and odour.

Measures to minimise consumption and emission levels are very much influenced by planning each process technically and operationally at each unit operation level. Some BAT therefore, relate to this.

Regulation (EC) No 1774/2002 of the European Parliament and of the Council of 3 October 2002 laying down health rules concerning animal by-products not intended for human consumption specifies requirements for the handling, storage, transport and processing of animal by-products and describes the disposal routes allowed for TSE risk material. Care has been taken to ensure that the BAT conclusions do not conflict with the requirements of this Regulation. Likewise care has been taken to ensure consistency with other legislation relating to, e.g. public health, food safety, animal welfare and health and safety at work. A great deal of the discussion about the BAT conclusions examined the potential impact of the use of techniques on these issues.

The following paragraphs summarise the key BAT conclusions relating to the most relevant environmental issues. During the discussion of the information exchanged by the TWG, many issues were raised and discussed. Only some of them are highlighted in this summary and it should not be read instead of the “Best available techniques” chapter, which should not be read in isolation from the rest of the BREF.

General management and operation

BAT options related to general management and operational techniques contribute to the overall minimisation of consumption and emission levels, by providing systems of work which encourage good practice and raise awareness. The BAT identified focus on issues such as using an environmental management system; providing training; using a planned maintenance programme; implementing energy, refrigeration, light and noise management systems; managing and minimising the quantities of water and detergents consumed and, in slaughterhouses, managing and monitoring the use of hot water.

Water consumption and the emission of high organic strength liquids in waste water

It is recognised that minimising water consumption and contamination has wide reaching environmental benefits, beyond just that. Increasing the volume of water used automatically affects the volume of waste water which has to be treated at either an on-site or a municipal waste water treatment plant. The treatment of waste water consumes energy and sometimes chemicals and it can lead to odour problems. Every time water makes contact with a carcase or any animal by-product, whether during production or cleaning, contaminants such as fats or blood are entrained and these increase the burden on the waste water treatment plant. In many cases the water used is hot, so energy will have been used to heat it. Also the fats can melt in hot water and then become more difficult to separate from the water.

The availability of water varies depending on factors such as climate, hydrogeology, other demands for its use and price. Whether consumption is considered to be a key environmental issue at site level may, therefore, vary. The Water Framework Directive requires that water

pricing policies provide adequate incentives for users to use water resources efficiently. The BREF identifies BAT to minimise water consumption.

Some examples of the type of BAT conclusions reached are included in the following list, although this is only a summary and there are more in the BAT chapter. BAT is to remove all running water hoses and repair dripping taps and toilets; fit and use drains with screens and/or traps to prevent solid material from entering the waste water; dry clean vehicles and installations before cleaning with a high-pressure hoses fitted with hand-operated triggers; use a squeegee for the initial cleaning of the blood collection trough; where the equipment is suitable, operate a cleaning-in-place system; avoid carcase washing and where this is not possible to minimise it, combined with clean slaughter techniques; re-use cold water within pig de-hairing machines; re-use cooling water from pig singeing kilns; empty stomachs and small intestines dry; remove carcase washing equipment from poultry slaughter-lines except after de-feathering and evisceration and use recycled water, e.g. from the scalding tank, for the carriage of feathers.

Some of the techniques apply to all slaughterhouses and animal by-products installations and others are applicable in e.g. only in large animal or only in poultry slaughterhouses. Many, but not all, of the techniques applicable to animal by-products installations are waste water treatment techniques to clean water which has been contaminated by the process, e.g. during rendering; fish-meal and fish-oil manufacture or gelatine manufacture. Waste water treatment techniques are listed.

Energy

Power generation has major global implications, due to the emissions of greenhouse gases from large combustion plants, so minimising energy consumption, including the use of hot water is a key issue to be addressed. Hygiene standards have always been paramount in slaughterhouses and to a great extent in animal by-products installations producing food or pharmaceutical grade products. The Regulation (EC) No 1774/2002 of the European Parliament and of the Council of 3 October 2002 laying down health rules concerning animal by-products not intended for human consumption has increased the emphasis on hygiene, at all animal by-products installations, to protect the food and feed chain and to control the risk to public health. Some examples of the types of relevant BAT which have been identified include: dry clean installations and transport by-products dry, followed by pressure cleaning using hoses fitted with hand-operated triggers and where the use of hot water is necessary, using thermostatically controlled steam and water valves; insulating and covering knife sterilisers and insulating scalding tanks and the steam scalding of pigs and poultry.

In animal by-products installations carrying out fat melting, rendering, fish-meal and fish-oil production, blood processing, bone processing, gelatine manufacturing or glue making the majority of the energy consumed is generally associated with the drying process. For example 2/3 of the energy consumed in a rendering plant may be directly due to drying. Some examples of the types of BAT techniques identified include: rationalising and insulating steam and water pipework; removing water from blood, by steam coagulation, prior to rendering; for raw material throughputs less than 50000 t/yr, to use a single effect evaporator and for raw material throughputs greater than, or equal to 50000 t/yr, to use a multiple-effect evaporator, to remove water from liquid mixtures and to concentrate plasma, prior to spray drying, using reverse osmosis, vacuum evaporation or by steam coagulation.

In slaughterhouses, in particular, refrigeration is a very large consumer of energy. It may also be significant where animal by-products are kept in refrigerated storage prior to treatment at animal by-products installations. Although this was identified as a key environmental issue, very little information was provided to assist with the determination of BAT. Some general BAT have been identified, including: implementing refrigeration management systems; operating controls over refrigeration plant running times; fitting and operating chill room door closing switches and recuperating heat from refrigeration plants.

Infectivity

Infectivity was identified as a key environmental issue, principally due to the concerns arising from the BSE crises regarding both animal health, especially with respect to the feed and food chain and human health after the links between TSE in animals and CJD, in humans were discovered. Control of the handling and treatment of confirmed TSE infected materials, those suspected of being infected and those arising from animals killed in the context of TSE eradication measures is regulated by *Regulation (EC) No 1774/2002 of the European Parliament and of the Council of 3 October 2002 laying down health rules concerning animal by-products not intended for human consumption*.

The BREF contains BAT conclusions both directly and indirectly associated with the prevention of the spread of TSE and the destruction of TSE risk materials. These are particularly related to rendering and incineration. For example, BAT is to do the following: continuously collect by-products dry and segregated from each other, along the length of the slaughter-line and throughout animal by-products treatment; optimise bleeding and the collection of blood; use sealed, storage, handling and charging facilities for animal by-products; enclose any buildings used for delivery storage, handling and processing of animal by-products; clean and disinfect delivery vehicles and equipment, after each delivery/use; reduce in size animal carcasses and parts of animal carcasses, before incineration; restrict feedstock to exactly that tested during trials; operate continuous incineration; operate an ash burnout chamber, where adequate combustion is not otherwise achievable, e.g. immediately downstream from rotary kilns; operate a monitoring regime for emissions, including a protocol for monitoring burnout, including biohazard from TSE prions, in ash; to achieve emission levels as low as reasonably practicable below those shown in the table below. This table includes BAT associated levels for total carbon and total protein, in ash.

Odour

Although odour is widely considered to be an issue of local nuisance, it can in reality be the most troublesome day to day environmental problem for slaughterhouses and animal by-products installations and so it has to be controlled. Typically it will be caused by the decomposition of animal by-products and this has other related environmental consequences, e.g. it reduces the usability of the animal by-products and hence increases waste. Also, the substances causing odour can cause problems during waste water treatment.

Odour has been considered in detail by the TWG and BAT has been identified to minimise odour and to destroy it when prevention has not been possible. The main conclusion was that animal by-products should be used or disposed of as soon as possible after the animal is slaughtered. Preservation techniques to prevent decomposition and to minimise the formation of malodorous substances and abatement techniques incur significant cross-media effects, including energy consumption and often they require significant economic investment and running costs. Taking account of the cross-media effects and their global implications and the economic factors, the TWG concluded that BAT is to implement some such techniques, but only if the animal by-products cannot be treated before the malodorous substances form, if the animal by-products are inherently malodorous or if the process is inherently malodorous.

Some examples of the BAT identified include: store animal by-products for short periods and possibly to refrigerate them; where it is not possible to treat blood or other animal by-products before their decomposition starts to cause odour problems and/or quality problems, refrigerating them as quickly as possible and for as short a time as possible, to minimise decomposition; where inherently malodorous substances are used or are produced during the treatment of animal by-products, to pass the low intensity/high volume gases through a biofilter. For rendering, when it has been impossible to use fresh raw materials and thereby to minimise the production of malodorous substances, BAT is to do either of the following: to, burn the non-condensable gases in an existing boiler and to pass the low intensity/high volume odours through a biofilter or to burn the whole vapour gases in a thermal oxidiser and to pass the low intensity/high volume odours through a biofilter. For fish-meal and fish-oil production, BAT is to use fresh, (low total volatile nitrogen) feedstock and incinerate malodorous air, with heat

recovery. For incineration of animal by-products, some examples of BAT include, to duct air from the installation and the pre-combustion equipment to combustion chambers, operate odour arrestment techniques, when the incinerator is not working, when odour prevention is not reasonably practicable and use a carbon filter for odour abatement, when incinerators are not operating.

Collaboration with upstream and downstream activities

The operations of those involved in the supply of animals to slaughterhouses, including the farmers and the hauliers, can have environmental consequences in the slaughterhouse. The suppliers of feedstock to animal-by-products installations and other downstream users can also influence the environmental impact of those installations. Their impact can be affected by the properties of the feedstock, e.g. the freshness, degree of separation of different materials and the specification.

BAT is to seek collaboration with upstream partners, to create a chain of environmental responsibility, to minimise pollution and to protect the environment as a whole. Several BAT are identified and most of these are associated with the delivery and feeding of animals or the storage of animal by-products.

Sites with more than one activity

Several examples have been identified where sites with more than one activity can collaborate to minimise consumption and emission levels. BAT is to re-use heat and/or power produced in one activity in other activities and to share abatement techniques, where these are required, e.g. for waste water or odour treatment.

Three examples are listed in the BREF, but the principle can probably be applied to any same-site activities, of which there are many, for instance, slaughterhouses may, e.g. be on the same site as fat melting plants, rendering plants, blood processing plants, incinerators and composting plants.

It is also very common for slaughterhouses to have meat cutting plants and further processing plants on the same site. In such cases information from the “Food, drink and milk” BREF can be used to identify opportunities for collaboration.

The TWG also concluded that BAT is to export any heat and/or power produced which cannot be used on-site

BAT associated levels

BAT associated levels were identified for waste water treatment and for the incineration of animal by-products.

The emission levels given below are generally considered to be appropriate for protecting the water environment and are indicative of the emission levels that would be achieved when applying those techniques generally considered to represent BAT. They do not necessarily represent levels currently achieved within the industry but are based on the expert judgment of the TWG.

Parameter	COD	BOD ₅	SS	Nitrogen (total)	Phosphorus (total)	FOG
Achievable emission level (mg/l)	25 - 125	10 - 40	5 - 60	15 – 40	2 - 5	2.6 - 15

Emission levels associated with BAT for minimising waste water emissions from slaughterhouses and animal by-products installations

Executive Summary

BAT for the incineration of animal by-products, is to achieve emission levels as low as reasonably practicable below those shown in the table below.

Releases to air		Performance associated with BAT ⁽³⁾	
		Typical	Monitoring
SO ₂	(mg/m ³)	< 30 ⁽²⁾	Continuous
HCl	(mg/m ³)	< 10 ⁽²⁾	Continuous
HF	(mg/m ³)	n/a	
NO _x	(mg/m ³)	< 175 ⁽²⁾	Continuous
CO	(mg/m ³)	< 25 ⁽²⁾	Continuous
VOCs	(mg/m ³)	< 10 ⁽²⁾	Periodic
Dust	(mg/m ³)	< 10 ⁽²⁾	Continuous
Dioxins and furans	(ng/m ³)	< 0.1 ⁽⁴⁾	Periodic
Heavy metals total (Cd, TI)	(mg/m ³)	< 0.05 ⁽⁵⁾	
Heavy metals (Hg)	(mg/m ³)	< 0.05 ⁽⁵⁾	
Heavy metals total (Sb, As, Pb, Cr, Co, Cu, Mn, Ni, V)	(mg/m ³)	< 0.5 ⁽⁵⁾	
NH ₃	(mg/m ³)	< 10	
Residence time	>850 °C	3.5 s	
Oxygen	(minimum after last injection)	9 %	Continuous
Pressure, Temperature, Water vapour; Volumetric flow			Continuous
Ash - (total carbon)		< 1 % ⁽⁶⁾	Periodic
Ash – (total protein)	(Aqueous extract) (mg/100g)	0.3 – 0.6	Periodic
⁽²⁾	Releases control – “95 % percentile <u>hourly</u> average over 24 hours”. Measurements at 273 K (temp.), 101.3 kPa (pressure) and 11 % O ₂ dry gas		
⁽³⁾	Actual performance results operating a dry flue gas-cleaning system with bag filters and injected reagents Values measured over a sample period of a minimum of 6 hours and a maximum of 8 hours expressed as toxic equivalent in accordance with Annex 1 of the Waste Incineration Directive		
⁽⁵⁾	Values measured over a sample period of a minimum of 6 hours and a maximum of 8 hours		
⁽⁶⁾	Total organic carbon		
Note: Protein analysis is not relevant to the dedicated incineration of poultry by-products			

Emission levels associated with the dedicated incineration of animal by-products in either bubbling fluidised bed, circulating fluidised bed or rotary kiln incinerators

Emerging techniques (Chapter 6)

Chapter 6 includes 2 techniques that have not yet been commercially applied and are still in the research or development phase. They are “Bio-refining of animal by-products to produce soil improvers and fertilisers” and “Biotechnological treatment of animal by-products in order to increase energetic valorisation”. They have been included here to raise awareness for any future revision of this document.

Concluding remarks (Chapter 7)

Information provided

Many reports from industry and Member State authorities were used as sources of information in the drafting of this BREF and these were supplemented by information from individuals based on example plants. A great deal of information was received during and following site visits to slaughterhouses and animal by-products installations in several Member States. The formal consultations on each draft of the document also prompted the provision of a huge amount of information as well as providing the main opportunities for the TWG to verify the information already submitted.

Although over 350 pieces of information were provided, some significant gaps remain. Energy consumption is a key environmental issue in slaughterhouses, due to chilling and refrigerated storage and in many animal by-products installations, especially during drying. In spite of this, very little data or information about energy saving techniques was submitted.

There is a lack of consistency in the data on the measurement of odour and the identification of the options for keeping odour streams separate for treatment. Prevention of odour is addressed, however, albeit qualitatively.

In general the consumption and emission data provided was not well explained in terms of operating conditions and analytical methods and its relationship with the techniques described was not always made clear. This is one of the reasons why there are very few associated BAT levels quoted. The TWG attempted to collect data “per tonne of carcase produced” and “per tonne of animal by-product treated” for each unit operation, to allow direct comparisons to be made and to identify the areas with high consumption and emission levels, so that these could be addressed. Large gaps remain in this data.

Very little information was received about bone processing, glue manufacture, gasification of meat and bone meal, land spreading/injection, shellfish shell cleaning and the manufacture of fertiliser from animal meal. This may in some cases be due to local legislation prohibiting or restricting the application of animal by-products to land and restrictions under the new *Regulation (EC) No 1774/2002 of the European Parliament and of the Council of 3 October 2002 laying down health rules concerning animal by-products not intended for human consumption*.

Driving forces

The content of the BREF, as well as its time-scale for preparation has been strongly influenced by issues such as food and feed safety concerns, e.g. arising from BSE; food hygiene and animal welfare. The focus has remained on the prevention and control of pollution, but care has been taken to ensure there is consistency with legislation and good practice associated with these other important drivers. The main legal driver has been the new *Regulation (EC) No 1774/2002 of the European Parliament and of the Council of 3 October 2002 laying down health rules concerning animal by-products not intended for human consumption*.

Level of consensus

The conclusions of the BREF were agreed at the final TWG meeting and there are no split views.

Recommendations for future work

The gaps in the information indicate areas where future work could provide results which might assist in the identification of BAT when the BREF is revised, thereby helping operators and permit writers to protect the environment as a whole.

The lack of data “per tonne of carcase produced” and “per tonne of animal by-product treated”, for each unit operation, could be addressed via the regulatory authorities and the various industry NGOs which represent the slaughterhouses and animal by-products operators. They could encourage and co-ordinate the increased measurement of consumption and emission levels at the unit operation level, including details on operating conditions; descriptions of techniques applied; sampling protocols; analytical methods and statistical presentation.

A great deal of the information provided about techniques was incomplete. The TWG decided that although there was insufficient information in these techniques to help with the determination of BAT, they should still be included in the document. The incomplete techniques are appended to chapter 7. They are included to provoke both the collection and provision of further information, when the BREF is revised.

Suggested topics for future R & D projects

The following topics might be considered for future research and development projects:

- 1 minimisation of energy consumption associated with chilling and refrigerated storage
- 2 minimisation of energy consumption associated with the drying of animal by-products
- 3 opportunities to use non-potable water at slaughterhouses, without compromising hygiene and food safety
- 4 optimisation of the use of animal by-products, to minimise waste and
- 5 the development of benchmarking tools to improve the quality of future information exchanges and revisions of the BREF.

The EC is launching and supporting, through its RTD programmes, a series of projects dealing with clean technologies, emerging effluent treatment and recycling technologies and management strategies. Potentially these projects could provide a useful contribution to future BREF reviews. Readers are therefore invited to inform the EIPPCB of any research results which are relevant to the scope of this document (see also the preface of this document).

PREFACE

1. Status of this document

Unless otherwise stated, references to “the Directive” in this document means the Council Directive 96/61/EC on integrated pollution prevention and control. As the Directive applies without prejudice to Community provisions on health and safety at the workplace, so does this document.

This document forms part of a series presenting the results of an exchange of information between EU Member States and industries concerned on best available technique (BAT), associated monitoring, and developments in them. It is published by the European Commission pursuant to Article 16(2) of the Directive, and must therefore be taken into account in accordance with Annex IV of the Directive when determining “best available techniques”.

2. Relevant legal obligations of the IPPC Directive and the definition of BAT

In order to help the reader understand the legal context in which this document has been drafted, some of the most relevant provisions of the IPPC Directive, including the definition of the term “best available techniques”, are described in this preface. This description is inevitably incomplete and is given for information only. It has no legal value and does not in any way alter or prejudice the actual provisions of the Directive.

The purpose of the Directive is to achieve integrated prevention and control of pollution arising from the activities listed in its Annex I, leading to a high level of protection of the environment as a whole. The legal basis of the Directive relates to environmental protection. Its implementation should also take account of other Community objectives such as the competitiveness of the Community’s industry thereby contributing to sustainable development.

More specifically, it provides for a permitting system for certain categories of industrial installations requiring both operators and regulators to take an integrated, overall look at the polluting and consuming potential of the installation. The overall aim of such an integrated approach must be to improve the management and control of industrial processes so as to ensure a high level of protection for the environment as a whole. Central to this approach is the general principle given in Article 3 that operators should take all appropriate preventative measures against pollution, in particular through the application of best available techniques enabling them to improve their environmental performance.

The term “best available techniques” is defined in Article 2(11) of the Directive as “the most effective and advanced stage in the development of activities and their methods of operation which indicate the practical suitability of particular techniques for providing in principle the basis for emission limit values designed to prevent and, where that is not practicable, generally to reduce emissions and the impact on the environment as a whole.” Article 2(11) goes on to clarify further this definition as follows:

“techniques” includes both the technology used and the way in which the installation is designed, built, maintained, operated and decommissioned;

“available” techniques are those developed on a scale which allows implementation in the relevant industrial sector, under economically and technically viable conditions, taking into consideration the costs and advantages, whether or not the techniques are used or produced inside the Member State in question, as long as they are reasonably accessible to the operator;

“best” means most effective in achieving a high general level of protection of the environment as a whole.

Furthermore, Annex IV of the Directive contains a list of “considerations to be taken into account generally or in specific cases when determining best available techniques ... bearing in mind the likely costs and benefits of a measure and the principles of precaution and prevention”. These considerations include the information published by the Commission pursuant to Article 16(2).

Competent authorities responsible for issuing permits are required to take account of the general principles set out in Article 3 when determining the conditions of the permit. These conditions must include emission limit values, supplemented or replaced where appropriate by equivalent parameters or technical measures. According to Article 9(4) of the Directive, these emission limit values, equivalent parameters and technical measures must, without prejudice to compliance with environmental quality standards, be based on the best available techniques, without prescribing the use of any technique or specific technology, but taking into account the technical characteristics of the installation concerned, its geographical location and the local environmental conditions. In all circumstances, the conditions of the permit must include provisions on the minimisation of long-distance or transboundary pollution and must ensure a high level of protection for the environment as a whole.

Member States have the obligation, according to Article 11 of the Directive, to ensure that competent authorities follow or are informed of developments in best available techniques.

3. Objective of this Document

Article 16(2) of the Directive requires the Commission to organise “an exchange of information between Member States and the industries concerned on best available techniques, associated monitoring and developments in them”, and to publish the results of the exchange.

The purpose of the information exchange is given in recital 25 of the Directive, which states that “the development and exchange of information at Community level about best available techniques will help to redress the technological imbalances in the Community, will promote the worldwide dissemination of limit values and techniques used in the Community and will help the Member States in the efficient implementation of this Directive.”

The Commission (Environment DG) established an information exchange forum (IEF) to assist the work under Article 16(2) and a number of technical working groups have been established under the umbrella of the IEF. Both IEF and the technical working groups include representation from Member States and industry as required in Article 16(2).

The aim of this series of documents is to reflect accurately the exchange of information which has taken place as required by Article 16(2) and to provide reference information for the permitting authority to take into account when determining permit conditions. By providing relevant information concerning best available techniques, these documents should act as valuable tools to drive environmental performance.

4. Information Sources

This document represents a summary of information collected from a number of sources, including in particular the expertise of the groups established to assist the Commission in its work, and verified by the Commission services. All contributions are gratefully acknowledged.

5. How to understand and use this document

The information provided in this document is intended to be used as an input to the determination of BAT in specific cases. When determining BAT and setting BAT-based permit conditions, account should always be taken of the overall goal to achieve a high level of protection for the environment as a whole.

The rest of this section describes the type of information that is provided in each section of the document.

Chapters 1 and 2 provide general information on the slaughterhouses and animal by-products industries on the industrial processes used within the sector. Chapter 3 provides data and information concerning current emission and consumption levels reflecting the situation in existing installations at the time of writing.

Chapter 4 describes in more detail the emission reduction and other techniques that are considered to be most relevant for determining BAT and BAT-based permit conditions. This information includes the consumption and emission levels considered achievable by using the technique, some idea of the costs and the cross-media issues associated with the technique, and the extent to which the technique is applicable to the range of installations requiring IPPC permits, for example new, existing, large or small installations. Techniques that are generally seen as obsolete are not included.

Chapter 5 presents the techniques and the emission and consumption levels that are considered to be compatible with BAT in a general sense. The purpose is thus to provide general indications regarding the emission and consumption levels that can be considered as an appropriate reference point to assist in the determination of BAT-based permit conditions or for the establishment of general binding rules under Article 9(8). It should be stressed, however, that this document does not propose emission limit values. The determination of appropriate permit conditions will involve taking account of local, site-specific factors such as the technical characteristics of the installation concerned, its geographical location and the local environmental conditions. In the case of existing installations, the economic and technical viability of upgrading them also needs to be taken into account. Even the single objective of ensuring a high level of protection for the environment as a whole will often involve making trade-off judgements between different types of environmental impact, and these judgements will often be influenced by local considerations.

Although an attempt is made to address some of these issues, it is not possible for them to be considered fully in this document. The techniques and levels presented in chapter 5 will therefore not necessarily be appropriate for all installations. On the other hand, the obligation to ensure a high level of environmental protection including the minimisation of long-distance or transboundary pollution implies that permit conditions cannot be set on the basis of purely local considerations. It is therefore of the utmost importance that the information contained in this document is fully taken into account by permitting authorities.

Since the best available techniques change over time, this document will be reviewed and updated as appropriate. All comments and suggestions should be made to the European IPPC Bureau at the Institute for Prospective Technological Studies at the following address:

Edificio Expo, c/ Inca Garcilaso, s/n, E-41092 Seville, Spain
Telephone: +34 95 4488 284
Fax: +34 95 4488 426
e-mail: JRC-IPTS-EIPPCB@cec.eu.int
Internet: <http://eippcb.jrc.es>

Reference Document on Best Available Techniques in the Slaughterhouses and Animal By-products Industries

EXECUTIVE SUMMARY.....	I
PREFACE.....	XV
SCOPE	XXXIII
1 GENERAL INFORMATION	1
1.1 The slaughtering industry in the European Union.....	1
1.2 The animal by-products industry in the European Union.....	10
1.2.1 Fat melting	11
1.2.2 Rendering.....	11
1.2.3 Fish-meal and fish-oil production	12
1.2.4 Blood processing.....	13
1.2.5 Gelatine manufacture	14
1.2.6 Dedicated incineration of carcasses, parts of carcasses and animal meal	14
1.2.7 Burning of tallow	15
1.2.8 Land spreading/injection.....	15
1.2.9 Biogas production	15
1.2.10 Composting.....	16
1.3 Key environmental issues.....	16
1.3.1 Slaughterhouses	16
1.3.2 Animal by-products installations	18
1.3.2.1 General information about key environmental issues	18
1.3.2.2 Fat melting	18
1.3.2.3 Rendering.....	19
1.3.2.4 Fish-meal and fish-oil production	19
1.3.2.5 Blood processing.....	20
1.3.2.6 Gelatine manufacture	20
1.3.2.7 Glue manufacture.....	20
1.3.2.8 Dedicated incineration of carcasses.....	21
1.3.2.9 Dedicated incineration of animal meal.....	21
1.3.2.10 Burning of tallow	22
1.3.2.11 Land spreading/injection.....	22
1.3.2.12 Biogas production	22
1.3.2.13 Composting	23
1.4 Economic overview.....	23
1.4.1 Slaughterhouses and animal by-products.....	23
1.4.2 The economic cost of consumption and emissions	25
1.5 Food and veterinary legislation influences.....	27
2 APPLIED PROCESSES AND TECHNIQUES	29
2.1 Slaughter	29
2.1.1 Activities described in this chapter	29
2.1.2 Slaughter of large animals.....	29
2.1.2.1 Animal reception and lairage	30
2.1.2.2 Slaughter	31
2.1.2.3 Bleeding	32
2.1.2.4 Hide and skin removal	33
2.1.2.5 Head and hoof removal for cattle and sheep	34
2.1.2.6 Pig scalding	34
2.1.2.7 Pig hair and toenail removal.....	35
2.1.2.8 Pig singeing.....	35
2.1.2.9 Rind treatment.....	35
2.1.2.10 Evisceration.....	36
2.1.2.11 Splitting.....	36
2.1.2.12 Chilling.....	37
2.1.2.13 Associated downstream activities - viscera and hide and skin treatments	38
2.1.3 Slaughter of poultry	41

2.1.3.1	Reception of birds.....	41
2.1.3.2	Stunning and bleeding	41
2.1.3.3	Scalding	42
2.1.3.4	De-feathering	42
2.1.3.5	Evisceration	43
2.1.3.6	Chilling.....	43
2.1.3.7	Maturation	44
2.1.4	Slaughterhouse cleaning.....	44
2.1.5	Storage of slaughterhouse by-products.....	45
2.2	Animal by-products installations	46
2.2.1	Fat melting.....	46
2.2.2	Rendering	50
2.2.2.1	Rendering of carcasses and waste	53
2.2.2.2	Rendering of feathers and pig hair.....	56
2.2.3	Fish-meal and fish-oil production.....	57
2.2.4	Bone processing.....	61
2.2.5	Blood processing - plasma and dried red cell production	61
2.2.6	Gelatine manufacture.....	64
2.2.7	Glue manufacture	82
2.2.8	Dedicated incineration of carcasses and parts of carcasses and of meat and bone meal.....	82
2.2.8.1	Dedicated incineration of carcasses and parts of carcasses.....	82
2.2.8.2	Dedicated incineration of animal meal	85
2.2.8.3	Gasification of meat and bone meal.....	87
2.2.9	Burning of tallow.....	88
2.2.10	Landfill and land spreading/injection	88
2.2.11	Biogas production.....	88
2.2.12	Composting	90
2.3	Waste water treatments used at slaughterhouses and animal by-products installations.....	93
2.3.1	Slaughterhouse waste water treatment.....	93
2.3.1.1	Primary slaughterhouse waste water treatment.....	96
2.3.1.2	Secondary slaughterhouse waste water treatment.....	97
2.3.1.3	Tertiary slaughterhouse waste water treatment.....	99
2.3.2	Animal by-product installation waste water treatment	99
2.3.2.1	Rendering waste water treatment.....	99
2.3.2.1.1	Mechanical waste water treatment.....	100
2.3.2.1.2	Physico-chemical treatment	100
2.3.2.1.3	Biological treatment.....	101
2.3.2.1.4	Feathers - elimination of hydrogen sulphide.....	101
2.3.2.2	Fish-meal and fish-oil manufacturing waste water treatment	101
2.3.2.3	Blood processing waste water treatment.....	101
2.3.2.4	Gelatine manufacture waste water treatment	102
3	CURRENT CONSUMPTION AND EMISSION LEVELS.....	103
3.1	Slaughterhouses	103
3.1.1	Slaughterhouses - overall consumption and emission data at installation level	103
3.1.2	Slaughter of large animals	114
3.1.2.1	Animal reception and lairage.....	115
3.1.2.2	Bleeding.....	115
3.1.2.3	Hide and skin removal	116
3.1.2.4	Head and hoof removal for cattle and sheep.....	116
3.1.2.5	Pig scalding.....	116
3.1.2.6	Pig hair and toenail removal	117
3.1.2.7	Pig singeing	117
3.1.2.8	Rind treatment	117
3.1.2.9	Evisceration	117
3.1.2.10	Splitting	118
3.1.2.11	Chilling.....	118
3.1.2.12	Associated downstream activities - viscera and hide and skin treatments	118
3.1.3	Slaughter of poultry	119
3.1.3.1	Reception of birds.....	119
3.1.3.2	Stunning and bleeding	119
3.1.3.3	Scalding	120
3.1.3.4	De-feathering	120

3.1.3.5	Evisceration.....	120
3.1.3.6	Chilling.....	120
3.1.4	Slaughterhouse cleaning - equipment and installation	121
3.1.5	Storage and handling of slaughterhouse by-products.....	123
3.1.6	Slaughterhouse waste water treatment	123
3.2	Animal by-products installations.....	124
3.2.1	Fat melting	124
3.2.2	Rendering.....	124
3.2.2.1	Rendering of carcasses and waste.....	134
3.2.2.2	Rendering of feathers and pig hair	134
3.2.3	Fish-meal and fish-oil production	136
3.2.4	Blood processing	139
3.2.5	Bone processing	140
3.2.6	Gelatine manufacture	141
3.2.7	Dedicated incineration of carcasses, parts of carcasses and meat and bone meal	142
3.2.7.1	Dedicated incineration of carcasses and parts of carcasses	142
3.2.7.2	Dedicated incineration of animal meal.....	143
3.2.8	Burning of tallow	146
3.2.9	Biogas production	147
3.2.10	Composting.....	148
3.2.11	Animal by-products installation waste water treatment plants.....	149
3.2.12	Combined processes and techniques	149
4	TECHNIQUES TO CONSIDER IN THE DETERMINATION OF BAT.....	151
4.1	General techniques applicable in slaughterhouses and animal by-products installations.....	151
4.1.1	Environmental management tools.....	153
4.1.2	Training provision.....	160
4.1.3	Use of a planned maintenance programme	161
4.1.4	Dedicated metering of water consumption.....	162
4.1.5	Separation of process and non-process water.....	163
4.1.6	Use of cooling water and water from vacuum pumps.....	164
4.1.7	Removal of running water hoses and the repair of dripping taps and toilets	164
4.1.8	Use of pressure cleaning throughout the installation	165
4.1.9	Fit cleaning-hoses with hand-operated triggers.....	166
4.1.10	Supply of pressure-controlled water and via nozzles.....	167
4.1.11	Fit and use floor drains with screens and/or traps to prevent solid material from entering the waste water.....	167
4.1.12	Dry cleaning of installations and dry transport of by-products	168
4.1.13	Overfilling protection on bulk storage tanks, e.g. containing blood or tallow	169
4.1.14	Bunding of bulk storage tanks containing, e.g. blood or tallow	170
4.1.15	Double skin protection of bulk storage tanks, e.g. containing blood or tallow	171
4.1.16	Implement energy management systems.....	171
4.1.17	Energy management at a red meat plant	173
4.1.18	Implement refrigeration management systems.....	175
4.1.19	Control refrigeration plant running times.....	179
4.1.20	Use of binary ice as a cooling fluid (secondary refrigerant)	180
4.1.21	Chill room door closing microswitches	182
4.1.22	Heat recuperation from refrigeration plants	183
4.1.23	Use of thermostatically controlled steam and water blending valves	183
4.1.24	Rationalisation and insulation of steam and water pipework	184
4.1.25	Isolation of steam and water services.....	185
4.1.26	Implementation of lighting management systems.....	185
4.1.27	Short and possibly cold storage of animal by-products.....	186
4.1.28	Audit odour	188
4.1.29	Enclose animal by-products during transport, loading/unloading and storage.....	189
4.1.30	Design and construction of vehicles, equipment and premises for easy cleaning.....	191
4.1.31	Frequent cleaning of materials storage areas - odour prevention.....	192
4.1.32	Transport blood in insulated containers	192
4.1.33	Biofilters	193
4.1.34	Odour control using activated carbon filters	197
4.1.35	Dilution of odours by capture into one or more chimneys.....	197
4.1.36	Noise management.....	198
4.1.37	Reduced noise by roof extract fans - by routine maintenance.....	200

4.1.38	Reduced noise at balance lagoon blower.....	201
4.1.39	Abatement of noise from refrigeration plants by the use of insulated doors	202
4.1.40	Replacement of fuel oil with natural gas	203
4.1.41	Replacement of boiler fuel with tallow.....	203
4.1.42	Installation and equipment cleaning	204
4.1.42.1	Management of quantities of water and detergents consumed	204
4.1.42.2	Selection of those detergents which cause the minimum impact on the environment	205
4.1.42.3	Avoid and reduce the use of cleaning and disinfection agents containing active chlorine	206
4.1.43	Waste water treatment	206
4.1.43.1	Provision of a waste water holding capacity in excess of routine requirements	206
4.1.43.2	Regularly conduct laboratory analysis of the effluent composition and maintain records	207
4.1.43.3	Prevention of stagnant waste water.....	207
4.1.43.4	Screening of solids – sieves (type unspecified)	208
4.1.43.5	Static wedge/curved screen.....	209
4.1.43.6	Inclined screw press.....	210
4.1.43.7	Cylindrical screen	211
4.1.43.8	Rotary drum screen.....	212
4.1.43.9	Fat removal from waste water, using a fat trap.....	215
4.1.43.10	Flotation plants	216
4.1.43.11	Waste water equalisation tanks.....	219
4.1.43.12	Minimise liquid seepage and cover waste water treatment tanks	220
4.1.43.13	Minimise liquid seepage and aerate waste water treatment tanks.....	221
4.1.43.14	Anaerobic pretreatment using down-flow or up-flow reactors	221
4.1.43.15	Aerobic digestion combined with either intermittent or alternating denitrification under anoxic conditions	223
4.2	Slaughterhouses	226
4.2.1	Slaughterhouses - general techniques applicable at installation level	226
4.2.1.1	Dry scraping of delivery vehicles, prior to washing	226
4.2.1.2	Wash delivery lorries using a high-pressure trigger-operated pistol with an adjustable jet.....	227
4.2.1.3	Automation of the first part of the clean slaughter-line	228
4.2.1.4	Avoid and minimise carcase rinsing, combined with using clean slaughter techniques	230
4.2.1.5	Apply automated water start/stop controls throughout the slaughter-line	231
4.2.1.6	Continuous, dry and segregated collection of by-products along the length of the slaughter-line	232
4.2.1.7	Double drain from the bleed hall	234
4.2.1.8	Refrigeration/cooling of blood.....	234
4.2.1.9	Dry collection of floor waste	236
4.2.1.10	Use of wet suction of by-products/waste collection prior to wet cleaning	237
4.2.1.11	Reduction of water consumption in poultry slaughter	238
4.2.1.12	Use pressurised water to wash the carcase	239
4.2.1.13	Removal of unnecessary taps from the slaughter-line	239
4.2.1.14	Insulated and covered knife sterilisers.....	240
4.2.1.15	Periodic change of water in electrically heated knife sterilisers, controlled by a timer.....	240
4.2.1.16	Double knife sterilisation tanks	241
4.2.1.17	Knife sterilisation using low-pressure steam	242
4.2.1.18	Hand and apron cleaning cubicles – default “water off”	242
4.2.1.19	Management and monitoring of compressed air use.....	243
4.2.1.20	Management and monitoring of ventilation use	244
4.2.1.21	Use of backward bowed centrifugal fans.....	244
4.2.1.22	Management and monitoring of hot water use.....	245
4.2.1.23	Installation of groundwater cooling of refrigerant.....	245
4.2.2	Slaughter of large animals	246
4.2.2.1	Animal reception and lairage.....	246
4.2.2.1.1	Cessation of feeding of animals 12 hours prior to slaughter.....	246
4.2.2.1.2	Minimise animals’ time in the slaughterhouse to reduce manure production	247
4.2.2.1.3	Addition of dry bedding to existing bedding, to soak up manure	247

4.2.2.1.4	Demand-controlled drinking water.....	248
4.2.2.1.5	Showering of pigs, using water saving, timer controlled nozzles	248
4.2.2.1.6	Dry cleaning of the lairage floor and periodically cleaning it with water	249
4.2.2.2	Bleeding	249
4.2.2.2.1	Optimisation of bleeding and blood collection.....	249
4.2.2.2.2	Use of a squeegee for initial cleaning of the blood collection trough	252
4.2.2.3	Pig scalding	252
4.2.2.3.1	Condensation/steam scalding of pigs (vertical scalding).....	252
4.2.2.3.2	Insulation and covering of pig scalding tanks	255
4.2.2.3.3	Water level control on pig scalding tanks	256
4.2.2.4	Pig hair and toenail removal.....	257
4.2.2.4.1	Recirculation of water within pig de-hairing machines.....	257
4.2.2.4.2	Replace irrigation pipes at the top of de-hairing machines, with nozzles	258
4.2.2.5	Pig singeing.....	258
4.2.2.5.1	Re-use of cooling water from the singeing kiln	258
4.2.2.5.2	Heat recovery from pig singeing exhaust gases, to preheat water	259
4.2.2.5.3	Post singeing showering with flat jet nozzles.....	261
4.2.2.6	Rind treatment.....	261
4.2.2.6.1	Replace irrigation pipes with flat jet nozzles.....	261
4.2.2.7	Evisceration.....	262
4.2.2.7.1	Saw sterilisation in a cabinet with automated hot water nozzles.....	262
4.2.2.7.2	Regulation and minimisation of water use for moving intestines.....	262
4.2.2.8	Chilling.....	263
4.2.2.8.1	Blast-chilling/shock-cooling tunnel - for chilling pigs.....	263
4.2.2.8.2	Water-spraying/mist-cooling as a method of cooling pigs	264
4.2.2.8.3	NOT showering carcasses before they are chilled in a chilling tunnel	265
4.2.2.9	Associated downstream activities - viscera and hide and skin treatments	266
4.2.2.9.1	Removal of chopping blades from a by-product washer	266
4.2.2.9.2	Dry emptying of stomachs	267
4.2.2.9.3	“Dry” collection of the contents of small intestines	268
4.2.2.9.4	“Dry” emptying of pig intestines, which are not to be used for casings.....	268
4.2.2.9.5	Use of nozzles instead of showers to flush out large intestines (pigs).....	269
4.2.2.9.6	Control of water consumption for small and large intestine washing	269
4.2.2.9.7	Use of a mechanised fat trap for removing fat from water	270
4.2.2.9.8	Collection of the mucosa from small intestines (pigs)	271
4.2.2.9.9	Minimise water usage during rinsing of tongues and hearts	271
4.2.2.9.10	Trimming of all hide/skin material not destined for tanning immediately after removal from the animal	272
4.2.2.9.11	Storage of hides/skins at 10 - 15 °C.....	273
4.2.2.9.12	Drum salting of hides and skins	274
4.2.2.9.13	Drum salting of sheep/lamb skins - with added boric acid.....	275
4.2.2.9.14	Dry collection of salt residues from hide, skin or fur preservation	275
4.2.2.9.15	Preservation of hides and skins by refrigeration	276
4.2.2.9.16	Preservation of hides and skins by cooling with flaked or crushed ice	277
4.2.3	Slaughter of poultry	278
4.2.3.1	Reception of birds	278
4.2.3.1.1	Re-use of crate washing water.....	278
4.2.3.1.2	Dust abatement at bird reception, unloading and hanging stations - fabric filters	279
4.2.3.1.3	Dust abatement at bird reception, unloading and hanging stations – wet scrubber.....	280
4.2.3.1.4	Dust abatement at bird reception, unloading and hanging stations – washable metal mesh	280
4.2.3.2	Stunning and bleeding.....	281
4.2.3.2.1	Using inert gases for poultry stunning.....	281
4.2.3.3	Scalding.....	283
4.2.3.3.1	Steam scalding of poultry.....	283
4.2.3.3.2	Insulation of scalding tanks	283
4.2.3.4	De-feathering	283
4.2.3.4.1	Use of nozzles instead of irrigation pipes.....	283
4.2.3.4.2	Use of recycled water, e.g. from scalding, for the carriage of feathers	284
4.2.3.5	Evisceration.....	284
4.2.3.5.1	Water efficient and fewer shower heads.....	284

4.2.3.6	Chilling	285
4.2.3.6.1	Air-chilling	285
4.2.3.6.2	Controlling the supply of water to the immersion/spin chiller	285
4.2.4	Slaughterhouse cleaning	286
4.2.4.1	Use of detergents using enzymes	286
4.2.4.2	Pre-cleaning blood and meat juice contamination with cold water	287
4.2.4.3	CIP (Cleaning-in-place)	287
4.2.4.4	Use of cyclonic vacuum cleaners	288
4.2.5	Storage and handling of slaughterhouse by-products	289
4.2.5.1	Segregated storage and handling of different kinds of by-products	289
4.2.6	Slaughterhouse waste water treatment	290
4.2.6.1	Treatment of slaughterhouse waste water at municipal WWTPs	290
4.2.6.2	Use of sequencing batch reactors (SBR) in slaughterhouse waste water treatment	291
4.2.6.3	Moving bed trickling filter - for the treatment of air, water and air/water mixtures	295
4.2.7	Slaughterhouse waste treatment	296
4.2.7.1	Microbiological treatment of slaughterhouse waste	296
4.3	Animal by-products installations	299
4.3.1	Animal by-products installations - general techniques applicable at installation level	299
4.3.1.1	Continuous and segregated collection of by-products throughout animal by-products treatment	299
4.3.1.2	Maintenance of negative pressure in storage, handling and processing areas	299
4.3.1.3	Sealed storage, handling and charging of animal by-products	300
4.3.1.4	Use of fresh refrigerated raw materials	301
4.3.1.5	Multiple-effect evaporators	302
4.3.2	Fat melting	304
4.3.3	Rendering	304
4.3.3.1	Totally enclosed rendering line	304
4.3.3.2	Size reduction of animal carcasses and parts of animal carcasses before rendering	304
4.3.3.3	Continuous rendering of, e.g. fresh raw feathers and hair	305
4.3.3.4	Removal of water from blood, by steam coagulation, prior to rendering or spray drying	306
4.3.3.5	Single effect evaporator	307
4.3.3.6	Ammonia stripping of exhaust vapour condensates from rendering	308
4.3.3.7	Ammoniacal-N removal from rendering condensate by ammonia conversion	309
4.3.3.8	Bioscrubber – general	310
4.3.3.9	Wet scrubbing – general	311
4.3.3.10	Thermal oxidiser for combustion of vapour, non-condensable gases and room air	312
4.3.3.11	Burning malodorous gases, including non-condensable gases, in an existing boiler	316
4.3.3.12	Chlorine dioxide scrubber generated from sodium chlorite - odour abatement	317
4.3.3.13	Chlorine dioxide scrubber generated from sodium chlorate - odour abatement	317
4.3.3.14	Use of H ₂ O ₂ to remove H ₂ S from waste water in feather rendering plants	318
4.3.3.15	Biological waste water treatment using overpressure in conjunction with ultrafiltration	318
4.3.4	Fish-meal and fish-oil production	321
4.3.4.1	Use of fresh low total volatile nitrogen (TVN) feedstock	321
4.3.4.2	Use of heat from vapour from drying fish-meal in a falling film evaporator, to concentrate stickwater	322
4.3.4.3	Incineration of malodorous air, with heat recovery	325
4.3.4.4	Washing of air with condensate instead of with seawater	326
4.3.5	Blood processing	327
4.3.5.1	Concentration of plasma, prior to spray drying - reverse osmosis	327
4.3.5.2	Concentration of plasma, prior to spray drying - vacuum evaporation	327
4.3.6	Bone processing	328
4.3.7	Gelatine manufacture	328
4.3.7.1	Insulation of bone de-fatting equipment	328
4.3.8	Dedicated incineration of carcasses, parts of carcasses and animal meal	329
4.3.8.1	Enclosing buildings for the delivery, storage, handling and processing of animal by-products	329

4.3.8.2	Cleaning and disinfection of delivery vehicles and equipment after each delivery	329
4.3.8.3	Carrying carcasses (not dragging)	330
4.3.8.4	Size reduction of animal carcasses and parts of animal carcasses before incineration	331
4.3.8.5	Restriction of feedstock to <u>exactly</u> that tested during trials.....	332
4.3.8.6	Agreeing the fat:moisture:ash content of animal meal, with the renderer.....	332
4.3.8.7	Agreeing a specification with the renderer, regarding receipt of material manufactured to the optimal physical characteristics for incineration and associated handling and storage	333
4.3.8.8	Handling and burning of animal meal as pellets	333
4.3.8.9	Handling and burning of packaged MBM.....	333
4.3.8.10	Avoid receipt of material for incineration in PVC packaging	334
4.3.8.11	Auger feed of parts of carcasses or animal meal	334
4.3.8.12	Pumping of parts of carcasses or animal meal.....	335
4.3.8.13	Incineration of incinerator waste water.....	335
4.3.8.14	Sealed storage, handling and charging of animal by-products to incinerators	336
4.3.8.15	Ducting of air from the installation and the pre-combustion equipment to the combustion chamber	337
4.3.8.16	Combustion temperatures alarmed and interlocked to charging mechanisms.....	339
4.3.8.17	Bubbling fluidised bed (BFB) incineration of animal by-products	340
4.3.8.18	Circulating fluidised bed incineration of animal by-products	345
4.3.8.19	Rotary kiln incinerator design	346
4.3.8.20	Continuous incineration	348
4.3.8.21	Provision of an ash burnout chamber	349
4.3.8.22	Automated continuous de-ashing	349
4.3.8.23	Vacuum cleaning of ash - not sweeping.....	350
4.3.8.24	Wet quenching of ash.....	350
4.3.8.25	Monitoring regime for emissions, including a protocol for monitoring burnout, including biohazard from TSE prions, in ash.....	351
4.3.8.26	Regular cleaning and disinfection of installations and equipment	352
4.3.8.27	Operation of odour arrestment techniques when the incinerator is not working ..	353
4.3.8.28	Biofilter for odour abatement when the incinerator is not operating.....	353
4.3.8.29	Carbon filter for odour abatement when the incinerator is not operating.....	354
4.3.9	Land spreading/injection.....	354
4.3.9.1	Land spreading of sludge from gelatine and leather glue manufacture	354
4.3.9.2	Land spreading of solid residues from biogas production.....	355
4.3.10	Biogas production	355
4.3.10.1	Biogas production from slaughterhouse by-products	355
4.3.10.2	Biogas from manure and fat containing waste	356
4.3.10.3	Re-use of heat during biogas production.....	358
4.3.11	Composting.....	359
4.3.11.1	Sufficient drainage capacity for windrow composting on a hard standing.....	359
4.3.11.2	Hard standing – concrete.....	360
4.3.11.3	Hard standing - asphalt or macadams.....	360
4.3.11.4	Windrow composting of animal by-products	361
4.3.12	Manufacture of fertiliser from meat and bone meal.....	362
4.3.13	Alkaline hydrolysis of animal carcasses and parts of animal carcasses at elevated temperature	362
4.4	Integrated same-site activities	364
4.4.1	Integrated site - slaughterhouse and rendering plant.....	364
4.4.2	Integrated site - slaughterhouse and animal carcase incinerator	365
4.4.3	Integrated site – rendering plant and animal meal incinerator	366
5	BEST AVAILABLE TECHNIQUES	369
5.1	Slaughterhouses and animal by-products installations.....	373
5.1.1	General processes and operations	373
5.1.1.1	BAT for environmental management.....	374
5.1.2	Integration of same site activities.....	375
5.1.3	Collaboration with upstream and downstream activities.....	375
5.1.4	Installation and equipment cleaning.....	375
5.1.5	Treatment of waste water	375
5.2	Additional BAT for slaughterhouses.....	377

5.2.1	Additional BAT for the slaughter of large animals	377
5.2.2	Additional BAT for the slaughter of poultry	378
5.3	Additional BAT for animal by-products installations.....	379
5.3.1	Additional BAT for fat melting.....	379
5.3.2	Additional BAT for rendering.....	379
5.3.3	Additional BAT for fish-meal and fish-oil production.....	379
5.3.4	Additional BAT for blood processing.....	380
5.3.5	Additional BAT for bone processing.....	380
5.3.6	Additional BAT for gelatine manufacture.....	380
5.3.7	Additional BAT for the incineration of animal by-products.....	380
5.3.8	Additional BAT for biogas production.....	382
5.3.9	Additional BAT for composting.....	382
6	EMERGING TECHNIQUES.....	383
6.1	Bio-refining of animal by-products to produce soil improvers and fertilisers	383
6.2	Biotechnological treatment of animal by-products in order to increase energetic valorisation	384
7	CONCLUDING REMARKS.....	385
7.1	Timing of the work	385
7.2	Information provided.....	385
7.3	Driving forces	386
7.4	Level of consensus.....	387
7.5	Recommendations for future work	387
7.6	Suggested topics for future R & D projects.....	388
7.7	Techniques not included in Chapter 4, “Techniques to consider in the determination of BAT”, due to lack of sufficient information.....	389
7.7.1	General techniques applicable in slaughterhouses and animal by-products installations	389
7.7.1.1	Hoses can be fitted with flat-jet spray nozzles.....	389
7.7.1.2	Fat/sludge collector.....	389
7.7.1.3	Fat cleaning.....	389
7.7.1.4	Conductivity controlled blowdown on cooling towers	389
7.7.1.5	Design of refrigeration space to minimise energy consumption.....	390
7.7.1.6	Energy saving motors	390
7.7.1.7	Heat recovery.....	390
7.7.1.8	Airlock provision between the indoor loading/unloading area and outdoors	390
7.7.1.9	Ozone.....	391
7.7.1.10	Use of low rpm fans for air conditioning.....	391
7.7.1.11	Separation of metals	391
7.7.2	General techniques applicable in slaughterhouses.....	391
7.7.2.1	Control of water supply, by, e.g. department or unit operation	391
7.7.2.2	Air-cooling of vacuum pumps instead of water-cooling.....	391
7.7.2.3	Once a day knife washing – multiple knife supply at work stations.....	391
7.7.2.4	Use of a hot dry airline to sterilise knives.....	392
7.7.2.5	Use of an autoclave to sterilise knives (off-line, e.g. between shifts).....	392
7.7.2.6	Automatic magnetic valve controlled water sprays	392
7.7.2.7	Recuperation/recovery of energy.....	392
7.7.3	Slaughter of large animals	392
7.7.3.1	Collect water used to clean aprons and boots	392
7.7.3.2	Lairage.....	392
7.7.3.2.1	Re-use of water to wash vehicles.....	392
7.7.3.2.2	Pig delivery planned for times least sensitive for noise	392
7.7.3.2.3	Unloading using unloading bridges	393
7.7.3.2.4	Use of slatted lairage floors	393
7.7.3.2.5	Re-use of water to wash the lairage floor (pigs)	393
7.7.3.2.6	Collection of urine, for use as a fertiliser.....	393
7.7.3.2.7	Washing animals before slaughter	393
7.7.3.3	Slaughter.....	393
7.7.3.3.1	Drive pigs to the stunning pen, as quietly as possible.....	393
7.7.3.3.2	Carbon dioxide stunning of pigs	394
7.7.3.4	Hide and skin removal	394
7.7.3.4.1	Pneumatic removal of hides and skins.....	394
7.7.3.5	Pig scalding.....	394

7.7.3.5.1	Design of pig scalding tank, to ease emptying and cleaning	394
7.7.3.5.2	Reducing water carried out of scalding tanks	394
7.7.3.5.3	Stopping the water supply to the scalding tank during breaks in production	394
7.7.3.5.4	Heat recovery from tank water	394
7.7.3.5.5	Use of a scalding tank with a steep base	395
7.7.3.6	Pig hair and toenail removal	395
7.7.3.6.1	Control of the water supply to de-hairing machines	395
7.7.3.7	Pig singeing	395
7.7.3.7.1	Reduce the pig singeing time	395
7.7.3.7.2	Efficient use and design of singe pipes	395
7.7.3.7.3	Install switches which initiate the singeing flame only when a carcass is present	395
7.7.3.7.4	Insulate the singeing oven	396
7.7.3.8	Evisceration	396
7.7.3.8.1	Move viscera by conveyor	396
7.7.3.8.2	Use of fat separators	396
7.7.3.9	Splitting	396
7.7.3.9.1	Optimise the use of the carcass splitting saw	396
7.7.3.10	Chilling	396
7.7.3.10.1	Batch chilling	396
7.7.3.11	Downstream activities	397
7.7.3.11.1	Water control at rumen washing machine	397
7.7.3.11.2	Removal and use/disposal of water from the “dry” intestine contents	397
7.7.3.11.3	Dry removal of gut manure	397
7.7.3.11.4	Re-use of finish water from casing washing	397
7.7.3.11.5	Minimise noise on the intestine mucus machine	398
7.7.3.11.6	Chilling of red and green offals, using ice	398
7.7.4	Slaughter of poultry	398
7.7.4.1	Reception of birds	398
7.7.4.1.1	Multi-stage crate washing units	398
7.7.4.1.2	Collection of materials screened off crate washing machines	398
7.7.4.1.3	Sealing of the crate-washing machines	398
7.7.4.2	Poultry scalding	399
7.7.4.2.1	Limitation of water loss from the scalding tank	399
7.7.4.3	De-feathering	399
7.7.4.3.1	Transport of heads and feet using a vacuum system	399
7.7.4.4	Evisceration	399
7.7.4.4.1	Dual water supply system	399
7.7.4.4.2	Integrated transport and cooling of red offal from poultry slaughter	399
7.7.4.4.3	Reduce water flow at knife wash points	399
7.7.4.4.4	Reduced water flow in mini-chiller	400
7.7.4.5	Slaughterhouse cleaning	400
7.7.4.5.1	Large tray and box washing units	400
7.7.4.5.2	High-pressure cleaning	400
7.7.4.5.3	Monitor contamination removal	400
7.7.4.6	Waste water treatment	400
7.7.4.6.1	Trough screen	400
7.7.5	Rendering	401
7.7.5.1	Provide sufficient production capacity	401
7.7.5.2	Discontinuous sterilisation using a “strainer basket boiling apparatus”	401
7.7.5.3	Discontinuous sterilisation using a sieve disc-drier	402
7.7.5.4	Rendering, with periodic mixing	402
7.7.5.5	Rendering, with a disc drier	402
7.7.5.6	Recirculation of solid residues from pre-treatment into the raw material (if there is no feed production)	402
7.7.5.7	Recirculation of excess sludge into the raw material (if there is no feed production)	402
7.7.5.8	Air-cooling of condensate, instead of water-cooling	402
7.7.5.9	Use of a decanter system	403
7.7.5.10	Centrifuge blood	403
7.7.5.11	Disinfection chute for vehicles and footwear	403
7.7.5.12	Sludge traps, settling tanks and oil/petrol separators for waste water from vehicle cleaning	403

7.7.5.13	Grease traps and oil traps (DIN 4040)	403
7.7.5.14	Cover all tanks to enable air treatment	403
7.7.5.15	Enclosure of WWTP balance tanks and ducting air stream to odour treatment...	403
7.7.5.16	Dosing of nutrients, acids and alkalis	404
7.7.5.17	Thermal disinfection of cleaning water - dedicated water heating unit	404
7.7.5.18	Neutralisation tanks	404
7.7.6	Fish-meal and fish-oil production.....	404
7.7.6.1	Vacuum unloading of fish from fishing vessels.....	404
7.7.6.2	Product loss audit and control.....	404
7.7.6.3	Controlled cooking - preventing over-boiling	405
7.7.6.4	Indirect cooling of vapour from production of evaporated stickwater, using seawater	405
7.7.6.5	Vacuum drying at 65 °C	405
7.7.6.6	Drying by heating	405
7.7.6.7	Stripping plant to remove volatile nitrogen from water	405
7.7.6.8	Use of a decanter instead of a press and decanter.....	405
7.7.6.9	Control of suction on the drier	405
7.7.6.10	High-pressure removal of burned products instead of using NaOH	405
7.7.6.11	Waste water treatment of certain fractions of the impure condensate	406
7.7.7	Blood processing	406
7.7.7.1	Back venting of tankers during unloading	406
7.7.8	Gelatine manufacture.....	406
7.7.8.1	Neutralisation of acid waste waters by alkaline waste waters	406
7.7.8.2	Re-use of heat from evaporators.....	406
7.7.9	Incineration.....	406
7.7.9.1	Initial cleaning of vehicles and equipment, by dry vacuuming	406
7.7.9.2	Monitoring amino compounds in salt fractions recovered in wash-water	406
7.7.10	Burning of tallow.....	407
7.7.10.1	Back venting of tankers during unloading	407
7.7.11	Composting	407
7.7.11.1	In-vessel composting of animal by-products	407
7.7.11.2	Use of a high carbon source to prevent pungent ammonia odours	407
7.7.11.3	Avoiding dusty activities on windy days	407
7.7.12	Integrated same-site activities.....	407
7.7.12.1	Combining gasification of MBM with thermal oxidation on a rendering site	407
8	REFERENCES	409
9	GLOSSARY	419
10	ANNEXES.....	427
10.1	Monitoring protocol - ash and particulate testing methods and frequency (for analysis of carbon, nitrogen and amino acid content)	427

List of figures

Figure 2.1: Relationships between slaughterhouses and downstream activities (summary)	29
Figure 2.2: Schematic diagram of a simple refrigeration system	38
Figure 2.3: The batch wet fat melting system with autoclaves	47
Figure 2.4: The conventional batch dry fat melting/rendering method	48
Figure 2.5: The continuous low temperature wet fat melting system	49
Figure 2.6: Flow diagram for the rendering of feathers and hair	57
Figure 2.7: Material flow in fish-meal and fish-oil production	58
Figure 2.8: Schematic diagram of the production process in a large Danish fish-meal factory	60
Figure 2.9: Flow diagram for bone processing	61
Figure 2.10: Spray dried plasma manufacturing process	63
Figure 2.11: The main gelatine manufacturing processes	65
Figure 2.12: Flow diagram for the demineralisation of bone to produce ossein for gelatine manufacture	67
Figure 2.13: The limed bone gelatine manufacturing process	73
Figure 2.14: The acid bone gelatine manufacturing process	74
Figure 2.15: The acid bone gelatine manufacturing process with alkaline pretreatment	75
Figure 2.16: The heat and pressure gelatine manufacturing process	76
Figure 2.17: The limed hide gelatine manufacturing process	77
Figure 2.18: The acid hide gelatine manufacturing process	78
Figure 2.19: The sodium hydroxide gelatine manufacturing process	79
Figure 2.20: The pig skin gelatine manufacturing process	80
Figure 2.21: Flow chart showing the windrow composting process	92
Figure 2.22: Diagram illustrating the in-vessel composting process	93
Figure 2.23: Waste water streams through a pig slaughterhouse	95
Figure 2.24: Block diagram of a mechanical/physical-chemical preliminary waste water plant	100
Figure 3.1: Typical water balance for areas in a UK pig slaughterhouse	108
Figure 3.2: Data for water consumption in a typical Italian pig slaughterhouse	109
Figure 3.3: Consumption and emission levels for an example rendering plant	131
Figure 3.4: Consumption and emission data for rendering with on-site energy generation	150
Figure 4.1: Binary ice system with a conventional refrigeration plant	180
Figure 4.2: Curved screen	209
Figure 4.3: Static wedge screen	209
Figure 4.4: Inclined screw press	211
Figure 4.5: Cylindrical screen	212
Figure 4.6: Example of a rotary drum screen	213
Figure 4.7: Principal components of dissolved air flotation	218
Figure 4.8: Outline of a condensation scalding tunnel	253
Figure 4.9: Recirculation of water for de-hairing pigs	257
Figure 4.10: The Grinsted system re-using cooling water from a singeing kiln	259
Figure 4.11: Heat recovery from pig singeing gases	260
Figure 4.12: Diagram of a moving bed trickling filter designed to treat waste water and air emissions	295
Figure 4.13: Schematic of the biological treatment process for high-strength slaughterhouse wastes	297
Figure 4.14: Multiple-effect evaporator	303
Figure 4.15: Single effect evaporator	308
Figure 4.16: Flow diagram of biological waste water treatment using overpressure in conjunction with ultrafiltration	319
Figure 4.17: Schematic representation of a 4-stage self-circulating evaporator	323
Figure 4.18: Schematic representation of a falling film surplus heat evaporator	323
Figure 4.19: 40 MW twin stream MBM fluid bed combustion facility	340
Figure 4.20: Consumption and emission data for rendering with on-site burning of MBM	367
Figure 5.1: How the BAT conclusions are presented for slaughterhouses and animal by-products installations	372
Figure 7.1: Trough screen – cross-section	401

List of tables

Table 1.1: Numbers of cattle, sheep and pigs slaughtered in the EU in 1998.....	1
Table 1.2: Number of slaughterhouses (excluding poultry) in Germany, with turnover data for 1997 - 1999.....	3
Table 1.3: Numbers of slaughterhouses, animals slaughtered and associated live/carcase weights in Europe	7
Table 1.4: Raw material processed in the German meat meal industry (2001)	11
Table 1.5: EU Fish-meal and fish-oil production in 2001	13
Table 2.1: Treatment of hides and skins undertaken at slaughterhouses	40
Table 2.2: The relationship between rendering/fat melting system and the quality of fat produced	50
Table 2.3: Summary of rendering processes allowed under ABP Regulation 1774/2002/EC – for detailed information on what is required, permitted and prohibited, see the legislation.....	51
Table 2.4: Typical product quantities after rendering 1000 kg of various slaughterhouse by-products	53
Table 2.5: Commonly used rendering and fat melting systems	55
Table 2.6: Relative efficiencies of fat removal at the end of the batch dry rendering process	55
Table 2.7: Typical liming process schedule.....	68
Table 2.8: Fat, moisture and ash composition of meat and bone meal	85
Table 2.9: Composition of meat and bone meal	86
Table 2.10: Optimum MBM composition (% mass dry) for gasification and thermal oxidation	87
Table 2.11: Typical chemical composition of syngas produced by the gasification of MBM.....	87
Table 2.12: Reported biogas composition from the biodegradation of unspecified animal by-products.....	90
Table 2.13: Summary of technologies for treating slaughterhouse waste water emissions	96
Table 3.1: Consumption and emission data for cattle slaughter	104
Table 3.2: Consumption and emission data for pig slaughter	105
Table 3.3: Consumption and emission data for sheep slaughter.....	106
Table 3.4: Consumption and emission data for poultry slaughter.....	107
Table 3.5: The range of air emissions from 3 Finnish slaughterhouses	108
Table 3.6: Estimated distribution of water consumption in some large Danish pig slaughterhouses	109
Table 3.7: Estimated distribution of waste water pollution in a Danish cattle slaughterhouse	110
Table 3.8: Estimated distribution of water consumption in a Norwegian sheep slaughterhouse	110
Table 3.9: Estimated distribution of water consumption in some Danish poultry slaughterhouses.....	111
Table 3.10: The distribution of water consumption reported for a Finnish slaughterhouse.....	111
Table 3.11: Sources of energy consumption at a large Danish pig slaughterhouse	112
Table 3.12: Sources of energy consumption at a Danish cattle slaughterhouse.....	113
Table 3.13: Distribution of electricity consumption in a Danish cattle slaughterhouse.....	113
Table 3.14: Distribution of heat in a Danish cattle slaughterhouse	113
Table 3.15: Estimated distribution of water temperature requirements at Danish poultry slaughterhouses	113
Table 3.16: The distribution of energy consumption in poultry slaughterhouses in the Nordic countries.....	114
Table 3.17: Calculated/estimated emissions of copper and zinc, from Danish slaughterhouses	115
Table 3.18: Specific waste water amounts and pollutant loads with and without de-sliming of bowels	118
Table 3.19: Summary of water requirements for immersion chilling of poultry	120
Table 3.20: Reduced consumption of water and detergents achieved without loss of cleanliness	121
Table 3.21: Quantities of detergent used in Danish pig slaughterhouses.....	122
Table 3.22: Typical discharge levels from slaughterhouse WWTPs	124
Table 3.23: The range of air emissions from two Finnish rendering plants.....	124
Table 3.24: Data for untreated waste water in a rendering plant - seasonal differences	126
Table 3.25: Energy consumption for a dry rendering process	126
Table 3.26: Energy consumption for a plant using the “Atlas” rendering process	127
Table 3.27: Energy consumption data from Finnish rendering plants	127
Table 3.28: Comparison of two types of rendering systems	128
Table 3.29: Summary of energy data from rendering plants	128
Table 3.30: Average consumption and emission data per tonne of raw material treated - four dry rendering plants processing 515000 t/yr.....	130
Table 3.31: Consumption and emission data for dry rendering - feedstock unspecified	132
Table 3.32: Consumption and emission data for blood rendering	133
Table 3.33: Data from 6 rendering plant WWTPs, applying nitrogen elimination.....	134
Table 3.34: Consumption and emission data for feather/hair rendering.....	135
Table 3.35: Consumption and emission data reported from fish-meal and fish-oil manufacturing plants.....	137
Table 3.36: Emissions per tonne of processed raw material from a Danish fish-meal factory	138

Table 3.37: Consumption and emission data reported from blood processing plants	139
Table 3.38: Consumption and emission data for bone processing	140
Table 3.39: Waste water emission limits for individual gelatine factories.....	142
Table 3.40: Achieved emission levels from animal carcase incineration, before WID Council Directive 2000/76/EC	143
Table 3.41: Direct air emissions from an animal carcase incinerator (no energy recovery)	143
Table 3.42: Raw emission data for the incineration of MBM in a BFB incinerator.....	144
Table 3.43: Consumption and emission data from an installation incinerating 50000 t/yr MBM	145
Table 3.44: Direct air emissions from incinerating MBM (no energy recovery)	145
Table 3.45: Total amino acid residues reported in fly ashes from BFB incinerators incinerating MBM.	146
Table 3.46: Emission data from burning animal fat in a heavy fuel boiler	146
Table 3.47: Analysis of animal fat	147
Table 4.1: Format of information about techniques for consideration in the determination of BAT	151
Table 4.2: Water losses from leaking taps, running hoses and toilets	165
Table 4.3: Energy management matrix	172
Table 4.4: Summary of costs and savings associated with environmental improvements	174
Table 4.5: Summary of main energy saving features in a modified cold store	179
Table 4.6: Comparison between the volumes of binary ice and brine required to achieve a 3 °C decrease in temperature	181
Table 4.7: Annual energy and cost savings per hose from lowering the water temperature from 71 °C..	184
Table 4.8: Storage requirements for animal by-products in the Flemish region of Belgium	187
Table 4.9: Reference values for the size and rating of biofilters	194
Table 4.10: Emission reductions achieved using unspecified biofilters in a German rendering plant	195
Table 4.11: Performance figures for a pasteurised worm compost biofilter in a fish-meal and fish-oil processing plant	195
Table 4.12: Purification performance of a flotation plant during production and cleaning.....	217
Table 4.13: Purification performance of a flotation plant using precipitation and flocculation agents	217
Table 4.14: Influent/effluent data – for preliminary mechanical/physical-chemical waste water treatment after rendering.....	217
Table 4.15: Cost and maintenance requirements for DAF treatment - (750 m ³ /d effluent)	218
Table 4.16: Influent and effluent data from an anaerobic waste water pretreatment plant.....	222
Table 4.17: Dimensional and operating data of the aerobic treatment stage at a rendering plant	224
Table 4.18: Influent and effluent levels achieved during the period 1992 - 1996	224
Table 4.19: Dimensional and operating data of the aerobic treatment stage at a slaughterhouse.....	225
Table 4.20: Data from a waste water treatment plant of a slaughtering plant in Germany	225
Table 4.21: Operational data for automated splitting of pig breasts.....	228
Table 4.22: Operational data for automated splitting of pig carcasses	228
Table 4.23: Operational data for automated evisceration of pigs – existing slaughter-line.....	228
Table 4.24: Operational data for automated evisceration of pigs – new slaughter-line.....	228
Table 4.25: Operational data for removal of plucks and viscera	229
Table 4.26: Operational data for automated back finning of pigs	229
Table 4.27: Expected effect of installing decontamination by spraying with hot water.....	229
Table 4.28: Operational data for rectum loosening pigs	229
Table 4.29: Reduced emissions associated with cooling of blood prior to rendering	234
Table 4.30: Comparison of consumption data of different scalding methods (producers' information)..	254
Table 4.31: Comparison of actual consumption data of “water circulation spray scalding” and “condensation scalding”	254
Table 4.32: Comparison of water consumption data for different scalding methods (producers' information)	255
Table 4.33: Consumption data for shock-cooling and mist-cooling.....	263
Table 4.34: Reduction in production shift waste water contamination, due to removal of the washer blades	266
Table 4.35: Annual cost savings associated with removal of the washer blades.....	267
Table 4.36: Cyclonic vacuum cleaner specifications	288
Table 4.37: Operational data for a SBR at a poultry slaughterhouse pilot plant	292
Table 4.38: Operational data for a SBR at a 40 m ³ /d poultry slaughterhouse	293
Table 4.39: Operational data for a SBR at a 100 m ³ /d poultry slaughterhouse	293
Table 4.40: Operational data for a SBR at a 470 m ³ /d poultry slaughterhouse	293
Table 4.41: Reported selling prices of SBR treatment plants in 6 slaughterhouses	294
Table 4.42: Economic analysis of biotechnological treatment of slaughterhouse waste.....	299
Table 4.43: Data of a stripping plant for ammonium (average values - daily mixed samples)	309
Table 4.44: Reported performance data for a biotrickling installation.....	311
Table 4.45: Operational data for a case study rendering plant using a thermal oxidiser	314

Table 4.46: Cost elements for replacing an existing boiler with a thermal oxidiser	314
Table 4.47: Consumption, emission and economic data for a thermal oxidiser for the combustion of vapour, non-condensable gases and room air in rendering.....	315
Table 4.48: Effluent production during the 2001 financial year.....	320
Table 4.49: Average effluent concentrations	320
Table 4.50: Contamination loads in waste water from a fish-meal/fish-oil factory, before substitution of seawater by condensate in an air scrubber	326
Table 4.51: Reductions in emissions to sea from a fish-meal/fish-oil factory, due to substitution of seawater by condensate in an air scrubber	326
Table 4.52: Emission levels associated with the dedicated incineration of MBM in a fluidised bed incinerator	343
Table 4.53: Analysis of fly ash from BFB incineration of MBM for amino acids	344
Table 4.54: Analysis of bed ash from BFB incineration of MBM for amino acids	344
Table 4.55: Emissions incinerating 100 % animal meal in a circulating fluidised bed.....	346
Table 4.56: Analysis of ashes from a rotary kiln incinerator dedicated to the incineration of SRM comprising cattle heads and vertebral columns.....	347
Table 4.57: Energy, heat and economic data for biogas/CHP units using (or planning to use) manure and fat containing waste on Danish farms	358
Table 5.1: Emission levels associated with BAT for minimising waste water emissions from slaughterhouses and animal by-products installations.....	376
Table 5.2: Emission levels associated with the dedicated incineration of animal by-products in either bubbling fluidised bed, circulating fluidised bed or rotary kiln incinerators.....	381

SCOPE

The IPPC Directive

This document reflects an exchange information about the activities listed in Annex I, paragraphs 6.4.(a) and 6.5. of the IPPC Directive, i.e.

6.4.(a) Slaughterhouses with a carcase production capacity greater than 50 tonnes per day and

6.5. Installations for the disposal or recycling of animal carcasses and animal waste with a treatment capacity exceeding 10 tonnes per day

Some processes are covered in this document because they are associated activities of 6.4.(a) even though on first examination they would more obviously be 6.5. processes, but they fall below that threshold.

Slaughterhouses

The document covers the slaughter of all animals that might contribute to the overall output of an IPPC installation, even if it is unlikely that one installation would, for a given animal, fulfil the threshold requirements of Annex 1 of the Directive.

The “slaughter” activity is considered to end with the making of standard cuts for large animals and the production of a clean whole saleable carcase for poultry. Directly associated activities of the slaughter process are included. The degree of cutting of large animals in slaughterhouses is limited by legislation [169, EC, 1991].

Disposal and recycling of animal carcasses and animal waste

In recent years there has been a change in the terminology used to describe outputs from slaughterhouses. The term “by-product” is being used increasingly and it is widely used in this document. The word “waste” is only used in the document when referring to disposal activities.

The animal by-products activities covered include treatments for entire bodies or parts of animals and those for products of animal origin. These activities include treatments of animal by-products both intended and not intended for human consumption.

Some of the processes covered are both 6.5. activities and 6.4.(a) “directly associated activities”. Some 6.5. activities are included because the aggregated capacities of more than one activity in some cases bring an installation up to the IPPC threshold. This can vary in any given installation because the proportion of “animal carcasses and animal wastes” used in the various process streams can change and is dependant on market forces.

A wide range of by-products activities are covered in the BREF. These include fat melting; rendering; fish-meal and fish-oil production; bone processing; blood processing associated with slaughterhouses and to the degree where the blood becomes a material for use in the preparation of another product. The dedicated incineration of carcasses, parts thereof and MBM and burning of tallow, are covered principally as routes for disposal. Land spreading; land injection; biogas production; composting; preservation of hides and skins for tannery use, in slaughterhouses and gelatine manufacture are also covered. Landfill is not covered, except when mentioned as a route for disposal.

Another BREF in the series, i.e. the “Food drink and milk” BREF [328, EC, 2003] covers the production of food products downstream of those covered by this document. The relevant activities covered in that BREF are listed in Annex I, paragraphs 6.4.(b) of the IPPC Directive, i.e.

6.4.(b) Treatment and processing intended for the production of food products from: - animal raw materials (other than milk) with a finished product production capacity greater than 75 tonnes per day

Activities after the standard cuts are made (except chilling at slaughterhouses) may be covered by the “Food, drink and milk” BREF.

Where animal by-products are disposed of or recycled within another industry, BAT for those activities comes within the scope of the relevant BREF for that industry.

Hides and skins which are by-products of the slaughter process may be destined for processing in tanneries. The reader’s attention is drawn to the “Tanning of hides and skins” BREF [273, EC, 2001].

1 GENERAL INFORMATION

1.1 The slaughtering industry in the European Union

The slaughtering industry throughout the EU is diverse with many different national characteristics. There does, however, appear to be a trend towards fewer slaughterhouses with increasing average throughputs. All MSs have to comply with common hygiene and structural standards [99, EC, 1964, 169, EC, 1991] and it is widely believed that this is the reason for the increased consolidation of slaughtering into fewer and larger installations [57, DoE, 1993, 127, MLC Economics, 1999].

Table 1.1 shows the number of cattle, pigs, and sheep (including goats) slaughtered by species, for all MSs in 1998. To enable comparisons, the MLC has calculated total slaughter on the basis of GB cattle units. They have defined a GB cattle unit, as follows:

1 GB cattle unit = 1 cattle beast or 3 calves or 5 sheep or 2 pigs

(This differs from the definition given in Council Directive 91/497/EEC, which refers to livestock units as follows: bovines and solipeds = 1.0 livestock unit; pigs = 0.33 livestock units and sheep = 0.15 livestock units [169, EC, 1991]. Interestingly, this definition is used even though the average slaughter weights of some species vary significantly between MSs, sometimes by a factor as high as 100 %.)

	Adult cattle	Calves	Sheep ⁽¹⁾	Pigs	Total expressed in GB cattle units	% change 1998/87 ⁽²⁾
	' 000	' 000	' 000	' 000	' 000	
Belgium	612	311	203	11531	6523	+ 22
Luxembourg	21	3	-	129	87	-5
Denmark	615	50	66	20960	11125	+ 24
Germany	4126	485	2151	41352	25394	-
Greece	225	82	11993	2241	3772	-4
Spain	2331	133	21963	33428	23482	+ 64
France	3858	1984	8639	26567	19531	+ 9
Ireland	1899	7	4067	3339	4384	+ 40
Italy	3317	1099	7806	12571	11530	+ 3
Netherlands	1039	1373	650	19277	11266	+ 1
Austria	550	135	366	5359	3348	nc
Portugal	264	118	1271	4954	3034	+ 52
Finland	372	14	61	2195	1487	nc
Sweden	480	46	159	3962	2508	nc
United Kingdom	2297	32	18698	16286	14191	-6
EU-15	22005	5872	78092	204151	141656	+ 12
⁽¹⁾ Includes goats						
⁽²⁾ Comparison made on the basis of GB cattle units (cattle beast or 3 calves or 5 sheep or 2 pigs)						
nc No comparison						

Table 1.1: Numbers of cattle, sheep and pigs slaughtered in the EU in 1998
[127, MLC Economics, 1999]

Table 1.1 shows that Germany accounted for the largest share of EU slaughter, i.e. 18 % of the total, followed by Spain with 17 % and then France with 14 %.

Between 1987 and 1998 the numbers of animals slaughtered in the EU, based on GB cattle units, rose by about 12 %. Most of the increase occurred in pig and to a lesser extent, sheep slaughtering. Overall, cattle and calf slaughter fell. Spain and Portugal were responsible for much of the increase. Both of these countries were new EU members in 1987, and since then their livestock industries have expanded rapidly. Spain has increased in all parts of the industry.

In Portugal the increase has been greatest for pigs, with cattle slaughter actually falling in that period.

Although Germany slaughtered more animals than the other EU countries, its total in 1998 was more or less unchanged compared with its 1987 number. The Netherlands also showed little change. It had recently slaughtered fewer pigs, following the introduction of environmental measures to reduce the pig herd and problems with swine fever outbreaks. The drop in numbers of animals slaughtered in the UK was primarily due to fewer cattle being slaughtered because of BSE.

In 1999 the largest cattle slaughterhouse groups in the EU, comprised 4 companies in France and Germany, which together accounted for 11 % of the EU kill. Pig slaughtering was even more concentrated, being dominated by two large groups in Denmark, which between them slaughtered 8 % of the EU total. These two groups have since merged. France dominated the poultry slaughter industry, with its two largest groups accounting for 14 % of EU slaughter.

Some slaughterhouses have on-site animal by-products processing activities. ABP Regulation 1774/2002/EC sets out the rules for preventing cross contamination. This is achieved by various requirements covering segregation, hygiene and record keeping.

Belgium

Pig slaughtering dominates the Belgian industry and accounts for practically all the expansion in slaughter in the period 1987 to 1998. However, the industry is fragmented and profitability is poor.

No company slaughters more than one million pigs per year. Several of the country's largest meat processing companies belong to international groups.

Of the EU-accredited slaughterhouses in Belgium there are 21 for slaughtering pigs exclusively, 2 for cattle and/or calves exclusively and 42 for slaughtering poultry. In addition, there are 41 EU-accredited slaughterhouses for slaughtering pigs and other animals, 46 that slaughter other animals in addition to cattle and/or calves and 80 poultry slaughterhouses with an annual slaughtering capacity of fewer than 150000 birds.

In Flanders, slaughterhouses are typically SMEs employing fewer than 50 people. Demand has been falling in recent years for beef and pork, but exports are increasing, mainly to other EU countries. [346, Belgian TWG member, 2003]

Denmark

The majority of pig and cattle slaughterhouses in Denmark are co-operatively owned. Pig slaughtering is dominant. The industry is very concentrated, due to a round of amalgamations and company take-overs during the 1980s. The largest slaughter company operating in Denmark in 1997 had 12 slaughter units, accounting for around half the national kill. At this time, it was the largest pig slaughter group in the EU and ranked second or third in the world. It has since merged with the second largest company, which also previously ranked amongst the world's top ten.

The resultant company operates 5 cattle slaughterhouses and slaughters more than 60 % of Danish cattle. One cattle slaughterhouse also slaughters approximately 20000 lambs per year on a separate line. The remaining sheep and lambs are slaughtered in a large number of plants. Previously one of these companies accounted for 38 % of cattle slaughter in Denmark and was ranked eighth in size in the EU. It operated out of both Denmark and the UK. Its market share is even greater now.

Generally, Danish poultry slaughterhouses are privately owned. Two companies each slaughter 40 % of the total national kill, i.e. about 25 million chickens each per year and six others slaughter between 9 and 13 million each.

Germany

Germany is the EU's largest slaughterer of both cattle and pigs. In 1987 there were estimated to be 350 slaughterhouses in West Germany alone. In 1995 there were 268 EU approved slaughterhouses. In 1997, there were 200 slaughterhouses employing more than 20 people. Several thousand more reportedly operate under the "Kleinbetrieb Regelung", i.e. slaughtering up to 20 GB units a week.

Germany's prime position within the EU is reflected in the fact that 3 of its companies are ranked high in terms of cattle slaughter, occupying the third, fourth and tenth positions for EU cattle slaughter. The company that is ranked tenth biggest for cattle slaughter is also the EU's third largest pig slaughterer. Germany also has the EU's eighth largest pig slaughtering company. Three of the largest companies are producer co-operatives.

An overview of the economic position of slaughterhouses in Germany is given in Table 1.2.

	Slaughtering and meat processing (excluding poultry)		
	1997	1998	1999
Number of companies	200	219	228
Staff per company	83	75	76
Staff total	16668	16459	17430
Turnover (DEM million) (exclusive of VAT)	14122.9	12532.1	12693.4
Turnover per company (DEM million)	70.4	57.2	55.7
Export ratio (%)	8.8	10.6	11.0

Table 1.2: Number of slaughterhouses (excluding poultry) in Germany, with turnover data for 1997 - 1999

[163, German TWG Members, 2001]

Spain

The numbers of cattle, sheep and particularly pigs slaughtered in Spain have all grown in the ten years to 1999, following the accession of Spain to the EU. One of the largest slaughter companies controls about 12 % of the Spanish market.

France

In the ten years between 1987 and 1997, the slaughter of cattle, calves and sheep all decreased in France but the numbers of pigs slaughtered rose. The number of slaughterhouses decreased from 602 in 1986 to 344 in 1997, but the average throughput size rose. One of the main characteristics of the French industry is the continuing importance of public slaughterhouses, even though practically all of the decline in slaughterhouse numbers has been in the public sector and their average throughput is lower than the private sector. They still account for more than half of the slaughterhouse numbers.

In 1997, there were 187 public slaughterhouses and 157 private slaughterhouses in France. Public slaughterhouses dominate in the smaller size group, whereas the private sector has more in the larger size group.

There has been a reduction in the number of slaughterhouses for all species, implying that the average throughput has increased across the board. The rise in the number of pigs slaughtered, however, means that pig slaughter has become particularly concentrated.

For cattle slaughter, France has the two largest groups in the EU, and between them they account for about half of the French national kill.

Ireland

The slaughtering of all species in Ireland grew between 1987 and 1997. This was carried out by a relatively small number of companies, many of which also own considerable business in the UK. The biggest player in cattle slaughter has an estimated 22 % of the total Irish kill and is also a substantial player in the UK.

There is a small number of major companies operating in cattle slaughter, where there is over-capacity. This has been influenced by a decline in cattle numbers and the gradual removal of intervention as a major market. In 1998, Forbairt, an Irish Government development agency, sponsored a rationalisation scheme. This was essentially an industry funded buy-out scheme. By 1999 it had not resulted in any major re-structuring, reportedly due to a lack of interest from the industry in the amount of compensation that was being offered to reduce slaughter capacity.

One company in particular has a large interest in the Irish pig industry, controlling about 42 % of slaughter.

Italy

In the last twenty years there has been a gradual decrease in red meat slaughterhouses in Italy [161, Italy, 2001]. The slaughter industry is highly fragmented, particularly for pigs. In cattle slaughter, five groups account for about 39 % of the national total. The five leading pig slaughtering companies account for only 16 % of the national kill. None of these slaughter more than 500000 pigs a year.

All Italian pig slaughterhouses over the IPPC threshold kill pigs for typical Italian cured products, such as ham and salami. Only pigs with an average live weight higher than 160 kg and a minimum carcase weight of about 130 kg are killed. The main difference between Italian pig slaughterhouses and others is that all the carcasses are split to portions of maximum weight 15 kg, before cooling or chilling. [331, Italy, 2003]

Netherlands

In 1987, the Netherlands had the third highest pig kill in the EU, after Germany and France. In the early 1990s measures were introduced to reduce the number of pigs held, because of environmental concerns, but then in 1997, a swine fever epidemic led to the destruction of millions of animals. Pig slaughtering has, therefore, been cut significantly and this has in turn led to a reduction in the number of companies slaughtering pigs. In 1987, the number of slaughterhouses slaughtering more than 25000 pigs annually was 55. By 1997, this had fallen by half to 27. Since then it has dropped even further due to the slaughter capacity being concentrated in fewer and larger plants [240, The Netherlands, 2002].

By 1995, the problems of over-capacity in cattle and pig meat slaughter led to efforts, on behalf of the industry, for rationalisation by closing plant capacity. By 1997, it was estimated that 15 % of the capacity from the Dutch slaughter/processing industry, had been removed. At the same time two co-operatives in the meat industry were merged to form a new farmers company. This new company is a slaughtering, trading and meat processing business. It produces 650000 tonnes of pig meat each year from 6 - 7 million pigs, equivalent to 40 % of the Dutch kill and 35000 tonnes of cattle.

It is anticipated that the production of pigs, poultry and cattle may fall even further over the coming years due to a programme by the Dutch agriculture ministry to tackle phosphate pollution from the farming industry [170, ENDS Daily, 2001].

Austria

The biggest Austrian slaughter group slaughters 500000 pigs and 85000 head of cattle a year. Three companies process nearly 20 % of all Austrian meat products.

130 out of the 4900 cattle, pig and small ruminant slaughterhouses are EU-approved. Slaughterhouses that are not EU-approved operate under the "Kleinbetrieb Regelung", i.e. slaughtering up to 20 GB units a week. [348, Austrian TWG member, 2003]

UK

In Great Britain, between the years 1987/1988 and 1998/1999 the numbers of slaughterhouses decreased from 919 to 416. Over the same period the market share of slaughterhouses killing over 50000 GB cattle units per year increased from 59 % to 78 % and those killing more than 100000 rose from 30 % to 56 %. Concentration has increasingly taken place, especially in pig slaughtering, but also to a lesser extent in sheep slaughtering and less still in cattle slaughtering.

EU funding of red meat slaughterhouses in the late 1970s and early 1980s contributed to overcapacity. Low profit margins then led to cheap sales, resulting in low cost takeovers and mergers, many of which involved investment from Ireland. Capacity has to some extent been restricted as a consequence of new temperature requirements for fresh meat, which require filled refrigeration space and increased regulatory inspection, which has slowed down slaughter-line speeds.

Conglomerates of medium-sized slaughterhouses have been replaced by groups controlling large slaughterhouses, which are closely controlled by the main customers, i.e. supermarkets. Many of the top ten plants have also been investing in integrated slaughter, cutting, deboning and in some cases further processing plants.

Finland

Most of the large slaughterhouses in Finland are privately owned, although 77 % of pig slaughter and 65 % of cattle slaughter is carried out by co-operatives. Sheep slaughter is limited in Finland and is always done on the same slaughter-lines as cattle. [134, Nordic States, 2001]

There are 10 slaughterhouses in Finland with a carcase production capacity greater than 50 tonnes per day. Together these slaughter about 83 % of the total in Finland. There are also a number of smaller slaughterhouses. The processes and the type of animals being slaughtered vary a lot. The main animals slaughtered are pigs, cattle, chicken, and turkeys. [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

Sweden

One Swedish co-operative group dominates both the cattle and pig slaughter industries, accounting for 76 % of the country's cattle throughput and 79 % of the pig throughput. It is the EU's ninth largest cattle slaughter group and its seventh largest pig slaughter group. There is a slight trend towards private slaughterhouses and away from co-operatives [134, Nordic States, 2001].

Generally Swedish poultry slaughterhouses are privately owned. Their total production is 65 million chickens per year, 99 % of which are slaughtered by companies belonging to one organisation [134, Nordic States, 2001].

Norway

In Norway there is a low animal density, so most of the slaughterhouses are small compared to other countries. The supply market is divided between one producer owned company and a number of private slaughterhouse companies. The producer owned company owns a number of subsidiary slaughter companies, which together slaughter about 75 % of the total. The low animal density also means that very few of the 55 or so slaughterhouses slaughter only a single species. [134, Nordic States, 2001]

The numbers of slaughterhouses, the numbers of animals slaughtered, the average live weights and average carcase weights for the MSs and some PACs are summarised in Table 1.3.

Country	Species	No of slaughter-houses	No of animals slaughtered each year	Average live weight (kg)	Average carcase weight (kg)
Belgium [127, MLC Economics, 1999, 136, Derden A, 2001, 242, Belgium, 2002, 346, Belgian TWG member, 2003]	Cattle	48	923000	670	410
	Sheep		203000	42	21
	Pigs	62	11531000	120	93
	Poultry	42	276520055	2.15	1.4
Denmark [132, Thy-Christensen, 2001, 134, Nordic States, 2001]	Cattle	13	650000	450	250
	Sheep	1	74000		33
	Lambs				21
	Pigs	24	21000000	100	77
	Chickens	6	136600000	1.8	(chicken + giblets) 1.4
	Turkeys	1	1000000		9.9
	Ducks		1750000		
Germany [127, MLC Economics, 1999, 163, German TWG Members, 2001]	Cattle		4611000		321
	Sheep		2151000		20
	Pigs		41352000		92
Greece [127, MLC Economics, 1999]	Cattle		307000		
	Sheep		11993000		
	Pigs		2241000		
Spain [69, AINIA, 2000, 70, AINIA, 2000, 127, MLC Economics, 1999, 271, Casanellas J., 2002]	Cattle	128 (production cap > 50 t)	2464000		
	Sheep	included in cattle	21963000		
	Pigs	included in cattle	33428000		85
France [127, MLC Economics, 1999]	Cattle		5842000		
	Sheep		8639000		
	Pigs		26567000		
Luxembourg [127, MLC Economics, 1999]	Cattle		24000		
	Pigs		129000		
Netherlands [127, MLC Economics, 1999]	Cattle		2412000		
	Sheep		650000		
	Pigs		19277000		
Austria [348, Austrian TWG member, 2003]	Cattle		598445	638	339
	Sheep		83808	49	23
	Pigs		5274285	118	95
Portugal [127, MLC Economics, 1999]	Cattle		382000		
	Sheep		1271000		
	Pigs		4954000		
Ireland [127, MLC Economics, 1999, 215, Durkan J., 2001]	Cattle		1906000	330	
	Sheep		4067000		
	Pigs		3339000		
Italy [127, MLC Economics, 1999, 137, Leoni C., 2001, 248, Sorlini G., 2002]	Cattle		4416000		270
	Sheep		7806000		
	Pigs		12920465	143	130
Finland [127, MLC Economics, 1999, 134, Nordic States, 2001, 148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]	Cattle	5	103000	470	260
	Sheep and goats		61000		16
	Pigs	3	756000	100	82
	Mixed species (named)	10	Cattle 270000 Pigs 1390000		255
	Chickens	4	43800000	1.9	1.4

Country	Species	No of slaughter-houses	No of animals slaughtered each year	Average live weight (kg)	Average carcass weight (kg)
Sweden [134, Nordic States, 2001]	Cattle	15	518000	530	290
	Sheep	10	187000		sheep 25
	Lambs				lambs 19
	Pigs	16	3900000	110	84
	Chickens	6	69300000	1.8	1.3
	Turkeys		200000	15	
	Ducks		57000		
	Geese		30000		
United Kingdom [12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000, 127, MLC Economics, 1999]	Cattle	376	2329000		(England and Wales) 263
	Sheep	included in cattle	18698000		(England and Wales) 18
	Pigs	included in cattle	16282000		(England and Wales) 51
	Mixed species	included in cattle			
	Chickens	130	(England and Wales) 780000000		4
	Turkeys	included in chickens	(England and Wales) 24000000		5
Norway [134, Nordic States, 2001]	Cattle	55	353725		cattle 263 calves 81
	Sheep	included in cattle	1156065		18
	Pigs	included in cattle	1324571		80
	Mixed species	included in cattle			
Slovenia [143, Skodlar M., 2001]	Cattle	5	127128	484	261
	Sheep				
	Pigs				
	Mixed species	5	500000	104	82
	Chickens	2	21000000	2	1.5
	Turkeys	1	90000		
Czech Republic					
Hungary					
Malta					
Latvia [312, Latvia TWG, 2002]	Cattle		46248	300	140
	Sheep/goats		953	50	25
	Pigs		211211	100	60
	Horses		144		
	Rabbits		399		
	Poultry		3101222	2	1.2
"Cattle" includes calves where calves are not reported separately "Sheep" includes goats where goats are not reported separately "Chickens" includes hens					

Table 1.3: Numbers of slaughterhouses, animals slaughtered and associated live/carcass weights in Europe
(Sources listed in column 1)

Trends which may influence future resources in the slaughtering industry

The following view is a summary of information reported by the Nordic countries [134, Nordic States, 2001].

Main tendencies

There are some clear general tendencies, which may influence the future consumption of resources in the slaughtering industry. These are: the trend for larger and larger units; the

increasing demand for better food safety; the increasing focus on animal welfare; the growing requirements for good eating quality; the need to improve the working environment and the increasing level of processing required to produce ready-to-eat-food.

Larger installations

Production is progressively being concentrated in fewer and larger plants. For individual plants, the larger units might, in theory, be expected to result in lower consumption per unit. However, in practice this is not the case. An analysis of the Norwegian and Danish meat and poultry slaughter plants has shown no significant difference between large and small plants. It is claimed that it is easier and cheaper, per unit, to solve environmental problems by odour abatement and waste water cleaning at large plants. There are some notable exceptions to this trend, towards larger plants e.g. in Austria the trend has been towards smaller slaughterhouses, due to stricter animal transport regulations and consumer pressure [348, Austrian TWG member, 2003].

Food safety

The occurrence of *Salmonella*, including the multiresistant strain DT 104; *Listeria*; VTEC (0157) and other microbiological contaminants in meat products, plus the BSE crisis, have created a strong focus on food safety. This has led to increased hygiene requirements at slaughterhouses and as a consequence a higher intensity of cleaning and sterilisation operations. This in turn leads to an increased consumption of water and energy. Increasing quantities of water at 82 °C are now consumed for the sterilisation of knives and other tools. Showering cabinets are now available for showering pig or cattle carcasses with hot water, typically using 40 litres per pig carcass. An increased use of such systems could result in a significant increase in water and energy consumption. Cleaning chemicals are also used in greater amounts [237, Italy, 2002, 240, The Netherlands, 2002].

Lower temperatures may be demanded where meat is handled and a safer and more effective cool chain from the slaughterhouse to the consumer may be required. All this could increase energy consumption. Increased hygiene requirements may also result in increased packaging and even new types of packaging [241, UK, 2002].

Prohibiting the feeding of “processed animal proteins” to farmed animals, i.e. those kept fattened or bred for the production of food, due to the BSE crisis has changed the concept of what is waste and what may have a further use. This may change further, in the future.

Animal welfare/ethics

Animal welfare issues influence stunning methods. Examination of the safety and ethics of feeding animals to animals has led to a reduction in the use of animal by-products in animal feed and an increase in the amounts disposed of as waste.

Eating quality

The growing requirement for good eating quality is receiving increasing attention. In pig slaughter, for example, careful control of carcass chilling processes can improve the tenderness of meat. To decrease the frequency of PSE, it is important to chill warm pig carcasses as soon as possible after slaughter. It has been reported that the reduction of water consumption on the slaughter-line, e.g. in de-hairing machines, after singeing and in scraping/polishing machines, has slowed down the temperature decrease in the carcasses on the slaughter-line. It has, therefore, been suggested that carcasses should be showered with a large volume of cold water before being opened.

Working environment

To preserve the health of the employees and to attract sufficient good labour to the industry, it is necessary to avoid heavy lifting, repetitive working operations and arduous operations. This is leading to the automation of some tasks. If there is a lack of available labour, this will also speed up the introduction of automation. Automated equipment requires energy for its operation and in, e.g. Italy, there is a requirement for cleaning and sterilisation between each carcass, if the meat is destined for export to the US [237, Italy, 2002]. In any case the

equipment must be cleaned and sterilised several times a day and always at the end of each working day [99, EC, 1964] as a minimum, although it is actually recommended between each carcass. Efficient washing and sterilisation require training [241, UK, 2002], supervision and the maintenance of equipment [241, UK, 2002], as well as the use of considerable quantities of both cold and 82 °C water.

Improved lighting and ventilation in working areas also consumes energy. In many cases, the environment in the lairage will often have to be improved for both the staff and the animals by, e.g. increased ventilation to remove dust, and by the showering of pigs.

Processing

The degree of processing of meat products is increasing at the moment, due to the demand for products which can be prepared quickly and simply. This means that meat processors now carry out a higher level of processing and packaging, usually combined with chilling and freezing. Processing and packaging are not within the scope of this document, but they will be associated activities on many slaughterhouse sites.

Other considerations

The best possible utilisation of gut sets from pigs (those from ruminants are SRM), may be in conflict with the wish to reduce water consumption and pollution. There is a tendency not to clean intestines, or parts of the gut sets, if a reduction in water usage or pollution of the waste water is required. The cooling of blood for rendering is becoming more common and the cooling of other raw materials for rendering, e.g. those from the slaughter-line, is being discussed. This demands a considerable amount of energy, but does provide other advantages, such as better products and less air and water pollution.

Changes in the EU agricultural support scheme could result in changes in capital availability/profitability in the meat industry. When there is only a limited amount of money available for capital investments, it has been forecast that there would be a tendency for it to be used for production improvements, rather than for environmental purposes, even when the latter have a short repayment period. It has also been anticipated that investments in environmental improvements will probably, to an increasing extent, be for odour and noise abatement, due to local community pressures. It is perceived that reducing odour problems leads to increases in energy consumption, e.g. to overcome the pressure drop in ducts, chimneys and filters and to move large volumes of air. Many cleaning systems also require the use of water and chemicals.

Technical characteristics of slaughterhouses

Large animal slaughterhouses can, in general, be classified into two groups. The first group carries out slaughterhouse operations only, i.e. they slaughter, dress and chill carcasses for sale to wholesalers. The second group does the same operations, but also operates cutting plants to produce specific meat cuts and portions, both on- and off-the-bone. These are then packed as chilled or frozen meat for sale to wholesalers and retailers [57, DoE, 1993], or sent to processing plants [331, Italy, 2003]. Most poultry processors carry out slaughtering, cutting and portioning at the same site. There is a trend for slaughterhouses to expand to produce value-added products, such as diced meat and mince and to diversify into further processing. This requires large investments, which often only the bigger, multinational companies can make. [127, MLC Economics, 1999]. Concentration of the industry into fewer larger units may, therefore, further increase.

Where downstream activities and/or disposal or recycling of animal by-products take place on the same premises as slaughtering, it will be possible to consider opportunities to reduce consumption and emission levels on the integrated site as a whole. This may require other BREFs in the IPPC series to be taken into account when determining BAT-based conditions for IPPC permits.

Many process lines are automated. Throughputs of, e.g. 80 cattle, 350 sheep and 300 pigs per hour are not uncommon. [57, DoE, 1993]. The throughput at a typical cattle or pig slaughterhouse is relatively constant throughout the year. For sheep slaughter, June and December are normally busy periods. [12, WS Atkins-EA, 2000]. Easter is a peak period for lamb slaughter due to Islamic traditions.

Poultry slaughter is very highly mechanised. Slaughtering rates of 100 birds per minute are common. Throughput is typically constant throughout the year [67, WS Atkins Environment/EA, 2000].

In general, the anticipated lifetime of a slaughterhouse plant is about 25 - 40 years. Slaughterhouses must meet the criteria and standards set down in Council Directive 64/433/EEC [99, EC, 1964], as amended. These include specifications for process plant design, building finishes [12, WS Atkins-EA, 2000] and hygiene considerations.

1.2 The animal by-products industry in the European Union

Introduction to the animal by-products industry

Animal by-products from slaughterhouses are sometimes known in the industry as the 'fifth quarter'. They include edible materials such as tongue, edible offal, edible fats and casings, as well as hides/skins and other non-food materials. In previous decades, these by-products provided a valuable source of slaughterhouse income. In recent years, especially because of BSE, the value of the fifth quarter materials has reduced substantially and much of the material previously used is now disposed of as waste. [12, WS Atkins-EA, 2000]

The animal by-products industry handles all of the raw materials that are not directly destined for human consumption and some that are destined for eventual human consumption. The use and disposal routes permitted are governed by ABP Regulation 1774/2002/EC. After processing, the raw materials may have several applications, e.g. food and feed, cosmetics, medicinal products and medical devices, technical products, fertilisers and many others. Many of the animal by-products used and disposed of are derived from healthy animals which have been slaughtered in slaughterhouses and whose carcasses have been found fit for human consumption following ante- and post-mortem inspection. [349, GME TWG members, 2003]. Due to food and feed safety concerns an increased proportion of such animal by-products are disposed of as waste.

Hides and skins are sold to the leather industry. Edible offal and fats are sold for direct use or inclusion in processed products. Inedible offal and fats are usually processed to produce animal meal and tallow. Some edible fats and trimmings are processed to produce lard and dripping [57, DoE, 1993]. The first flush of blood, e.g. from pigs, may be collected, for use as food, animal feed or pharmaceuticals.

Of the 47 million tonnes of animals slaughtered for meat production in Europe every year, 17 million tonnes, minus hides, skins and bones for gelatine production, are handled by the animal by-products industry. About 14 - 15 million tonnes [13, UKRA, undated, 24, EURA, 1997] are processed by renderers and fat melters. As society becomes more affluent and eating habits change the proportion of an animal eaten directly is less than ever before. The amount of by-product available for processing is, therefore, increasing. [24, EURA, 1997]. About half the tallow and animal fats produced are used by the oleochemical industries as raw materials for a wide variety of chemicals, which are then used in soaps, cosmetics, pharmaceuticals, detergents and a large range of industrial products, e.g. from paint to car tyres. Oils and fats produced by fat melters are used in the food industry, e.g. in baking and food processing; frying and margarine production. [24, EURA, 1997]

Considerable numbers of carcasses are also left to rot or are illegally dumped. [20, UKRA, 2000]. The burial of fallen animals is illegal in the Netherlands, Denmark, Germany and France. Authorised burial is allowed in Italy and Spain. In the UK, the burial of carcasses is allowed if DEFRA guidelines are followed and in line with EU rules implemented through national legislation.

In November 1991, the use of MBM produced from specified bovine offals as a fertiliser was banned in the UK [19, UKRA, 2000].

Until the BSE crisis, a high proportion of the solid end-products of rendering, i.e. the protein fraction, were important ingredients of animal feed. Feeding MBM to cattle, sheep or goats has now been banned within the EU since 1 July 1994. Since December 2002, the feeding of “processed animal proteins” to farmed animals, kept fattened or bred for the production of food, was prohibited, pending a total re-evaluation of Community legislation in MSs [88, EC, 2000]. The restrictions have led to an increased proportion of solid material being disposed of to landfill and by incineration. MBM has an energy content of about two-thirds that of coal, so energy can be recovered, as heat and/or power. The limits placed on the traditional uses for animal by-products have led to further alternative uses and to new routes for disposal being researched and developed. [22, UKRA, 2000]. These include, e.g. the combustion of MBM as an ancillary fuel for cement production [22, UKRA, 2000]; the burning of tallow as a fuel [22, UKRA, 2000]; biogas production [22, UKRA, 2000, 287, EC, 2002]; composting [287, EC, 2002]; biodiesel production [22, UKRA, 2000]; the use of MBM as fertiliser for non-grazing land [22, UKRA, 2000] and the use of fat as a fuel in turbines and engines [22, UKRA, 2000]. These alternatives are at various stages of development and under environmental and economic evaluation.

The ban remains in place at the time of writing.

1.2.1 Fat melting

Belgium

There are 3 installations in Belgium producing fat for human consumption [242, Belgium, 2002].

1.2.2 Rendering

Belgium

There are 5 rendering plants in Belgium processing Category 1, 2 and 3 animal by-products, either individually or mixed together [346, Belgian TWG member, 2003].

Denmark

Denmark has one rendering company which has 5 plants. The company is co-operatively owned by the slaughterhouses. In 2000/2001, it processed 750000 tonnes of animal by-products. All SRM is processed in one of the plants. [239, Denmark, 2002]

Germany

In 2000, the rendering plants operating in Germany disposed of a total of approximately 2.6 million tonnes of raw material. The number of companies in Germany, the raw material amounts they processed and their products in 2001 are reported in Table 1.4.

Number of companies	Processed amount (t)	Meat meal (t)	Meat and bone meal (t)	Blood meal (t)	Animal fat (t)
63	2600000	460000	214000	21000	310000

Table 1.4: Raw material processed in the German meat meal industry (2001)
[163, German TWG Members, 2001]

Finland

In Finland, approximately 200 million kg of animal derived by-products are generated annually. About 170 million kg, including slaughterhouse waste and waste from fur animal production, is considered to be low-risk material. High-risk material and SRM, from slaughterhouse waste and dead farm animals, each contribute about 15 million kg to the total animal by-product treatment industry.

There are two rendering plants in Finland approved for the treatment and the disposal and/or further recovery of the high-risk material and SRM. There are 14 plants with a treatment capacity greater than 10 tonnes per day, for the recycling of the low-risk material for further recovery as fur animal feed. Finland is among the biggest fur animal producers in the world, using an annual 370 million kg of fur animal feed, more than half of which are by-products from the meat and fish industry. [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

United Kingdom

In 2000, it was reported that 1.25 million tonnes of animal by-products were collected annually from UK red meat slaughterhouses to be incinerated or rendered and then landfilled [12, WS Atkins-EA, 2000], from a total of 1.75 million tonnes from cattle, sheep, pigs and poultry [13, UKRA, undated].

Slovenia

Slovenia has 3 rendering plants with a treatment capacity exceeding 10 tonnes per day [219, Skodlar M., 2002].

1.2.3 Fish-meal and fish-oil production

The following information is largely from the Nordic countries, [155, Nordic Council of Ministers, 1997], other sources are cited, when appropriate.

The raw material of the fish-meal industry is mainly small-sized fish species which cannot be sold for human consumption. They are caught for use in the processing of fish-meal and fish-oil. In many areas, a substantial part of the raw material consists of fish waste left over from filleting or other processes.

When processing pelagic fish species such as herring and mackerel, which are landed ungutted, the filleting industry can only utilise 50 % of the landed raw material. The remaining part of the raw material is offal, which the industry then has to sell or dispose of in some way.

Fish-meal is used as a protein supplement in agriculture, especially in pig and chicken production. Small quantities are used for mink feed. Its use in aquaculture feed is the most profitable, with producers buying considerable quantities of fish-oil.

Without fish-meal and fish-oil, the large scale Scandinavian production of salmon and trout would not be possible. Competition from Peru and Chile in the market for standard fish-meals, makes it difficult for European producers to achieve reasonable prices, due to the far higher production costs in Europe.

A substantial amount of pollution is caused by poor quality raw material. Pollution can be considerably reduced by improving the raw material quality. It is technically feasible to increase the fish-meal yield and reduce pollution by improving the quality of the raw material. Technical, environmental and economic conditions vary greatly from plant to plant.

Some fish-meal factories, in the Nordic countries, can influence investments in equipment for improving raw material quality. Some of the factories are owned by fishermen co-operatives. The factory operators can influence raw material quality through the purchase terms of the raw

material, at delivery. A sufficiently large price differentiation seems to result in considerable improvements in raw material quality. A decrease in quality can also occur during the storage of raw material. Improved management of the storage tanks has reportedly resulted in an improvement in the quality of the raw material supplied to the cookers.

Improvement of the quality of the raw material not only reduces pollution. It also increases the fish-meal yield and makes it possible to produce high priced and specialised products. These products require a certain quality of raw material, i.e. the TVN content must not exceed a certain value.

Table 1.5 summarises the EU fish-meal and fish-oil production for 2001.

	Number of Factories	Year	Fish-meal (t/yr)	Fish-oil (t/yr)
Denmark	4	2001	300000	80000
Germany	1	2001	15000	6000
Spain	?	2001	40000	6000
France	?	2001	10000	2000
Ireland	1	2001	25000	6000
Sweden	1	2001	12000	5000
United Kingdom	3?	2001	46000	14000
TOTAL			448000	119000

Table 1.5: EU Fish-meal and fish-oil production in 2001
[303, Minck F., 2002]

Denmark

Denmark produces about 5 % of the world's fish-meal and 8 % of the fish-oil. There are 3 companies, with one being one of the world's largest fish-meal and fish-oil producing companies, producing approximately 215000 tonnes of fish-meal per year, i.e. 67 % of Denmark's output. The process uses fish which are caught specifically for the production of fish-meal and fish-oil, mainly from species which are not caught for direct consumption, e.g. sand eels, and it also uses by-products from fish processing, such as offal. Sand eels make up 60 % of the raw material. 60 % of the catch is caught between April and July. The total fish-meal production in Denmark was 300000 tonnes in 2001.

United Kingdom

The UK produces about 0.25 % of the world's fish-meal and fish-oil. Fish by-products are used.

1.2.4 Blood processing

Blood contains easily assimilated iron, when used for human food or pet food. Blood proteins have a high nutritional value and a high water binding capacity in processed products. The red blood cells burst if water is added to blood. If they are kept intact, red blood cells can be removed by centrifugation, in order to prepare plasma. Plasma is a yellow liquid, rather like egg-white, which may be dried to a powder for food use. [27, University of Guelph, undated]

There are 11 blood processing plants in the EU. They process a total of 300000 million tonnes of blood every year.

There is one plant in each of Belgium, Denmark, Spain, France, the Netherlands, Italy and Sweden and 2 in both Germany and the UK. [271, Casanellas J., 2002]. In addition to these dedicated sites there are others which are associated activities of slaughterhouses.

1.2.5 Gelatine manufacture

The gelatine industry is represented by the Gelatine Manufacturers of Europe Association (GME), which has 9 members and 18 production units, i.e. 2 in Belgium, 3 in France, 7 in Germany, 2 in Italy, 2 in Spain, 1 in the UK and 1 in Sweden. In the year 2001, they produced 117000 tonnes of gelatine. The industry employs approximately 3600 people. There are 3 other production units in the EU operated by non-GME members, i.e. 1 in the Netherlands, 1 in Germany and 1 in Spain. [349, GME TWG members, 2003]

1.2.6 Dedicated incineration of carcasses, parts of carcasses and animal meal

MBM is brown in colour, weighs approximately 600 kg/m³ and has an intense sweet odour. It is a highly calorific, easily flammable fuel. [164, Nottrodt A., 2001]. The incineration of MBM, in particular has, therefore, developed into a relatively large scale activity since the use of animal proteins in animal feed was banned.

Some MSs co-incinerate MBM and other animal meals in municipal waste incinerators, hazardous waste incinerators, sewage sludge incinerators, coal-fired power stations, cement works, gasification plants and residue incinerators in paper plants. [164, Nottrodt A., 2001]. Information in this section has been provided as background, although co-incineration and mixed waste incineration are not described or evaluated further in this BREF.

Germany

The first case of BSE in Germany was confirmed on 26 November 2000. This led to a ban on the use of processed animal proteins as animal feeds for livestock, e.g. pigs and poultry, with effect from 1 December 2000. This was followed by a ban on all uses and the requirement to dispose of processed animal proteins as waste by incineration. The development of dedicated incineration plants was not considered to be economically viable due to the relative uncertainty about future feedstock availability in the long-term. The possibility of siting an incinerator at a rendering plant and recovering the energy through CHP has been raised. [164, Nottrodt A., 2001]

The relative treatment prices for incinerating animal meal and other wastes and the higher calorific value of animal meal, have reportedly stopped plants operating at almost full capacity from actively pursuing animal meal incineration, for economic reasons. They can make more money by incinerating lower calorific value wastes. The prices vary for hazardous waste incinerators, sewage sludge incinerators, power plants and cement works. [164, Nottrodt A., 2001]

Gasification of both animal meal and tallow has been tried successfully. [164, Nottrodt A., 2001]

France

France produces approximately 850000 tonnes of MBM and approximately 150000 tonnes of tallow annually. Approximately 130000 tonnes of MBM and 40000 tonnes of tallow are from SRM and are co-incinerated by the cement industry.

It is planned that the remaining MBM will also be incinerated in cement works and power stations.

Animal meal from BSE-infected animals are disposed of in hazardous waste incineration plants.

In 2001, 400000 tonnes of MBM were either stored in warehouses or sent to landfill. [164, Nottrodt A., 2001]

Italy

The dedicated incineration of carcasses and parts of carcasses has recently been developed and implemented in Italy.

United Kingdom

The UK has a tradition of burning single carcasses in small, mainly on-farm, incinerators. It is currently the only MS with dedicated incineration plants for animal meal. Three dedicated animal meal incinerators have been operating at 2 sites since the late 1990s. At one site there are 2 incinerators, each with a capacity 3.5 t/h and at the other location there is a single incinerator, which has a capacity of 7.5 t/h [199, PDM Group and Wykes Engineering (Rushden) Ltd, 2000]. Together the 3 incinerators incinerate a total of 60000 t/yr. A further dedicated animal meal incinerator, with a capacity of 60000 t/yr, came into operation in April 2001.

All of the UK's purpose-built dedicated animal meal incinerators are fluidised beds.

Since 1999 a power plant previously running on chicken manure has been adapted and now runs on animal meal exclusively. It burns 85000 tonnes of animal meal every year. It is a stoker-fired furnace. It does not burn animal meal derived from SRM.

In addition to animal meal incineration, approximately 3000 cattle carcasses are incinerated directly every year in incinerators with capacities < 50 kg/h. It is estimated that there may be between 2000 and 2600 of these incinerators for burning animal carcasses presently in use in the UK [227, ADAS, 2001].

1.2.7 Burning of tallow

Tallow has been burned as a replacement fuel for heating oil or electricity. This disposal route is, however, not approved under ABP Regulation 1774/2002/EC.

1.2.8 Land spreading/injection

This activity is strictly regulated by ABP Regulation 1774/2002/EC and is completely prohibited in some Member States, e.g. Germany [347, German TWG members, 2003].

1.2.9 Biogas productionGermany

The first large scale plant in Germany for the methanisation of fresh rumen and flotation tailings was an anaerobic reactor situated in a slaughterhouse in Hamburg [206, Tritt W. P. and Schuchardt F., 1992].

Current legislative requirements for animal by-products to be pretreated or for the biogas residues to be treated reportedly make biogas production uneconomic [244, Germany, 2002].

Austria

An industrial plant for the methanisation of rumen contents is situated in Greinsfurt [206, Tritt W. P. and Schuchardt F., 1992].

Sweden

The treatment of manure, stomach and intestinal contents, bits of hides/skins, waste blood and similar products is carried out in biogas installations in Sweden. Some slaughterhouses have their own biogas installations, whereas some others have a share in a public unit [134, Nordic States, 2001].

There are 7 biogas plants specifically approved for the use of certain qualities of animal by-product as raw material, together with the use of other raw materials such as manure and products of vegetable origin. The in-reactor wet digestion technique is used.

United Kingdom

Full-scale digestion plants were installed at several UK slaughterhouses in the 1990s, but operational difficulties and high costs discouraged more widespread application. Most of the original digestion plants have now shut down. [12, WS Atkins-EA, 2000]. It has been reported that biogas production from animal by-products is not currently commercially available within the UK. [144, Det Norske Veritas, 2001], although it is being reconsidered.

1.2.10 Composting

It has been reported that until recently the potential benefits of composting animal by-products have not been exploited, mostly due to a lack of knowledge about their compostability and the economic benefits of composting over some other uses and routes for disposal. It is possible that the composting of animal by-products may increase in the future [206, Tritt W. P. and Schuchardt F., 1992]. On the other hand, the pretreatments required for certain by-products, before they can be composted and the restrictions on their use, which are required by ABP Regulation 1774/2002/EC, may limit any such expansion. ABP Regulation 1774/2002/EC bans the application of compost derived from animal by-products to pasture land [287, EC, 2002]. Opportunities remain for their use in landscaping, forestry, horticulture and land restoration [176, The Composting Association, 2001]. The growth or decline of the composting industry will depend, to some extent, on economic factors, such as the cost or profitability of alternative uses and disposal routes.

Germany

It has been reported that in 1986 rumen contents were composted by 9 slaughterhouses in the 11 Federal States of former West Germany [206, Tritt W. P. and Schuchardt F., 1992].

Finland

Composting is carried out in windrows or reactors. It is a common method for treating materials such as excrement and urine; the contents of stomachs and intestines and the solid products of waste water treatment, such as screenings, fat from grease traps, settlings, excess activated sludge and flotation tailings. The compost produced is then applied to land. [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

1.3 Key environmental issues

1.3.1 Slaughterhouses

The most significant environmental issues associated with slaughterhouse operations are water consumption, emissions of high organic strength liquids to water and the energy consumption associated especially with refrigeration and heating water.

Air

Most emissions to air from slaughterhouses are water vapour from the boilers used to raise hot water and steam. There is also a potential for the release of refrigerant gases from chilling and freezing plants and CO₂ from stunning equipment. These issues are common throughout much of the food and drink industry.

Dust emission arising during the unloading of poultry and the hanging of live birds on the slaughter-line is a key environmental issue at poultry slaughterhouses [240, The Netherlands, 2002].

Water

The most significant environmental impact resulting from slaughterhouses is the emissions to water [177, EA SEPA and EHS, 2001]. This is related to the water consumption, which is the other major environmental issue [12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000].

High water consumption and high BOD, COD and TSS concentrations arise during slaughter and carcase dressing. Solids break down, releasing colloidal and suspended fats and solids and leading to an increase in the BOD and COD. [177, EA SEPA and EHS, 2001]. Other key contaminants are nitrogen and phosphorus, e.g. from the breakdown of proteins; copper and zinc from, e.g. pig feed residues and chloride, from hides/skins salting. The consumption of water is partly governed by EU and MS meat legislation, which require fresh, potable water to be used for almost all washing and rinsing operations and which limit the scope for the re-use of water within the slaughterhouse.

The excessive use of water is not only an environmental and economic issue in itself, it also adds to the WWTP burden. Waste water may be fully or partially treated at a WWTP at the slaughterhouse. If the treatment is undertaken at a municipal WWTP, there is usually some pre-treatment done at the slaughterhouse. The contamination of waste water can be minimised by collecting by-products and waste as close to the source as possible, and by preventing their contact with water. Minimising the water use in slaughter and carcase dressing can also reduce the actual contaminant load, by reducing the opportunities for the entrainment of organic matter such as fat or faeces. If by-products are entrained in water, the opportunities for their re-use are limited. The opportunities for eliminating or reducing water use need to be explored at each unit operation of the process.

In any slaughterhouse, a major factor affecting water consumption is the amount of floor area used. For hygiene reasons, all process floor areas must be washed down at least once a day [99, EC, 1964]. Water consumption is, therefore, highly dependent on the layout of individual slaughterhouses and in poultry slaughterhouses will also depend on, e.g. the size of bird; the method of slaughter, carcase dressing, carcase cooling and the degree of automation. Large quantities of water are consumed in poultry slaughterhouses for evisceration, cleaning and washing operations. [67, WS Atkins Environment/EA, 2000, 177, EA SEPA and EHS, 2001]

Blood has the highest COD strength of any liquid effluent arising from both large animal and poultry slaughterhouses [12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000]. The polluting potential of blood and the huge quantities which are handled and stored, therefore, make it a key environmental issue for assessment and control. The potential contamination of water needs to be considered from the process and from all potential sources ranging from small leaks to major technical and operational accidents.

In some countries, such as Denmark, Finland, Sweden and Norway the waste water from slaughterhouses is considered to be an important source of carbon for denitrification at municipal WWTPs, so only limited treatment is undertaken at the slaughterhouses. [134, Nordic States, 2001]

Energy

The majority of large animal slaughterhouses do not submeter their electricity consumption. The total consumption is measured by looking at utility bills. Some slaughterhouses do submeter energy consumption by process area and expect to make substantial cost savings through monitoring and targeting programmes. [12, WS Atkins-EA, 2000]. Most slaughterhouses have a stand-by generator to enable partial operation of the plant if the power is interrupted. [12, WS Atkins-EA, 2000]

At most slaughterhouses, the refrigeration plant is the biggest consumer of electricity. It constitutes 45 - 90 % of the total site load during the working day and almost 100 % during non-production periods. Refrigerated areas include chills, freezers and cold stores. It is common

practice for each refrigerated room to be a self-contained, direct-expansion unit, which comprises a compressor, evaporator and condenser. Some larger sites have a centralised compressor and condenser plant [12, WS Atkins-EA, 2000, 57, DoE, 1993]. The requirement to cool carcasses sets a legal duty for them to reach a maximum temperature of 7 °C before leaving the slaughterhouse and for offals not to exceed 3 °C [169, EC, 1991]. For a large animal, cooling may take 48 hours [239, Denmark, 2002]. Some exceptions to the rule for cooling carcasses before leaving the slaughterhouse have been reported in Italy, in integrated slaughterhouses and cutting plants producing typical Italian cured products. It is also reported that because smaller pieces are cooled, the energy required for cooling is less than that needed to cool whole or half carcasses. [237, Italy, 2002].

The use of energy to heat water is another key environmental issue. Oil and/or natural gas are the principal fuels used to produce hot water. Boiler water is usually softened before use. The requirement for hot water is split between basins and showers, pig scalding tanks (58 – 65 °C), washing down (60 - 65 °C), and implement sterilising baths (> 82 °C). [57, DoE, 1993]. Some slaughterhouses have their own laundry on site.

In pig slaughtering, either natural gas, LPG (principally propane), or oil burners are used for the direct flame singeing of carcasses. It is reported that singeing with oil burners can cause hygiene and quality problems [237, Italy, 2002].

On the slaughter-line, hoists, cutters, hide pullers and saws are powered pneumatically or by electric motors. [57, DoE, 1993]

Odour

Odours emitted from blood storage and handling, slurry, occupied lairages and inedible offal storage are reported to be the most problematic. Yard areas, unwashed by-products containers and WWTPs, including the initial screening of solids, are also reported to be potential problem areas. [285, Brindle J., 2001]

Noise

The main sources of pollution from noise and vibration are the animal noises during unloading and marshalling, vehicle movements, compressors, air conditioners and ventilation fans. [134, Nordic States, 2001]

Site restoration

Slaughterhouse activities are not expected to result in significant site restoration issues. Leakage from underground drainage pipes and tanks could possibly cause subsidence in the longer term, but there are unlikely to be any significant land or groundwater contamination issues. All materials, apart from the brine from hide/skin salting, which is discharged to the foul sewer from slaughterhouses, are readily biodegradable, including cleaning chemicals. [12, WS Atkins-EA, 2000, 241, UK, 2002]

Non industry specific site restoration issues might arise from any leakage from fuel and oil storage tanks. [12, WS Atkins-EA, 2000]

1.3.2 Animal by-products installations

1.3.2.1 General information about key environmental issues

1.3.2.2 Fat melting

Energy

Energy consumption is an important issue during the melting process and at decanters, centrifuges and crushers [319, NL TWG, 2002].

Noise

Noise emissions from vehicles and refrigeration equipment can be significant [333, Netherlands TWG, 2003].

1.3.2.3 Rendering**Water**

The contamination of water, as well as foul water produced by the rendering process, is a key environmental issue [243, Clitravi - DMRI, 2002].

Energy

Significant amounts of energy are consumed, e.g. to produce steam for the process.

Odour

One of the key environmental issues associated with rendering is odour. Both the process and associated activities can give rise to objectionable odours. These are associated with the reception, handling and storage, transfer and preparation of raw material; the cooking process; handling and storage of processed product and the handling, storage, treatment and disposal of solids, liquid effluents and process gases. [241, UK, 2002]

The fresher the raw materials are, the fewer odour problems they will cause, either directly or during the rendering process. The odorous substances are characterised by some being insoluble in water and others being volatile in steam. They are detectable at low concentrations. The concentration and composition of the emitted substances can change suddenly during the production process. If the formation of these substances is not prevented then abatement techniques need to be capable of coping with these characteristics. This may possibly require the adoption of a variety of techniques. [49, VDI, 1996]

Infective matter

The raw materials of rendering are potential sources of infection, depending on their origin, age and state of preservation. This is particularly significant with respect to the destruction of TSE materials and SRM. Infectivity is, therefore, a key environmental issue [243, Clitravi - DMRI, 2002].

1.3.2.4 Fish-meal and fish-oil production**Water**

Large quantities of seawater are used. The pollution from fish-meal factories stems from many different sources. The pollutants are often mixed with large quantities of seawater, which is used for cooling, in the processing plant. [155, Nordic Council of Ministers, 1997]

A number of compounds are formed during the bacteriological decomposition of the raw material before it is cooked. These compounds are volatile under the process conditions and they can pollute the marine environment, as well as generating odour problems in areas around the factories. The marine environment is also polluted as a result of product losses, including fish-meal, stickwater and a liquid known as evaporated stickwater, which contains approximately 40 % dried matter. The degree of bacteriological deterioration, the raw material quality and the concentration of volatile substances, especially ammonia and trimethylamine (TMA), in the raw material, are all related to each other.

Energy

Large quantities of energy are used for drying [155, Nordic Council of Ministers, 1997].

Odour

Odour from the raw material, the process and from the waste water treatment can be a significant problem. The volatile compounds that cause the odours arise from the degradation of the fish and freshness is, therefore, not just an important influence on the quality of the product, but also determines the odour emissions from a site.

1.3.2.5 Blood processing

Water

Liquid blood has a COD of about 400 g/l and a BOD of about 200 g/l. Congealed blood has a COD strength of about 900 g/l [12, WS Atkins-EA, 2000] and it has a total nitrogen content of approximately 30 g/l. Preventing the accidental discharge of liquid blood or the spillage of dried blood by, e.g. explosion of the spray drier or tearing of packaging during storage or handling, needs to be treated as a priority.

The main requirement for water is for cleaning operations. Blood is about 82 % water, so emissions to water will include the water derived from the blood during the various separation techniques.

Energy

Energy consumption is significant, especially with respect to spray drying. If the blood is not processed quickly, then refrigerated storage is needed, which can also consume significant energy.

Odour

On a routine daily basis, odour problems can arise during the unloading of blood from the transport tanker [168, Sweeney L., 2001].

Noise

Spray driers are noisy.

1.3.2.6 Gelatine manufacture

Water

The key environmental issues associated with gelatine manufacture is the water consumption during the early stages of the extraction process and the associated waste water treatment.

Energy

Drying the product consumes significant amounts of energy.

Odour

Odour from the degreasing units of gelatine plants processing bones and pigskins and raw material delivery may be a key environmental issue [349, GME TWG members, 2003].

1.3.2.7 Glue manufacture

Energy

Drying the product consumes significant amounts of energy [244, Germany, 2002].

Odour

Odour from both the liming pit and from drying is a key environmental issue [244, Germany, 2002].

1.3.2.8 Dedicated incineration of carcasses

Air

Potential emissions to air commonly associated with the incineration of animal carcasses include particulate matter; hydrogen chloride; oxides of sulphur, nitrogen and carbon and organic compounds, such as dioxins. Chlorine can lead to hydrogen chloride production. There is a potential release of particulate matter from incomplete combustion.

Land

Potential emissions to land include dioxins, organic compounds, alkali metals and their oxides and alkaline earth metals and their oxides [65, EA, 1996].

The chlorine in the salt in carcasses means there is a potential for dioxin formation.

Infectivity

The raw materials are, depending on their origin, age and state of preservation, potential sources of infection. This is particularly significant, with respect to the destruction of TSE materials and SRM. Infectivity is, therefore, a key environmental issue [244, Germany, 2002]. The incineration of animal carcasses may give rise to a biohazard in the form of undestroyed organics released to air, water and land.

Odour

In common with all installations handling, storing or processing animal by-products odour is a potential problem [65, EA, 1996].

1.3.2.9 Dedicated incineration of animal meal

Air

Quantities of dioxins and furans of 0.2 and 0.3 ng/kg have been found in MBM samples in Ireland and Portugal, respectively [164, Nottrodt A., 2001] but these are likely to be destroyed by the incineration process. There is, however, a risk of dioxin formation during the incineration process, the degree of risk depending to some extent on the techniques used to operate the incinerator [65, EA, 1996]. Dust emissions may also arise from incomplete combustion.

Land

The loss of phosphorus through incinerating animal meal, instead of recovering the phosphorus from it for use as a fertiliser, is considered to be key environmental issue [239, Denmark, 2002].

Infectivity

If the animal meal production process prescribed in ABP Regulation 1774/2002/EC is followed, the potential risk from BSE pathogens should be insignificant. The incineration of properly produced animal meal should, therefore, require no additional protective measures regarding the TSE biohazard. The same should be true for animal meal imported within the conditions required by ABP Regulation 1774/2002/EC. If animal meal from an unreliable source is incinerated then there may be occupational health risks associated with potential contact or airborne exposure, so controls may be required.

There may be a risk of pests, vermin, bacteria and fungi being attracted by the large amounts of nutrients and moisture in the animal meal. If animal meal is stored in damp conditions, it will provide an ideal medium for these. If the storage temperature is allowed to exceed 40 °C, animal meal may heat up and spontaneously combust. Certain grades, or distributions of grades can carry a risk of explosion. [164, Nottrodt A., 2001]

1.3.2.10 Burning of tallow

Tallow is currently burned in boilers and this gives rise to emissions of CO₂, and NO_x. At the time of writing, the burning of tallow is not permitted in the EU, due to the fact that in ABP Regulation 1774/2002/EC, it is neither listed, nor has it been approved in accordance with the procedure referred to in Article 33(2) therein, after consultation of the appropriate scientific committee.

1.3.2.11 Land spreading/injection

Air

If, e.g. manure from slaughterhouse lairages is spread on land then emissions to air of volatile substances, such as ammonia, may be an issue. The potential nutritional advantage to the soil is thereby lost. There may also be an odour problem.

Water

Surface water and groundwater contamination may occur from manure, slurry and/or sewage sludge, if they contain, e.g. pathogens, such as *Salmonella*, *E. coli* 0157 and *Campylobacter* and metals. The residues from biogas production and compost should be free of pathogens as they should already have been destroyed during these processes.

Soil

Solids containing above about 4% fat or oil content, have been demonstrated to have a detrimental effect on plant growth. They are, therefore, considered to be unsuitable for land spreading [179, EA SEPA & EHS, 2001].

Odour

Odour is a key environmental issue [244, Germany, 2002].

Infectivity

If the deactivation of pathogens is inadequate there is a risk of land and groundwater contamination [244, Germany, 2002]. Soil contamination may occur from manure, slurry and/or sewage sludge, if they contain, e.g. pathogens, such as *Salmonella*, *E. coli* 0157 and *Campylobacter* and metals. The residues from biogas production and compost should be free of pathogens as they should already have been destroyed during these processes.

1.3.2.12 Biogas production

Air

The main product of biogas production is methane. CH₄ is a “greenhouse gas”. In terms of its potential to cause damage, one molecule of CH₄ is 30 times more powerful than one of CO₂. Consequently, the requirement to prevent accidental release into the atmosphere is significant. There are also safety controls required, due to the fire and explosion hazard, which are also related to pollution prevention and control.

Odour

Odour may arise from raw materials and from the process.

1.3.2.13 Composting

Air

Key environmental issues include bioaerosols and dust.

Energy

Some consider it a key environmental issue that using animal by-products for composting does not make use of their energy value [243, Clitravi - DMRI, 2002].

Water

The risk of leachate contaminating soil and groundwater is a key environmental issue.

Odour

Odour results from the raw materials and during the composting process, especially during windrow composting.

Infectivity

If the deactivation of pathogens is inadequate there is a risk of land and groundwater contamination [244, Germany, 2002].

1.4 Economic overview

1.4.1 Slaughterhouses and animal by-products

The FAO have forecast that global meat consumption will grow by 2 % per year, until the end of 2015. It has warned that the associated increase in trade and transport links required will raise the risks of the spread of animal diseases across borders. These trends are reported to have already started in the early 1980s, driven by population growth, rising incomes, urbanisation, changing diets and by the opening up of markets, particularly for poultry and pig meat.

It is predicted that most of this increase will occur in the developing world, where consumption is expected to grow by 2.7 % per year, compared to 0.6 % year in rich countries. The FAO has also stated that recent animal disease outbreaks in major meat exporting countries, such as BSE, had accelerated a shift in consumption away from red meat to poultry. The FAO predict a 2.9 % per year increase in demand for poultry meat until the end of 2015, and a 1.4 % increase in annual demand for beef.

According to the FAO, there are many hidden costs in animal disease epidemics. In total, 11.0 million animals were slaughtered in the Netherlands during the classical swine fever outbreak in 1997/98 and 6.24 million were killed in Great Britain during the FMD crisis in 2001.

The FAO report that *The disposal of slaughtered carcasses has huge environmental implications; during the first six weeks of the UK FMD outbreak, the burning of carcasses released dioxins into the atmosphere amounting to some 18 percent of the UK's annual emissions, and Furthermore, the mass slaughter of animals resulted in the loss of bio-diversity of native livestock populations, with some breeds left critically endangered following the UK FMD outbreak.* [324, Brough D., 2002]

In 2000, EURA reported that the animal by-products industry manufactures products with an annual value of greater than EUR 2.2 billion and that this represents a very significant source of income for the European agriculture industry. [24, EURA, 1997]

In the past few years the BSE crisis has meant that costs to slaughterhouses for disposal of their animal wastes have increased significantly. To keep costs to a minimum, most have sought to

place contracts with the larger rendering companies offering economies of scale. Due to fierce competition, many rendering companies went bankrupt or were bought out by the larger companies. As a result there are now only two very large rendering companies left in the UK and about 20 smaller companies. [12, WS Atkins-EA, 2000]

Costs have increased for the treatment and disposal of animal by-products and this has been passed along the meat supply chain to the customer. [18, UKRA, 2000]. For example, in the UK before the BSE crisis many animal by-products, including fallen stock were sold to rendering companies or collection charges were minimal. The European Commission prohibitions limiting the use and export of “processed animal proteins” from 1 January 2001 has led to additional storage and disposal costs [18, UKRA, 2000]. Rendering companies now impose significant charges for the collection of animal by-products.

The numbers of cases of BSE in the UK has significantly exceeded those elsewhere in Europe and this has led to the UK and Ireland taking some preventive actions, which have had financial consequences, ahead of the other EU MSs. In the UK, prior to the BSE crisis, the value of the protein and fats produced by the rendering industry was GBP 150 million. In 2000, this had fallen to nearer GBP 50 million. [17, UKRA, 2000]. In 1996, MAFF provided temporary financial support of GBP 100 million to prevent the collapse of the meat industry. In 1997/98, it provided a further GBP 59 million. [18, UKRA, 2000]

The action by the UK to prohibit the feeding of processed animal proteins to all livestock, not just ruminants and to ban exports to third countries before the rest of the EU, placed financial burdens on the meat industry there, exceeding those experienced elsewhere at that time.

In the UK, government support to the meat industry was withdrawn in 1998. Until cases of BSE were discovered in some MSs, for the first time, from December 2000 onwards, their market for animal meal was largely unaffected, although the feeding of processed animal proteins to ruminants had been banned. The other MSs then introduced legislation to quickly restrict their use further.

Each MS had its own financial arrangements for paying for rendering and for the subsequent disposal of animal meal. In Denmark, the co-operative system, whereby the farms, slaughterhouses and rendering plants are jointly owned, means that additional costs are passed to the customer and there is no government support. In Italy, France and the Netherlands the cost is passed to the customer. In Germany, support can be provided to rendering plants. In France, the government funds the collection, processing and disposal of SRM and all dead ruminants, pigs and poultry by imposing a customer tax on meat sales. This amounts to approximately GBP 59 million per year. [21, UKRA, 2000]

Compensation was temporarily made available to farmers unable to obtain the “trigger price”, i.e. a minimum market value, applicable to their MS, for beef and veal. The scheme was known as the “over thirty months scheme” (OTMS). The cost was divided between the European Commission, which paid 70 % and the MS, which paid 30 %. The OTMS was for cattle not eligible for intervention purchases, which were more than 30 months of age and which had all been tested negatively for BSE. The price paid to farmers for these animals, that were no longer available for human consumption, was fixed on the basis of the market price in the MSs, according to the quality category of the meat concerned. For those MSs without full testing capacity, the provisions of the “purchase for destruction scheme” remained in force until 30 June 2001, when the compulsory testing came into force. This was to avoid non-BSE-tested meat from cattle over 30 months from entering the food chain.

The continuing ban on the use of processed animal proteins in feed for animals farmed for food has led to the diversification of the animal by-products industry into incineration and to research into alternative ways of disposing of by-products and in particular TSE materials and SRM. The rendering industry still processes most of the animal by-products not intended for human consumption although some are stored frozen, for future incineration.

1.4.2 The economic cost of consumption and emissions

General considerations

The minimisation of consumption and emission levels, in many cases has direct financial benefits. These can be seen from, e.g. reduced energy costs and a decreased requirement to use “end-of-pipe” abatement techniques.

Some of the financial costs associated with the consumption of resources and emissions to air, water and land are easy to measure. The use of some resources, such as electricity, fuels and in some cases water, are measured, for payment purposes. At some installations measurements are made at unit operation level for monitoring and identifying possible areas for reducing consumption levels. Some emissions, including, e.g. solid wastes, are taken away for disposal, by waste contractors who are paid per unit load transported. Some animal by-products which are now considered to be wastes were used in the past and in some countries were sold for profit. The provision and maintenance of abatement equipment, e.g. the replacement of filter material, can also be quantified relatively easily.

Some of the insured and uninsured costs associated with cleaning up and repairing damage, to the plant and the environment, after an accident can be quantified.

To measure the full consumption and emission economic costs requires a focused effort. It must, e.g. take into account all of the man-hours spent identifying, planning, sourcing, buying, installing, commissioning, operating, adjusting, maintaining, cleaning, repairing or transporting equipment for pollution abatement.

The costs associated with changing technological and operating techniques which improve environmental performance and have an effect on the process may be more difficult to calculate accurately, for various reasons, including the element of cost saving due to, e.g. the reduced consumption of electricity.

Some examples

Water

The cost of water depends on factors such as whether it is bought from an external source or abstracted directly at the installation and what pretreatment, such as softening, is required. The attitude to water usage varies considerably depending, to some extent, on its cost. Some users who have their own plentiful sources of water and abstraction facilities do not consider water to be a key environmental or economic issue.

The Water Framework Directive [180, EC, 2000] addresses this and sets out to ensure that all users value and pay for the water they use. This Directive introduces a principle of recovery of the costs of water services, including environmental and resource costs associated with any damage or negative impact on the aquatic environment, invoking in particular, the “polluter pays principle”. It requires that water pricing policies provide adequate incentives for users to use water resources efficiently. The attitude which encourages increased consumption of water because the supplier provides it at a lower unit cost if more is consumed, may cease to have foundation.

The link between water consumption and energy use is very important in the slaughterhouses and animal by-products industries. Typically about half of the total water usage at a slaughterhouse is heated to between 40 and 60 °C and some is heated to 82 °C. In England and Wales in 1998, slaughterhouses reliant on local water authorities for their supply, typically paid GBP 0.70 (EUR 1.13)/m³. If the water requires softening before use, on-site water processing costs may increase the cost by a further GBP 0.30 (EUR 0.48)/m³. For every 10 °C increase in water temperature there is an additional cost of typically GBP 0.16 (0.26)/m³, if water is heated by gas, or GBP 0.47 (EUR 0.76)/m³, if water is heated by electricity (1998) [12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000].

The user does not only have to pay for the consumption of water. The water used has to be treated before being discharged. Whether the treatment is done on-site or at a municipal WWTP the consumer will have to pay. The WWTP will have to be capable of treating both the volume and the pollutant load. Reducing both of these parameters will reduce the investment and operating costs for the WWTP. WWTPs, in common with other “end-of-pipe” techniques, only control emissions; they do not add other benefits to, e.g. productivity, which “process-integrated” techniques may do [327, EC, 2002].

In Denmark, most of the waste water treatment is undertaken at municipal sewers, with only the preliminary removal of solids using a 2 mm mesh being done at the slaughterhouse. The waste water is considered to be desirable for the denitrification process and surcharges are normally calculated according to the BOD levels. Water costs in 1998 were on average DKK 14 - 16/m³. “Green taxes” are levied on the final discharge plant. [134, Nordic States, 2001]

In Italy, most slaughterhouses abstract groundwater directly and treat it to drinking water standard. Several small slaughterhouses use the local authority supply. The cost of the water from the public network depends on the particular site and the volume. The average cost is EUR 0.80/m³. The cost of the abstraction and treatment of well water is about EUR 0.16 - 0.20/m³, depending on the depth. If softening is required, only for water that must be heated and for steam production, an additional cost of EUR 0.24/m³ must be paid. Heating water costs EUR 0.52/m³ for every 10 °C increase in temperature. The average cost of waste water treatment, including sludge disposal is EUR 0.5 – 0.7/m³. Some slaughterhouses discharge their waste waters to municipal sewers after a physico-chemical pretreatment at a cost of EUR 1 - 2/m³, plus EUR 0.35/m³ for treatment in WWTPs. [237, Italy, 2002]

All Finnish slaughterhouses discharge their waste water to municipal WWTPs. Some have their own pretreatment systems (flotation). There are no special “green taxes” on water consumption for slaughterhouses, but the water charge consists of a clean water cost and a waste water charge. The charges vary so much, from authority to authority, that quoting an average would be meaningless. [134, Nordic States, 2001]

Water costs at Swedish slaughterhouses are typically SEK 15 - 18/m³. This covers clean water use and the treatment of waste water at municipal WWTPs. Where slaughterhouses have their private water supplies, the costs are significantly lower.

Charges for water use and waste water discharge are based on the measured usage, although they consist of both a water charge and a discharge fee. Surcharges for particularly high levels of pollution are rarely used, but when applied they normally consist of an extra payment of 20 % over the standard charges. [134, Nordic States, 2001]

Energy

There is some information available about the relationship between economics and the environmental impact from the meat industry. In the simplest sense the annual energy costs paid by an installation may be compared to the annual profits made. This does not take full account of the environmental impact of the energy generation, e.g. the extraction of fuel and the building and operation of the power plant. It does, however, show that if energy use was reduced profits could be greater. An MLC survey of red meat sites in 1987 found that average profits were of the same magnitude as energy costs. The study concluded that there was considerable scope for profit improvement through increased operating efficiency. A UK survey in 1991 showed that in the red meat slaughtering industry, although electricity was less than 39 % of the total energy usage it accounted for 78 % of the energy costs [57, DoE, 1993]. Reduction in electricity use is therefore a worthwhile goal both environmentally and economically.

In Denmark, a “green tax” is levied on electricity supply. In 2000, the average cost of electricity for slaughterhouses was DKK 0.48/kWh. Denmark has a district heating system

which is subject to “green taxes”. The average cost of heat energy in 2000 was DKK 0.165/kWh. [134, Nordic States, 2001]

In Italy, the average price of electricity is EUR 0.087/kWh. For natural gas, the average price is EUR 0.248/m³ gas, which is equivalent to EUR 0.03/kW thermal. [237, Italy, 2002]

In Finland, there is a “green tax” on electricity supply of FIM 0.026 (EUR0.1)/kWh. The electricity cost varies, depending on the supplier, between FIM 0.22 and 0.37 (EUR 0.1 and 0.6)/kWh (electricity price + transfer cost + all taxes). The heating energy used by slaughterhouses is produced with light or heavy fuel oil. “Green taxes” are levied on these at a rate of FIM 0.40 (EUR 0.7)/l and FIM 0.34 (EUR 0.6)/l, respectively. [134, Nordic States, 2001]

In Sweden, industry is exempt from energy tax. The electricity cost is SEK 0.23 - 0.30/kWh. The cost of heat for process and room heating varies according to the method of production. Some slaughterhouses use wood chips from the forest industry, but fuel oil and gas oil are also used. The cost is similar to the cost of electricity, unless it has been found profitable to invest in heat recuperation. [134, Nordic States, 2001]

The Norwegian meat industry pays on average NOK 0.265/kWh for electric power. For oil, the cost is about NOK 0.35/kWh or (NOK 3.50/l). About 65 % of the energy consumed is from electricity and the rest is from oil. The average energy cost is NOK 0.295/kWh. The Norwegian meat industry is exempt from electricity tax.

1.5 Food and veterinary legislation influences

There are other legal requirements and prohibitions, which must be considered when identifying “best available techniques” in the slaughterhouses and animal by-products industries. There are specific requirements relating to, e.g. food safety and animal welfare.

Council Directive 91/497/EEC of 29 July 1991 amending and consolidating Directive 64/433/EEC on health problems affecting intra-Community trade in fresh meat to extend it to the production and marketing of fresh meat [169, EC, 1991] and *Council Directive 92/116/EEC of 17 December 1992 amending and updating Directive 71/118/EEC on health problems affecting trade in fresh poultrymeat* [223, EC, 1992] set out the main hygiene requirements for slaughterhouses. Some of these requirements have significant environmental consequences, in terms of, e.g. water and energy consumption.

There is legislation, which is also very relevant to the animal by-products activities covered in this document, which has been taken into account, i.e. *Regulation (EC) No 1774/2002 of the European Parliament and of the Council of 3 October 2002 laying down health rules concerning animal by-products not intended for human consumption* [287, EC, 2002].

Whereas other food, veterinary and animal welfare legislation influences the applied processes and techniques, e.g. with respect to water temperature requirements in slaughterhouses, ABP Regulation 1774/2002/EC goes further. It stipulates specific treatments requiring, e.g. materials to be heated to a certain temperature for a specified time. It states what uses and routes for disposal are permitted or required for animal by-products not intended or not fit for human consumption. Where there is more than one process permitted under ABP Regulation 1774/2002/EC operators may decide which to follow due to market preferences, or economic considerations. Consequently, such decisions may differ either geographically or through time.

ABP Regulation 1774/2002/EC allows for currently unspecified processes to be approved for the use or disposal of animal by-products not intended for human consumption and refers to procedures for such approval.

The objective of implementing ABP Regulation 1774/2002/EC, is to prevent animal by-products derived from animals not fit for human consumption, following health inspection, from entering the feed chain and thereby presenting a risk to animal or public health. ABP Regulation 1774/2002/EC also applies to parts of slaughtered animals which are fit for human consumption, but are not intended for human consumption for commercial reasons.

Some of the materials processed by the animal by-products industry are edible and are eaten by humans. Some of the activities covered in this document produce food for human consumption and care has been taken to ensure that nothing conflicts with relevant food safety legislation.

Until recently EU legislation covering the animal by-products industry referred to the animal tissues not directly consumed by humans as “waste”. The current practice of using the term “by-product” for materials reserves the use of “waste” for by-products disposed of as waste.

2 APPLIED PROCESSES AND TECHNIQUES

2.1 Slaughter

2.1.1 Activities described in this chapter

This chapter describes the slaughterhouses and animal by-products activities covered by the BREF. The relationships between the activities downstream from the slaughterhouse are illustrated in a very simplified and general form in Figure 2.1. The final use or disposal route for many of the individual by-products of slaughter and of the treatment of waste water from slaughterhouses and animal by-products installations varies geographically and also from time to time. This depends on whether the by-products are considered, within food and veterinary legislation, to be fit for use as food for humans, pet food or animal feed; on economic factors and on local/national traditions and preferences. Local/national tradition is a significant factor with respect to, e.g. the choice between the use of landfill, incineration and biogas alternatives and it may be determined by local legislation.




Figure 2.1: Relationships between slaughterhouses and downstream activities (summary)

The unit operations in slaughterhouses are described first in Section 2.1. This section is divided between the slaughter of large animals and the slaughter of poultry. Although many of the environmental issues are common to both, the actual processes differ significantly. The different processes at individual animal by-products installations are then described in Section 2.2, in the following order: fat melting, rendering, fish-meal and fish-oil processing, bone processing, blood processing gelatine manufacture, incineration, burning of tallow, land spreading/injection, biogas production and composting. Some waste water treatment processes that are applied in the industries are then described, firstly for slaughterhouses and then for animal by-products installations.

2.1.2 Slaughter of large animals

Processing operations at slaughterhouses vary depending on the type of animal being slaughtered. The most significant difference is that for cattle and sheep the hide is removed. Pig skins are usually retained, although the bristles are removed and the surface of the skin is singed. Other differences relate to the difference in animal physiology and size. [12, WS Atkins-EA, 2000]

The slaughter process, although relatively labour intensive, is becoming increasingly automated. For instance, machinery is being developed to mechanise carcass dressing and this tends to incorporate automatic carcass washing at every stage. Up to 140 cattle and 600 pigs can be killed in an hour. Hundreds of cattle and thousands of pigs can, therefore, be killed in a slaughterhouse, on a daily basis.

2.1.2.1 Animal reception and lairage

The animals are unloaded via ramps which should preferably be at the same level as the truck, have a non-slip surface and be sufficiently long to allow adult animals to be able to put all four hooves on. Looking after the animals' welfare reduces the risk of injury to them and subsequent waste, so it also has environmental advantages. [332, COTANCE, 2003]. After animals are unloaded the lorries are cleaned, for hygiene reasons. Most slaughterhouses have a dedicated vehicle wash area for this purpose. In some cases bedding, such as straw or sawdust is used. If so this is removed during vehicle washing after each delivery. The wash-water is discharged for waste water treatment and the manure and dirty bedding are collected.

Ideally animals should arrive at the slaughterhouse clean, although they may get dirty during the journey, e.g. from manure and washing upon arrival is an option. Washing the live animals can cause problems if there is not enough time for them to dry before they are slaughtered. Wet hides and skins can deteriorate more quickly than dry. [332, COTANCE, 2003]. There are conflicting views about the value of clipping. It has been encouraged to minimise the risk of both carcass contamination and operator exposure to *Escherichia coli* 0157.

The animals are often held in the lairage to allow them to recover from the stress of the journey. This improves the quality of meat by allowing adrenaline and glycogen levels to recover to normal levels. Pigs do not have sweat glands and are prone to heat stress during warm weather. To prevent this, they are kept cool by fine water sprays applied by shower arrangements in the lairage pens.

Most animals are retained for only a couple of hours before slaughtering, but some may be kept overnight to facilitate an early morning start. In general, farmers prefer their animals to be slaughtered on the day of arrival. Farmers are paid on the carcass weight of each dead animal, and many believe that this decreases if the animals are kept overnight.

A variety of lairage floor constructions are used. The most common are solid concrete floors; dimpled concrete floors, to allow animals adequate grip; or slatted concrete floors with under floor drainage to slurry tanks. For animal welfare reasons, slatted concrete floors are not generally used for sheep because their hooves can become trapped in the slats. Suspended mesh flooring is reported to work well in sheep lairages and like slatted floors they allow dirt to drop through and generate heat, which helps to dry the animals before they are slaughtered. Lairages for sheep/lambs are often simple and may have only a simple supported roof without walls.

Bedding is only used to a minor extent, but an official veterinary surgeon will insist that there is enough bedding to prevent the animals from getting dirty while in the lairage and/or there is sufficient dry bedding to dry off any wet animals. It is also generally used for overnight lairage. This is usually straw, but waste paper and sawdust are used at some installations. It has to be dry and of good quality. Lairages are normally cleaned by shovelling the solid manure and straw into a skip and then washing the lairage floor with HPLV hoses. In Italy, lairages are washed down and disinfected each time the lairage is emptied [331, Italy, 2003].

Straw and manure from delivery vehicles and lairages may be used as fertiliser, subject to public health legislation.

Sheep/lambs may be sheared before slaughter, but this may reduce the value of the skin, because it removes the option of “doubleface” production, i.e. skins tanned with the wool on and it reduces the possibilities for recovering wool from the pelt.

Cattle that are dirty may have clumps of manure intertwined with their hair. This material is removed prior to slaughter. This is usually done by dry clipping the hair. At some slaughterhouses the animals are washed with a powerful hose. [288, Durkan J., 2002]

2.1.2.2 Slaughter

Animals are taken from the lairage along a fenced or walled passageway constructed to allow them to walk in single file, or in small groups to where they are stunned and slaughtered.

Cattle are led one at a time into a stunning pen, which prevents the animal from moving and has a tiltable bottom and sides. The animal’s head must be positioned in such a way that the stunning equipment can be applied and operated easily, accurately and for the appropriate time. The competent authority may authorise the use of head restraints. [115, EC, 1993]. After stunning the animal collapses to the bottom of the pen, the operator then actuates a handle and the pen side opens allowing the animal to slide out onto a dedicated landing area on the slaughter hall floor.

Cattle are stunned before bleeding, normally using a captive bolt pistol activated by expanding gas either from an air compressor or a blank ammunition cartridge. The pistol is accurately located at a point on the midline of the skull, above the level of the brow ridges of the eye sockets. Bulls and boars, which have massive skulls, are sometimes shot with a rifle bullet. There are also some non-penetrative percussion pistols in use. One captive bolt pistol, known as the Hantover stunner, injects air as well, thus scrambling the brain. This can result in central nervous system material entering the blood stream. It is not used in Germany, Spain, Ireland or the UK [202, APC Europe, 2001].

Pithing during slaughter is prohibited under legislation, to prevent the transmission of TSE [173, EC, 2001]. There is some resistance to the prohibition of pithing on slaughterman safety grounds [111, EC, 2001]. Pithing involved the insertion of a long rod into the hole left by the captive bolt and reduced muscle contractions during carcass dressing. Paper and cloths used to clean the captive bolt are classed as SRM. Electrical stunning of cattle is undertaken in the US, Australia and New Zealand [332, COTANCE, 2003].

Sheep and pigs are also stunned before bleeding, using a captive bolt pistol or electrical tongs. The traditional stunning method for pigs involves applying scissor-like tongs or head plates with a current of at least 1.3 A, at a minimum voltage of 190 V, for about 5 s. For sheep, the current is normally at least 1 A. For pigs, in recent years the use of CO₂ baths has become more popular. The pig is exposed to two stages of gas, firstly a mixture of 30 % CO₂ to increase respiration and then a mixture of 70 - 82 % CO₂ (depending on the size of the pigs), to induce anaesthesia. The concentration of CO₂ for stunning pigs must be at least 70 % by volume [115, EC, 1993].

The removal of as much blood as possible is important to maximise the quality of the meat. In many cases, animals such as pigs and sheep could be killed by electrocution, rather than being merely electrically stunned. In pigs, cardiac arrest does not affect the rate and extent of bleeding.

After stunning, the animals are hung by one or both of their hind legs on an overhead rail which carries the carcasses through the intermediate processes and into the chiller unit. Small multi-species slaughterhouses may have a common slaughtering and processing line, where the height of the workstation can be adjusted to match the height of the carcass. Large slaughterhouses typically operate separate slaughtering and processing lines for different species.

In at least one Danish slaughterhouse, the cattle are tipped from the stunning pen onto a table, where their neck arteries are then severed. The animal is then shackled and raised using an elevator platform to the hanging position, for bleeding.

During ritual slaughter, the restraint of bovine animals before slaughter using a mechanical method intended to avoid any pain, suffering or agitation and any injuries or contusions to the animals is obligatory [115, EC, 1993].

2.1.2.3 Bleeding

EU animal welfare legislation dictates that bleeding must be started as soon as possible after stunning and be carried out in such a way so as to bring about rapid, profuse and complete bleeding [115, EC, 1993]. In any event, it must be carried out before the animal regains consciousness. There are special provisions in the legislation which apply to slaughter according to certain religious rites. In the EU MSs, the religious authority on whose behalf slaughter is carried out is the competent authority for the application and monitoring of these provisions, operating under the responsibility of the official veterinarian. Otherwise, all animals that have been stunned must be bled, by incising at least one of the carotid arteries or the vessels from which they arise. After incision of the blood vessels, no further dressing procedures or any electrical stimulation may be performed on the animals before the bleeding has ended. Bleeding also aids the preservation of the meat, by removing a breeding ground for micro-organisms.

Carcases are bled over a trough or tank, to collect the blood. In some slaughterhouses the blood tanks are only large enough to hold the blood of a small number of animals, e.g. 10, to ensure that if one animal's blood is contaminated, or if a carcass is condemned after inspection by the veterinarian, only a small portion has to be disposed of.

The blood trough is normally fitted with a double drain, one opening for the blood to be pumped to a tanker for disposal and the other for wash-water. Removable plugs seal the openings when they are not in use. Some slaughterhouses have installed additional blood collection sumps at other parts of the process, such as at the legging platform where the back legs are skinned.

At cattle and pig slaughterhouses, some blood may be hygienically collected for human consumption, e.g. for black pudding or pharmaceutical use. Hygienic blood collection from pigs can be carried out by traditional bleeding, e.g. in small pans or a trough or by using hollow knives. The hollow knife is slightly broader than an ordinary knife and is double edged. The operator can hold the knife in place, or it can be fixed in position by a clamp or by a small hook fixed at its base. The blood runs from the hollow knife through the handle and a tube to a collection vessel. When bleeding is completed, the knife is placed back into its holding carousel for automatic cleaning and a clean knife is selected for the next animal. Bleeding/sticking knives can be washed, but not sterilised to the standards necessary to destroy all pathogenic organisms, especially TSE agents, in the interval between two kills [202, APC Europe, 2001].

Typically, a total of between 2 - 4 litres of blood is collected from each pig and about 10 - 20 litres per head of cattle. After the collection of the initial flush of blood the animals are hung over a blood trough to collect the remainder of the free-flowing blood. Whilst the use of hollow knives is considered to be a very good system for obtaining high quality blood it gives a lower yield of blood collection at this stage on the slaughter-line and, therefore, increases the potential for blood to continue to drip from the carcass, leading to contamination of waste water later [220, APC Europe, 2001]. The lower yield is related to the back pressure associated with the use of the hollow knife and the time that the hollow knife is allowed to remain in the animal. In most cases the time is limited to 20 - 40 seconds because of the speed of operation of the slaughter-line. In practice, the hollow knives are only used in big slaughterhouses and only for the length of time required to obtain the quantity needed for the collection of food grade blood. In addition, it is not possible for the slaughterman to know whether the incision of the blood vessels has been accurate. [260, EAPA, 2002]

Typically, the blood collected is pumped from the trough to a refrigerated tank/tanker where additives, e.g. citric acid or sodium citrate, are added to prevent coagulation. The addition of 100 ml of a 20 % solution of sodium citrate per pig may be added automatically using a flow-meter. Alternatively, the fibrin which binds blood clots together can be removed by stirring with a paddle. Plate heat-exchangers may also be used to chill the blood to a temperature of about 2 °C. The blood can be continually agitated in the tank [260, EAPA, 2002]. In the UK, approximately 15 % of mammalian blood is chilled prior to collection and processing. The main reason for this is to maintain the functionality of the plasma proteins for, e.g. use in pet foods. The storage of blood above 10 °C is reported to quickly lead to odour problems.

Some UK slaughterhouses use an electrical conditioning process to improve the meat quality for cattle, pig and lamb carcasses. At one slaughterhouse pig carcasses are subjected to 600 V for 5 minutes on a carousel system. It is reported that bleeding with a hollow knife together with electrical stimulation, e.g. at 40 V for one minute, facilitates hide removal as well as improving the quality of hides and skins, due to earlier rigor mortis. It is reported that the pH of meat is reduced from 7.0 to 5.6 in 2 hours instead of 18 hours. There is some debate about whether it may also help to drain the blood from the carcass.

Blood has the highest COD strength of any liquid effluent arising from meat processing operations. Liquid blood has a COD of about 400 g/l and a BOD of about 200 g/l. The containment of blood is, therefore, one of the most important environmental controls at a slaughterhouse. The spillage of blood is potentially one of the most environmentally harmful accidents that can happen. Spillage from blood tanks has occurred when blood trough pumps have been left on overnight during floor cleaning, thereby causing the blood tank to overflow. The blood may escape to local water courses or cause problems in an on-site WWTP, due to shock loading. The risk of this can be reduced by installing a high level alarm on the blood tank, linked to an automatic cut-off device for the blood trough pumps. Here a ballcock hits an electrical switch and a solenoid activates a valve, which prevents any further addition [288, Durkan J., 2002].

During bleeding blood coagulates on the base/walls of the trough. This is either hosed down and washed directly to the WWTP or in some slaughterhouses it is collected by shovels, squeegees or by vacuum suction and as much as possible is pumped to a blood tanker. Such coagulated blood can be rendered, but cannot be used in blood processing. In most slaughterhouses, the blood trough is pitched and curved so that partially congealed blood can be directed into the drain and to the blood tanker. If the coagulated blood is collected first, a few litres of water can, usually with the permission of the renderer, be used to rinse blood into the blood tanker. The plug in the drain leading to the WWTP is then opened and the whole trough is washed down with water.

Some slaughterhouses have traditionally allowed all or a significant proportion of the blood they collect to run to their WWTP. This has always been considered to be bad practice, due to the high COD and BOD and because it also removes the possibility of other routes for the use and/or disposal of blood being followed. This route is not permitted under ABP Regulation 1774/2002/EC, which prescribes permitted routes for use and disposal, depending on the Category, as defined therein.

2.1.2.4 Hide and skin removal

Machines to remove hide and skin typically pull the hide/skin from the carcass. Two chains are hooked to the hide/skin and are then wound onto a drum to pull the hide/skin. Some sheepskins are removed manually, but automated removal is also common. The hides and skins are supplied to tanneries for the production of leather goods. In some slaughterhouses, the hides and skins are salted to improve preservation, as described in Section 2.1.2.13.

Knives and similar tools, such as flaymasters, which are pneumatic tools with guards commonly used to minimise flay cuts, are used to remove animal hides and skins. These have a tendency to become contaminated with faecal material. Care is taken to ensure that dirty knives are not be used for any operations where the carcass meat has been exposed. They must be decontaminated first by removing any debris and then, e.g. dipping them in hot water at 82 °C for 10 seconds.

In some slaughterhouses, pig carcasses are skinned like cattle carcasses. Pigs are washed before the skin is removed using a hide-puller. The hide-puller is driven by a powerful motor or hydraulic piston and it pulls the skin off the carcass. The vertebral axis of the animal can be temporarily strengthened by brief electrical stimulation to tighten the muscles, otherwise some hide-pullers can cause a separation of the vertebrae, particularly in younger cattle. [27, University of Guelph, undated]

After the hides/skins are removed, the carcasses are conveyed to the part of the slaughter-line known as the clean slaughter-line, for dressing and the hides/skins are taken to the hide/skin treatment area.

2.1.2.5 Head and hoof removal for cattle and sheep

After the bleeding of cattle and sheep, the animals' forelegs, tail and udder/testicles are manually removed using knives. At some cattle slaughterhouses, the operator cuts a slit in the neck to allow further blood to escape, before cutting the head off. The tongue and cheeks may also be removed for human consumption, except in certain MSs where cheeks are SRM [113, EC, 2000]. Cattle and sheep heads are washed, inspected, then stained with the other SRM and disposed of.

Hooves are traditionally supplied for use in the manufacture of glue but may also be ground for use in pet food. They may also be used to produce horn meal fertiliser.

2.1.2.6 Pig scalding

Pig carcasses are normally passed through a series of unit operations to remove the bristles. Traditionally the pig carcass is passed through a static or rotary scalding tank filled with water between 58 °C and 65 °C for 3 – 6 minutes to loosen the bristles and toenails. Under normal conditions, there is little or no heat penetration into the underlying flesh, so the meat quality is unaffected. Scalding at this temperature for longer than 6 minutes damages the skin. Lime salts or a depilatory agent, such as sodium borohydride, may be added to the water to facilitate loosening of the hair.

For a slaughterhouse processing about 100 pigs per hour, a typical static scalding tank would be about 4 metres long, 1.7 metres wide and 0.8 metres deep and would contain about 5500 litres of water. A typical rotary scalding tank may contain about 2500 litres of water and hold up to 14 carcasses at a time. Some large slaughterhouses use a conveyor system to drag the carcass through a longer tank with countercurrent water filtration and recycling. In Italy, because pigs are bigger, a typical scalding tank is longer, i.e. up to 10 metres long and it may contain 12000 litres of water [237, Italy, 2002].

Steam heating is normally used to maintain the temperature in the scalding tank and continuous make-up water is required to balance drag-out, which drips onto the floor and into the de-hairing machine. The scalding process produces some steam and odour.

Debris and sludge builds up in the scalding tank during the day. It is common practice to empty the water and sludge directly into the site waste water drainage system at the end of production.

Alternative scalding methods may involve the use of either condensation or steam. Microbial contamination can be minimised by the use of steam [27, University of Guelph, undated]. Condensation/steam scalding uses humidified air. The heat is transferred to the carcass surface through the condensation of steam. The heat and moisture are transferred to the scalding air by the atomisation of hot water in the circulating airflow. This process can maintain a constant temperature and 100 % humidity under varying loads, which is crucial for good scalding performance.

2.1.2.7 Pig hair and toenail removal

An automatic de-hairing machine is used to remove bristles and toenails from pig carcasses. This comprises a number of rotating rubber flails, or similar, which brush or scrape the surface of the carcass.

In some de-hairing machines, the carcasses are tumbled two at a time horizontally between two sets of rubber flails, with a water spray from above to wash the hair out of the bottom of the machine. The water spray is used to flume hair and toenails to a primary screen. In some slaughterhouses, toenails are collected dry and sent for rendering. In Denmark and Ireland, hair and toenails are rendered [243, Clitavi - DMRI, 2002, 288, Durkan J., 2002].

In some slaughterhouses, the fluming water is recycled back to the de-hairing machine and the water is discharged to the site waste water drainage system once a day. In others, the water spray uses water from the once-through cooling system of the conveyor rail which is used to transport the pigs through the singeing unit.

2.1.2.8 Pig singeing

Pig carcasses are singed to remove residual hair which has not been removed by the de-hairer, to provide a firmer skin texture and to eliminate micro-organisms. The singeing unit commonly uses propane gas burners firing intermittently, usually for about 20 seconds in any minute, or alternatively oil burners, although this is becoming less common. Propane is used in preference to natural gas because of the higher flame temperature, although natural gas is sometimes used if the slaughterhouse has an existing supply. A gas singeing unit may consist of 40 burners that are triggered to fire for 5 seconds as each carcass enters the unit. The singeing time, per carcass, can vary between 5 and 15 seconds, depending on the slaughter rate. The degree of singeing is controlled by the amount of energy supplied. Singeing temperatures are around 900 - 1000 °C. [12, WS Atkins-EA, 2000, 134, Nordic States, 2001, 145, Filstrup P., 1976]

If the pig meat is to be used to make bacon, the carcass is given a “heavy singe”, by leaving the burners switched on continuously during the production run. This produces the rind. In some slaughterhouses, additional singeing may be carried out manually using portable gas burners. If a heavy singe has been applied the carcass undergoes rind treatment. If not, it is rinsed in cold water to cool the carcass.

If the meat is for the production of typical Italian cured products, a light singe is applied.

2.1.2.9 Rind treatment

After singeing, pig carcasses are passed through a black scraping machine to polish the skin and to remove singe hair and other debris. The polisher consists of sets of rotating rubber flails, similar to the de-hairing unit. At some slaughterhouses, additional carcass polishing may be carried out manually using handheld scrapers. Water is applied during rind treatment to cool the carcasses, soften the outer layer of skin and to rinse the bits of skin away.

2.1.2.10 Evisceration

Evisceration involves manual removal of the respiratory, pulmonary and digestive organs. This is done by pulling out the bladder and the uterus, if it is present; the intestines and mesenteries; the rumen and other parts of the stomach; the liver and then, after cutting through the diaphragm, the plucks, i.e. the heart, lungs and trachea. The resulting offal is loaded into pans for inspection and transportation to the offal processing area. The heart, liver, kidneys and non-ruminant intestine may be sold for human consumption. At some pig slaughterhouses the pancreas may be sold to pharmaceutical companies to produce insulin. Some edible fats and trimmings may be rendered to produce lard and dripping.

Australia and New Zealand have recently developed large-scale automated systems for cattle and lamb evisceration, respectively. If successful, these systems are destined to have a dramatic impact on the meat industry, where labour costs in slaughtering have always been a major factor in locating slaughterhouses in relation to meat producing regions. [27, University of Guelph, undated].

Offal, including the lungs and trachea for all animals and the first stomach for cattle and sheep, can be used in the production of pet food. For cattle and sheep, the first stomach is cut open on a table and the contents are removed using either a wet or dry process. In the wet process, it is cut open in a water flow to produce a slurry which is discharged over a screen and then pumped to a holding area. For veal cattle, less than one year old bulls and for cows, the first stomach contents weigh up to 10 kg, 40 kg and 50 kg, respectively [248, Sorlini G., 2002].

In the dry process, the first stomach is opened without water. The contents are removed manually and transported by a pneumatic system or screw conveyor to a collection point. First stomach contents are normally disposed of by spreading on agricultural land, subject to veterinary approval and the nutritional needs of the soil. Some companies use a piston compactor to reduce the volume of the contents for easier handling. After dry contents removal, the first stomach is washed in running or recirculated water.

The majority of slaughterhouses use a compressed air ring main to power equipment. In such cases, it is standard practice to use this to power a pneumatic system to blow the first stomach contents to the collection point.

In some slaughterhouses macerator equipment is used to chop, wash and spin-dry the remaining offal prior to supply to the rendering company. This can reduce the offal volume by over 50 %.

It is not necessary to wash the carcasses in the evisceration area, although it is sometimes undertaken if there is contamination present from damaged viscera.

2.1.2.11 Splitting

After evisceration, the cattle, mature sheep (not lamb, because it is not necessary to remove the spinal cord as a TSE precaution) and pig carcasses are split along the spine using a saw. Water is sprayed onto the blade to remove any bone dust which is generated. The spinal cords of the cattle and mature sheep are then removed from the carcass and disposed of as SRM. Some slaughterhouses use a vacuum system which sucks the spinal cord material to the SRM waste skip. In other slaughterhouses, the spinal cord is removed manually and the cavity is cleaned using a steam spray/suction device. In Italian pig slaughterhouses on the same sites as cutting plants, the carcasses are cut into portions weighing a maximum of 15 kg, before chilling, for the production of typical Italian cured products [237, Italy, 2002].

In some slaughterhouses, the carcass is given a final rinse with low-pressure potable water before chilling or freezing. At every stage of production the meat is inspected visually to maintain quality standards.

For cattle which are known or suspected TSE sufferers at the time of slaughter, the carcasses are sawn in two, lengthways, ensuring that the spinal cord remains completely enclosed and intact and are sent for rendering followed by incineration or direct incineration.

2.1.2.12 Chilling

The carcasses are chilled to reduce microbiological growth. To reduce the internal temperature to less than 7 °C, they are chilled in batch chillers with air temperatures between 0 °C and 4 °C. Typical chilling times are 24 – 48 hours for beef sides, 12 hours for lamb and 12 – 24 hours for pig carcasses. Pig carcasses can be chilled quickly in a chill tunnel for about 70 minutes at -20 °C, followed by temperature equalisation at about 5 °C for 16 hours. Alternatively, they may be batch chilled at -5 to -10 °C.

The carcasses may then be held in a chilled meat store to further condition the meat prior to despatch to cutting plants, wholesalers, or on to further processing. For cattle, the storage time varies depending on the degree of maturation required by the customer and may be up to 17 days.

Description of refrigeration technology [292, ETSU, 2000]

The refrigeration systems use a refrigerant to transfer heat from the carcasses to be cooled to ambient air (or sometimes water in the case of poultry). A simple refrigeration system comprises the following elements and is depicted in Figure 2.2:

- an evaporator, in which the refrigerant boils (or evaporates) at a temperature lower than the product by absorbing heat from the carcasses or standard cuts
- a compressor, which compresses the gas generated in the evaporator
- a condenser, in which the high-pressure gas pumped by the compressor is liquefied (or condensed). During this process the refrigerant emits heat, usually to ambient air or water
- an expansion device, which reduces the pressure of the condensed liquid back down to the pressure of the evaporator
- a set of controls, such as a thermostat that switches the refrigeration system off when the required temperature has been reached, and switches the system on again when the product has reached its upper temperature limit. The differential between off and on must not be so low as to cycle the refrigeration compressor rapidly
- a high-pressure cut-off switch, which turns the compressor off when the pressure on the high-pressure side of the system rises too high and a low-pressure cut-out, which shuts off the compressor if the suction pressure drops below a set limit (for example, due to loss of refrigerant from the system)
- compressor motor protection devices, which switch off the compressor if the electrical current rises too high.

The amount of heat a refrigeration system removes is measured in watts (W). The heat extraction rate will depend on the size of the system and the conditions under which it is operating.

To drive the system, energy, usually in the form of electrical power, has to be put in to the compressor's motor and to other motors for pumps, fans, etc. This is also measured in watts. The system is operating at optimum efficiency when the minimum input power achieves the maximum heat extraction. The expression used to describe the efficiency of a refrigeration system is the COSP (coefficient of system performance).

$$\text{COSP} = \frac{\text{Refrigeration capacity (watts)}}{\text{Total system power input (watts)}}$$

The COSP should not be confused with the commonly quoted COP (coefficient of performance), which relates to the power consumed by the compressor alone.




Figure 2.2: Schematic diagram of a simple refrigeration system

Refrigerants commonly used include ammonia; ethylene glycol and water; R404 and R22 (an HCFC). The refrigeration condensers may be water-cooled or air-cooled. Some slaughterhouse refrigeration units include heat recovery equipment to capture waste heat in the form of usable hot water.

2.1.2.13 Associated downstream activities - viscera and hide and skin treatments

Viscera treatment

The use of casings varies from country to country. Parts of cattle and sheep intestines are SRM [113, EC, 2000] and these currently cannot be used for sausage casings. Pigs produce about 19 metres of intestine, which can be used for sausage casings. In Denmark, a large proportion of the intestines are used for edible products. In Norway, intestines are rendered.

If the intestines are destined for food use, after veterinary approval, the pancreas gland is cut off the intestine set. The intestine set is then conveyed to the casing cleaning area. It is then separated into the following parts: stomach, fat end (rectum), small intestine (duodenum, jejunum), large intestine (colon) and “blind” intestine (caecum). These are then cleaned and may be salted at the slaughterhouse or off-site.

If the intestines are to be rendered, the contents may be removed first, by, e.g. cutting followed by centrifugation. [134, Nordic States, 2001]

The mucose membrane of the small intestine of pigs can be used for the pharmaceutical industry or in biogas production. [134, Nordic States, 2001]

Hide and skin treatment

Whether hides/skins are salted or not may depend on customer requirements. If hides/skins can be delivered to a tannery and processed within 8 – 12 hours after slaughter they generally don't require any treatment at the slaughterhouse. They need to be chilled if they are to be processed within 5 – 8 days. For longer storage times, e.g. if they have to be transported overseas, then salting is reported to be the preferred option, due to the weight of ice and the energy consumption required for ice production and for refrigeration. [273, EC, 2001]

If sheep/lamb skins and cattle hides are to be salted, they may be cooled first with cold water or chilled prior to being stacked flat and then salted, using sodium chloride, or alternatively they may be salted directly. After approximately 6 days they are packed with additional salt and

stored or transported to tanneries for leather production. The hides and skins are normally stored in cool conditions, at about 4 °C.

If trimming is undertaken before salting is performed [276, Anão M., 2002], this reduces the amount of salt consumption, and there is a subsequent reduction in waste water contamination at the slaughterhouse and if the trimmings are used for the manufacture of gelatine, at the manufacturing installation too.

Salt in waste water is difficult to treat [332, COTANCE, 2003]. Specific treatments for preventing or controlling salt emissions via waste water have not been identified. It has been suggested that this may be due to a lack of awareness of salt emissions. Dilution and not treatment appears to be the mechanism by which harm to water courses and plant life is presently reduced.

The tanning industry reports that the washing of animals prior to slaughter is a questionable practice since animals should not be slaughtered in a wet condition for hygiene reasons. From the tanning industry point of view, it is much better that animals are kept clean on the farm and delivered in a clean condition to the slaughterhouse. [332, COTANCE, 2003]. Veterinarians require animals to be clean and dry to prevent carcase contamination during the slaughter and dressing operations. A CEN standard on hide and skin preparation in slaughterhouses is in preparation. Hides and skins are reportedly often sold with, e.g. legs, hooves and parts of heads still attached. It is claimed that tanneries do not have the variety of use and disposal routes for by-products available to them that slaughterhouses have. Fleshing is considered to be a skilled job, possibly not always appropriate to the slaughterhouse operation.

The tanning industry encourages chilling of hides/skins, but considers that salting cannot be phased out where the material is to be transported significant distances, so it encourages its careful execution, avoiding the use of excessive amounts of salt. Brining is not undertaken at slaughterhouses, although it is done at hide/skin markets or in tanneries. The routine use of biocides is considered to be unnecessary, if preservation is undertaken correctly but they may have a role to play, e.g. for storage or transport in hot climates [286, COTANCE, 2002]. Drying is not undertaken in Europe, but it is done in Africa. Icing is encouraged by the tanning industry. Irradiation is not known to take place at slaughterhouses. [286, COTANCE, 2002]. Table 2.1 shows the treatment of hides and skins undertaken at slaughterhouses throughout Europe.

	Belgium	Denmark	Finland	France	Germany	Greece	Ireland ¹	Italy ⁵	Netherlands	Norway	Portugal ¹	Spain ¹	Sweden	UK ¹	Czech Republic
Washing	No ⁴	No		No	No		Yes (some)	Yes (10 %)	No	No	Yes	No	No	Yes (some) ²	Yes
Chilling	Yes (some)	Sometimes		Yes (2) bovine	No		Yes (some)	Yes (5 %)	No	No	No	No	Yes	Yes (20 %)	Yes
Trimming	Yes (bigger ones)	Sometimes		Yes (150)	Yes (South)		Yes ³	No	No	Yes	Yes (some)	Yes	Yes	Yes ³	Yes
Fleshing	No	No		No	No		No	No	No	No	No	No	No	No	Very little
Salting (sodium chloride)	Yes (small)/ No (big)	Sometimes		Yes (100 - 150)	Yes	Yes	Yes (some)	Yes (95 %)	No	Yes	Yes	Yes	No	Yes (3 - 4)	Yes
Salting (potassium chloride)	No	No		No	No		No	Yes (5 %)	No	No	No	Yes/No	No	No	No
Brining	No	No		Yes (few)	No	Yes	No	No	No	No	No	No	No	No	No
Biocide addition	No	No		Yes (100)	No	Yes	No	No	No	No	Yes (ovine/caprine) partly in bovine	No	No	No	No
Drying	No	No		Yes (10) caprine	No		No	No	No	No	No	No	No	No	No
Preservation in flake ice	Yes (slowly)	Sometimes		Yes (50) bovine	Yes (in some smaller slaughterhouses)		Yes (some)	No	No	No	No	Partly	No	Yes	Very little
Preservation in flo-ice	No	No		No	No		No	No	No	No	No	No	No	No	No
Irradiation	No	No		Experimental - bovine	No		No	No	No	No	No	No	No	No	No

¹ Unconfirmed

² If excessively dunged animals are rejected for slaughter

³ On animals over 30 months trimming takes place at the slaughterhouses, on others at the hide/skin market

⁴ Weak enforcement of health and safety recommendations

⁵ None of these processes are undertaken at pig slaughterhouses

Numbers in brackets refer to the numbers of installations

Table 2.1: Treatment of hides and skins undertaken at slaughterhouses
[286, COTANCE, 2002, 323, Czech Republic TWG, 2002]

2.1.3 Slaughter of poultry

2.1.3.1 Reception of birds

It is essential that crates, modules and vehicles used to transport birds are thoroughly cleaned between collections, to reduce the spread of any infection which may be present. The poultry processor generally provides separate facilities for cleaning and disinfecting the crates, modules and vehicles, unless there are facilities available elsewhere at officially authorised facilities. [223, EC, 1992]

The withdrawal of feed prior to loading the birds for transportation to slaughter can help reduce the level of faecal contamination during transportation and, therefore, can reduce the amount of effluent produced during cleaning operations. It can also reduce the amount of crop and intestinal tract contents.

In general, crate cleaning is a three-stage process, which offers considerable opportunities for re-using and recycling water. Many of the larger poultry processors have installed automated crate washing equipment to permit a thorough cleaning immediately following delivery of the birds. Other processors provide a variety of manual and semi-automatic cleaning facilities.

Due to the birds struggling and flapping their wings during unloading and hanging, a significant quantity of dust is produced in those areas. The dust is generally removed using exhaust ventilation and bag filters.

2.1.3.2 Stunning and bleeding

After the birds have had time to settle they are removed from their crates/modules and put onto the killing line. They are required to be stunned, before being killed, except in the case of slaughter according to religious rites [223, EC, 1992]. They are hung upside down by their feet, using shackles on a conveyor which moves them towards the stunning equipment. A commonly used stunning system uses a water-bath, which constitutes one electrode and a bar which comes into contact with the shackles and forms the other electrode. The bird is stunned as soon as the head comes into contact with the water. After stunning, the bird is bled for up to two minutes before being dressed. Bleeding may be initiated by an automatic circular knife system. The neck arteries of turkeys are sometimes cut using a handheld knife.

Normal bleeding also occurs in poultry that have been killed by electrocution instead of being electrically stunned [27, University of Guelph, undated].

Turkeys may be stunned using CO₂ [27, University of Guelph, undated].

Since poultry are bled whilst they are hanging from a moving conveyor, the majority of poultry slaughterers collect the blood in a tunnel or walled area.

The cheapest option for the disposal of blood is to collect it separately. Efficient bleeding processes and maximum blood collection in the killing tunnel are therefore essential. Well designed blood tunnels need to be long enough and have high enough walls to capture all the spurting blood from freshly killed birds.

The blood trough is normally fitted with a double drain, one opening for the blood to be pumped to a tanker for disposal and the other for wash-water. Removable plugs seal the openings when they are not in use.

Blood has the highest COD strength of any liquid effluent arising from meat processing operations. Liquid blood has a COD of about 400 g/l and a BOD of about 200 g/l. The containment of blood is, therefore, one of the most important environmental controls at a

slaughterhouse. The spillage of blood is potentially one of the most environmentally harmful accidents that can happen. The blood may escape to local water courses or cause problems in an on-site WWTP, due to shock loading. Spillage from blood tanks has occurred when blood trough pumps have been left on overnight during floor cleaning, thereby causing the blood tank to overflow. The risk of this can be reduced by installing a high level alarm on the blood tank, linked to an automatic cut-off device for the blood trough pumps. Here a ballcock hits an electrical switch and a solenoid activates a valve, which prevents any further addition [288, Durkan J., 2002].

During bleeding blood coagulates on the base/walls of the trough. This is either hosed down and washed directly to the WWTP or in some slaughterhouses it is collected by shovels, squeegees or by vacuum suction and as much as possible is pumped to a blood tanker. This coagulated blood can be rendered, with the other poultry blood. In most slaughterhouses, the blood trough is pitched and curved so that partially congealed blood can be directed into the drain and to the blood tanker. If the coagulated blood is collected first, a few litres of water can, usually with the permission of the renderer, be used to rinse blood into the blood tanker. The plug in the drain leading to the WWTP is then opened and the whole trough is washed down with water.

Some slaughterhouses allow all or a significant proportion of the blood they collect to run to their WWTP. The WWTP in these cases needs to be capable of treating the high COD and BOD. This may incorporate the production of biogas. It is more usual for poultry blood to be sent for rendering [271, Casanellas J., 2002].

Excessive body movement of the slaughtered poultry may splatter blood on to the conveyor, out of the bleeding area and onto the feathers of adjoining birds, where it will be washed off in the scalding process. Ensuring that the birds are adequately stunned at slaughter will reduce such movements, allowing more efficient blood collection and reducing waste water effluent strength.

2.1.3.3 Scalding

After stunning and bleeding, the birds are immersed in a scalding tank to loosen the feathers to facilitate de-feathering. Birds destined to be sold frozen are usually 'hard scalded' at 56 - 58 °C. Carcasses to be air-chilled, for fresh sale, are most often 'soft scalded' at 50 - 52 °C to avoid damage to the cuticle and resultant skin discolouration. In the Nordic countries, chickens for freezing are scalded at approximately 58 – 60 °C and chickens for chilled distribution are scalded at approximately 50 - 51 °C [243, Clittravi - DMRI, 2002].

As birds enter the scalding tank they may involuntarily defecate, leading to the accumulation of faecal materials in the water. In water, poultry faeces dissociate to form ammonium nitrate and uric acid which form a natural buffer which has the effect of maintaining the scalding tank at about pH 6, the point at which salmonellas are most heat resistant. In most cases, the scalding tanks are emptied into the wet feather flume at the end of the day shift.

2.1.3.4 De-feathering

Feathers are removed mechanically, immediately after scalding, by a series of on-line plucking machines. The machines comprise banks of counter-rotating stainless steel domes or discs, with rubber fingers mounted on them. Rubber flails mounted on inclined shafts are sometimes used for finishing. Any feathers remaining on the bird after mechanical plucking, including pin feathers, are removed by hand. In Finland, de-feathering may be performed by rubbing the scalded carcass with rotating rubber fingers and using pressurised water jets.

Continuous water sprays are usually incorporated within the machines for flushing out feathers. Feathers are commonly taken to a centralised collection point via a fast-flowing water channel located below the machine. The feathers may then be sent for rendering, composting, co-incineration with chicken litter in large combustion plants, or landfill, although the latter is becoming less available as an option [241, UK, 2002]. Dry feather collection systems, using a conveyor belt in conjunction with a vacuum or compressed air arrangement are sometimes used, e.g. if the feathers are to be supplied to the feather/down industry.

After plucking, the surfaces of the chickens are cleaned by showering, possibly combined with beater straps. The chickens are then transferred from the unclean to the part of the slaughter-line to where the clean processes are carried out, known as the clean slaughter area. They are then inspected externally and the heads and feet are cut off. Some slaughterhouses have equipment for cleaning the feet for human consumption. The feet are cleaned with water at 80 °C. The equipment is only used when there is a viable market for this product.

For ducks, wax is used to remove the feathers. The ducks are dipped in a bath of hot wax and then passed through cool water sprays so that the wax hardens. The hardened wax, with the feathers attached, is either mechanically or hand stripped. The plucked carcasses are then spray-washed. The wax is melted and recycled.

2.1.3.5 Evisceration

After de-feathering and head and feet removal the birds are eviscerated, i.e. the internal organs are removed. In the majority of production sites, evisceration is carried out mechanically, but manual evisceration is still practised in some of the smaller companies. On automated lines, a cut is made around the vent, a spoon-shaped device is inserted into the opening and the viscera are withdrawn. Common practice is to allow the viscera to remain attached by their natural tissues and to hang them over the back of the carcass for post-mortem inspection. Some modern machinery holds the birds horizontally by the head and hocks so that when the viscera are removed from the body cavity they come out sideways and are placed on a tray beside the bird.

2.1.3.6 Chilling

After evisceration and inspection, fresh poultry meat must be cleaned immediately and chilled in accordance with hygiene requirements to a temperature not exceeding 4 °C. There are several designs of chilling equipment used; the most popular are immersion chillers, spray chillers and air-chillers. Council Directive 92/116/EEC of 17 December 1992 amending and updating Directive 71/118/EEC on health problems affecting trade in fresh poultrymeat [223, EC, 1992] sets out the legal requirements. Poultry carcasses and parts must not be water chilled by simple immersion in a container of cold water. Water chilling must solely be used in a countercurrent chiller. [355, AVEC, 2003] Poultry meat to be subjected to an immersion chilling process must, immediately after evisceration, be thoroughly washed, both internally and externally, by spraying and then immersed without delay. The water must be potable and a minimum consumption per bird is specified in public health/food hygiene legislation [174, EC, 1880, 223, EC, 1992].

Immersion/spin chilling

Carcasses are chilled in a single water-bath or in a series of water-baths. They are moved through a countercurrent of water, so that they are constantly moving into cleaner water. The water needs to have a continuous and opposite flow to the direction of the bird. This is usually achieved by designing the system so that the outlet for the water is a weir at the bird input end. If there is more than one chiller, then the flow in the first stage has to be greater than in the previous and then progressively reduced through each stage. This system can lead to a build-up of blood and carcass material in the water, depending on the effectiveness of the pre-chilling

washing system and the countercurrent. The birds are passed through a series of water-baths filled with water at 0 - 1 °C. Flaked ice is added, e.g. at a rate of 6 tonnes per hour for a slaughterhouse killing 20000 turkeys per day.

At present, immersion chilling is the least expensive method of chilling poultry. Carcasses take up water during chilling and in some MSs microbial contamination is controlled by chlorination of the water, within potable water limits. This is generally done using chlorine dioxide, even though it costs more than using chlorine. Immersion chilling has the highest legal limit of water uptake, i.e. 4.5 % [243, Clitravi - DMRI, 2002].

Spray chillers

These avoid the problems associated with the build-up of contamination in chiller tanks, but they can give rise to the spread of bacteria through aerosols. Spray chillers may also use high volumes of water, reportedly up to 1 litre of water per bird.

Air-chillers

These are generally used when the carcasses are destined for sale fresh. Chilling is either carried out in batches in a chill room or by continuous air blast. Tests have shown that air-chilling can reduce the contamination rate by up to three times more than immersion chilling [67, WS Atkins Environment/EA, 2000].

Most chicken processors have now switched to air-chilling because this uses the least amount of water and extends the shelf-life of the product. Water chilling is, however, widely used by turkey processors in order to comply with USDA and UK hygiene requirements for rapid chilling of these larger carcasses. After spending about an hour in a countercurrent immersion chilling tank to reduce the carcass temperature, the turkeys are further chilled for 24 hours by loading 30 - 40 birds into 1m³ tanks filled with water at 0 - 1 °C and ice at -8 °C, to achieve the requirement for the water temperature of the final chiller to be less than 4 °C [67, WS Atkins Environment/EA, 2000, 246, AVEC, 2002]. Air-chilling can cause dehydration of the carcass, but it helps to preserve the flavour of the poultry meat and can help the product command a premium price [27, University of Guelph, undated].

Description of refrigeration technology (see Section 2.1.2.12)

2.1.3.7 Maturation

Where carcasses require maturation after chilling, further conditioning using a refrigeration medium (air, ice, water or other food-safe process) can be used which may continue the cooling process of the carcass or parts of carcasses. Council Directive 92/116/EEC of 17 December 1992 amending and updating Directive 71/118/EEC on health problems affecting trade in fresh poultrymeat allows maturation, after chilling, by water immersion in static slush ice tanks. Unlike water chilling they do not have to move through a countercurrent of water. [355, AVEC, 2003]. The birds are immersed in stainless steel tanks in water and ice, to cool them to 1 °C. They are then stored in a room with temperature control at 0 - 1 °C for up to 24 hours. [214, AVEC, 2001]

2.1.4 Slaughterhouse cleaning

For hygiene reasons, many slaughterhouse operators wash down process areas with hot water during breaks in production. All process equipment, containers, etc., must be cleaned and disinfected several times a day and after the day's work is finished in preparation for work starting again [169, EC, 1991]. A typical cleaning routine at a slaughterhouse consists of the following steps.

Meat scraps, fat, etc. are squeegeed and shovelled up throughout the shift and collected for use/disposal according to ABP Regulation 1774/2002/EC. In some slaughterhouses, the meat scraps are hosed to the catch pots, if present and drains. Some areas are also hosed down lightly at regular intervals during the shift. Hosing down uses water which becomes contaminated with solid material as well as FOG. At breaks in production, some drain catch pots are emptied into the waste bins. Each drainage point can have a grate cover and a catch pot, typically with a 4 mm mesh. Some slaughterhouses use a two-stage catch pot, comprising a coarse screen above a fine screen in an “inverted top hat” arrangement.

Typically, at the ends of shifts, all process areas are washed using low-pressure hoses and all drain catch pots are emptied into the waste skip. A dilute proprietary detergent is then applied as foam onto all surfaces. After about 20 minutes or so the surfaces are then rinsed with high-pressure hot water. In some slaughterhouses, a very dilute sanitising compound is sprayed on to all surfaces and left to dry. At many slaughterhouses, hooks, shackles, pans, etc., are cleaned *in situ* in a similar way.

Only food grade cleaning agents can be used. There is a wide variety of cleaning materials available. Some have traditional chemical formulations and others are based on biotechnology. Some are formulated for specific or difficult cleaning problems, whereas others are intended for general use.

Hygiene requirements prohibit the use of HPLV sprays in meat areas during processing operations, as the atomised water can lead to airborne contamination. They can, however, be used for cleaning at the end of production. Good hygiene is vital for food safety reasons and there are strict EU and MS legal requirements. Using too much water can, however, have negative hygiene consequences. For instance, a very humid environment combined with the constant movement of machinery and the close proximity of carcasses to each other on the slaughter-line can lead to the spread of contamination by direct splashing and aerosols.

When the use of cleaning agents is reviewed at slaughterhouses, it is often found that changing to a more appropriate cleaning agent can reduce the amount of chemical required and in some cases can also improve hygiene standards. It is not unusual to find that higher doses than required are being used, especially during manual dosing. Automated dosing, if correctly set, has the advantage of stopping overdosing. It also has health and safety advantages because it minimises both personal exposure to hazardous substances and manual handling. In any case, adequate operator training and supervision are essential. There are, therefore, often opportunities to reduce the environmental impact of cleaning agents by selecting/substituting and applying them correctly.

In many slaughterhouses, it is common practice for the personnel involved in cleaning to remove floor grates and to flush meat scraps directly down the drain, believing that a subsequent screen or catch pot will trap all solids. In fact, when these meat scraps enter the waste water stream they are subject to turbulence, pumping and mechanical screening. This breaks the meat down and releases high COD substances into solution, along with colloidal and suspended fats and solids. Subsequent waste water treatment, either on-site or at a municipal WWTP can then be expensive. The breakdown of suspended fats and solids is increased if the water is hot. A review of cleaning practices may also identify if there is an excessive use of energy to heat water and possibly unnecessarily high water consumption.

2.1.5 Storage of slaughterhouse by-products

The animal and public health rules laid down in ABP Regulation 1774/2002/EC cover, amongst other things, the storage of animal by-products.

Arrangements for the storage of animal by-products vary between premises. To some extent they depend on the nature and characteristics of the by-product and its intended use or disposal

route. Generally, the storage of materials can be undertaken within an enclosed area, operated under negative pressure, provided with extractive ventilation connected to a suitable odour abatement plant. The decision whether to store by-products in such an enclosed and sometimes refrigerated space may depend on whether they are intended for sale or for disposal, at a cost. A major consideration in any case is whether unrefrigerated storage will result in odour problems. Some by-products, such as intestines are malodorous when fresh and others become so as they degrade. Malodorous materials can cause problems both during storage at slaughterhouses and during storage, handling, processing and disposal at animal by-products installations.

Some slaughterhouses store animal by-products in open containers in the open air and rely on frequent removal from the site, e.g. once or twice a day, to prevent odour problems from putrescible materials.

Some, but not all, slaughterhouses store blood and other non-process liquids, such as fuel oils, in double skinned tanks. Other hazardous substances commonly stored at slaughterhouses include cleaning and sanitising chemicals, effluent treatment chemicals, ethylene glycol, ammonia and other refrigerants. These may be stored in bulk storage tanks, IBCs, or dedicated drum storage areas.

There is a risk of spillage of these substances, especially during handing or transport around the site. Tanks and containers are often located in areas where there is a risk of them being damaged by moving vehicles [12, WS Atkins-EA, 2000]. In addition to the environmental risks, there are also health and safety risks associated, not only with the spillage of substances hazardous to health, but also from the vehicle/pedestrian interface. Management of site layout and use, in conjunction with hardware safeguards such as the provision of bunds and crash barriers around storage areas, can reduce the risk of accidents.

2.2 Animal by-products installations

Annex IV of the Directive requires *the furthering of recovery and recycling of substances generated and used in the process and of waste, where appropriate* to be considered when determining BAT. Some MSs have national legislation which is in line with this policy.

Article 3(c) of the Directive supports sustainable development, by promoting preventive measures for minimising the waste generated and for diminishing the harmful properties of waste. It requires the recovery of waste, if this is technically and economically feasible. This can be primarily in the form of material, and secondarily as energy [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001].

2.2.1 Fat melting

Although this section describes fat melting, the reader's attention is drawn to the fact that this activity is similar in many ways to rendering and some of the equipment described is identical for both processes. The feedstocks differ and consequently the conditions for separating the fat, water and solids fractions vary accordingly. The product of fat melting is generally for food use, so feedstocks are required to be fresh and consequently cause less odour problems during storage and processing.

Three methods of fat melting have been reported: batch wet fat melting, batch dry fat melting and continuous wet fat melting. The method used affects the quality of fat produced. The most important quality demands are: low content of free fatty acids (FFA); low water content; good keeping qualities; low peroxide value; neutral taste, flavour and colour and high solidification point. Extended storage and processing times adversely affect both quality and environmental standards. Unfresh raw materials may cause odour problems and add to the waste water pollution burden.

Under certain conditions, fat undergoes two important chemical changes, i.e. hydrolysis and oxidation. Hydrolysis is a chemical reaction between fat and water, through which free glycerides and FFAs are formed. The compounds formed during oxidation give the product a rancid taste.

The handling and storage of the raw material before processing and the type of processing carried out determine the FFA and the peroxide value.

To achieve a low water content the fat may be purified in a separator. The water content of the fatty raw material normally ranges between 6 - 25 %.

The FFA content increases with the duration of storage and treatment, especially any time at raised temperatures. To avoid this, the constituents need to be separated quickly.

Batch wet fat melting

Batch wet fat melting is the oldest method of fat melting. An autoclave is filled with precut raw material and is then closed. Live steam is then injected into the raw material at a pressure corresponding to a saturation temperature of about 140 °C. To minimise the heating time, the cooking vessels are not too large and are equipped with agitators.

Since the method is wet a good separator needs to be used, to ensure the final water content is below the required level.

After a heat treatment lasting 3 - 4 hours, depending on the size of the autoclave and the nature of the raw material, the pressure is slowly reduced to atmospheric pressure, in order to avoid emulsification.

After a settling period, the free fat is drained from the autoclave to an intermediate tank, and the moist greaves are pressed and then dried. The fat collected is allowed to settle or is separated.

The batch wet fat melting/rendering process is illustrated in Figure 2.3.




Figure 2.3: The batch wet fat melting system with autoclaves
[145, Filstrup P., 1976]

Batch dry fat melting

Batch dry fat melting employs indirect heating. The melting vessel is steam-jacketed and often also has a steam-heated agitator. The operating pressure can vary from slightly above atmospheric to a vacuum. The latter will require a shorter processing time because the water is evaporated at a lower temperature.

The material is agitated during heat treatment and good heat transfer is obtained. It is, therefore, possible to use lower temperatures than for wet fat melting and to still liberate the fat in one batch within a shorter period of 1.5 - 2 hours. The water in the raw material is removed by evaporation. It is important that the heating process is stopped before all the water is evaporated, otherwise the product will be discoloured.

After discharge into a percolator, the free fat is drained to an intermediate tank. The greaves are then pressed or centrifuged, and then milled.

As with wet fat melting, the liberated fat is either allowed to settle or is centrifugally separated before packaging.

Dry fat melting requires less space and time than wet fat melting. Due to the process being dry, the fat yielded will not be equally neutral in taste, flavour, or colour, even if the cooking cycle has been carried out correctly. The slightly roasted taste of the fat is a desirable feature in some countries. Compared to wet processing, an advantage is that all of the water is removed by evaporation and there is less waste water contamination, because water is not added to the raw material which would then need to be subsequently removed. The evaporated water will, however, contain some volatile substances released during the drying process. There is a disadvantage, in that certain discolouring elements, which would otherwise have been extracted with the water, now remain in the fat.

The batch dry fat melting/rendering process is illustrated in Figure 2.4.




Figure 2.4: The conventional batch dry fat melting/rendering method
[145, Filstrup P., 1976]

Continuous wet fat melting

Continuous processing combines mechanical and thermal treatments in order to minimise the processing time.

The raw material is first passed through a mincer. It is then conveyed to an airtight section, where it is heated in two stages to about 60 °C and 90 °C respectively, in a matter of a few minutes.

The heated material is then separated in a decanter centrifuge, especially designed for the continuous removal of solids from a liquid. The solids, known as greaves, leave the plant at this point. The liquid, now consisting mainly of fat, but also containing some water and fines, is subjected to a final purification. In this stage, it is separated into three phases. The “fines” are automatically discharged from the purifier at preset intervals.

The final purified fat flows through a plate heat-exchanger, in which it is cooled down to about 40 °C before leaving the plant.

The direct injection of steam makes the processing time very short, displaces the air and minimises oxidation of the product. It has been reported that there is no rise in the FFA content or peroxide value in fat processed by continuous wet fat melting.

Continuous wet fat melting takes less time and space than either batch wet fat melting or batch dry fat melting. The fat yield is, however, lower than the batch methods because the effluent water and the greaves contain more of the fat.

The continuous wet fat melting process is illustrated in Figure 2.5.




Figure 2.5: The continuous low temperature wet fat melting system
[145, Filstrup P., 1976]

The combinations of techniques in use are numerous. Some further examples also used in rendering are described briefly in Section 2.2.2 and Table 2.5. Their relationship with the quality of fat produced is shown in Table 2.2.

System	Quality of fat produced
Batch dry rendering/fat melting	
Continuous drying in recycled fat	Low quality fat
Wet pressing or other separation, evaporation, drying in fat, pressing	Fair quality fat
Separation, evaporation, drying in natural fat	Drying difficult with pressure cooking before
Cooking and drying in added fat in multiple-effect evaporator, pressing	Fair quality fat
Wet pressing, separation, multiple-effect evaporation, drying without fat	Good quality fat

Table 2.2: The relationship between rendering/fat melting system and the quality of fat produced [289, EFPA, 2002]

2.2.2 Rendering

Although this section describes rendering, the reader's attention is drawn to the fact that this activity is as previously stated in Section 2.2.1, similar in many ways to fat melting and some of the equipment described is identical for both processes. The feedstocks differ and consequently the conditions for separating the fat, water and solids fractions vary accordingly. The raw materials used in rendering are frequently waste and are in practice have often been allowed to degrade so they cause more odour problems during storage and processing and require techniques for the treatment of odour and of high BOD waste water.

The term "processing" in ABP Regulation 1774/2002/EC [287, EC, 2002] is used to describe operations traditionally referred to as "rendering".

The rendering process uses animal by-products from meat production. These originate from, e.g. slaughterhouses, meat processing plants, butcher's shops, supermarkets and livestock rearing facilities. The by-products include carcasses, parts of carcasses, heads, feet, offal, excess fat, excess meat, hides, skins, feathers and bones. For example, about 10 – 11 % of a pig is rendered [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]. In Germany, an average of 35 % of the live weight of all species is treated by inedible rendering [347, German TWG members, 2003]. The type of raw material in each rendering plant varies. Some plants specialise in individual species, e.g. producing just poultry meal and fats.

The rendering process comprises a number of processing stages, as follows, although the order may vary between installations. The raw material is received at the installation and stored. Preparing the raw material for rendering generally involves size reduction, to meet the requirements of ABP Regulation 1774/2002/EC. The material is then heated under pressure to kill micro-organisms and to remove moisture. The liquefied fat and the solid protein are separated by centrifugation and/or pressing. The solid product may then be ground into a powder to make animal protein meal, such as MBM or feather meal. The final products are transferred to storage and despatch [241, UK, 2002]. The waste solids, liquids and gases are then treated and disposed of, possibly with some intermediate storage. For certain materials, the conditions under which sterilisation must be carried out are prescribed in ABP Regulation 1774/2002/EC.

ABP Regulation 1774/2002/EC specifies the operating conditions required for rendering animal by-products not intended for human consumption. These vary depending on the risk associated with the materials. The risks are divided into Category 1, 2 or 3 materials, which are defined. The conditions include, e.g. requirements for the segregation of slaughterhouses from animal by-products processing premises; separation of clean and unclean areas; adequate capacity of specified services and size reduction equipment. It also states general hygiene requirements and details operating conditions, including particle size, temperature, time and pressure. These are summarised in Table 2.3.

METHOD	Maximum particle size (mm)	Simultaneous temperature & time (°C) (min)		Pressure requirement	Batch	Continuous	ABP Regulation 1774/2002/EC Category 1 TSE confirmed suspected & for eradication (if not directly incinerated)	ABP Regulation 1774/2002/EC Category 1 (except TSE) (if not directly incinerated)	ABP Regulation 1774/2002/EC Category 2 (if not directly incinerated)	ABP Regulation 1774/2002/EC Category 3 (if not directly incinerated)
1 (sterilisation)	50	> 133	20	Yes ⁽¹⁾	Yes	Yes	Yes then incinerate or co-incinerate	Yes then incinerate, co-incinerate or landfill	Any one of these methods MUST be used, but the subsequent required/allowed routes for use or disposal of the outputs are prescribed in ABP Regulation 1774/2002/EC.	Any one of these methods MAY be used and the subsequent allowed routes for disposal of the outputs are prescribed in ABP Regulation 1774/2002/EC.
2	150	> 100 > 110 > 120	125 120 50	No	Yes	Yes	Yes then incinerate or co-incinerate	Yes then incinerate, co-incinerate or landfill		
3	30	> 100 > 110 > 120	95 55 13	No	Yes	Yes	Yes then incinerate or co-incinerate	Yes then incinerate, co-incinerate or landfill		
4	30	> 100 > 110 > 120	16 13 3	No	Yes	Yes	Yes then incinerate or co-incinerate	Yes then incinerate, co-incinerate or landfill		
5	20	> 80 > 100	120 60	No	Yes	Yes	Yes then incinerate or co-incinerate	Yes then incinerate, co-incinerate or landfill		
⁽¹⁾ 3 bar (300 kPa) pressure produced by saturated steam, i.e. all air is evacuated and replaced by steam in the whole sterilisation chamber Co-incineration and mixed waste incineration are not within the scope of this document										

Table 2.3: Summary of rendering processes allowed under ABP Regulation 1774/2002/EC – for detailed information on what is required, permitted and prohibited, see the legislation

The operating conditions and the sequence of unit operations may vary due to the nature of the raw material or the desired properties of the product, as long as the requirements of ABP Regulation 1774/2002/EC are also met.

The higher the fat-free solids content of the raw material, the larger will be the quantity of animal meal produced. The more bone in the raw material, the less protein the meal will contain, since bone has a lower protein content than meat or soft offal. If the raw material has a high bone content, the product will have a high mineral content. The average yield of fat and meal from a rendering plant will be about 35 – 45 % of the quantity of raw material fed into the plant. Examples of some extreme raw material contents include, e.g. pure meat which can contain up to 75 % water; cleaned bone from a deboning department, which can contain 45 % solid and very fatty material which can contain 95 % fat. Further information is given in Table 2.4.

The composition of the product to some extent dictates its suitability for further use or disposal. The feedstock can be any part of the animal and may comprise a single substance, such as feathers or blood, or may be a mixture. During the years before the BSE crisis there was a trend towards rendering various parts of the animal separately for specific customer requirements. This may have changed with the ban on the use of meal in animal feed and with the consequent use of the rendering process as part of the disposal route for a large proportion of animal by-products. The feeding of processed animal proteins to farmed animals which are kept, fattened or bred for the production of food is, at present, prohibited, with limited exceptions, by the *2000/766/EC Council Decision of 4 December 2000 concerning certain protection measures with regard to transmissible spongiform encephalopathies and the feeding of animal protein* [88, EC, 2000].

Raw material Finished products Condensate (Waste water)	Quantity	Proteins		Mineral matter		Fat		Water	
	kg	%	kg	%	kg	%	kg	%	kg
Animal carcasses	1000	15	149	4	38	12	118	68	683
Animal meal	240	62	149	16	38	12	29	5	12
Animal fat	90	0	0	0	0	99	89	1	1
Condensate	670	0	0	0	0	0	0	100	670
Slaughterhouse waste (red meat)	1000	9	90	2	20	14	137	74	739
Animal meal	150	60	90	13	20	12	18	5	8
Animal fat	120	0	0	0	0	99	119	1	1
Condensate	730	0	0	0	0	0	0	100	730
Bones	470	40	188	40	188	12	56	5	24
Bone meal	470	40	188	40	188	12	56	5	24
Animal fat	90	0	0	0	0	99	89	1	1
Condensate	440	0	0	0	0	0	0	100	440
Blood	1000	12	123	1	7	0	3	87	867
Blood meal	140	88	123	5	7	2	3	5	7
Condensate	860	0	0	0	0	0	0	100	860
Bristles	1000	28	255	1	6	2	21	72	718
Bristle meal	300	85	255	2	6	7	21	6	18
Condensate	700	0	0	0	0	0	0	100	700
Poultry waste	1000	12	124	2	21	18	181	66	663
Poultry meal	190	65	124	11	21	12	23	6	11
Animal fat	160	0	0	0	0	99	158	1	2
Condensate	650	0	0	0	0	0	0	100	650
Feathers	1000	28	281	1	7	2	23	69	690
Feather meal	330	85	281	2	7	7	23	6	20
Condensate	670	0	0	0	0	0	0	100	670
The sum of protein, mineral matter, fat and water portions need not be 100 %, as there are other ingredients in the substances mentioned, e.g. starch, nucleic acid and raw fibres. The figures serve only as a guide, as they depend on the actual composition of the raw material)									

Table 2.4: Typical product quantities after rendering 1000 kg of various slaughterhouse by-products
[49, VDI, 1996]

Blood not intended for food or pharmaceutical use may be rendered. Blood generally comprises about 18 % dry matter, but often less, e.g. in the UK it contains a maximum of 16 % dry matter in winter and 10 % in summer. [289, EFPPA, 2002]. Some of the water may be removed, by various means, before processing. In the first stage of the drying operation the blood is coagulated with steam, but this can lead to high effluent discharges, due to the substantial amount of soluble material that can be lost with the blood water during centrifuging of the coagulated blood. Up to 50 % of the water can be removed by this process, before drying. The liquor is drained and the remaining 40 % water is then driven off by a variety of oven and air drying equipment. This gives a yield of about 15 - 20 % blood meal from the raw blood. One type of drier is the continuous ring drier. It consists of a jacketed vessel with blades that rotate, to prevent burn-on. The exhaust air can be passed through a water scrubber to reduce dust emissions. Blood contamination of water can be reduced, by clarification in a settling tank, before the water is discharged.

2.2.2.1 Rendering of carcasses and waste

The preparation of the materials to be rendered and some examples of the numerous rendering methods in use, which illustrate the main principles, are described below.

Pretreatment and pre-breaking

The qualities of animal meal and tallow produced by rendering animal by-products will depend on the type of raw material, the storage time and temperature before rendering and the rendering process itself.

Traditionally there was a requirement to keep the FFA low. To do this: the raw material must be treated as soon as possible after removal from the animal; excessively high storage temperatures must be avoided; the raw material must not come into contact with the contents of the paunch and intestines and pre-cutting of the raw material should be carried out just before the heat treatment is started. These conditions make good environmental sense too because, by minimising the degree of breakdown of the materials to be rendered, they reduce odour and waste water problems.

Manual de-hiding/skinning may be undertaken at rendering plants.

Whole carcasses and parts of carcasses are mechanically reduced in size before rendering. ABP Regulation 1774/2002/EC specifies maximum particle size limits for by-products being rendered. These depend on which Category they are as defined in ABP Regulation 1774/2002/EC and their intended route for use or disposal. The size limits are shown in Table 2.3.

Sterilisation

ABP Regulation 1774/2002/EC prescribes the circumstances under which sterilisation, i.e. Method 1 from Annex V, Chapter III, is required. The conditions that must be achieved are summarised in Table 2.3. Examples of batch and continuous sterilisation are described. The sterilisation process may be applied as the whole process or as a pre- or post process phase. The by-products, which have been reduced in size to no greater than 50 mm, are sterilised at 133 °C, for at least 20 minutes without interruption at a pressure (absolute) of at least 3 bar (300 kPa) produced by saturated steam.

Batch sterilisation

A horizontally lying cooker with a steam jacket and stirrer, known as a dry rendering cooker, may be used. One example of this type of equipment can handle batches of up to 15 tonnes of by-product. The stirring implements are made up of classical heated dry melting implements. They can simultaneously serve as driers and stirrers and are mainly used in smaller plants with lower throughputs. The sterilisation and drying time is 3 – 5 hours with a batch of about 1.5 - 10 tonnes. [163, German TWG Members, 2001]

Continuous sterilisation

Current continuous sterilisers consist of a system of preheaters, heaters, and a holding device. These can be constructed horizontally in series, or vertically as a compact system. The raw material is conveyed from the loading equipment, where fat may be mixed into it, into a piston pump, which presses the material at high pressure through the entire system. In the preheaters, which consist of a cylindrical container containing heated pipes, the raw material is heated to approximately 75 - 80 °C, using the exhaust vapour from the sterilisation. In a second stage, i.e. the heater stage, the material is brought to a temperature of 133 °C through the indirect supply of steam. The heater is also a heat-exchanger containing heated pipes. The third stage is the holding device, which must be sized for the maximum throughput volume. The pressure of 3 bar (300 kPa) is guaranteed by the pressure keeping system installed at the end of the holding device, which only opens at a pressure of 3 bar (300 kPa). The mixing of the raw material is ensured within the pipe system. After discharge of the sterilised material, the exhaust vapour steam is separated in a cyclone and used again for the preheating.

Some rendering systems

A large number of rendering systems are used in different EU countries, all based on similar principles. The combinations of the various unit processes are numerous. Some examples of

the more commonly used systems are listed in Table 2.5 and described in the following paragraphs.

System	Energy use ⁽¹⁾ (kg oil/tonne by-product treated)	Pressure cook		Fat (% remaining in animal meal)
		Before	After	
Batch dry rendering/fat melting	55 - 60	No		12 - 15
Continuous drying in recycled fat	approx. 55	No	Yes	10 - 15
Wet pressing or other separation, evaporation, drying in fat, pressing	40 - 45	No	Yes	10 - 15
Separation, evaporation, drying in natural fat	approx. 55	No	Yes	8 - 10
Cooking and drying in added fat in multiple-effect evaporator, pressing	35 - 40	No	Yes	10 - 15
Wet pressing, separation, multiple-effect evaporation, drying without fat	35 - 40		No	8 - 9
⁽¹⁾ Energy in kWh not submitted				

Table 2.5: Commonly used rendering and fat melting systems
[289, EFPRA, 2002]

Batch dry rendering

The sequence of treatments can vary between installations, but the principles are the same.

The conventional batch dry rendering method is shown in Figure 2.4 and is basically the same equipment as used in the batch fat melting process. The cooker, which is charged with a batch of raw material, consists of a horizontal jacketed vessel which is indirectly heated by steam. An agitator, which is often of a hollow design and indirectly heated by steam, is used to mix the contents and to provide quick and even heating. The jacket and agitator may both be supplied with steam at a pressure of approximately 6 – 7 Pa.

The cooking period takes about 2.5 hours, during which the contents are heated, sterilised and most of the water is evaporated, i.e. down to a water content of 8 – 10 %. The remaining contents of the cooker are then discharged into a percolator, which is a tank equipped with a strainer at the bottom for draining the free fat. The solid residue from the percolator, which still contains about 30 – 35 % fat, is then de-fatted down to the desired fat content by means of a screw press (expeller), a pusher centrifuge, or a basket centrifuge. Alternatively, the material can be discharged to a solvent extraction plant, although this technique is being used less and less. Table 2.6 shows the relative efficiencies of different types of separation equipment. The fat recovered is purified separately.

Equipment used	Fat content (%) (from a starting level of 30 - 35 %)
Expeller	10 - 13
Pusher	12 - 15
Basket centrifuge	12 - 17
Solvent extraction	2 - 8

Table 2.6: Relative efficiencies of fat removal at the end of the batch dry rendering process
[145, Filstrup P., 1976]

The fat drained from the percolator and from the de-fatting equipment contains a certain amount of fines. It can be clarified in a separator.

Continuous drying in added fat

The raw materials are reduced to a maximum particle size of 50 mm. They are then sterilised either immediately, in a batch cooker or a continuous pressure cooking vessel, or after drying and separation in a batch cooker with injection of live steam. Cooking and drying take place in a continuous drier with recycled fat. The dried material is drained and pressed to expel fat. The process has a high energy consumption but the plant is compact and the system well established. [289, EFPRA, 2002]

Pressing, evaporation, drying in fat and pressing

The raw materials are reduced to particle sizes between 20 – 30 mm and then pressure cooked. They are then pressed in a screw press to separate the solids from the liquids, i.e. the fat and stickwater. The press cake is dried in a continuously operating disc drier. The liquid is evaporated in a multiple-effect vacuum evaporator and the concentrate is mixed up with the press cake. Evaporation and drying thus takes place in the fat phase and the fat is expelled afterwards, in a press. The energy consumption is low and the meal has a high fat content. [289, EFPRA, 2002]

Separation, evaporation and drying in natural fat

The raw materials are reduced to particle sizes between 25 – 50 mm and pressure cooked. Coarse bones may be removed by screening. Solids, stickwater and fat are separated in a tricanter. Fat is further purified and stickwater is concentrated in a vacuum evaporator. The concentrate is mixed up with the solid phase and dried in a continuous drier. The fat content in meal is low. The drying for raw materials with high bone content can be difficult and recirculation of the meal may be necessary. [289, EFPRA, 2002]

Cooking and multiple-effect evaporation in added fat, pressing

The raw materials are finely minced and fluidised with recirculated fat. The resulting slurry is evaporated in multiple-effect vacuum evaporators, i.e. vertical tube heat-exchangers, with flash chambers, using live steam and waste steam from the process. Fat is separated in expellers. The pressure cooking cycle can be applied before or after drying and may be continuous. The system has a low energy consumption and is used, e.g. in Belgium, Germany, the Netherlands and the UK. [289, EFPRA, 2002]

Pressing, separation, vacuum evaporation, drying without fat

Raw materials are reduced to particle sizes less than 20 mm, coagulated and pressed in a double screw press. The press cake is dried in a disc drier, which is heated indirectly by live steam. The liquid phase is separated in a tricanter into fat, stickwater and sludge. The fat is purified and sterilised and the stickwater is evaporated in a multiple-effect vacuum evaporator using waste steam from the process. The concentrated liquid is mixed into the press cake for drying. The resulting meal is pressure sterilised by live steam. The system has a low energy consumption. The residual fat in the meal is less than 10 %. The system is mainly used in Denmark, Ireland and Italy. [289, EFPRA, 2002]

2.2.2.2 Rendering of feathers and pig hair

The first stage of rendering feathers and pig hair is hydrolysis, to release keratin. Keratin is an indigestible protein. The hydrolysed protein is then dried, to produce a digestible high protein meal. Before the ban on the use of certain animal proteins in animal feed this could be sold separately, but it was normally mixed with other types of meal and used as a protein concentrate.

Pig hair and feathers are treated separately, as the conditions (temperature/time) for a suitable hydrolysis of the two products are different. A more powerful heat treatment is required to “open” pig hair.

The processes can be carried out in batches in dry rendering cookers, where the keratin containing material is exposed to high temperature (135 - 145 °C) and pressure for 30 -60 minutes. The pressure is then released and the product is dried and milled. This can eliminate the need for mechanical dewatering.

Special rendering equipment is also available for the continuous hydrolysis of feathers and/or hair. The material is transported in small batches to a compression chamber, where it is preheated and then to the hydrolysis unit, where it is treated with direct steam under suitable pressure conditions for a shorter period (normally 10 - 15 minutes). The hydrolysed material leaves the reactor at the bottom. Part of the water is then removed in a decanter. An evaporative unit is used for the concentration of the liquid phase. The dewatered product is dried separately or with other rendering products. [134, Nordic States, 2001]

The process for rendering feathers and pig hair is summarised in Figure 2.6.




Figure 2.6: Flow diagram for the rendering of feathers and hair
[163, German TWG Members, 2001]

Feathers and hair processing produce high sulphide emissions in the waste water. The removal of H₂S is, therefore, important as the sulphide can impair the activated sludge activity and thus the biological waste water treatment process. [163, German TWG Members, 2001]

2.2.3 Fish-meal and fish-oil production

In principle, the fish-meal process is the removal of oil and water from the raw material and the separation of the material into 3 fractions, i.e. oil, meal and water. The water fraction is disposed of, normally to sea. The process is characterised by the continuous processing of very large quantities of raw material. Production normally takes place 24 hours a day, using large quantities of energy and seawater and with a minimum of manual labour.

The fish-meal and fish-oil production process may be summarised as follows, with Figure 2.7 illustrating the raw material, intermediate material and final product process order.




Figure 2.7: Material flow in fish-meal and fish-oil production
[140, Minck F., 2001]

Raw material

Whole marine fish caught in the sea, or parts of fish from the filleting industry.

Unloading

If the fish are specifically caught for fish-meal and fish-oil processing, they are unloaded from the fishing vessels and weighed. During unloading, fish samples of 300 - 500 kg, i.e. 70 – 100 spot samples, are taken and analysed to determine the quality of the raw material. Freshness is extremely important to the final product quality. The parameter used to measure freshness is the total volatile nitrogen (TVN). This is the nitrogen created by the degradation of protein in the raw material. Ideally, the raw material should be fresh and dry. It often contains melt water from ice used to conserve the fish.

Raw material buffer silo

The raw material is stored in a silo, which has enough capacity for 16 – 24 hours. The unloading capacity is greater than the production capacity because the plants cannot control the delivery times of the vessels, so production takes place 24 hours a day. Unloading tends to take place during the day. The buffer silos have to be empty when offloading starts the next day, to maintain a fresh throughput.

Cooker

Fish are 70 - 75 % water. They are indirect-steam cooked for 20 minutes in their own water at 90 - 100 °C. The protein coagulates and it is this which forms the press cake.

Press

The cooked fish are pressed for 15 minutes, in a screw press to produce a liquid phase, known as press water and a solid phase known as press cake. The press water contains some dry matter and solid matter, known as fines. The press cake is 50 % dry matter.

Decanter

The press water is separated further, in a decanter, to produce decanter water and another solid phase, known as grax.

Centrifuge

The decanter water is separated further in a centrifuge to produce fish-oil and a liquid containing dissolved dry matter and small amounts of suspended solids, known as stickwater. Approximately 20 % of the fish-meal is in the stickwater.

Evaporator

The stickwater is concentrated by evaporation in a evaporator, for 30 minutes, into a liquid containing approximately 40 % dried matter, i.e. evaporated stickwater. Seawater is used as cooling water in the evaporators.

Drier

The press cake and grax and evaporated stickwater are mixed and dried for 1 - 2 hours to produce fish-meal. The driers used in fish-meal factories are nowadays almost exclusively the indirect steam-heated type. Heat is transferred to the drying material by hollow, rotating discs mounted on a horizontal axle. Older types of directly fired drum driers are being replaced, and other drying methods such as spray-drying are only used for relatively small quantities of special meal types. [155, Nordic Council of Ministers, 1997]. The removal of oil from the meal is, in some cases, becoming increasingly important due to increased levels of dioxins detected in the fish and fears about the risks to human health associated with these.

Fish-meal consisting of press cake, decanter sludge (grax) and evaporated stickwater is called “whole meal”. Depending on the drying temperature, the meal is called “normally dried meal” or “low temperature dried meal” (LT-meal). The latter is dried in vacuum driers. By far the largest part of the fish-meal produced is whole meal of many different types and qualities. In addition, many special meals are produced, based on one or several of the intermediate products of the fish-meal factories. These have names such as press cake meal and evaporated stickwater meal. [155, Nordic Council of Ministers, 1997]

Meal cooler

The fish-meal is air-cooled in a meal cooler. This protects the quality and makes grinding possible.

Grinder

The fish-meal is ground to a specific particle size using hammer mills.

Oil finishing/purification

The fish-oil from the centrifuge is washed with hot water in another centrifuge, then settled and stored. If necessary it may be passed through a carbon filter-press to remove traces of dioxins. The spent carbon is incinerated in a hazardous waste incinerator.

Storage

Fish-meal and fish-oil can be stored for at least one year in storage houses and in tanks.

Example plant

Figure 2.8 shows a simplified schematic diagram of the production process in a large fish-meal factory. This overview shows only the most important mass flows.




Figure 2.8: Schematic diagram of the production process in a large Danish fish-meal factory [155, Nordic Council of Ministers, 1997]

Figure 2.8 shows how production can be divided into two completely separate units through which different raw material qualities and meal types can be processed simultaneously. The buffer tanks for press liquor, stickwater and evaporated stickwater, the blood water intake, the blood water processing unit and the newest special fish-meal production unit are not shown.

An energy exchange valve has been mounted at point “X”, so that stage 1 of the surplus heat evaporator can be supplied with energy, i.e. surplus steam, from the two LT-driers (vacuum driers), and the remaining steam can be conducted to the barometric condensers. Alternatively, the heat evaporator can be supplied with surplus steam from the normal driers, which work at atmospheric pressure.

When the factory represented in the schematic diagram produces surplus heat, it is conducted through the heat-exchanger to a district heating system, if required. Only a few fish-meal factories supply heat in this way. During operation, a surplus of condensate is continuously produced at the primary side of the heat-exchanger. This surplus is channelled away. The heat-exchanger can also receive heat from other sources of condensate, but this is not shown on the figure, to preserve clarity.

2.2.4 Bone processing

The flow chart in Figure 2.9 summarises bone processing.




Figure 2.9: Flow diagram for bone processing
[163, German TWG Members, 2001]

2.2.5 Blood processing - plasma and dried red cell production

Rendering is covered by Section 2.2.2.1.

Blood processing uses blood from animals which have been passed as fit for human consumption by an official veterinarian, after a post mortem inspection.

Blood collection

At the slaughterhouse, following hoisting, the stunned beast is stuck with a sticking knife at the lower end of the neck. This severs the major blood vessels, including at least one of the carotid arteries and jugular veins. Blood gushes from the stick hole to drain into a tank, canal or collection trough that receives the blood from multiple animals. For the collection of blood for the preparation of spray dried plasma, it should not be allowed to clot. To prevent this, blood is mixed with a solution of sodium citrate and/or sodium phosphate. Collections can be made singly but this is generally not practical for large numbers of animals. Thus it is usually pooled at the point of collection.

Filtering and centrifugation

The blood is filtered at the slaughterhouse and at the manufacturing plant. Following filtration, it is centrifuged to separate the plasma from the blood cells. This is done either at the slaughterhouse or at the processing plant. These two processes also assist in removing gross particles. If there is infectivity present, it will mostly be in the cellular fraction. Plasma would not necessarily be free of infectivity but it would be likely to be significantly reduced by separation of the cells. Following centrifugation there are 3 further filtration steps. Subsequent equipment is dedicated either to plasma or to cells.

Plasma production

The plasma yield is collected in a refrigerated stainless steel storage tank and chilled to 4 °C. At this point the plasma from various sources is allowed to mix in the storage tank. One tank may

hold the blood from 1500 - 8000 pigs or 350 - 750 adult cattle. Cattle and pig plasma may be mixed. [202, APC Europe, 2001]

The plasma received from the slaughterhouse contains approximately 8 % solids. These are removed by reverse osmosis and/or nano-filtration. This also concentrates the plasma, removing water and minerals, as well as the anticoagulant. The filters remove particles down to a 1 nm diameter. The purified plasma is then machine-homogenised and pressurised, in preparation for spray drying.

Alternatively, the plasma may be concentrated by vacuum evaporation. This technique involves the removal of the water from the plasma, under vacuum at < 40 °C.

The spray drying involves the injection of the plasma into a heated drying chamber, at high pressure to form very fine droplets of 10 - 200 µm diameter, using a high-pressure nozzle. The type of nozzle used depends on the configuration of the drying chamber and on the flow of heated air. The drying chamber is the part of the system where the tiny plasma droplets contact the heated air and hence which the drying process takes place.

When the droplets encounter a stream of heated air the moisture quickly evaporates to form a dry powder. It is important that the drops are uniformly sized and are produced at a consistent rate, so that all the particles are exposed to the same temperature conditions. Specially designed and engineered nozzles are used to achieve this.

The air circulating through the drying chamber is atmospheric air, finely filtered and warmed by passing through a steam heater or an indirect gas heater. A centrifugal ventilator moves the heated air into the circulation system. The inlet temperature at one installation is reported to be 240 °C. The minimum contact time is 15 seconds at that same installation. It may be up to 30 seconds in other plants. The outlet temperature is 90 °C.

The plasma fraction is then bagged and stored. It has a moisture content of < 10 %. It is used in pet food and piglet feed. [201, APC Europe, 2000]. Plasma can currently be used by the meat industry, e.g. in cooked ham and cooked sausages and for pet food production [271, Casanellas J., 2002].

The process is illustrated in Figure 2.10.




Figure 2.10: Spray dried plasma manufacturing process
[202, APC Europe, 2001]

Red cell production

The red cell fraction is pumped under high pressure, spray dried, bagged and stored, in the same way as previously described for the plasma, except that because the red cell fraction already comprises 30 % solids, it is not necessary to concentrate it prior to drying. The temperature for spray drying the red cells is higher than that for plasma, i.e. $> 250^{\circ}\text{C}$. The process is illustrated in Figure 2.10. The dried red blood cells are used as a natural pigment in the meat industry, pet food, animal feed and for fertilisers.

Waste disposal

Solid and liquid waste is produced during the spray-drying process. The solid waste is largely biological waste from filtration, osmosis and cleaning. All of the biological waste is suspended in water. It is filtered and the waste water then undergoes biological degradation at a WWTP. The waste water contains solids, detergent and disinfectants from cleaning vehicles and equipment, such as centrifuges. The solids are incinerated or landfilled. The sludge from the WWTP is rich in protein and can be composted with other materials.

2.2.6 Gelatine manufacture

Gelatine is natural, soluble protein, gelling or non-gelling, obtained by the partial hydrolysis of collagen produced from bones, hides and skins, tendons and sinews of animals (including fish and poultry) [85, EC, 1999]. The raw materials used comprise bones, fresh or frozen hides, pig skins and fish skins. The use of hides and skins submitted to tanning processes is prohibited for the production of gelatine intended for human consumption [85, EC, 1999]. ABP Regulation 1774/2002/EC requires all material destined for gelatine production to be Category 3 material, as defined therein.

There are several processes for the production of gelatine. These depend to some extent on the raw materials used, although after the de-fatting and demineralisation of bones and the acid treatment of pig skins, the gelatine extraction steps in some of the processes using bones hides and pig skins are very similar. The main gelatine manufacturing processes are summarised in Figure 2.11 and the individual process steps are described below.

DESCRIPTION OF THE MAIN GELATINE MANUFACTURING PROCESSES [249, GME, 2002]

The unit operations for the processes for each of the eight types of gelatine produced are shown Figure 2.11 and then again individually in Figure 2.13 to Figure 2.20 inclusive. As can be seen from Figure 2.11, many of the unit operations are common to several and, in some cases, all of the processes. Techniques which minimise consumption and emission levels at such unit operations may, therefore, be widely applicable throughout the gelatine manufacturing industry.




Figure 2.11: The main gelatine manufacturing processes
[249, GME, 2002]

See also Figure 2.13 to Figure 2.20, inclusive

The unit operations are described next.

A Degreasing

The untreated bones contain a large amount of meat, soft tissue and fat, which has to be removed. A typical example of the composition of a batch of fresh bones is: 46 % water, 15 % fat, 19 % protein and 20 % minerals.

The bones are crushed in a pre-breaker to a maximum particle size of 20 mm diameter, before being degreased, using hot water, at a temperature of 75 - 90 °C, for 15 - 30 minutes. A continuous process has been reported, using a steam jacketed and steam-heated screw conveyor. The turbulent action of the hot water and the sliding and rubbing of the crushed bone loosens the meat and other soft tissue from the bone. The contents of the degreasing vessel are separated to give hard bone, sinew (soft bone) and liquids containing tallow and water.

The hard bone may be washed using hot water, to give a final moisture content of around 10 %. The sinew may be pressed to remove fat and water before being dried with the hard bone to give a final moisture content of 14 %. Drying at 85 °C takes 45 minutes. [208, Croda Colloids Ltd, undated]

Alternatively the sinew and liquid stream may be separated into a liquid stream containing tallow and water using a decanter or tricanter system and the sinew stream can then be dried in a rotating disc drier, to give a moisture content well below 10 %. The product temperature reached in the drier is about 110 °C, for at least 45 minutes. [249, GME, 2002]

The dried bone and sinew are sieved at 2 mm and 5 mm to give bone meal (< 2 mm fraction), intermediate bone pieces (2 - 5 mm fraction) and degreased gelatine bone/sinew (> 5 mm fraction).

The tallow/water mix is separated using centrifuges to give purified tallow and process water. The liquids are maintained at a temperature of 85 °C for 30 minutes during separation.

Fine solids removed from the liquid during separation, together with fine solids from the pressing of the sinew are combined and dried to give a moisture content typically < 10 %. The product temperature achieved in the drier is around 110 °C for at least 45 minutes.

Cyclones are used to remove the air and to separate the fines from the larger particles destined for the gelatine manufacture.

Bone chips are graded by density, using a hydrocyclone, because high-density bones require more processing than low-density bones, both to demineralise and to extract the gelatine. They are then dried in a band oven, with a starting air temperature of around 350 °C and an exit temperature of 150 °C. The chips are only in contact with the hot air for a short time and they are also cooled by the evaporation of the water, so their temperature will not normally exceed 85 °C. The drying time varies from 20 – 60 minutes. The dried bones are then classified by size, firstly using rotating or vibrating sieves, normally at 2 – 5 mm and then using a densimetry table, which comprises an inclined screen with an upward air-draught on to which the bone chips are dropped.



The amount of dried degreased bone chips obtained from 1 kg of bone is usually about 200 g.

If hides or skins are used this pretreatment stage is not required.

B Demineralisation

The demineralisation process is the removal of the inorganic component, which comprises mainly natural phosphates and calcium carbonate. The defatted bones are placed in a strong HCl solution at pH 1 - 2, where the tricalcium phosphate is converted into the soluble

monocalcium salt, which is run-off in solution, for later conversion to dicalcium phosphate, soluble calcium chloride and CO_2 . The chemical reaction with HCl is shown.



For 1000 kg of degreased bone, containing 8 % water and of which 63 % comprises 7 % CaCO_3 and 56 % $\text{Ca}_3(\text{PO}_4)_2$, approximately 7700 litres of 4 % HCl is required, for complete conversion.

The solid residue, which is known as ossein, is used in the gelatine manufacture process. The ossein production process may take several days depending on the nature, size and density of the raw material. Several pits, e.g. six, sit in series, containing ossein, at various stages in the process. Fresh HCl at a concentration of 3.5 %, is added to the pit containing the ossein which has been treated for the longest time. After approximately 24 hours, this acid is pumped to the pit containing the second oldest ossein, whilst the acid from this is pumped to the pit containing the third oldest ossein. The process continues by this batch countercurrent action. In this way the “newest” liquor, with the highest acid concentration and the lowest concentration of monocalcium salt is extracting the salt from the ossein with the lowest available yield. The “oldest” liquor, with the lowest acid concentration, i.e. about 0.5 %, is extracting the salt from the ossein which has the most salt to give up. The process can be helped by air agitation. The process is illustrated in Figure 2.12.

Each reactor tank in the process typically contains a batch of 20 – 50 tonnes of bone chips, but smaller tanks may also be used. The tank height may be about 7 metres and the diameter about 3.5 metres. New reactors are usually made from plastic coated steel. For a system with 4 reactor vessels, 200 tonnes of degreased bone chips can be treated in 4 days, in 4 batches of 50 tonnes. To demineralise these, approximately 1540 cubic metres of 4 % HCl is required. For an installation operating at an efficiency of approximately 90 %, this requirement increases to approximately 1710 cubic metres in four days or about 17.8 m^3 l/h.




Figure 2.12: Flow diagram for the demineralisation of bone to produce ossein for gelatine manufacture

C Liming

Liming is usually done in large concrete pits that can contain the ossein from one batch of demineralised bone chips. The ossein is submerged in a solution of supersaturated lime to purify and condition the collagen, to promote its hydrolysis. The pH during this process is approximately 12.5, i.e. the pH of fresh made lime solution. The supersaturated lime solution is refreshed regularly to compensate for its consumption during the process. Air is blown through regularly, to prevent local drops in the pH level.

After the last decanting of the lime the ossein is washed by filling the lime pit with about the same amount of water as the weight of the original bone chips and leaving it in for some time before running it off. The ossein is then washed a second time by agitating it with approximately the same amount of water, after which it is pumped in a stream of water to the neutralisation installation. The washings contain lime and can be used to neutralise the acid used in the early process, otherwise consumption of another alkali would be required for this.

A typical liming process schedule is shown in Table 2.7, the number of days varies between installations and can be as high as 90, depending on the quality of the bone chips, the average temperature of the lime and the desired physical properties of the gelatine. The frequency of refreshing the lime, the frequency and the time of blowing air into the pit and the number of times the ossein is washed, with or without agitation, also varies between installations and batches.

Day	Adding fresh lime	Decanting	Pumping air	Washing
1	X			
2	X	X		
3			X	
4	X	X		
8			X	
9	X	X		
12			X	
15			X	
17	X	X		
21			X	
25			X	
27	X	X		
31			X	
35			X	
37	X	X		
41			X	
43			X	
46		X		X

Table 2.7: Typical liming process schedule

D Neutralisation

The washed limed ossein still contains lime and has a high pH in the centre of the particles. It is treated with dilute acid to neutralise and remove the lime, and to change the pH to pH 4.5 – 7. The batch of ossein is submerged in at least as much water as the original weight of the bone chips from which the ossein was made. The ossein is stirred and the acid is added. The pH is measured continuously and can be used to control the flow of acid. When the pH remains constant for several hours within the desired pH range without acid being added, the ossein is considered to be neutralised. The acid water is then run-off and the ossein is washed with at least five times its own weight of fresh water, whilst remaining submerged. The neutralisation can be done in one or more stirred tanks in the extraction vessel. The installation is usually made of stainless steel or plastic coated steel.

E Extraction

The gelatine is extracted from the neutralised ossein, pretreated hides or pig skins, with hot water. This involves about 5 steps, at progressively higher temperatures, usually with no more than 10 °C difference between steps and typically ranging between 50 - 60 °C and 100 °C. The gelatine concentration of the extract is normally 3 - 8 %.

The water can be added cold and then heated, or already heated. The ossein in the extractors may be stirred carefully in the warm water or the water may be circulated over the ossein bed. This is continued until a concentration of about 5 % gelatine, is reached. The extract is then drained and the process is repeated, usually at a higher temperature. When drained, the extract usually passes through a sieve or a mesh to prevent large particles getting into the pipework. The final extraction is stopped when, while extracting at 100 °C, the concentration of gelatine does not reach 3 %, or when no ossein is left. The amount of water required is at least the amount needed to submerge the ossein or pig skins, plus the amount to fill the pipes, pumps and heat-exchangers. For ossein coming from 50 tonnes of bone chips, the amount of gelatine in each extract is between 1500 kg and 4000 kg. The installations are normally made of stainless steel.

F Filtration

The extract is filtered to remove any insoluble particles. The filtration can be done in one or more steps. The filter medium is generally diatomaceous earth or cellulose, although cotton may also be used. If diatomaceous earth is used, a filter aid, usually composed of the same kind of diatomaceous earth as the filter, is added to the gelatine solution, to prevent blocking by continuously building up the filter layer. When using cellulose, pulp pads of about 5 cm thickness can be used. Often the filtration is done in two steps, the diatomaceous earth filter being followed by a filter that uses commercially available cellulose filter pads, which are about 1 cm thick. The extract may pass a cloth filter bag first, to remove residual coarse particles. During filtration the temperature of the solution is kept at 55 - 60 °C.

The filtration equipment is usually of the same type as that used in several branches of the food industry and is readily available. The diatomaceous earth filtration can be either pressure or vacuum operated. For pressure operated filtration, the filter bed is in a closed vessel which is pressurised. When the maximum pressure is reached, the filter meshes are automatically cleaned and covered with new filter aid. For vacuum filtration, the filter is usually a rotating drum filter with the filter layer on the outside of the drum. The extract is sucked into the inside of the drum. With this kind of filter, the filter aid and the layer is automatically scraped off, so the filter continuously has a fresh surface.

G Ion exchange

The filtered extract is passed through an ion exchange resin to remove all the dissolved salts from the solution. The solution normally first passes the cation column and then the anion column. Most installations consist of two cation columns and two anion columns. One of each is in use at any one time, while the other two are either regenerating or are on standby. Modern installations have an automatic control system that diverts the flow to the standby column as soon as the column in use reduces in effectiveness, at the same time starting the automatic regeneration procedure for the exhausted column. Older installations are less automated. The cation and anion exchangers are regenerated with approximately 5 % HCl and 5 % NaOH and both are rinsed using de-ionised water. An example column size is 1.57 metres in diameter and 1.75 metres high. The flow through such a column is about 7 m³/h. During the ion exchange the temperature of the solution is generally kept at 55 - 60 °C. The installations are made of synthetic material or of plastic coated steel.

H Concentration

After the solution comes from the ion exchangers the next step is to concentrate it. Different designs of evaporators can be used for this. This facilitates the removal of water at relatively low temperatures. In multiple-effect vacuum evaporators, the vapour extracted from the first effect is used to heat the second and that from the second is used to heat the third. The heating

and cooling is undertaken very quickly so that the product is not damaged. Figure 4.14 shows a schematic diagram of a multiple-effect evaporator. At this stage in the process the solution is about 20 - 30 % gelatine. The equipment is made of stainless steel.

I Sterilisation

The concentrated gelatine solution is sterilised either by direct steam injection, such that the temperature is raised to 138 - 140 °C, or by operating the final effect, known as a finisher, at a temperature of about 120 - 140 °C. The increase in temperature is achieved by injecting steam from another source. If direct steam injection is used, the solution is kept at this temperature for at least 4 seconds whilst maintaining a pressure of at least 4 bar (400 kPa). The temperature of the gelatine is measured and monitored continuously. The sterilising equipment is made of stainless steel.

J Drying

The sterilised concentrated gelatine solution is pumped through a heat-exchanger and cooled to a temperature of less than 30 °C, to form a gel. The gel is extruded through a perforated sheet to form thin threads. A small pivoting conveyor belt is used to deposit the threads on to a large metal wire conveyor belt, which runs through a segmented drying tunnel. In the drying tunnel, the gel is dried with clean purified pre-dried warm air. Each subsequent segment of the tunnel has a higher temperature, ranging from 25 - 30 °C to 50 - 60 °C. The drying takes up to 6 hours. The heat for the drier may be recovered heat from the hot water from the evaporator. When the gel enters the drying tunnel it contains about 80 % water. The dried gelatine usually contains about 11 % water, although this may vary between 9 - 15 %. After drying, the gelatine is crushed and packed for intermediate storage. The dried threads are ground and bagged. Each batch is labelled for traceability. Various grades are blended to meet individual customer requirements. The equipment that comes into contact with the gelatine is usually made of stainless steel, but in some cases it is synthetic material.

K Acid treatment

After the demineralisation process the tank containing the ossein is filled again, with the same amount of water as the original weight of the bone chips, and is left to stand in it for about 0.5 - 1 day. The ossein still contains sufficient acid to keep the pH below 2. The liquid is then removed and the ossein is washed again, one or more times, to obtain a pH of about 2.5 or above. It is then transferred to the extractors, in a stream of water.

L Alkali pretreatment

Following demineralisation, the ossein is soaked twice in water, each “soak” lasts one hour and uses an equal volume of water to ossein. After each “soak”, the water is drained away. The ossein is further washed by stirring for 10 minutes with an equal volume of water to ossein and then drained.

One volume of 0.3 N NaOH (pH > 13) is added to the ossein and allowed to stand for 2 hours, with occasional agitation. The pH is monitored, recorded and maintained above pH 13.0 by the addition of NaOH solution, as required.

After the alkaline “soak”, the solution is drained and the ossein is washed twice. Each wash lasts for 15 minutes and uses an equal volume of water to ossein. Finally, the ossein is washed for 10 minutes with twice the volume of water to ossein.

M Acid treatment

1.2 times the volume of water compared to ossein are added to the alkali-pretreated ossein and by means of small additions of 1 N HCl, a pH of 2 is maintained for up to 6 hours, with occasional agitation.

The ossein is then washed a number of times, each wash using an equal volume of water to ossein, for at least 2 hours, until the pH is 2.5 or above.

N Preheating

An autoclave of about 6800 litres is filled with 2300 kg of degreased bone chips. It is preheated for 10 minutes by blowing steam at 1.7 bar (170 kPa) and 115 °C through it, from bottom to top.

O Autoclaving and extraction

The bone chips are pressurised and extracted in eight steps.

i - After preheating the exhaust is closed and the autoclave is pressurised and heated from the bottom with steam at a minimum of 300 kPa and 133 - 135 °C for at least 23 minutes. The autoclave is depressurised in 4 – 5 minutes and then 1500 litres of water is sprayed over the bone chips to extract the gelatine. The water is pumped out during the extraction. The pumping is continued for 12 minutes after the spraying is stopped.

ii - The autoclave is pressurised again for 20 minutes, with steam at 300 kPa and 133 - 135 °C, after which it is depressurised and the gelatine is extracted as described in step i.

iii - The autoclave is pressurised for 20 minutes with steam at 300 kPa and 133 - 135 °C, after which the autoclave is depressurised in 4 to 5 minutes. The autoclave is filled with 1500 litres of water at 10 °C, which is left in the autoclave for 20 minutes and then forced out with steam under pressure. After the third autoclaving and extraction, the extract is not pumped out but forced out with steam.

iv - The bone chips are autoclaved and extracted as in step ii. Instead of water the bone chips are, however, extracted with the extracts coming from steps 5 – 8 of the previous batch.

v and vi - The chips are autoclaved and extracted as in step ii. Parts of the extracts are saved for use as extraction liquid for this batch and the next batch.

vii and viii - The chips are autoclaved and extracted as in step iii. The bone chips are left to drain for 20 minutes and the liquid is pressed out by steam. All of the extract is saved for use in the extractions of the next batch.

P Cutting

The hide splits are cut and then washed with water.

Q Lime treatment

Slaked lime (Ca(OH)_2) is added until the relative density of the solution is 1.5 - 3° Bé. The treatment takes 6 – 11 weeks. During the liming process, the lime solution is controlled, by refreshing the lime and regularly blowing air through the solution, to maintain this relative density and a pH of approximately 12.5.

R Washing and acid treatment

When the lime treatment is finished, the raw material is washed in water in order to obtain a pH of 9 - 10. Acid is then added until a pH of 1.9 – 2.0, is obtained. During this time the pH is kept at 2.4 for 2 – 3 hours. Depending on the recipe, some alternative pH ranges or durations may be maintained, but the principle of washing and acid treatment is always the same.

S Neutralisation

The excess of acid is removed by washing with water until a slightly acid to neutral pH of, e.g. 5.5 – 6.5, is obtained.

T Acid treatment

HCl, or another acid, is added until the pH of the solution is 1 - 3. These conditions are kept for 24 – 48 hours, by adding more acid, if necessary.

U Neutralisation

The excess acid is removed by washing with water to reach a typical pH of 5.3 – 6.0, but a pH of 2.5 – 4.0 is also possible.

V Alkali treatment

NaOH solution is added to the washed hide splits, to a concentration of 0.6 - 1.4 %. The alkaline soak takes a minimum of 10 days. During the process, the pH is approximately 12.5 or higher. Finally air is regularly blown through the solution.

W Washing and acid treatment

When the caustic treatment is finished, the raw material is washed in water until a pH of about 10 is achieved. An acid solution is then added to neutralise the solution.

X Neutralisation

The excess acid is removed by washing with water, until a slightly acid, but close to neutral pH of approximately 5.5 – 7.5, is obtained.

Y Cutting

The pig skins are cut into pieces of about 10 x 10 cm, in a special cutting machine.

Z Washing

The pig skin pieces are washed in a tank, to remove external fat, before demineralisation.

A1 Acid treatment and rinsing

The pig skin pieces are acidulated, in a tank, with dilute H_2SO_4 or HCl to a pH of about 1.8, for at least 5 hours. The acid solution is then removed and the pig skin pieces are then rinsed.

B1 Neutralisation and rinsing

The tank is filled with an alkaline solution of e.g. ammonia, to neutralise the pig skin pieces. The solution is then removed and the neutralised pig skins are rinsed, to reach a pH suitable for extraction of the gelatine. The pH may vary according to customer specification. The treated pig skins are then transferred to the extraction tanks.

C1 Second filtration

A second filtration is made to remove any remaining particles. The filter medium is usually a cloth bag which is able to remove coarse particles.

BONE GELATINE

1 Limed bone process

The limed bone gelatine process is shown in Figure 2.13.




Figure 2.13: The limed bone gelatine manufacturing process

2 Acid bone process

The acid bone gelatine manufacturing process is shown in Figure 2.14.




Figure 2.14: The acid bone gelatine manufacturing process

3 Acid bone process with alkali pretreatment

The acid bone gelatine manufacturing process with alkaline pretreatment is shown in Figure 2.15.




Figure 2.15: The acid bone gelatine manufacturing process with alkaline pretreatment

4 HEAT AND PRESSURE PROCESS

The heat and pressure gelatine manufacturing process is shown in Figure 2.16.




Figure 2.16: The heat and pressure gelatine manufacturing process

HIDE GELATINE

Limed hide process

The limed hide gelatine manufacturing process is shown in Figure 2.17.




Figure 2.17: The limed hide gelatine manufacturing process

6 Acid hide process

The acid hide gelatine manufacturing process is shown in Figure 2.18.




Figure 2.18: The acid hide gelatine manufacturing process

7 Sodium hydroxide hide process

The sodium hydroxide hide gelatine manufacturing process is shown in Figure 2.19.




Figure 2.19: The sodium hydroxide gelatine manufacturing process

8 Pig skin process

Pig skins, whether they are fresh or frozen, contain a large amount fat. A typical example of the composition of a batch of pig skins is: 56 % water, 25 % fat, 18 % protein and 1 % minerals. There are 4 treatment steps, before gelatine extraction.

The pig skin gelatine manufacturing process is shown in Figure 2.20.




Figure 2.20: The pig skin gelatine manufacturing process

APPLICATION

Gelatine is used in a diverse selection of industries and products. The majority of gelatine produced is edible and pharmaceutical gelatine. It is used in the photographic industry, in both films and paper. Technical gelatine is used, e.g. in cosmetics and micro-encapsulation (carbon paper).

BY-PRODUCTS

Meat meal and some bone meal is produced from the removal of residual flesh from the bones.

Tallow is used in pet food and as rolling oil in the ferrous metal finishing industry.

Gelatine waste shavings are landfilled in the UK.

Sludge from the waste water treatment after both the pretreatment of bones and gelatine production is used for land injection, according to soil requirements. The sludge may need to be mixed with other substrates.


DICALCIUM PHOSPHATE MANUFACTURE FROM THE GELATINE MANUFACTURE DEMINERALISATION LIQUOR [249, GME, 2002]

Dicalcium phosphate is used for ceramics manufacture and in fertilisers.

The liquor containing the spent acid and the water soluble monocalcium phosphate is treated with lime (Ca(OH)_2) to extract the dicalcium phosphate. After precipitation and decanting, the precipitate is centrifuged or filtered, washed with water and dried with hot air.

Precipitation and decanting

Lime (Ca(OH)_2) slurry is added in a controlled manner and the pH is monitored. In an example installation, a tank of 75 cubic metres capacity is filled with 35 cubic metres of spent acid, containing monocalcium phosphate, at about pH 1.5 and 10 cubic metres of filtrate after the precipitation of dicalcium phosphate. The pH of the liquid is measured continuously. During powerful stirring, a solution of saturated lime is added quickly until pH 3.5 is reached. Then the addition of the lime is slowed down so that the pH rises to 5.5 in not less than 4 hours after the start of the addition. The suspension contains about 5 % solid matter. The chemical reaction is shown below.



The suspension is pumped to a decanter while stirring is continued, to maintain a suspension. In the decanter, the suspension is separated and pumped to a tank, where the pH is adjusted. The suspension contains about 20 % solid matter at this stage.

Calcium chloride (CaCl_2) is produced in the supernatant liquid, after dicalcium phosphate settles. It is treated in a WWTP.

Adjusting pH, filtration and washing

The tank containing the 20 % suspension is stirred to keep the solid matter suspended. The pH is measured continuously. A 4 % HCl solution is added to the suspension at a rate which ensures that the pH is maintained at about 5 for about 6.5 hours.

Stirring is continued, to keep the solid matter in suspension, while the mixture is pumped to a filtration installation. Either a centrifugal filter, a rotating vacuum filter or a vacuum conveyor belt filter is used. The filtrate is pumped back to the reactor tanks. The residue on the filter is washed with water and then sucked dry until the residue contains approximately 80 % dry matter. The dry matter is scraped off the filter and transported to a drier.

Drying

The dicalcium phosphate is dried with air of at least 70 °C in either a rotating drier or a ring drier, until it contains less than 3 % water. The air is then filtered.

The product is then packaged in bags or bulk tankers.

Associated activity - lime production

Production of the lime from quicklime (CaO) may in some cases be an associated site activity. Quicklime reacts vigorously with water to produce slaked lime.

2.2.7 Glue manufacture

The manufacturing process for hide glue is the same as that for food gelatine [244, Germany, 2002].

2.2.8 Dedicated incineration of carcasses and parts of carcasses and of meat and bone meal

Incineration is a high temperature oxidation, which converts materials into gaseous products and solid residues with a high degree of volume reduction. It is possible to incinerate a wide diversity of materials, including a variety of animal by-products.

High temperature oxidative technologies can destroy organic material, including infectious agents. ABP Regulation 1774/2002/EC sets out the incineration requirements for materials it defines as Category 1, from animals suspected of being infected by a TSE, or in which a TSE has been officially confirmed as being present, or from an animal killed in the context of TSE eradication measures. ABP Regulation 1774/2002/EC requires incineration to be in accordance with WID Council Directive 2000/76/EC, where it applies and sets out specific requirements where it does not apply.

Rotary kiln or fluidised bed incinerators tend to be used for the incineration of animal by-products. Liquids and finely divided materials are placed within the combustion zone so that they are destroyed after passing through the furnace only once. If a grate furnace is used there is a higher risk of run-out and pooling, especially when carcasses and parts of carcasses are heated, causing fat to liquefy and drip through the openings in the grate. The particle sizes of animal meal may also be small enough to fall through the grate openings. A technically and operationally reliable and well maintained system for conveying material which has passed through the grate back to the combustion zone, is therefore, a prerequisite for this type of equipment.

Both WID Council Directive 2000/76/EC and ABP Regulation 1774/2002/EC require the residues to be *minimised in their amount and harmfulness* and to be *recycled, where appropriate*. Most ash residues are currently disposed of to landfill, subject to protein destruction requirements. Ash is also used by the construction industry, e.g. in road building. Other routes for use and disposal are currently being assessed.

2.2.8.1 Dedicated incineration of carcasses and parts of carcasses

Description of animal carcasses and parts of animal carcasses

Carcasses containing up to 70 % moisture and up to 5 % incombustible solids have a heating value of approximately 5815 kJ/kg [29, US Environmental Protection Agency, 1997]. Other figures, based on a limited experience of large-scale carcase incineration quote calorific values in the order of 10000 - 12000 kJ/kg for whole carcasses, 11000 - 13000 kJ/kg for quartered meat

[6, EA, 1997] and 12000 – 15000 kJ/kg for SRM, comprising skulls, intestines and vertebral columns [248, Sorlini G., 2002].

Animal carcasses are incinerated in fixed hearth incinerators in the UK. Other combustion technologies which have been reported to be suitable include pulsed hearth, rotary kiln and semi-pyrolitic incinerators [65, EA, 1996, 144, Det Norske Veritas, 2001]. Promising trials using bubbling fluidised bed incinerators to dispose of crushed animal carcasses have been reported. [200, Widell S., 2001]. The incinerators are described below. BFB incinerators are described under 2.2.8.2, as the technique is more widely used for incinerating animal meal.

Fixed hearth incinerator

A fixed hearth incinerator operates as follows. A ram loader pushes the carcasses into a primary chamber where they are over-fired with primary air and/or with burners, depending on whether combustion is self-sustaining. Proper mixing of the material on the hearth can be difficult and requires careful adjustment of the feed and ash removal rates. Achieving constant burnout is difficult. The skill and training of the operator are particularly important.

A secondary chamber with an injection of supplementary fuel and secondary air is essential.

Semi-pyrolitic incinerators

This technology is described more a control method than a specific configuration of incineration. A primary chamber operates at less than the stoichiometric air requirement for complete combustion and a secondary chamber operates under excess air conditions. The material is dried, heated and pyrolised in the primary chamber, releasing moisture and volatile components. The gas is driven off and then burned in the secondary chamber which is supported by a supplementary fuel burner.

This method of combustion is reported to ensure a controlled burn with both relatively low releases of VOCs and CO. Also, the low combustion airflow results in a low entrainment of particulate borne pollutants.

Stepped hearth

Stepped hearth incinerators comprise a series of concrete steps, typically three, with embedded air channels. The materials are moved from step to step by a series of rams. The first step is a drying stage, with sub-stoichiometric oxygen conditions, during which most volatile compounds are released and burned above the grate in the combustion chamber. The remaining, less volatile material is pushed onto the next step, where the main combustion takes place. The third step is the burnout stage, before the ash is discharged into a final ash burnout chamber, which incorporates air injection and agitation. Material can take eight hours to pass through the hearths and a further eight hours in the burnout chamber. This depends, to an extent, on the feed rate, which will also determine the supplementary fuel requirements.

The steps between the hearths provide good agitation as the waste tumbles down the step, however, this also produces surges of unincinerated material, so good secondary combustion and residence time is important.

Pulsed hearth incinerator

Pulsed hearth incinerators use the pulsed movement of one or more refractory hearths to move the waste and ash through the incinerator. The hearths, which are stepped at each side to form a “U” shape, are suspended from four external supports. The smooth hearth can handle difficult wastes without the risk of jamming and there are no moving mechanical parts exposed to burning material or hot gases. There may, however, be problems achieving the good burnout of solid wastes. [65, EA, 1996].

Rotary kiln incinerator

Incineration in a rotary kiln is normally a two stage process, which takes place in a primary combustion chamber and a secondary combustion chamber. The kiln is a cylindrical shell lined

with a refractory substance. It is inclined downwards from the feed end and rotates slowly about its cylindrical axis. The rotation moves the waste through the kiln with a tumbling action, thus exposing fresh surfaces to heat and oxygen. Structures may be added within the kiln, to aid turbulence and to slow the passage of liquid wastes. The residence time of material incinerated in the kiln can be changed by adjusting its rotational speed.

Rotary kilns can operate at very high temperatures. Careful attention needs to be paid to the rotating kiln and the endplates, to prevent the leakage of gases and unburnt waste. The tumbling of waste may generate fine particles.

Commissioning

Commissioning tests carried out for new plants and existing installations planning to incinerate a different fuel from that for which it is authorised for or would normally incinerate, enable checks to be made about whether the desired results are achieved.

Delivery, storage and handling

Unloading, storage and handling can be done in totally enclosed buildings and equipment. There may be a risk of theft of meat which is unfit for human consumption, so security need to be applied.

Charging the incinerator

For batch processes, carcasses are generally fed into the incinerator intermittently, by front loader vehicles, ram-feed or manually. Opening of the doors for loading can allow considerable ingress of cold air which may upset combustion conditions and increase emissions. Fans capable of responding to changes in furnace pressure during charging, to avoid the escape of fumes or excess airflows may, therefore, be used. Large drops in temperature, e.g. during charging of batch incinerators, can be avoided by using charging systems which incorporate airlocks. Continuously operating incinerators are generally fed from enclosed handling and sometimes pretreatment and charging systems. Control of air and consequently combustion is easier with continuously operating systems.

The incineration process

Residence time in the furnace has to be long enough to ensure good burnout, as measured by the total organic carbon content and it needs to be controllable. The supply of air to different combustion zones also has to be controllable. Minimum conditions of 850 °C combustion gas temperature, with a gas residence time of 2 seconds are specified in ABP Regulation 1774/2002/EC [287, EC, 2002], for animal carcasses, which are excluded from the scope of WID Council Directive 2000/76/EC [195, EC, 2000]. WID Council Directive 2000/76/EC sets similar conditions, for all other animal by-products, including parts of carcasses, although it also allows the competent authority to lay down different conditions, provided the requirements of that Directive are met.

With most furnace designs, the minimisation of primary air will both minimise NO_x production as well as the velocities which lead to the entrainment of particles. An adequate distribution of air and fuel on the bed will prevent the formation of hot zones and thereby reduce the volatilisation of material, which could otherwise lead to the formation of heavy metal oxides and alkali metal salts in the fly ash. Combustion zones may be separate chambers or, as in the case of BFB incinerators, they may simply be areas within the same chamber where primary and secondary air are introduced.

Water cooling of grates may be an alternative to providing excess air in grates to control metal temperatures. This can also improve primary air control and hence combustion.

Ash handling and storage

Enclosed handling systems avoiding the use of brushes or compressed air minimise dust emissions and, therefore, assist compliance with both occupational health and environmental controls.

Cleaning

One rotary kiln incinerator operating continuously and its enclosed equipment upstream of the rotary kiln, i.e. the storage, handling, grinding and charging mechanisms, is cleaned by feeding wood chips through the system periodically, usually before maintenance and then incinerating them in the incinerator. This incinerator is dedicated to the destruction of SRM comprising cattle heads and vertebral columns.

2.2.8.2 Dedicated incineration of animal meal

Most of the following information is taken from UK guidance [82, EA, 1998]. Other sources are cited.

The collection and disposal of certain animal by-products may be subject to the requirements of the Council Directive 91/689/EEC of 12 December 1991 on hazardous waste, concerning the prevention of infection.

Bubbling fluidised bed incinerator

Animal meal can be incinerated in fluidised bed incinerators, as these are suitable for reasonably homogeneous materials. BFB incinerators are used for incinerating animal meal in the UK. A fluidised bed incinerator is normally a single stage process. It consists of a refractory-lined shell. The chamber contains a granulated bed consisting of an inert material such as sand or limestone. In at least one plant the granulated bed comprises ash from the incineration of animal meal. The granulated bed is supported on a distribution plate and fluidised air or another gas which is blown up through the plate. Ancillary equipment includes a fuel burner, a waste feed mechanism and possibly an after-burner chamber. BFB incinerators have the advantage of having a simple construction with no moving parts, so maintenance requirements are minimal. The granulated bed provides continuous attrition of the burning material, removing the char as it forms and exposing fresh material for combustion. This assists with increasing the speed and completeness of combustion.

Description of animal meal

Animal meal can be incinerated on the rendering site where it is produced, it can be sent directly from the rendering plant to the incinerator, or it may be kept in an intermediate store. It may be in the form of true meal, i.e. finely ground. In most cases, however, the grinding stage which would have been undertaken during animal feed preparation, will have been omitted. Normally it will comprise lumps of up to 50 mm down to dust and this can cause problems with both handling and combustion. Sometimes MBM is delivered in pellets [164, Nottrodt A., 2001]. The variability of MBM composition is shown in Table 2.8 and Table 2.9. The variability in supply may affect the combustion process and the emission levels.

Constituent	Intervention Board Analyses	Other analyses
Fat (%)	10 - 14	8.4 - 28.6
Moisture (%)	5 - 10	1.7 - 14.3
Ash (%)	25 - 30	12.8 - 30.7
Details of raw materials unknown		

Table 2.8: Fat, moisture and ash composition of meat and bone meal
[82, EA, 1998]

Substance and source	Units	MBM analysis	MBM sample	MBM sample	MBM sample ⁽¹⁾	MBM Cat 1 (OTMS)	MBM Cat 3	Feather meal
		Bavaria	Ireland	Portugal		UK		
Net calorific value	MJ/kg	18.0	15.7	17.8	16.13	19.1	14.4	21.2
Water	%	4.6	18.9	2.2	7.53	4.5	3.3	5.0
Ash	%	22.03	29.4	23.6	31.0	15.0	31.7	2.9
Nitrogen	%	7.65	5.8	10.6	7.3	9.0	6.2	13.2
Sulphur total	%	0.62	0.5	0.4	0.33	0.57	0.32	2.5
Hydrogen	%	5.86	7.7	6.9	5.07	6.1	4.4	8.1
Carbon	%	40.83	37.2	47.3	36.3	45.7	32.7	50.8
⁽¹⁾ Origin unknown Details of raw materials unknown								

Table 2.9: Composition of meat and bone meal
[164, Nottrodt A., 2001, 293, Smith T., 2002]

Only ground animal meal with a water content of under 5 % and a fat content of under 14 % can be transported pneumatically. There are reports of problems arising with fat contents above 10 %. There is rarely less than 10 % fat in MBM, so pneumatic transport is more practical for lower-fat bone meal and blood meal. [164, Nottrodt A., 2001]

Rotary kiln or fluidised bed furnaces are used for the dedicated combustion of MBM because they can handle the finely divided material.

Tallow may in some cases be incinerated as a support fuel. It burns readily and cleanly and has a very low sulphur content.

Delivery, storage and handling

Animal meal is delivered in bulk tipper lorries or in skips. Tankers can be used for ground animal meal with a water content less than 5 % by weight and a maximum fat content of 10 - 13 % by weight. It can also be delivered packaged, e.g. in 25 kg or 50 kg sacks [164, Nottrodt A., 2001]. It is then transferred to an unloading hopper, either mechanically via conveyors/augurs, or pneumatically. This takes place in enclosed buildings to avoid problems of possible wind dispersion of dusty material. The transfer and handling equipment may also be fully enclosed to avoid the spread of dust. Some animal meal will break down and become dusty, whilst that left at the bottom of stockpiles for long periods becomes compacted into large lumps which will have to be broken up sufficiently for handling and effective combustion. Tallow is likely to require heated storage.

Opinions vary about the potential problems associated with the storage of animal meal. The delivery of MBM in quantities which ensure that it is processed and incinerated on the day of delivery will minimise storage times and reportedly avoid problems with pests and vermin; spontaneous overheating and combustion and will avoid compaction and hardening over time. [164, Nottrodt A., 2001]. It is reported elsewhere, that unless there is already a specific problem with old or damp animal meal, storage times do not cause a problem [65, EA, 1996].

Charging the incinerator

The reported systems for charging incinerators are all continuous, usually by screw conveyor. Pumping can also be used for transferring and charging pasty material. In BFB incinerators, the material is injected into the combustion zone.

The incineration process

Residence time in the furnace should be controllable and must be long enough to ensure good burnout. This can be measured by the carbon content of the ash. For materials incinerated to destroy TSE risk material, the concentration of amino acids in ash is used to monitor the effectiveness of the destruction of proteins. The supply of air to different combustion zones also has to be controllable.

The circumstances when animal meal has to be incinerated are prescribed in ABP Regulation 1774/2002/EC and the conditions for incinerating it are specified in WID Council Directive 2000/76/EC.

Ash handling and storage

As with the incineration of animal carcasses and parts of carcasses, the use of enclosed handling systems without using brushes or compressed air can minimise dust emissions. This assists compliance with both occupational health and environmental controls.

2.2.8.3 Gasification of meat and bone meal

MBM has a significant calorific value and one option for incinerating it is by gasification to produce “syngas”, which can then be burned or used in methanol production. The conditions for incinerating it are specified in WID Council Directive 2000/76/EC. Heat and/or power can be generated during the process. MBM can be gasified without a support fossil fuel. The following information is largely taken from equipment supply literature [196, Therma CCT, 2000], other sources are cited.

There are optimum MBM characteristics for the gasification process, so the source and pretreatment affect the efficiency of the process. The optimal characteristics are shown in Table 2.10.

Chemical composition	%
Carbohydrate	18
Ash	25
Protein	40
Moisture	3
Fat	14

Table 2.10: Optimum MBM composition (% mass dry) for gasification and thermal oxidation

The gasification process involves partial combustion in a reduced oxygen environment. The MBM is fed by a vertical screw conveyor to a ring shaped combustion chamber, where process room air is added at sub-stoichiometric quantities compared to the fuel load at a temperature of 1300 - 1500 °C. The fuel is recirculated back to the gasifier, in the form of partially carbonised material. Syngas is the product of the low oxygen combustion process. The syngas has a lower heating value of 4605 kJ/m³(NTP) [194, EURA, 2000]. The gasification process is endothermic and the syngas is thereby cooled to between 680 °C and 850 °C.

The syngas then passes through a cyclone and a heat-exchanger to cool it further to 500 - 550 °C, for combustion in a thermal oxidiser and boiler.

The typical chemical composition of the syngas produced is shown in Table 2.11.

Chemical composition	%
CO	18 - 24
H ₂	15 - 22
CO ₂	10 - 14
CH ₄	1 - 4
N ₂	45

Table 2.11: Typical chemical composition of syngas produced by the gasification of MBM

The syngas can then be burned in a thermal oxidiser or boiler, to produce steam. The combined system can incinerate MBM; burn air, vapour and non-condensables, from rendering and produce steam. Ash residues containing some carbon are produced. [194, EURA, 2000]

2.2.9 Burning of tallow

Many boilers have been designed to burn fuel oil, natural gas or tallow, depending on what is available, however, this method of treatment of tallow is not allowed under ABP Regulation 1774/2002/EC, at the time of writing. ABP Regulation 1774/2002/EC requires incineration or co-incineration of Category 1 tallow and allows other specified treatments of “rendered fats”, from Category 2 and Category 3 material.

2.2.10 Landfill and land spreading/injection

Animal by-products which are landfilled include animal meal, feathers, gelatine shavings and WWTP solid residues. The requirements of the Landfill Directive must be met [352, EC, 1999].

ABP Regulation 1774/2002/EC bans the application to pasture land of organic fertilisers and soil improvers, other than manure and consequently limits the opportunities for the land spreading of animal by-products, including compost. It also sets out the limitations on what animal by-products can be used in the manufacture of compost and what pretreatments they require. [287, EC, 2002]

In the UK, a code of practice on water protection has been published by DEFRA and the Scottish Executive. It includes guidance on the land application of non-agriculturally derived wastes. Its objective is to describe management practices which can be adopted and which if vigorously followed should avoid, or at least minimise, the risk of causing pollution from agricultural practices. In Scotland, the use of untreated blood and gut contents has recently been prohibited, to prevent odour problems and possible health risks. Under the new rules, the total addition of nitrogen, phosphorus, potassium, magnesium, sulphur and trace elements being spread should not exceed the needs of the planned crop.

In Ireland, a “Code of Practice” has been established for land spreading, to ensure that it is undertaken with due regard to the pollution risks and taking into account the nutrient requirements of the land. During high rainfall months material destined for land spreading must be stored. Primary sludge from DAF plants is also deemed unsuitable due to its high fat content, which impairs drainage. [168, Sweeney L., 2001]

The land spreading of animal by-products is not permitted in Germany, on anti-epidemic and hygiene grounds [244, Germany, 2002].

In the Netherlands, manure from animal reception and lairage can be used within agriculture, within legal restrictions to regulate the application of nutrients to the soil. The concentrations of heavy metals in the sludge from WWTPs, have to comply with the limits for use as soil improvers in agriculture. [240, The Netherlands, 2002]

2.2.11 Biogas production

Animal waste and material like digestive tract content is easily digested anaerobically and it gives a high yield of biogas. The process is complex. The carbon-containing material is degraded by micro-organisms, thereby releasing biogas, comprising mainly CH₄ and CO₂. The digestion can be either wet or dry. Wet digestion allows normal pumps and stirrers to be used. The biogas is energy-rich and the digestion residues can often be used as organic fertilisers and soil improvers. [200, Widell S., 2001]. It is also reported that the biogas production process changes nutrients to a form that is more readily absorbed by plants and that the spreading of biogas residues on land leads to fewer odour problems than spreading untreated manure [222, Gordon W., 2001].

Biogas cannot be produced from pure animal material because the nitrogen content is too high. Animal waste must, therefore, be mixed with other organic matter to reduce the nitrogen content. In Denmark, approximately 75 % of the biomass resource for anaerobic digestion is animal manure, with the remainder mainly originating from food processing, including slaughterhouses, although some segregated domestic waste is also treated [152, Danish Institute of Agricultural and Fisheries Economics, 1999]. Animal by-products, manure and the sewage sludge from slaughterhouses can all be treated [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001].

Feedstock

The production of biogas from animal by-products is allowed for certain Category 2 materials and all Category 3 materials, as defined in ABP Regulation 1774/2002/EC, if they are treated, as specified therein. For certain Category 2 by-products, sterilisation under prescribed conditions is required before biogas production. The resulting animal meal can undergo a pasteurisation as prescribed and can be used in biogas production. Category 3 by-products must be subject to the same prescribed pasteurisation/hygienisation treatment. [287, EC, 2002]. It is reported that the pasteurisation process assists the subsequent anaerobic digestion, especially with the digestion of fats.

It is reported that most meat and poultry by-products could be anaerobically digested in a biogas plant, with the exception of hard bone, which is considered to have too high an ash content. Provided that the material is sufficiently reduced in size, feathers, viscera, heads and feet, as well as liquid wastes such as blood and effluent sludge, could be used. [222, Gordon W., 2001]

The treatment of manure, stomach and intestinal contents, bits of hide, waste blood and similar products in biogas installations is advocated in Sweden. [134, Nordic States, 2001]

Biogas production from solid digested and partially digested by-products such as rumen and stomach contents, screenings and of solids-rich substrates such as rumen press water, flotation tailings, grease trap residues and the excrement and urine from the lairage, reportedly have a significant energy potential. [206, Tritt W. P. and Schuchardt F., 1992]. There are, however, problems associated with the control of the formation of a floating scum, but these can be reduced by substitution with a wetter feedstock, e.g. pig slurry instead of rumen contents.

Loading and unloading

Odour can be minimised during the unloading of raw materials and the loading of solid products/by-products if undertaken in an enclosed area.

Production

A biogas production plant has reported the use of slaughterhouse by-products consisting of blood, stomachs and intestines, together with large quantities of process water. Previously, most of the process water was sent to a WWTP. To obtain a slower decomposition process, the materials are mixed with farmyard manure. Other forms of biological waste can also be used. All of the slaughterhouse by-products are pasteurised. After the heat treatment, the mix is allowed to decompose anaerobically. The bacteria culture converts the nutritious substrate to CH₄ and CO₂. [207, Linköping Gas AB, 1997]

A normal biogas composition is about 65 % CH₄ and 35 % CO₂, with small amounts of other gases. The biogas is saturated with moisture. CH₄ is the usable part of the biogas. In order for the CH₄ to be used as fuel, it has to be purified of CO₂, water vapour and small quantities of H₂S. [207, Linköping Gas AB, 1997]

If the biogas is to be used as fuel for vehicles, it has to be cleaned, to a CH₄ content of at least 95 %. The energy content is about 9 kWh/m³. When biogas is used as a fuel for vehicles, the gas is compressed to a pressure of 20 MPa. [207, Linköping Gas AB, 1997]

Electricity can be produced from biogas, which can be utilised for own consumption and, in some countries, it can be integrated into the national power grid.

Table 2.12 shows the reported composition of biogas produced from unspecified animal by-products.

Component	Volume (%)
CH ₄	40 - 70
CO ₂	30 - 60
Other gases, including	1 - 5
H ₂	0 - 1
H ₂ S	0 - 3

Table 2.12: Reported biogas composition from the biodegradation of unspecified animal by-products
[144, Det Norske Veritas, 2001]

Energy generation of 300 kWh/t of ABP processed have been reported. This represents a CH₄ production of 400 m³/h. [144, Det Norske Veritas, 2001]

To measure the energy recovery figures for CH₄ biogas produced from animal by-products, the CH₄ generated must be converted into electricity via a gas engine, taking into account the associated engine efficiency. The energy output quoted for biogas is similar to that produced by rendering with the on-site combustion of animal meal and tallow. [144, Det Norske Veritas, 2001]

For each unit of electricity generated, 1.5 units of waste heat are produced, as hot water at over 80 °C. In Denmark, this is used to provide district heating. If the biogas plant is close to major users of heat, such as industrial facilities or large municipal buildings, it may be possible to derive significant income from the waste heat. In general, the closer the users are to the plant, the more attractive it is to pipe the hot water to them. [222, Gordon W., 2001]

The solid digestion residue contains nitrogen, phosphorus and potassium and can be used as a fertiliser. It is checked regularly to ensure the absence of *Salmonella*.

Problems

There may be problems with damage to vessels, due to gravel etc. ingested by cattle. The vessels may be glass-lined to avoid leaks, due to the very corrosive nature of products. Leaks lead to pressure losses which can interfere with boilers using the biogas.

It has been reported that sulphur in the biogas can cause problems in gas generators and that it should be removed to lengthen the life of the generator. It has also been reported that the sulphur can be added to the digestion residue to improve its plant nutrient value. [222, Gordon W., 2001]

Abatement

The exhaust air from ventilation may require odour abatement or it may be burned in a burner. A flare can be used to prevent biogas from being discharged to air in cases where the capacity of the plant is insufficient or where there is overproduction or stoppage in a downstream power production unit. A temperature of at least 1000 °C for at least 0.3 seconds in the burning zone guarantees low emissions, including odours. Abatement may also be required to remove H₂S.

2.2.12 Composting

Composting has been defined as *the controlled biological decomposition and stabilisation of organic substrates, under conditions that are predominately aerobic and that allow the development of thermophilic temperatures as a result of biologically produced heat. It results*

in a final product that has been sanitised and stabilised, is high in humic substances and can be beneficially applied to land. [176, The Composting Association, 2001]. The composting of animal by-products and their application to land is controlled by ABP Regulation 1774/2002/EC and by Commission Regulation (EC) No 808/2003 of 12 May 2003 amending Regulation (EC) No 1774/2002 of the European Parliament and of the Council laying down health rules concerning animal by-products not intended for human consumption [356, EC, 2003]. Category 2 and Category 3 material may be composted, however, most Category 2 materials must be sterilised under specified temperature, time, pressure and size conditions first.

Raw materials

By-products from slaughterhouses, e.g. lairage bedding, manure, stomach contents, intestinal contents, blood and feathers; from waste water treatment, e.g. screenings, flotation tailings and sludge; solid residues from biogas production; sludge from blood processing and sludge from WWTPs, can all be used in composting.

It has been reported that with the exception of manure from delivery vehicles and lairage no single material from a slaughterhouse fulfils the necessary conditions for optimum composting. Rumen and stomach contents contain vegetable structural materials, but have high water contents. Flotation tailings and fat from grease traps contain no structural substances. Composting is possible, e.g. after mechanical phase separation, or after mixing moisture sorbing and structural components with liquid or pasty sludges. [206, Tritt W. P. and Schuchardt F., 1992]. Composting is carried out using the rumen contents and sludge from slaughtering from at least one Italian slaughterhouse, [248, Sorlini G., 2002]. Although blood is liquid, when combined with, e.g. paunch, it can be pumped and composted in windrows. Other liquids, such as pig slurry, are also mixed with “dry” materials such as the sludge from WWTPs, for composting.

Fresh and anaerobically pretreated rumen or pig stomach contents dried to a dry matter content of $\geq 20\%$ can be composted without additives, with a bed depth of 1 m. For greater bed depths, the dry matter should be at least 22 %. Anaerobic pretreatment can reduce the reaction time from 6 to 4 weeks. If strongly dehydrating machines, such as screw presses, are used to increase the dry matter to $\geq 35\%$, undehydrated flotation tailings and/or fat from the grease trap can be added. Experiments with dehydrated rumen content and flotation tailings, with dry matter contents of 37.6 % and 8.8 % respectively, have shown that compost can be prepared in 6 - 8 weeks. During composting the temperature reaches 70 °C, so decontamination is reportedly guaranteed [206, Tritt W. P. and Schuchardt F., 1992], although the pretreatment required under ABP Regulation 1774/2002/EC should control this.

Receipt and storage

Odour problems may arise from the composting feedstock.

Process

The most important composting condition is that the raw materials should be appropriately mixed to provide the nutrients needed for microbial growth and activity, which includes a balanced supply of carbon and nitrogen. There should be sufficient moisture to permit biological activity without hindering aeration; oxygen should be at levels that support aerobic organisms and temperatures should encourage active microbial activity from thermophilic micro-organisms. [210, Environment Agency, 2001]

Raw materials mixed to provide a C:N ratio of 25:1 - 30:1 are generally accepted as ideal for active composting, although ratios from 20:1 up to 40:1 can give good composting results. Low C:N ratios of below 20:1 allow the carbon to be fully utilised but without stabilising the nitrogen, which may be lost as NH_3 or N_2O . This can cause odour problems. [210, Environment Agency, 2001]

Windrows

A windrow is a long pile of composting materials, usually shaped as an elongated triangular prism [176, The Composting Association, 2001].

Windrows are constructed on a hard standing and drainage is provided to collect any leachate. Wind and rain protection are also provided to minimise air and water entrainment. Water is added to the windrows as and when required for the composting process. Rows reduce by at least one third of their starting size, mainly due to water losses.

The material being composted is turned sufficiently frequently to ensure the maximum sanitation and degradation of the total material and to keep the process fully aerobic [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001].

The windrow composting process is summarised in Figure 2.21.




Figure 2.21: Flow chart showing the windrow composting process
[176, The Composting Association, 2001] - adapted

In-vessel composting

In-vessel composting refers to a group of composting systems, such as bins or containers, agitated bays, silos, drums or tunnels and enclosed halls [210, Environment Agency, 2001]. If composting is undertaken in reactors, the process, including the exchange of respiration gases and temperature, can be controlled better than if windrows are constructed. Consequently the starting materials can be decontaminated and the malodorous and ammonia-laden air can be captured and treated. [206, Tritt W. P. and Schuchardt F., 1992]. The ammonia-laden air is cooled to 38 - 45 °C, by taking more air in through a damper near the exhaust fan and then sending it to a biofilter, via a water scrubbing tower to remove dust. [209, The Composting Association, undated]. For all year use of open systems, wind and rain protection are required. Regular turning is required during the high-temperature composting period, i.e. when the temperature is > 50 °C. [206, Tritt W. P. and Schuchardt F., 1992]. In any case, above 60 °C the microbial activity appears to decrease. The principle of in-vessel systems is to supply air in such excess that it cools the compost, allowing much higher rates of microbial activity.

When supplied in high volumes, air can also help to maintain an open structure in the material. This stops the compost from compacting under its own weight and becoming anaerobic. The material being composted should be 20 % structural material to maintain the airflow through the compost mass.

A reactor vessel composting system is shown in Figure 2.22.




Figure 2.22: Diagram illustrating the in-vessel composting process [209, The Composting Association, undated]

Maturation

This happens at mesophilic temperatures, i.e. within a range of 20 - 45 °C. The moisture evaporation, heat generation and oxygen consumption are all much lower than the active composting stage.

Product

Compost has been defined as *biodegradable municipal waste which has been aerobically processed to form a stable, granular material containing valuable organic matter and plant nutrients which, when applied to land, can improve the soil structure, enrich the nutrient content of the soil and enhance its biological activity.* [176, The Composting Association, 2001]

2.3 Waste water treatments used at slaughterhouses and animal by-products installations

2.3.1 Slaughterhouse waste water treatment

Slaughterhouses are divided between those that treat their waste water on-site and discharge directly to the local water course and those that discharge their waste water to the local WWTP with the permission of their local sewerage company. The latter category carry out some pretreatment of the waste water on-site, usually to at least screen solid materials, although they may also undertake other treatments. Slaughterhouses must comply with the conditions specified in trade effluent discharge consents, either for direct discharge or discharge to the municipal plant, in line with legislative requirements. Some municipal WWTPs can use the slaughterhouse waste water synergistically with influent received from other sources to maximise the efficiency of the plant.

Effluent discharge consents normally include limits for TSS, COD, BOD, pH, ammoniacal nitrogen, total nitrogen, total phosphorus, free or emulsified grease, anionic synthetic detergents, daily flow and maximum weekly flow. They may also include sulphide concentrations, due to the potential for anaerobic decomposition of sludge. Discharge permits for slaughterhouses that carry out hide salting, may also include limits for chloride concentrations.

In Denmark, the waste water is generally only pretreated, by screening through a 2 mm mesh, after which it is normally considered desirable for the denitrification process in the local authority WWTPs. Surcharges are normally calculated according to the BOD levels and in some areas the nitrogen and phosphorus contents are taken into account.

In the Flemish part of Belgium, about 40 slaughterhouses discharge their waste water to municipal WWTPs. Filters and screens, grease traps and coagulants/flocculants are used. About 20 Flemish slaughterhouses have biological treatment plants which treat the water to a high enough standard to enable it to be discharged directly without further off-site treatment. [346, Belgian TWG member, 2003]

Most slaughterhouses in the Netherlands discharge their waste water to municipal WWTPs. Due to the relatively high treatment costs at municipal WWTPs, all slaughterhouses have pretreatment systems, mostly consisting of rotary drum sieves and DAF, sometimes in combination with chemicals. Sometimes the slaughterhouses have a biological treatment installation. The treated effluent is almost suitable for direct discharge to surface water and is not considered a desirable commodity for the municipal WWTPs [240, The Netherlands, 2002].

In Austria, most slaughterhouses have systems for waste water treatment consisting of grate covers and catch pots, followed by activated sludge lagoons and fat separators. Large plants occasionally use rotary drum screens and flotation plants. [348, Austrian TWG member, 2003]

In Sweden, slaughterhouse waste water is considered to be an important source of carbon in the denitrification process at the municipal WWTP and mechanical screening is usually the only pretreatment required [134, Nordic States, 2001].

In Norway, the majority of slaughterhouses have fat traps with screens with 0.8 - 1 mm mesh and they either have their own biological or chemical cleaning units or they discharge to municipal WWTPs. [134, Nordic States, 2001]

Preventing animal material entering the waste water stream in the first place is the best way of minimising effluent loading. Some slaughterhouse managers have carefully assessed operations involving cutting and trimming and have designed or modified their installations and equipment to physically intercept animal by-products such as meat wastes and viscera before they enter the drains. Training personnel can bring benefits beyond just improving environmental performance. Cleaning up any dropped scraps during the processing time and emptying drain catch pots then replacing them before beginning to clean an area, does not just reduce the overall effluent load, it also reduces the risk of individuals slipping, one of the main causes of work related lost time accidents in the meat industry.

Figure 2.23 shows an example of the main uses of water in a pig slaughterhouse and the waste water pretreatments associated with various unit operations.




Figure 2.23: Waste water streams through a pig slaughterhouse
[134, Nordic States, 2001]

Good management of the selection and use of cleaning chemicals is essential to ensure that they do not kill the micro-organisms in the WWTP. [12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000]

The spillage of high strength organic liquids from overflow from the effluent treatment plant is potentially one of the most polluting events at slaughterhouses. To prevent overfilling and potential spillage into local water courses, effluent tanks can be fitted with high level alarms and devices to prevent automatic overfilling. Many DAF plants continuously monitor their effluent quality and automatically divert effluent to a stand-by storage if the DAF plant breaks down. [12, WS Atkins-EA, 2000]

The sludge produced may be used or disposed of in a variety of ways including the following: biogas production; composting, mixed with other biodegradable material, such as paunch and blood; land injection; rendering followed by incineration and by direct incineration. The processing of sludge can cause odour problems, which are exacerbated by mixing and aerosol production. Energy is required to remove water, by, e.g. centrifugation or pressing. [168, Sweeney L., 2001]

Some slaughterhouse waste water treatment techniques are shown in Table 2.13.

Technology	Emission type	Total suspended solids	Organics	Oils/fats/grease	Nitrates/ammonia	Phosphorus
Primary treatment						
Mechanical screening		Yes	Yes			
Fat separation		Yes	Yes	Yes	Yes	Yes
Equalisation/balance tanks						
Dissolved air flotation		Yes	Yes	Yes		
Dispersion flotation		Yes				
Mechanical flotation		Yes				
Coagulation/flocculation/precipitation			Yes	Yes	Yes	Yes
Sedimentation/filtration/flotation			Yes	Yes		
Secondary treatment						
Anaerobic treatment, followed by anoxic step			Yes			
Activated sludge/aeration lagoons		Yes	Yes		Yes	Yes
Extended aeration			Yes		Yes	
Nitrification/denitrification					Yes	
Tertiary treatment						
Filtration/coagulation/precipitation					Yes	Yes

Table 2.13: Summary of technologies for treating slaughterhouse waste water emissions
[3, EPA, 1996, 163, German TWG Members, 2001] adapted

2.3.1.1 Primary slaughterhouse waste water treatment

Waste water solids are collected for use/disposal according to ABP Regulation 1774/2002/EC. For example, ABP Regulation 1774/2002/EC definition of Category 1 material, includes, amongst other things, *all animal material collected when treating waste water from Category 1 processing plants and other premises in which specified risk material is removed, including screenings, materials from desanding, grease and oil mixtures, sludge and materials removed from drains from those premises, unless such material contains no specified risk material or parts of such material* and of Category 2 material, includes, amongst other things, *all animal materials collected when treating waste water from slaughterhouses other than slaughterhouses covered by Article 4(1)(d) or from Category 2 processing plants, including screenings, materials from desanding, grease and oil mixtures, sludge and materials removed from drains from those premises.*

Waste water from process areas at slaughterhouses is normally screened, to both remove organic debris such as hairs, some fats, tissue, meat scraps, paunch and gross solids and to avoid blockages in the WWTP. Apart from the by-products of actual slaughtering the waste water generally contains primary solids produced during transport, lairage and the washing of stomachs and intestines. These include, e.g. straw, faeces, urine and intestinal contents. Secondary solids e.g. sieve and rake material; fats and floating matter are produced during waste water and air treatment. Solids removal, e.g. by screening may, therefore, be required at the end of the WWTP, as well as at the beginning.

Screens can remove 10 - 15 % of the organic load. They may remove a large proportion of the visible particles [134, Nordic States, 2001].

The most commonly used screening equipment at slaughterhouses includes the static wedge screen, inclined screw press and the rotary drum screen. These screens typically have a mesh size of about 3 mm.

After screening, many large slaughterhouses use a DAF treatment plant to further treat their waste water prior to discharge. DAF uses very fine air bubbles to remove suspended solids. The suspended solids float to the top of the liquid and form foam, which is then skimmed off. In some cases some soluble colloidal substances and phosphates are removed from the waste

water by adding coagulation and flocculation chemicals, e.g. iron salts, aluminium salts and polyelectrolytes, to form precipitates [12, WS Atkins-EA, 2000, 216, Metcalf and Eddy, 1991]. Iron III salts also aid odour reduction, because they remove H_2S [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001].

DAF can remove 15 % of the BOD load and 70 % of the suspended solids, without chemicals and 50 - 65 % of the BOD and 85 - 90 % of the suspended solids, with chemicals. [215, Durkan J., 2001]

Other flotation methods include dispersion flotation, which involves the injection of “dispersion water” produced with compressed air, or mechanical flotation, where the water is agitated to produce air bubbles.

The oils, fats and greases and other solids removed may be sent for rendering, if the fat content is high. Otherwise they may be sent for land spreading, if they have a high nutrient content. [215, Durkan J., 2001]

The liquor may then be passed to a balance tank which is aerated with coarse bubbles/diffusers and surface aerators/venturis to keep the contents mixed and aerated. This removes 5 % of the BOD. [215, Durkan J., 2001]

2.3.1.2 Secondary slaughterhouse waste water treatment

Some large slaughterhouses have installed biological treatment plants which convert soluble and colloidal materials into biosolids. These are usually activated sludge plants which, depending on their capacity, may be preceded by sedimentation or DAF.

Aerobic digestion – activated sludge

The aerobic digestion process using activated sludge involves the production of an activated mass of micro-organisms, capable of stabilising a waste aerobically in an aerated tank. During endogenous respiration bacterial cells react with oxygen to produce CO_2 , water, NO_x and energy.

The addition of oxygen to the system is essential to the process for several reasons, including the oxidation of the organic matter and nutrients and for maintaining good physical mixing.

The organic matter acts as the essential carbon source for the micro-organisms, but they also require inorganic nutrients for their growth. Aerobic digestion is an effective technique for slaughterhouse waste water treatment. It removes principal inorganic nutrients such as nitrogen, phosphorus and sulphur as well as minor nutrients such as copper and zinc. In the case of nitrogen it oxidises ammonia nitrogen to nitrate nitrogen, thereby dealing with the oxygen demand. Further denitrification to nitrogen gas, under anoxic conditions is, however, required to remove the nitrogen. This involves a series of steps via the formation of NO and N_2O . The release of phosphorus also requires a subsequent anoxic step.

After a period of time a mixture of old and new cells, from the aerobic digester, is passed to a settling tank. Here the cells are separated from the treated waste water. The success of this settling/separation process is crucial to the overall success of the treatment. This relies on the good design and operation of the system and on the prevention of “bulking”. Bulking is controlled by preventing the excessive growth of the filamentous bacteria which would create bulky, loosely packed flocs which do not settle well and which lead to excessive BOD in the treated water. The presence of nitrogen and phosphorus in slaughterhouse waste water advantageously inhibit the growth of filamentous bacteria.

A portion of the settled cells is kept to maintain the biological activity of the system and the remaining activated sludge is dewatered and spread on land, used for biogas production, or incinerated. [216, Metcalf and Eddy, 1991]

In some slaughterhouses, an extended aeration is undertaken in the endogenous respiration phase. This requires a low organic loading and a long aeration time. Alternatively an oxidation ditch may be used. [12, WS Atkins-EA, 2000]. This comprises a ring or oval shaped channel and is equipped with mechanical aeration devices. They typically operate in extended aeration mode with long detention times and solid retention times. [216, Metcalf and Eddy, 1991]. Secondary sedimentation tanks are used in most applications.

There are other techniques available, which use the same principle, e.g. the moving bed trickling filter, on which the sludge is coated on plastic spheres. The waste water flows over the spheres and the system reportedly also operates as an odour abatement technique. [240, The Netherlands, 2002]

Anaerobic digestion

The anaerobic treatment of waste water is widely used, although it is favoured by some and not by others. Reported advantages include the considerable reduction of the concentration of impurities in the water, low excess sludge production, biologically stable excess sludge and the potential collection of the energy-rich biogas which is produced [206, Tritt W. P. and Schuchardt F., 1992]. Anaerobic treatment is especially suitable as a pretreatment for waste water which has a high organic load, prior to aerobic treatment.

Anaerobic biological degradation takes place in a three-part process. In the first step, known as hydrolysis, enzymes transform high molecular mass compounds, such as lipids, proteins and nucleic acids into compounds suitable for use as a source of energy and cell carbon, such as fatty acids, amino acids. In the second step, known as acidogenesis or the acid stage, bacteria break these acids down further. In the third stage the, methanogenic stage, the intermediate compounds are broken down into CH_4 and CO_2 . [216, Metcalf and Eddy, 1991]. The CH_4 (biogas) produced can be used as an integral part of the heating system in the plant.

There are two main techniques used. For the standard rate process, the contents of the digester are unheated and unmixed and the detention time is 30 – 60 days. In the high-rate process, the contents are heated and mixed completely and the detention time is typically 15 days or less. The optimum temperature for the process is 30 - 40 °C. The speed of this method and the short retention time makes the dimensions of the installation within reasonable size limits, even at slaughterhouses where the space is limited. Alternatively, a combination of both processes can be used, i.e. the “two-stage” process. The primary function of the second stage is to separate the digested solids from the supernatant liquor. Additional digestion and gas production may also occur. The sludges from aerobic digestion are commonly anaerobically digested.

The bacteria involved are mutually beneficial. Some of the bacteria consume substances which would inhibit the growth of others. An environment which sustains this dynamic equilibrium is, therefore, essential. This requires the absence of dissolved oxygen and sulphides. The pH should range between 6.6 - 7.6. A sufficient amount of nutrients, such as nitrogen and phosphorus, are necessary to ensure the maintenance of the biological community. [216, Metcalf and Eddy, 1991]

The active micro-organisms are inoculated at the waste water inlet and because the process is generally slow and the CH_4 conversion is significant, the amount of sludge that has to be disposed of is minimal. [216, Metcalf and Eddy, 1991]

Anaerobic degradation only converts the carbon-based impurities, measured as BOD levels. The nitrogen compounds are still left in the water after cleaning. [134, Nordic States, 2001]. It is, therefore, considered by some, not to be a realistic option for the treatment of slaughterhouse waste water [240, The Netherlands, 2002] and only suitable as a pretreatment prior to aerobic

treatment. The process does, however, reduce the pathogenic content of the waste water [216, Metcalf and Eddy, 1991].

Biosolids produced by the treatment plant may, e.g. be dewatered prior to land spreading as a soil conditioner or digested to yield biogas. Limitations on land spreading and land injection are leading to an increased trend towards the incineration of sludges [244, Germany, 2002]. Sludge storage, handling and spreading can lead to odour problems. As well as managing the usual operational issues related to activated sludge plants, such as the development of bulking sludges or carrying excessive biomass inventories, particular problems may be experienced with slaughterhouse effluents, which can cause the formation of biologically stable foam; or they may contain biocidal substances capable of inhibiting microbial activity. [12, WS Atkins-EA, 2000]

Removal of nitrogen and phosphorus

Processes have been developed which combine the carbon oxidation, nitrification and denitrification steps in a single process. These processes have several advantages, including reducing the volume of air needed to achieve nitrification and BOD removal; elimination of the need for the addition of organic sources to provide carbon for denitrification and elimination of the need for intermediate clarifiers and return-sludge systems required in a staged nitrification system. It has been reported that most of the systems can remove 60 - 80 % of the total nitrogen, although removal rates of 85 - 95 % have also been reported.

In the combined processes, the carbon in both the waste water and in the micro-organisms after endogenous respiration during the aerobic treatment, is used to achieve denitrification. For denitrification, a series of alternating aerobic and anoxic stages, without intermediate settling, have been used. Anoxic zones can be created, e.g. in oxidation ditches, by controlling the oxygenation levels. The sequencing batch reactor is also suited to providing aerobic and anoxic periods during the operating cycle and can achieve a combination of carbon oxidation, nitrogen reduction and phosphorus removal. Phosphorus can be removed by coagulant addition or biologically without coagulant addition. If the sequence: fill, anaerobic, aerobic, anoxic, settlement and decant is followed then phosphorus release and BOD uptake will occur in the anaerobic stir phase, with a subsequent phosphorus uptake in the aerobic stir phase. By modifying the reaction times nitrification or nitrogen removal can also be achieved. Carbon from the endogenous respiration phase can be used in the anoxic phase to support denitrification. [216, Metcalf and Eddy, 1991]

2.3.1.3 Tertiary slaughterhouse waste water treatment

Tertiary treatments, such as filtration, e.g. using sand filters, reed beds, coagulation, or precipitation, are sometimes used as a final cleaning step for the treated effluent, to reduce the BOD and suspended solids, prior to discharge to a water course.

2.3.2 Animal by-product installation waste water treatment

2.3.2.1 Rendering waste water treatment

See also Sections 2.3.1.1, 2.3.1.2 and 2.3.1.3.

Rendering plants produce waste water with a high organic load. The organic load from rendering a tonne of raw material is equivalent to that produced by 100 people/day. It also contains high levels of nitrogen and phosphorus. ABP Regulation 1774/2002/EC restricts the routes for the use and disposal of all animal material, as defined, collected from Category 1 and 2 processing plants. It also states *Waste water originating in the unclean sector must be treated to ensure, as far as is reasonably practicable, that no pathogens remain.*

2.3.2.1.1 Mechanical waste water treatment

The mechanical stages in the waste water treatment are implemented before any mixing or equalisation takes place. In the rendering industry, sludge catchers, fat separators, sieves, micro-strainers and settlement tanks are normally used. Undissolved animal matter, such as fat and fat particles, meat residues, hair, bristles and mineral admixtures from the process water can be conveyed back into the production process. Fat separation can be difficult, as the animal fat in the waste water can exist in a very fine form. This is especially true if the water temperatures are high and when the waste water contains tensides. High pH values also impair the fat separation, due to saponification.

Fat separators situated before the mixing and equalisation tanks need to be dimensioned for the maximum waste water production foreseeable. This maximum production occurs, for instance, during the exhaust vapour relaxation. Other issues such as temperature, the influence of rinsing and cleaning agents and the production of the different types and densities of fat need to be considered at the design stage.

In many plants, the fat separator is followed by additional strainer units with sieve apertures of 0.5 - 2 mm, for even more extensive solids separation.

2.3.2.1.2 Physico-chemical treatment

Physico-chemical methods, particularly flotation methods, are used for an extensive separation of the fat and solids. Flocculation agents are used as and when required. Fat retention can be done in fat traps with manual or automatic cleaning. If the fat is emulsified or contains stickwater from the edible fat rendering department, the separation can be very difficult. In such cases it is necessary to use chemical precipitation and flotation.

As with the fat separators, the efficiency degree of flotation plants is reduced by high temperatures and high pH values. Mechanical flotation using air supplied from especially developed submerged flotation aerators, is the method least susceptible to high pH values.

Stripping can be used for the treatment of the hot exhaust vapour condensates (EVCs). Due to low waste water volume flows, it can also be used for the main waste water stream. It is reported that any neutralisation of the stripping effluent is not done immediately after the stripping, but only after the reconvergence with the other waste water part-streams.

The position of the stripping plant in the waste water treatment process is shown in Figure 2.24.




Figure 2.24: Block diagram of a mechanical/physical-chemical preliminary waste water plant [163, German TWG Members, 2001]

Another option to reduce the ammoniacal nitrogen is ammonia conversion. The ammonia is conveyed with the exhaust vapours into a washing tower (converter) countercurrent to a nitrous solution and ammonium nitrate is formed. The ammonium nitrate is extracted from the filter tower when the desired concentration has been reached. The exhaust vapours freed from the ammonia are then condensed into acid exhaust vapours.

For the operation of such a converter, it is necessary that the exhaust vapours do not carry any solids. Cyclones or other suitable separation implements must, therefore, be installed before the converters.

2.3.2.1.3 Biological treatment

Aerobic part-treatment can be used to remove some of the organic material and thereby reduce the BOD of the waste water. It is sometimes undertaken at installations, prior to further waste water treatment at a municipal WWTP.

The composition of waste water from the rendering industry makes it suitable for anaerobic pretreatment. It is, however, unsuitable for the total elimination of the organic load or the elimination of nitrogen. The presence of sulphides may also cause problems.

Anaerobic treatment is generally followed by aerobic treatment to remove nitrogen (and phosphorus) at the rendering site or at the municipal WWTP. Release of phosphorus occurs under anoxic conditions. Thus, biological phosphorus removal requires both anaerobic and aerobic reactors or zones within a reactor. [216, Metcalf and Eddy, 1991]. Anaerobic pretreatment of the waste water is suitable, especially for indirect discharge combined, with a physico-chemical nitrogen elimination.

2.3.2.1.4 Feathers - elimination of hydrogen sulphide

For waste water with high sulphide concentrations, for instance the part-streams from the feathers processing, another preliminary treatment target is the reduction of the H_2S concentrations. Contents from about 80 – 100 mg/l of sulphide will impair the activated sludge biocoenosis and thus the subsequent biological treatment process.

Hydrogen peroxide may be used for the treatment of sulphide-containing waste water. To oxidise 1 kg sulphide stoichiometrically, about 13 litres of 30 % hydrogen peroxide are needed. The reaction time is about 10 minutes. [163, German TWG Members, 2001]

2.3.2.2 Fish-meal and fish-oil manufacturing waste water treatment

One plant has reported that it uses DAF on-site and then discharges its waste water to a local municipal WWTP.

2.3.2.3 Blood processing waste water treatment

A propriety WWTP has been described for a given blood processing plant. The first step is a physico-chemical treatment, during which polyamines and polyelectrolyte flocculants are added. This is followed by decanting the sludge to another tank. The clarified liquid is also transferred to another tank, where it is corrected for pH and anti-foaming agents are added. The liquid is then subject to a series of aerobic and anaerobic treatments. The WWTP is covered to prevent the release of NH_3 , from the breakdown of protein. The sludge is used in composting, due to its high protein content.

2.3.2.4 Gelatine manufacture waste water treatment

The water from the bone washing is cloudy and contains particles such as bone fragments, which are removed by screens. Solids are removed using sieves made from, e.g. a mechanical screen constructed from wedge wire. The solids are brushed off the screen into a skip, for disposal to landfill.

The liquid, which is highly organically contaminated [244, Germany, 2002], is delivered to a primary and secondary settlement tank, to allow separation of solids. Iron(III)chloride is injected with either H_2SO_4 or NaOH , depending on the pH, along with polyelectrolyte flocculant. The resultant liquor undergoes aerobic digestion using activated sludge. Nitrification and denitrification steps are also required [244, Germany, 2002]. A clarification step may be followed to remove the activated sludge. The resultant sludge is rich in nitrogen, phosphorus and calcium and is used for land injection and land spreading, possibly after mixing with other ingredients. Alternatively, the sludge may be used to produce biogas [349, GME TWG members, 2003].

3 CURRENT CONSUMPTION AND EMISSION LEVELS

Before reporting the specific consumption and emission level data for the unit operations, some levels for the overall processes are reported here. The units used reflect the information made available and its purpose. The Directive refers to slaughterhouse production capacities in tonnes per day and animal by-products installations with treatment capacities in tonnes per day. The average live and carcase weights reported from the various EU countries vary, as shown in Table 1.3 in Section 1.1.

Consumption and emission data has, to a large extent, been reported either per tonne of carcase produced or per tonne of by-product treated. This reflects the terminology of the Directive and it makes it easy to compare information from different sources. The main driving force for using “per tonne of carcase produced” and “per tonne of by-product treated”, is to closely examine the relationships between the actual processes and consumption and emission levels and to avoid misleading information based on, e.g. low concentrations, which are achieved by the overconsumption of water.

The actual consumption and emission levels reported in this chapter serve more than one purpose. Firstly, the ranges of levels for given processes and unit operations illustrate potential opportunities for improvement in environmental performance by those operating at the higher levels in the range. Secondly, the availability of data from unit operations also demonstrates that it is practicable to measure consumption and emission levels at that level. The information can also be used to identify priority unit operations which can be improved and to monitor the progress of improvements. The availability of data at unit operation level also makes it possible to compare techniques and determine BAT, for those parts of processes where consumption and emission levels are significant and alternatives are available.

3.1 Slaughterhouses

3.1.1 Slaughterhouses - overall consumption and emission data at installation level

Analyses of data from Danish and Norwegian slaughterhouses examining the trend between the consumption of water and energy as a function of the total production of a plant have been undertaken. These compared levels either per tonne produced or per animal. They show a weak tendency towards a lower relative water and energy consumption as the plant size increases. A statistical analysis indicates a very large standard deviation, so only a subjective evaluation can be made. This shows that the relationship is not clear. [134, Nordic States, 2001]

Consumption and emission data for slaughterhouses are summarised in Table 3.1, Table 3.2, Table 3.3 and Table 3.4.

All PER TONNE of CATTLE carcase	Water consumption (l)	Waste water (l)	Energy (TOTAL elec. + fuel) consumption (kWh)	Heat recovery (kWh)	BOD emission (kg)	COD emis. (kg)	Nitrogen emission (g)	Phosphorus emission (g)	Suspended solids emission (g)	Odour emission	Noise emission	Detergents (kg)	CO ₂ emission (kg)	SO ₂ emission (kg)	NO _x emission (kg)
	(1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 27)	(6, 8, 9, 28)	(3, 4, 6, 12, 13)	(6)	(3, 4, 5, 12, 9, 11, 14)	(12, 9, 11, 14)	(4, 6, 12, 9, 14)	(3, 4, 6, 12, 9, 14)	(6, 14)	(5, 12)	(5, 12)	(12)	(12)	(12)	(12)
Unloading + vehicle wash	200 - 320				0.4					Yes	Yes				
Lairage	152 - 180				0.4 - 3.0			26.6 - 30.4		Yes	Yes				
Slaughter										Yes	Yes				
Bleeding										Yes					
Hide removal	5									Yes	Yes				
Head + hoof removal											Yes				
Evisceration										Yes					
Splitting					2.2						Yes				
Chilling											Yes				
Red and green offal treatment										Yes					
Intestine washing										Yes					
Tripe washing	500 - 2760									Yes					
Hide preservation/storage		*5000													
Cleaning															
Air treatment															
Liquid effluent treatment															
Solid waste treatment															
Storage of by-product										Yes					
Total (including where individual data are not available)	1623 - 9000	1623 - 9000	90 - 1094	≤ 60	1.8 - 28	4 - 40	172 - 1840	24.8 - 260	11.2 - 15.9			**0.2	0.12	75.6	0.16
Techniques which provide or derive benefit to or from other activities															
* per/day - irrespective of no. of hides **0.11 kg/t alkali, 0.03 kg/t acid, 0.04 kg/t disinfectant, 0.02 kg/t "post-treatment" Ranges received - operating conditions, treatments and sampling methods neither described nor submitted References: (1) [12, WS Atkins-EA, 2000]; (2) [63, ETBPP, 2000]; (3) [132, Thy-Christensen, 2001]; (4) [134, Nordic States, 2001]; (5) [142, Derden A., 2001]; (6) [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]; (7) [163, German TWG Members, 2001]; (8) [215, Durkan J., 2001]; (9) [242, Belgium, 2002]; (10) [243, Clitravi - DMRI, 2002]; (11) [248, Sorlini G., 2002]; (12) [185, Pontoppidan O., 2001]; (13) [314, Viitasaari S., 2002]; (14) [315, Belgium, 2002] (27) [346, Belgian TWG member, 2003]; (28) [353, Clitravi - DMRI, 2003]															

Table 3.1: Consumption and emission data for cattle slaughter

All PER TONNE of PIG carcase	Water consumption (l)	Waste water (l)	Energy (TOTAL electricity + fuel) consumption (kWh)	Heat recovery (kWh)	BOD emission (kg)	COD emission (kg)	Nitrogen emission (g)	Phosphorus emission (g)	Suspended solids emission (kg)	Odour emis.	Noise emis.	Detergents emission (kg)	CO ₂ (kg)		SO ₂ emis. (g)	NO _x (g)	Ammonia (kg)
													Stunning + dry ice (cooling)	Other (not stunning + dry ice)			
	(1, 2, 3, 4, 15, 16, 5, 6, 7, 17, 18, 9, 19)	(6, 7, 18, 9, 28)	(3, 4, 6, 17, 18, 9, 13)		(3, 4, 5, 17, 9, 14)	(7, 9, 14)	(3, 4, 6, 9, 14)	(3, 4, 6, 18, 9, 20, 14)	(6, 14)	(5, 18)	(5, 18)	(17)	(3, 4, 17)	(17, 18)	(17)	(17)	(17, 18)
Unloading + vehicle wash	78 - 290				0.3					Yes	Yes						
Lairage	130 - 300									Yes	Yes						0.01
Slaughter	10 - 50									Yes	Yes		1.3 - 2.9				
Bleeding	30 - 40				0.3					Yes	Yes						
Skin removal	520 - 1750									Yes							
Scalding	150 - 156		17 - 39		0.23 - 0.26						Yes						
Hair + toenail removal	78 - 120				0.91 - 2.2					Yes	Yes						
Singeing	162 - 208		47 - 182	175						Yes	Yes			6 - 8			
Rind treatment	260 - 460				1.25 - 2.21					Yes	Yes						
Evisceration										Yes							
Splitting			55		5.5					Yes	Yes						
Chilling	0 - 226										Yes						Yes
Red and green offal treatment										Yes							
Intestine washing	442 - 680	220 - 540			0.98 - 3.25	1.41 - 3.04				Yes							
Cleaning	325									Yes							
Air treatment																	
Liquid effluent treatment														5 - 6			Yes
Solid waste treatment																	
Storage of by-product													1.7				
Total (including where individual data are not available)	1600 - 8300	1600 - 6000	110 - 760		2.14 - 10	3.22 - 10	180 - 2100	20 - 233	0.12 - 5.1	Yes	Yes	0.81	4.6 - 10	0.25	112	0.26	0.03 - 0.04
Techniques which provide or derive benefit to or from other activities																	
Ranges received - operating conditions, treatments and sampling methods neither described nor submitted References: (1) [12, WS Atkins-EA, 2000]; (2) [63, ETBPP, 2000]; (3) [132, Thy-Christensen, 2001]; (4) [134, Nordic States, 2001]; (5) [142, Derden A., 2001]; (6) [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]; (7) [163, German TWG Members, 2001]; (9) [242, Belgium, 2002]; (13) [314, Viitasaari S., 2002]; (14) [315, Belgium, 2002]; (15) [136, Derden A, 2001]; (16) [137, Leoni C., 2001]; (17) [182, Pontoppidan O., 2001]; (18) [237, Italy, 2002]; (19); [322, Finnish TWG, 2002] (20) [274, Pontoppidan O., 2002], (28) [353, Clitravi - DMRI, 2003]																	

Table 3.2: Consumption and emission data for pig slaughter

All PER TONNE of SHEEP carcase	Water consumption (l) (2, 4)	Waste water (l) (28)	Energy consumption (kWh) (4)	Heat recovery (kWh) (4)	BOD emission (kg) (4)	COD emission (kg)	Nitrogen emission (g) (4)	Phosphorus emission (g) (4)	Suspended solids (g)	Odour emission	Noise emission	Detergents	CO ₂ emis. (kg)	SO ₂ emis. (kg)	NO _x emis. (kg)	Salt consumption (kg) (4)	Salt waste (kg) (4)
Unloading + vehicle wash																	
Lairage																	
Slaughter																	
Bleeding																	
Skin removal																	
Head udder + hoof removal																	
Evisceration			4 - 7		0.44												
Splitting																	
Chilling																	
Red and green offal treatment	1667																
Intestine washing																	
Skin preservation	278				0.33											94	39
Cleaning																	
Air treatment																	
Liquid effluent treatment																	
Solid waste treatment																	
Storage of by-product																	
Total (including where individual data are not available)	5556 - 8333	5556 - 8333	922 - 1839	0	8.89		1556	500									
Techniques which provide or derive benefit to or from other activities																	
Ranges received - operating conditions, treatments and sampling methods neither described nor submitted																	
References: (2) [63, ETBPP, 2000]; (4) [134, Nordic States, 2001], (28) [353, Clitravi - DMRI, 2003]																	

Table 3.3: Consumption and emission data for sheep slaughter

All PER TONNE of POULTRY carcase	Water consumption (l) (3, 4, 6, 21, 22, 9)	Waste water (l) (6, 9, 28)	Energy (TOTAL elec. + fuel) consumption (kWh) (3, 4, 6, 21, 22, 13)	Heat recovery (kWh) (6)	BOD emission (kg) (4, 21, 22, 9, 14)	COD emis. (kg) (22, 9, 14)	Nitrogen emission (g) (4, 6, 21, 22, 9, 14)	Phosphorus emission (g) (4, 6, 21, 22, 9, 14)	Suspended solids emission (g) (6, 22, 14)	Odour emis. (21)	Noise emis. (d(B)A) (at source) (21, 22)	Detergent	CO ₂ emis. (kg)	SO ₂ emis. (kg)	NO _x emis. (kg)	Solid waste emis. (kg) (22)	By- product emis. (kg) (22)	Wax
Unloading + Vehicle/crate wash	19 - 3786									Yes	99							
Lairage	0 - 1039		5.4							Yes	91							
Stunning	0 - 22.8		1.1															
Bleeding	0		0.1								84					38.3		
Scalding	276 - 1000		34							Yes	93							
De-feathering	90 - 1429		7.5							Yes	93					52		
Evisceration	1300 - 2100		15								91					141	85	
Chilling	714 - 1700		20					15.1	157									
Cleaning	1973 - 2600		39															
Air treatment																		
Liquid effluent treatment	132		14		15.3	23.6		202	60.4	Yes	93							
Solid waste disposal or treatment																5.5		
Storage of by- product	1100																	
Utilities - please state																		
Maturation	1540		16			0.74		4.1	48								85	
Total (including where individual data are not available)	5070 - 67400	5070 - 67400	152 - 860	≤ 220	2.43 - 43	4 - 41	560 - 4652	26.2 - 700	48 - 700									
Techniques which provide or derive benefit to or from other activities																		
Ranges received - operating conditions, treatments and sampling methods neither described nor submitted																		
References: (3) [132, Thy-Christensen, 2001]; (4) [134, Nordic States, 2001]; (6) [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]; (9) [242, Belgium, 2002]; (13) [314, Viitasari S., 2002]; (14) [315, Belgium, 2002]; (21) [188, Pontoppidan O., 2001]; (22) [214, AVEC, 2001], (28) [353, Clitavi - DMRI, 2003]																		

Table 3.4: Consumption and emission data for poultry slaughter

Air

Reported emissions of CO₂, SO₂ and NO_x are shown in Table 3.5.

Substances emitted	Range of emissions per tonne of carcase (kg) (species and sources not specified)
CO ₂	22 - 200
SO ₂	0.45 - 1.1
NO _x	0.29 - 0.52

Table 3.5: The range of air emissions from 3 Finnish slaughterhouses
[148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

Water

Many slaughterhouses do not carry out any submetering of water or energy consumption, and are only aware of their total consumption from utility bills. Some have recently begun to submeter water and energy consumption by process area and expect to make substantial cost savings through monitoring and targeting programmes. The water balance for different process areas at a typical UK pig slaughterhouse is shown in Figure 3.1. It should be noted that the UK data do not include chilling. Data for water consumption in a typical Italian pig slaughterhouse are shown in Figure 3.2.

All slaughterhouses must have a pressurised supply of potable water within the meaning of Directive 80/778/EEC. A non-potable water supply is authorised in exceptional cases for steam production, fire fighting and the cooling of refrigeration equipment, provided that the pipes installed for this purpose preclude the use of this water for other purposes and present no risk of contamination of fresh meat. Non-potable water pipes must be clearly distinguished from those used for potable water. [169, EC, 1991, 223, EC, 1992]. This requirement for potable water to be used limits the opportunities for re-use of water.




Figure 3.1: Typical water balance for areas in a UK pig slaughterhouse
[12, WS Atkins-EA, 2000]




Figure 3.2: Data for water consumption in a typical Italian pig slaughterhouse

Where water consumption data has been collected for different groups of unit operations, comparison is not easy. If Figure 3.1 is compared with Table 3.6, some similarities can be seen, e.g. for vehicle washing and lairage washing. There are some wide variations too, e.g. for cleaning. Although the percentages cannot be attributed to absolute consumption levels, they illustrate, by the fact that there are variations, that for some unit operations the techniques which consume the least water are not universally applied.

Where water consumed	%
Vehicle wash area	5 %
Lairage	5 %
Scalding tank	3 %
Rind treatment	10 - 15 %
Clean-slaughter area	5 - 10 %
Cutting/deboning	5 - 10 %
Sterilisation (82 °C)	10 - 15 %
Casing-cleaning department	20 %
Cleaning	15 - 20 %
Refrigeration system	5 %
Boiler house	2 %

Table 3.6: Estimated distribution of water consumption in some large Danish pig slaughterhouses [134, Nordic States, 2001]

It has been stated, that it is difficult to reduce water consumption significantly, due to veterinary demands. There is, however, no EU legal requirement for the washing of large animal carcasses, but it is general practice. Also, there is only a limited requirement for the washing of poultry carcasses, in a specified volume of water, between the evisceration and chilling [223, EC, 1992]. Many slaughterhouses exceed this requirement. It has been reported that in one Danish poultry slaughterhouse killing approximately 25 million birds per year, at a rate of approximately 9000 birds per hour, the demanded minimum consumption for “external and internal wash” and for chilling comprises approximately 56 % of the total water consumption. [134, Nordic States, 2001]. Cleaning and carcass washing can account for more than 80 % of the total water use and the effluent volume [63, ETBPP, 2000].

Emissions to water from slaughterhouses can be divided into process emissions and emissions from spills and diffuse sources. The main emissions include organic material, which contributes to the BOD and COD levels and inorganic material such as ammonia and phosphorus. Sources

of process emissions include the washing of vehicles, washing of carcasses, cleaning of the production area and associated downstream activities such as e.g. stomach, tripe and casings washing. [3, EPA, 1996]. Those operations which emit manure and partly digested feed are increasingly believed to be significant sources of phosphorus emissions [274, Pontoppidan O., 2002].

It has been demonstrated in Norway, that the water consumption for cleaning after completion of the slaughter process, is nearly the same whether 1 or 150 animals have been slaughtered. A dirty slaughter-line must be cleaned, regardless of the number of animals processed. [134, Nordic States, 2001]. The water required for cleaning the plant, after completion of the slaughter process, may not differ much with respect to throughput, but it can be affected by the plant size. The other water consumption activities may also be more dependent on the throughput, e.g. vehicle washing, carcass washing and cleaning during the slaughter process.

The opportunity to reduce water consumption in some areas may be limited by hygiene and quality requirements. If these are genuinely excessive and both customers and regulators can be convinced of this, then a reduction may be possible. A comparison of actual water consumption with that recommended by equipment suppliers may identify opportunities for reducing consumption. Sub-processes for which the water use often exceeds the actual need include cleaning, meat sprays and rinses, pig scalding, vehicle washing and lairage washing. [12, WS Atkins-EA, 2000]

Table 3.7 shows the estimated distribution of water pollution between individual processes in a cattle slaughterhouse.

Where water consumed	%
Vehicle wash and lairage	~ 5
Slaughter area	40 – 50
Casing cleaning including tripe wash	40 – 50

Table 3.7: Estimated distribution of waste water pollution in a Danish cattle slaughterhouse [134, Nordic States, 2001]

The increased automation of carcass dressing and the incorporation of washing at every stage, are increasing both water consumption and the amount of material such as fat, blood and faeces entering the waste water. This consequently requires WWTPs which are capable of treating high volumes of contaminated waste water.

Table 3.8 shows the estimated distribution of water consumption between individual processes in a sheep slaughterhouse.

Where water consumed	%
Slaughter	~ 80
Cutting/deboning	~ 10
Casing cleaning	~ 10
Deboning is not within the scope of the BREF	

Table 3.8: Estimated distribution of water consumption in a Norwegian sheep slaughterhouse [134, Nordic States, 2001]

Table 3.9 shows the estimated distribution of water consumption between individual processes in a number of poultry slaughterhouses.

Where water consumed	%
Scalding tank	6
Plucking	11
Internal/external wash	9
Chiller	14
Wash/cooling of viscera	9
Refrigeration condensers etc.	3
Box/rackwash	2
Cleaning during operation	18
Cleaning after operation	28

Table 3.9: Estimated distribution of water consumption in some Danish poultry slaughterhouses [134, Nordic States, 2001]

Table 3.10 shows the distribution of water consumption reported for a Finnish slaughterhouse.

Use	The distribution of water consumption % of total	Water consumption per tonne of carcass produced (l)
Water at 4 - 7 °C		
Cleaning of intestines	17.34	730
Slaughter	8.90	380
Lairage	1.30	60
Vehicle washing	0.03	< 10
Cleaning of hides/skins and heads	3.09	130
Waste water treatment plant	0.11	< 10
Refrigeration	0.24	10
Sanitation	0.31	10
Total water at 4 - 7 °C	30.59	~1340
Water at 40 °C		
Slaughter	7.80	330
Cleaning	0.87	40
Various	15.39	650
Total water at 40 °C	24.06	1020
Water at 55 °C		
Cleaning of intestines	2.43	100
Cleaning	21.64	920
Various	0.75	30
Total water at 55 °C	24.82	1050
Water at 90 °C		
Slaughter	15.23	640
Cutting/deboning	3.77	160
Cleaning of intestines	1.53	60
Total water at 90 °C	20.53	860
Total water	100.00	4270

Table 3.10: The distribution of water consumption reported for a Finnish slaughterhouse [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

It has been reported that blood and intestinal mucous are responsible for the greatest part of water contamination [206, Tritt W. P. and Schuchardt F., 1992].

Slaughterhouse waste water may contain disease-causing agents and the high discharge temperatures of, e.g. scalding tanks make it a good breeding ground for germs. The rumen contents of healthy cattle have been found to contain rare *Salmonella* types. [206, Tritt W. P. and Schuchardt F., 1992]

Solid waste

Examples of solid waste include lairage and vehicle wash solids; animal by-products; sludge from WWTPs; clean and contaminated packaging; protective clothing and equipment. In the UK, WWTP solids are commonly sent to landfill. In Denmark, they are used in biogas production. Recent studies have revealed manure as the possible main source of phosphorus in solid waste and consequently in waste water too [274, Pontoppidan O., 2002].

Energy

Investigations in Norway have shown that slaughterhouses have an energy consumption even when no production takes place. Much of the energy is used for heating and operation of the refrigeration system. At a Norwegian slaughterhouse, the energy consumed during the sheep/lamb season was measured as 356 kWh/t sheep/lamb carcase and the annual average was calculated as 1256 kWh/t sheep/lamb carcase. This demonstrates the importance of implementing energy saving techniques, even outside the slaughtering times. [134, Nordic States, 2001]

In 1991, a study in the UK reported that the average specific electricity consumption (SEC) for large animal slaughterhouses carrying out slaughter, dressing, chilling and some freezing was 85 kWh/t carcase, with a range of 36 - 154 kWh/t carcase. Some cattle slaughterhouses have rendering plants so they consume more electricity [57, DoE, 1993]; this has, however, become less common.

Energy use is not only in the form of electricity. The 1991 UK study looked at other forms of energy as well and used the term “specific heating fuel consumption” (SHC), defined as “therms purchased to process one tonne of meat”, to standardise their measurement. 85 % of the sites involved in the study had SHCs below 15 therm/tonne carcase (440 kWh/t), with the average being 11 therm/tonne carcase (322 kWh/t). In Italy, pig slaughterhouses have a total energy consumption of 280 – 380 kWh/t carcase, of which 1/3 uses electricity and the remaining 2/3 thermal energy [237, Italy, 2002]. The information available suggests that generalisations cannot be made about which unit operations use electrical energy and which use other sources.

The 1991 study revealed that installations in Northern Ireland had higher SECs than those in Great Britain and this was attributed to the fact that all of the Northern Ireland installations were EC licensed. The higher consumption levels were attributed to the electricity consumption associated with the refrigeration requirements of the EC legislation. The best reported practice for slaughterhouses was 36 kW/t carcase (although it should be noted that the temperature to which installations cooled their meat products was not investigated). The best SHC (0.2 therm/tonne, 5.86 kWh/t carcase) found was from a site using an anaerobic digestion plant to produce biogas from solid slaughterhouse waste. A small amount of fuel was required to supplement the on-site generated fuel. [57, DoE, 1993]. Since then all of the installations in the UK have been licensed.

At a pig slaughterhouse in Denmark, the sources of energy consumption shown in Table 3.11 have been reported.

Energy source	%
Electricity	~ 35
Purchased heat	~ 50
Recouped heat	~ 15

Table 3.11: Sources of energy consumption at a large Danish pig slaughterhouse
[134, Nordic States, 2001]

At a cattle slaughterhouse in Denmark, the sources of energy consumption shown in Table 3.12 have been reported.

Energy source	%
Electricity	~ 40
Heat	~ 50
Recouped energy	~ 10

Table 3.12: Sources of energy consumption at a Danish cattle slaughterhouse
[134, Nordic States, 2001]

The same Danish cattle slaughterhouse had an electricity consumption distribution, as shown in Table 3.13 and heat consumption distribution, as shown in Table 3.14.

Where energy consumed	%
Refrigeration plant	~ 45
Compressed air	~ 10
Lighting	~ 10
Machines	~ 10
Ventilation	~ 5
Various	~ 20

Table 3.13: Distribution of electricity consumption in a Danish cattle slaughterhouse
[134, Nordic States, 2001]

Where energy consumed	%
Room heating	13
Water heating, total	80
Water heating to 40 °C	5
Water heating to 60 °C	54
Water heating to 82 °C	21
Transmission loss	7

Table 3.14: Distribution of heat in a Danish cattle slaughterhouse
[134, Nordic States, 2001]

The figures in Table 3.14 are similar to the German figures of 90 % of heat consumption attributed to water heating and 10 % to building heating [163, German TWG Members, 2001].

Most poultry slaughterhouses use cold and iced water, as well as water at 40, 60 and 82 °C. The distribution between the different types has been estimated as that shown in Table 3.15.

Temperatures of water consumed	%
Iced water	10 – 20
Cold water	~ 50
40 °C	10 – 15
60 °C	15 – 20
82 °C	~ 2

Table 3.15: Estimated distribution of water temperature requirements at Danish poultry slaughterhouses
[134, Nordic States, 2001]

In poultry slaughterhouses in the Nordic countries 60 % of the energy consumed is from electricity and 40 % is from heat sources. The distribution of electricity consumption throughout the process has been reported as shown in Table 3.16.

Where energy consumed	%
Refrigeration	52
Machines	22
Pumps	10
Compressed air	8
Lighting	2
Ventilation	2
Other	4

Table 3.16: The distribution of energy consumption in poultry slaughterhouses in the Nordic countries
[134, Nordic States, 2001]

In the Nordic countries, it is reported that hot water accounts for 85 % of heat consumption. The remaining 15 % is used for room heating. A considerable proportion of the energy consumption for water heating originates from recouped energy from refrigeration and compressed air machines. [134, Nordic States, 2001]

Odour

For many slaughterhouses odour is the most significant air pollution issue in terms of day-to-day local prevention and control, particularly in built-up areas and in warm weather/climates. The odours are generally associated with the collection and storage of blood, gut contents, inedible offal, heads, feet, bones, meat scraps and SRM waste. Other potential sources are the use of macerator equipment to chop and wash inedible offal, inadequate effluent treatment plant maintenance and any blockage of drainage by meat and fat scraps.

Urine and manure odour from the slaughterhouse lairage areas can also cause minor nuisance in built-up areas, although the hygiene and welfare standards required at slaughterhouses can mitigate against significant odour from this source.

There is a very limited amount of emission level data available and a lack of consistency in the use of units. This makes it difficult to approach the issue of odour prevention and control in a quantitative way. CEN is developing a standard for measuring odour, i.e. *prEN 13725:2001 - Air quality - Determination of odour concentration by dynamic olfactometry* [311, CEN, 2001]. Its availability should make consistency easier to achieve, in the future.

Noise and vibration

Typical noise levels found during working hours and measured at the perimeter fence of a slaughterhouse or at the nearest buildings are 55 - 65 dB(A). Typical levels of 40 - 50 dB(A) and 35 - 45 dB(A) have been reported for the evening and night, respectively. These figures depend on the local conditions such as distance, shielding, reflection, operating time and the local attitude towards minimising unnecessary noise. [134, Nordic States, 2001]

The main sources of noise and vibration are animal noises during unloading and marshalling to the slaughter-line; vehicle movements; compressors; air conditioners; ventilation fans and carcase splitting. Some of these sources are present 24 hours a day, whereas others coincide with intermittent activities such as animal deliveries or employee shift change-overs.

3.1.2 Slaughter of large animals

Specific consumption and emission data for the sub-processes of the large animal slaughter process are reported in this section.

3.1.2.1 Animal reception and lairage

The lairage is one of the main sources of noise at slaughterhouses due to vehicle movements and animal noises during unloading. Cattle and sheep are generally fairly quiet, but pigs may be noisy, particularly during unloading and marshalling operations. Washing the vehicles and the lairage area can introduce organic material; inorganics, e.g. ammonia, phosphorus and solids; oils/fats/grease and solids into the waste water [3, EPA, 1996].

There may be odour problems during animal delivery and storage.

In Denmark and Sweden, data have been collected from some large pig slaughterhouses about the proportion of their water pollution which arises from the lairage/vehicle wash activities. In Denmark, it is estimated that 5 % of the pollution emitted came from these. In Sweden, the proportion was estimated to be 16 %. [134, Nordic States, 2001]. With this information alone, it is not possible to comment on the difference because the overall Swedish figures included “cutting/deboning” (accounting for 7 %) and those from Denmark did not.

For hygiene reasons, animal delivery vehicles are be washed down after each delivery. At most installations dedicated hose pipes are provided for this purpose. Most slaughterhouses do not charge for this water as they realise that the costs would be passed back to them in the form of increased delivery charges. HPLV hoses and spray guns can decrease water consumption, but their initial investment cost is greater than traditional hoses. It is reported that they are seldom used because delivery drivers do not generally treat them with care, e.g. they are left lying in the yard where vehicles drive over them. [12, WS Atkins-EA, 2000]. The use of hoses suspended from an inertia reel device, together with adequate training and supervision of drivers, may make their use more widespread and cost effective.

To reduce water wastage some large slaughterhouses have installed a metered water dispenser. Some meters take coins and others operate by inserting a token that is given to the driver on arrival. A driver can request an additional token if he is unable to finish cleaning his vehicle with the specified amount of water. The metered system has reportedly reduced water consumption. [12, WS Atkins-EA, 2000]

Lairage manure, urine and wash-water is high in nutrients and can be collected for agricultural use as a fertiliser, provided specific conditions are met. [12, WS Atkins-EA, 2000]. At some slaughterhouses, clean water from other process areas, e.g. from chills and carcase refrigeration rooms, as well as cooling water and steam condensate, is used to provide a primary wash down of lairage areas [12, WS Atkins-EA, 2000].

According to an analysis of semi-liquid manure from Danish pig farms the emission of copper and zinc from the slaughter process has been calculated/estimated. Some *leaves* the slaughterhouse in solid organic waste, i.e. manure and some in the waste water. The calculated/estimated levels are shown in Table 3.17.

	In solid organic waste (mg/t)	In waste water (mg/t or µg/l)	Total (mg/t)
Copper	0.4	0.6	1.0
Zinc	1.0	1.4	2.4

Table 3.17: Calculated/estimated emissions of copper and zinc, from Danish slaughterhouses [187, Pontoppidan O., 2001]

3.1.2.2 Bleeding

Blood collected for blood processing tends to be collected more carefully and hygienically than that destined for rendering, so less may contaminate the waste water at the bleeding stage of the process. Less stringent hygiene requirements apply to blood which can be rendered, so if it is

collected from floors, the floors have to be washed and the waste water volume and contamination are consequently increased. Hollow knives used to collect blood for food or pharmaceutical use reduce spillage, but the back-pressure they cause means that they also capture less blood than when an animal's throat is cut and natural bleeding occurs. Hollow knives typically collect 75 % of a pig's blood. The remaining blood is then released later in the process and the degree of contamination it causes depends on the speed of the line and the blood collection arrangements along the line. Collection figures of 23 % along the line, for rendering, with the final 2 % going to the WWTP, have been reported. [220, APC Europe, 2001]

Blood has the highest COD strength of any liquid effluent arising from meat processing operations. Liquid blood has a COD of about 400 g/l and a BOD of about 200 g/l. Congealed blood has a COD strength of about 900 g/l. If the blood from a single cattle carcass was allowed to discharge directly to a water company sewerage system the COD effluent load would be equivalent to the total sewage produced by 50 people on an average day. [12, WS Atkins-EA, 2000]. Blood has a total nitrogen content of approximately 30 g/l. It has been reported that retention of the blood is by far the most successful way of minimising waste water contamination in a slaughterhouse [206, Tritt W. P. and Schuchardt F., 1992].

Even if blood is collected carefully, i.e. by positioning the animal over the collection pit for the duration of the sticking procedure and allowing enough time for completion of the bleeding before the carcass is moved on, it has been reported that there may be dripping blood losses of up to 0.5 litres per pig (5.4 l/t carcass) and 2 litres per head of cattle (6.2 l/t carcass). [163, German TWG Members, 2001]. Collecting the blood before the carcass moves away from the sticking area so that it does not drip as it moves down the slaughter-line adds time to the overall process. It has been reported that the additional time taken is compensated for, because the blood collected for processing has a value, otherwise there is a charge for its removal as waste.

It has been reported that 30.5 kWh/t of electrical energy is used to refrigerate raw blood to ~5 °C [272, Woodgate S., 2002].

3.1.2.3 Hide and skin removal

The practice of de-hiding pigs is relatively rare, but where it is carried out, the pigs are machine washed and dried before the hides are removed. Limited figures for the de-hiding of pigs report that water is used at a rate of approximately 70 l/pig, for de-hiding. This includes thorough cleaning of the pigs in the lairage and after bleeding, to avoid contamination during the de-hiding process. [274, Pontoppidan O., 2002]

3.1.2.4 Head and hoof removal for cattle and sheep

Significant blood spillage occurs from the large blood vessels when the head is cut off.

Rinsing the heads to remove blood, can as well as increasing water consumption and water contamination, spread impurities to other areas of the carcass. The need to rinse can, therefore, be limited by using correct slaughter procedures.

3.1.2.5 Pig scalding

The scalding tanks are filled with water at the beginning of each day. They are kept at a temperature of approximately 60 °C throughout the day. Debris and sludge build up in the tanks during production. It is common practice in many slaughterhouses to empty the water and sludge directly into the site waste water drainage system at the end of each day. In some cases, the tank is refilled by leaving the water supply running until it is switched off by the cleaning staff, or the water is even left to run overnight, allowing excess water to spill over the tank into the drain. Some slaughterhouses have made considerable savings by installing a simple ball

valve or other level sensing device to switch off the water supply when the scalding tank is full. [12, WS Atkins-EA, 2000]

In many slaughterhouses there are opportunities to recover useable heat from the exhaust emission and opportunities to minimise heat losses during scalding. The condensation that occurs following evaporation can be removed by extraction.

3.1.2.6 Pig hair and toenail removal

The de-hairing of pig carcasses can cause minor odour problems [3, EPA, 1996]. There is some mechanical noise and vibration from de-hairing machines, but this is not detectable outside the slaughterhouse buildings [12, WS Atkins-EA, 2000].

At this stage of the process, blood is still dripping from the animal. The de-hairing process is wet, so the waste water COD loading may be raised significantly.

3.1.2.7 Pig singeing

In most pig slaughterhouses, the singeing unit is exhausted directly to atmosphere, through a hood just above roof level. Sometimes, the exhaust may include an extraction fan. This emission is estimated to have a temperature of 600 – 800 °C. It also contains fine burnt hair dust. Some slaughterhouses recover useable heat from the exhaust emission. Due to the high flue temperatures, the equipment used to recover heat from singeing units requires storage, pumps and safety devices as well as a heat-exchanger. [12, WS Atkins-EA, 2000]

If LPG is used to singe carcasses, approximately 19.6 l/t is consumed, for a light singe.

Water is used to cool the overhead rail and conveyor system. [134, Nordic States, 2001]

The exhaust air has an odour of burnt hair. [134, Nordic States, 2001]

3.1.2.8 Rind treatment

The main consumption and emission issues are associated with the water consumption and contamination.

3.1.2.9 Evisceration

The first stomach contents are about 75 % water, weigh about 15 – 20 g per head of cattle, and produce a slurry with a COD of over 100 g/l. [12, WS Atkins-EA, 2000]

Evisceration processes are carried out dry, but water is used for rinsing, knife sterilisation, the sterilisation of other equipment and for cleaning. The removed parts and the carcasses are rinsed with water to remove blood and other impurities. The introduction of water not only increases water consumption and water contamination, but it also potentially masks microbiological contamination, by removing potential visible signs.

The fat contained in the waste water from slaughterhouses is mainly produced during evisceration [163, German TWG Members, 2001] and intestine washing.

The rumen contents (paunch) of fully grown cattle amount to 40 - 80 litres per head (wet) [163, German TWG Members, 2001].

Blood drips from the carcasses during evisceration.

3.1.2.10 Splitting

Carcass splitting is one of the main sources of noise in a slaughterhouse. Noise levels of about 95dB(A) have been measured. Further noise is produced when the standard cuts are made. The sound may be detectable outside the building. In addition, the saw operator and anyone in the near vicinity has a significant risk of contracting noise induced hearing loss and health and safety legislation requires this risk to be minimised.

3.1.2.11 Chilling

Refrigeration systems affect the environment through the energy they consume and the effect they can have if refrigerants leak to atmosphere. Making the plant as energy efficient as possible will minimise its environmental impact. [292, ETSU, 2000]

The refrigeration plant is operated continuously and the condensing units, compressors and cooling towers associated with it can be a source of noise. Refrigerated trucks parked outside slaughterhouses can sometimes lead to noise problems if the refrigeration is powered from the truck engines. Many slaughterhouses provide mains power cables to power the refrigeration unit, thereby reducing the noise levels.

3.1.2.12 Associated downstream activities - viscera and hide and skin treatments

Viscera treatment

In Denmark and Sweden, data have been collected from some large pig slaughterhouses about the proportion of their water pollution which arises from washing casings. In Danish slaughterhouses, it is estimated that 30 - 50 % of the pollution emitted comes from washing casings. In Sweden, the proportion was estimated to be 10 %. [134, Nordic States, 2001]. Even allowing for the fact that the overall Swedish figures included "cutting/deboning" (accounting for 7 %) and those from Denmark did not, the difference is significant. The difference is explained by the fact that in Denmark approximately 100 % of stomachs, 100 % of small casings, 100 % of fat ends and 40 % of large casings are cleaned for human consumption. In Sweden the production is much lower. [274, Pontoppidan O., 2002]

Table 3.18 shows that de-sliming intestines makes a significant contribution to the overall pollutant load for waste water.

	Examination days	Specific waste water amount	Specific pollutant loads					
			Settleable solids		BOD ₅		COD	
			(l per animal)	(g DS per animal)	Without sediment (g per animal)	With sediment (g per animal)	without sediment (g per animal)	with sediment (g per animal)
Pigs - with intestine de-sliming	7	100 - (250)	1 - 18	30 - 80	240 - 750	260 - 850	340 - (1080)	-
- without intestine de-sliming	19	58 - 254	0.2 - 1.9	8 - 65	60 - 366	70 - (430)	80 - 430	-
Calculated values are shown in brackets, i.e. extrapolated of 60:70 (measured) for 366 to calculate 430 ($60/70 = 366/430$)								

Table 3.18: Specific waste water amounts and pollutant loads with and without de-sliming of bowels
[163, German TWG Members, 2001]

The wet emptying of stomach and intestinal contents can contribute 20 % of the total BOD in screened waste water from a slaughterhouse and approximately 15 % of the nitrogen. [134, Nordic States, 2001]. In Danish slaughterhouses, total water consumption levels between 800 and 1200 litres and 4.4 to 5.2 kg BOD per tonne of cattle carcase have been reported, for cleaning stomachs and intestines. It has been reported that in Germany 30 % of the total waste water and organic contamination originates from stomach washing [206, Tritt W. P. and Schuchardt F., 1992].

In those slaughterhouses where macerator equipment is used to chop, wash and spin-dry offal prior to supply to the rendering company, the resulting cost savings usually outweigh the increased energy and effluent costs. The cost benefits of this approach result from the reduced volumes of waste for disposal. If offal was cut and washed the tallow colouring during rendering would be reduced and its value could increase. Macerator equipment usually consists of hook-shaped blades set to counter rotate against themselves, or to rotate against fixed anvils. The cut offal is then washed in a rotating mesh drum. The equipment needs to be maintained regularly to optimise the speed and separation of the blades. If the blades are kept in good condition this will optimise the efficiency of the cutting operation and reduce the amount of waste offal, which goes on to become mixed with the wash-water. [12, WS Atkins-EA, 2000]

The cleaning of secondary process areas where, e.g. stomach washing, tripe blanching and sausage skins are made can lead to emissions to water containing organic material; inorganics, i.e. phosphorus, ammonia and solids and oils, fats and grease [3, EPA, 1996].

Hide/skin treatment

Salting using sodium chloride is the most common method of hide and skin preservation. Excess salt which spills off the salting table or is dropped during hand salting may be swept up and re-used. If it is unacceptably contaminated it is normally disposed of, by incineration. Salinity can reduce the efficiency of the WWTP and unless there is a naturally saline water course for receipt of the treated waste water, the salt content can have adverse effects on plant growth. The presence of salts affects the plant growth by osmotic effects, due to the concentration of salt in soil water; the specific ion toxicity, caused by the concentration of an individual ion and the soil particle dispersion caused by high sodium and low salinity. Under these conditions, the plants expend more of their available energy on adjusting the salt concentration within the tissue to obtain water from the soil, so less is available for plant growth. [216, Metcalf and Eddy, 1991]

3.1.3 Slaughter of poultry

Specific consumption and emission data for the sub-processes of the poultry slaughter process are reported in this section.

3.1.3.1 Reception of birds

Cold or hot potable water is used to wash crates. Detergents are added because crates are a potential source of microbiological risk from, e.g. *Salmonella*. The strength of detergent used depends on the species of poultry. High strength detergent is used for turkeys.

Dust is emitted from the birds' feathers during unloading and hanging [316, May G., 2002].

3.1.3.2 Stunning and bleeding

Blood has the highest COD strength of any liquid effluent arising from poultry slaughter operations. Poultry blood has a COD strength of about 400 g/l, which would lead to a doubling of the effluent strength at a typical poultry slaughterhouse if it was allowed to enter the waste water stream.

3.1.3.3 Scalding

Scalding is undertaken at temperatures between 50 and 58 °C. The accumulation of faecal materials in the water has the effect of maintaining the scalding tank at about pH 6, the point at which salmonellas are most heat resistant.

3.1.3.4 De-feathering

Water is virtually always used to wash the birds and transport away the feathers. The wet transportation of feathers creates a potential for water contamination. It also adds moisture to the feathers, which naturally hold a lot of water. This increases the energy required to transport them during further processing. It also increases the amount of energy required to drive off moisture during rendering and the amount of condensate produced. If the feathers are landfilled the additional moisture may also create leachate problems.

The birds are washed in potable water, which in some MSs is chlorinated. In, e.g. the UK, the washing is undertaken with water chlorinated with, e.g. chlorine dioxide, at a concentration approved for potable water [241, UK, 2002].

3.1.3.5 Evisceration

As the viscera are kept with the carcase, for post mortem inspection, there shouldn't be elevated BOD and COD levels at the evisceration station.

The birds are washed in potable water, which in some MSs is chlorinated. In, e.g. the UK, the washing is undertaken with water chlorinated with, e.g. chlorine dioxide, at a concentration approved for potable water [241, UK, 2002].

3.1.3.6 Chilling

Immersion/spin chilling can lead to a build-up of blood and carcase material in the chilled countercurrent of water. The pre-chilling wash, which may be manual or automatic, should remove any particulate matter and any blood from inside the cavity and blood residue from the outside. Depending on the effectiveness of the original bleeding, some additional bleeding may occur in the chiller. If there is more than one chiller in a line, this will occur in the first chiller. The water flow can be increased to the first chiller to aid dilution. If tails and/or necks are left on the bird these may sometimes become separated from the bird because during processing they are partly cut through. The use of automated processes and the fact that the birds are not a uniform shape or size also makes the prevention of contamination more difficult. The conditions applied for chilling, including, e.g. the volume of water required per bird, are prescribed in law and depend on the number of tanks and the weight of the carcase [223, EC, 1992]. Table 3.19 summarises the requirements for water, excluding that used for first filling the tanks.

Carcase weight (kg)	Pre-chill wash	Immersion chilling	
	Minimum water volume (l)	Minimum total flow (l)	Minimum flow last tank, if several (l)
≤ 2.5	1.5	2.5	1
2.5 - 5	2.5	4	1.5
≥ 5	3.5	6	2

Table 3.19: Summary of water requirements for immersion chilling of poultry [223, EC, 1992]

Spray chillers avoid the problems associated with the build-up of contamination in chiller tanks, but they can give rise to the spread of bacteria through aerosols. They use up to 1 litre of water per bird. Spray chilling has the lowest energy consumption. Air-chilling can reduce the contamination rate of the birds by up to three times more than immersion chilling and it uses less water. [67, WS Atkins Environment/EA, 2000, 134, Nordic States, 2001]

Most chicken processors have switched to air-chilling as this uses the least amount of water. Water chilling is, however, widely used by turkey processors in order to comply with hygiene requirements for the rapid chilling of these larger carcasses. After about an hour in a countercurrent immersion chilling tank, to reduce the turkey carcass temperature to less than 4 °C, the turkeys are further chilled for 24 hours by loading 30 – 40 birds into 1m³ tanks filled with water and ice at 2 °C. [67, WS Atkins Environment/EA, 2000]

In some MSs microbial contamination is controlled by chlorination, within potable water limits

Refrigeration plants operate continuously and the condensing units, compressors and cooling towers associated with them can be a source of noise. Refrigerated trucks parked outside slaughterhouses can sometimes lead to noise problems if the refrigeration is powered from the truck engines. Many slaughterhouses provide mains power cables to power the refrigeration unit, thereby reducing the noise levels.

3.1.4 Slaughterhouse cleaning - equipment and installation

The level of cleanliness achieved depends on a combination of several factors. These include the cleaning agents used, including the detergent reaction time; the water temperature for washing and rinsing and the mechanical treatment applied, e.g. the use of “force” in the water pressure and the use of scouring sponges and brushes. If one of these components is reduced, the others must be increased to achieve the same result.

If the water pressure is increased, the water consumption can be reduced. Enough water is still required, however, to contain the rinsed off dirt in suspension and to transport it to the floor drains. A high water pressure can also influence the working environment, by, e.g. causing increased noise, vibration and aerosol formation and it can damage electrical installations, machines and building materials. A pressure of approximately 2.53 MPa, i.e. a low-pressure cleaner, used with foam-borne detergents and rinsing water at 50 – 60 °C, is reported to be most widely used.

Significant resources are consumed during the cleaning but significant savings can be achieved. A slaughterhouse, where no special attention had previously been paid to the use of resources for cleaning achieved the following results shown in Table 3.20, without reducing the standard of cleanliness. Thorough instructions were given to cleaning staff into methods of environmentally correct cleaning, taking account of the use of detergents and water. This was combined with working time studies. As a result, the time used for preparation, pre-cleaning and removal of waste increased, but the total cleaning time was reduced.

	Before	After
Water consumption	9.3 m ³	6.4 m ³
Detergent consumption	9.2 kg	3.0 kg

Table 3.20: Reduced consumption of water and detergents achieved without loss of cleanliness
[134, Nordic States, 2001]

Alkaline detergents dissolve and break down proteins, fat, carbohydrates and other types of organic deposit. They can be corrosive, so an inhibitor is sometimes added. These detergents often contain sodium or potassium hydroxide. Their pH varies from approximately 8 to 13, depending on their composition and their degree of dilution for use.

Acid detergents are used to dissolve lime deposits. Nitric, hydrochloric, acetic and citric acids are commonly used. The pH is low and it varies according to the composition of the detergent. They are corrosive. They have some disinfectant properties.

Detergents contain a number of active ingredients, each with a specific function.

Tensides reduce the surface tension of the water and improve the wetting of surfaces. They produce micelles to facilitate fat emulsification. They include soaps and syndetes. Compounds used in the meat industry must be biodegradable in normal biological waste water cleaning. The tenside nonyl phenol ethoxylate (NPE) can be broken down to release its surfactant properties, but some stable compounds which are suspected toxins are produced and its use as a cleaning agent will soon be banned in all but limited applications, so it will not be available for use in slaughterhouses and animal by-products installations, under the forthcoming 26th amendment of Council Directive 76/769/EEC, by Council Directive 2003/53/EC. Linear alkylbenzene sulphonates (LAS) also give rise to environmental problems. They are toxic towards organisms in an aquatic environment and cannot be broken down in anaerobic environments.

Complexing agents ensure that calcium and other minerals are not “bound” to soap or syndetes. In the past, sodium carbonate (washing soda) was used to bind calcium in the cleaning water. Today phosphates are mainly used, but other compounds such as phosphonates, EDTA, NTAA, citrates and gluconates are also used.

Disinfectants are used after cleaning to kill residual micro-organisms. The disinfectants commonly used include various chlorine compounds, e.g. sodium hypochlorite and chlorine dioxide. Hydrogen peroxide, peracetic acid, formaldehyde and quaternary ammonia compounds (QACs) are also used, all in aqueous solution. Ethanol is also used. Sodium hypochlorite is the most commonly used compound. With the exception of ethanol, disinfectants must be rinsed off after use.

The choice of detergent used has an effect on the waste water treatment. Some WWTPs have a system for removing phosphates. Others can handle EDTA, phosphonates or similar compounds. The quantity of calcium binder used will vary depending on how soft or hard the water is. Detergent residues may remain in the sludge from the waste water treatment. This may limit the options for disposal of the sludge. This needs to be considered when choosing the detergents.

A study at a Danish pig slaughterhouse showed the consumption of detergents given in Table 3.21. The quantity of detergents used at a slaughterhouse can be based on the surface area of the equipment and installation to be cleaned. [134, Nordic States, 2001]

Detergent type	Use per slaughtered pig (g)	Use per tonne of pig carcass (g)
Acid detergents	11 (3 - 15)	143 (39 - 195)
Alkaline detergents	41 (18 - 48)	533 (234 - 623)
Neutral detergents	3 (estimate)	39 (estimate)
Disinfectants	15 (7 - 17)	195 (91 - 221)
Liquid paraffin	4 (1 - 5)	52 (13 - 64)
Total		962

Table 3.21: Quantities of detergent used in Danish pig slaughterhouses
[134, Nordic States, 2001]

Sprays and rinses typically account for a high proportion of water consumption at slaughterhouses. Sprays and rinses typically consume about 24 % of the water used at poultry slaughterhouses and 30 % of that used at large animal slaughterhouses. Trigger operated spray nozzles, which control and direct the water, are commonly used to both reduce the water consumption and to provide adequate washing efficiency. Spray technologies have improved in

recent years. The latest designs are less susceptible to blockage than those previously available. New designs are also available with improved water efficiency whilst maintaining, or often improving the washing effect. [12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000]

3.1.5 Storage and handling of slaughterhouse by-products

The collection and storage of slaughterhouse by-products, such as blood, gut contents, inedible offal, heads, feet, bones meat scraps and SRM waste cause some of the most significant day-to-day pollution problems, because of the odours they generate. Some by-products, such as gut contents, inherently have offensive odours. Others, such as blood, become offensive very rapidly. Freshly cut fat takes longer to degrade and cause odour problems. The existence and extent of odour emissions depends on what preventive and control measures are implemented, as well as the local weather and climate. Odour problems increase with exposure, time and temperature of storage. Odour emissions can be minimised and prevented.

To an extent, the emissions during storage depend on the process upstream of the storage, i.e. the whole collection and handling procedure. If, e.g. blood is collected directly into closed and sealed containers then emissions will be prevented whilst the container is closed, however the blood will ferment within a few hours after being collected and become malodorous. There is always an air valve in the storage container, to exhaust any gas which may be produced, so the escape of odours is possible. If blood cannot be processed immediately, refrigeration is the only reported way to prevent odour production [271, Casanellas J., 2002], although charcoal filters can reduce odour emissions.

If the storage time of by-products which do not have an offensive smell when fresh, is kept below the time in which they become offensive, the problem of odour emissions should be avoided. If the time from slaughter to animal by-product use or disposal is kept below the time for odours to be produced, then this will prevent problems both at the slaughterhouse and at the animal by-products installation. Fresher ingredients also produce higher quality products, e.g. from fat melting and fewer malodorous emissions, e.g. from rendering. For example, the fat collected after stomach washing, which is wet and has a high protein level, is subject to rapid decay and the production of organic acids, which make processing difficult and lead to high production costs [206, Tritt W. P. and Schuchardt F., 1992]. The processing of malodorous materials can also lead to odour problems at the WWTP.

If by-products, which smell worse as they degrade, are refrigerated then odour emissions are reduced, but energy needs to be consumed to achieve this.

3.1.6 Slaughterhouse waste water treatment

Water

A characteristic of slaughterhouse waste water is that it contains organic compounds which are easily broken down in a biological waste water plant. It does not contain persistent nitrogen, and the typical C:N ratio (BOD:total N) of 7-9:1 is advantageous. Salt from hide/skin preservation is difficult to remove and can cause corrosion damage in WWTPs [244, Germany, 2002].

The temperature of the waste water considerably affects the solubility of various pollutants and their microbial decomposition rate. The temperature of waste water in Finnish slaughterhouses is typically 25 - 35 °C. In general, biological processes perform faster at higher temperatures, whereas fat emulsification at higher temperatures causes substantial difficulties in fat removal by flotation, as well as in an activated sludge plant. [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

Typical discharge levels are shown in Table 3.22.

Pollutant	Level achieved
BOD	< 10 – 75 mg/l
Suspended solid	< 30 – 60 mg/l
Total nitrogen	≤ 15 - 65 mg/l
Ammonia	10 mg/l
Phosphate	2 ppm

Table 3.22: Typical discharge levels from slaughterhouse WWTPs
[215, Durkan J., 2001, 240, The Netherlands, 2002, 346, Belgian TWG member, 2003]

The treatment of slaughterhouse waste water can achieve a high enough quality standard for it to be suitable for discharge to water courses, but the pathogenic risk renders it unsuitable for recirculation within the slaughterhouse. The recirculation of treated process water and wash-water is forbidden by veterinarians.

Odour

Odour problems may arise, e.g. where solids are screened and during sludge treatment.

Noise

Aerators associated with effluent treatment plants, which operate continuously, can produce significant noise impacts, particularly from badly maintained gearboxes and especially at night. [12, WS Atkins-EA, 2000]

3.2 Animal by-products installations

3.2.1 Fat melting

Energy

Energy consumption is an important issue during the melting process and at decanters, centrifuges and crushers [319, NL TWG, 2002].

Odour

Odour can be more of a problem during dry melting than wet melting. [240, The Netherlands, 2002, 319, NL TWG, 2002]

Noise

Noise is produced by machines, during the melting process and at decanters, centrifuges and crushers. [319, NL TWG, 2002]

3.2.2 Rendering

Air

Reported emissions of CO₂, SO₂, NO_x and dust are shown in Table 3.23.

Substances emitted	Range of emissions per tonne of unspecified animal by-product treated (kg)
CO ₂	10.2 - 146
SO ₂	1.2 - 1.6
NO _x	0.51 - 0.59
Dust	0.19 - 0.21

Table 3.23: The range of air emissions from two Finnish rendering plants
[148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

Water

The water consumption from unspecified rendering processes has been reported to be 500 - 1000 l/t of raw materials. Consumption is divided as follows: condensers consume 200 - 500 l/t; boilers 150 - 200 l/t and cleaning 200 - 300 l/t. [134, Nordic States, 2001]. In Finland the reported water consumption is 440 - 510 l/t, with about 30 - 40 % consumed by boilers [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001].

For every tonne of raw materials used 1000 - 1500 litres of waste water is produced, including approximately 600 litres in the form of condensate, i.e. water evaporated from the raw materials. The waste water comprises the following: production waste water; rinsing water from the vehicles and raw material storage; the water fraction from mechanical blood separation; vapour condensate from sterilisation and drying and from abatement techniques, such as seeping water from a biofilter. [163, German TWG Members, 2001]. The composition varies a lot depending on the process and the freshness of the feedstock. On average, one tonne of raw material is reported to produce 5 kg of COD, 600 g of nitrogen [134, Nordic States, 2001] and 1.65 kg of solids [144, Det Norske Veritas, 2001], before waste water treatment.

50 - 90 % of the waste water contamination originates from the vapour condensate. If wet rendering is undertaken, there will be a higher volume of contaminated waste water produced. Breakdown products of degradation of the raw material are conveyed into the waste water through the vapours from sterilisation and drying of the material. The amount of water pollutants expelled during processing is less for fresh animal by-products than for raw materials that have been allowed to decompose. [163, German TWG Members, 2001]

The main components among the pollutants are: organic acids, particularly acetic acid; propionic acid; butyric acid and iso-butyric acid but also valeric acid, isocaproic acid and others. They also include ammonia, aliphatic amines, aldehydes, ketones, mercaptans and hydrogen sulphide. [49, VDI, 1996]

Waste water from the cleaning of the “clean side” of the process has a considerably lower load than that from the “unclean side”. This does not increase proportionately with the size of the plant. Waste water from the exhaust air treatment comprises waste water from the process exhaust air and from the room exhaust air. The treatment can be done together or separately. The waste water from the process exhaust air treatment can be highly loaded with organic components, up to 25 g/l COD; mercaptans ≤ 2 g/l; hydrogen sulphide ≤ 800 mg/l; ammonium nitrogen ≤ 400 mg/l; volatile oils, phenols, aldehydes and others. [163, German TWG Members, 2001]

Waste water from the lorry cleaning may contain mineral oil, solids and possibly cleaning agents [163, German TWG Members, 2001].

De-sludging waste water from the evaporators has hardly any organic load, but it may contain phosphorus compounds from any conditioning agents used. It can also have high pH-values, which need to be neutralised. There is also waste water from the de-sludging of the cooling water recirculation. [163, German TWG Members, 2001]

Reported contamination data for waste water from a rendering plant are shown in Table 3.24. The data illustrate the significant effect of the warehouse storage temperature for raw materials on the waste water contamination loads.

Parameter	Maximum (summer)	Minimum (winter)	Annual average values
Quantity of waste water			0.9 – 1.6 m ³ /t
Temperature			18 – 35 °C
COD	8 – 20 kg/t	0.5 – 3.8 kg/t	3 – 10 kg/t
BOD ₅	3 – 12 kg/t	0.3 – 2.3 kg/t	1.6 – 5 kg/t
Sediments	1 – 55 mg/t	≤ 1 mg/t	0.3 – 8 mg/t
Nitrogen (NH ₄ -N)	1.3 – 2.7 kg/t	0.1 – 0.7 kg/t	0.6 – 1 kg/t
pH value			6 – 9.7 ⁽¹⁾
AOX ⁽²⁾	25 – 30 µg/l	< 10 – 24 µg/l	15 – 39 µg/l
⁽¹⁾ Range reported over the period of one year			
⁽²⁾ At sewage plant outlet, not crude waste water			

Table 3.24: Data for untreated waste water in a rendering plant - seasonal differences
[49, VDI, 1996]

Land

Leakage from drainage pipes and tanks could cause emissions to soil. The bulk storage of fuels and other chemicals, if not properly managed, pose a risk of accidental spillages and leaks, which could potentially result in contamination of the soil and groundwater. [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

Energy

The energy and heat consumption for this process has been reported as shown in Table 3.25.

Electricity consumption	approximately 75 kWh per tonne of raw material
Heat consumption	approximately 775 kWh per tonne of raw material
Excluding odour abatement and waste water treatment (approximately an additional 20 kWh)	
Feedstock unspecified	

Table 3.25: Energy consumption for a dry rendering process
[134, Nordic States, 2001]

Details of the energy consumption for a plant using the “Atlas” rendering process are given in Table 3.26.

The plant processes 310000 tonnes of raw materials per year, using the Atlas wet rendering process. Meal and fat are sterilised at the end of the process. Pig hair is hydrolysed in a continuous process and decanted. The grax is mixed with the press cake, before drying and the liquid phase is mixed with the stickwater from the Atlas system for final processing. A minor part of the concentrate is separately spray dried.

Energy consumption	Process	heat energy kWh	% of total heat	electricity kWh	% of total electricity
In - process	Grinding, coagulation, pressing	83	17.0	13.1	16.5
	Drying	250	51.3	8.4	10.6
	Meal sterilisation	43	8.8	1.6	2.0
	Heating of press liquid	22	4.5	1.9	2.4
	Vacuum evaporation	11	2.3	5.0	6.3
	Fat treatment	14	2.9	0.6	0.8
	Heating of concentrate	9	1.8	0.6	0.8
	Milling plant			6.6	8.3
	Spray drying	47	9.7	9.5	12.0
	Hydrolysis of hair	3	0.6	1.1	1.4
	Total - process	482	99	48.5	61
For secondary purposes	Odour abatement			10.3	13.0
	Cooling towers			5.6	7.1
	Waste water cleaning			7.1	8.9
	Compressed air			1.4	1.8
	Water boring and preparation			0.1	0.1
	Other common systems			5.8	7.3
	Heating of buildings, hot water	0.5	0.1	0.6	0.6
	Heating of buildings, heated by waste energy	4.4	0.9		
	Total - secondary uses	4.9	1	30.9	39
	Total energy consumption	487	100	79.4	100

Table 3.26: Energy consumption for a plant using the “Atlas” rendering process [221, Hansen P.I., 2001]

Drying consumes about 2/3 of the energy demand of a rendering plant. [163, German TWG Members, 2001]. The most efficient means of saving energy in rendering is to utilise heat from the evaporated water. This can be achieved by simple heat-exchange, e.g. using a multiple-effect evaporator. [243, Clitravi - DMRI, 2002, 271, Casanellas J., 2002]

The figures reported from Finland are shown in Table 3.27. The total energy consumption is higher than that reported from the Nordic States.

It is difficult to meaningfully compare consumption and emission data without full details of the process. Rendering techniques vary between the wet and dry process, but also, e.g. depending on whether sterilisation is undertaken as a separate step or incorporated into the cooking/drying process and on whether presses or centrifuges or a combination of both are used to separate the tallow meal and residual water.

Electricity consumption	65 - 72 kWh per tonne of raw material
Heat consumption	850 - 910 kWh per tonne of raw material
Heat recovery	≤ 170 kWh per tonne of raw material

Table 3.27: Energy consumption data from Finnish rendering plants [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

Table 3.28 shows the comparison of energy consumption for 2 rendering systems, i.e. System 1 - The Atlas rendering system (continuous, defatted, with post sterilisation) and System 2 – Pre-sterilisation, followed by continuous drying in added fat and pressing in a screw press.

System	Raw materials processed (t/yr)	Total heat energy (kWh/t)	Electricity for process (kWh/t)	Electricity for environmental measures (kWh/t)	Total electricity (kWh/t)
1	310000	487	55	24	79
1	175000	456	77	14	91
2	65000	986	54	14	68
System 1 - Atlas rendering system (continuous, defatted, with post sterilisation)					
System 2 – Pre-sterilisation, followed by continuous drying in added fat and pressing in a screw press					

Table 3.28: Comparison of two types of rendering systems
[221, Hansen P.I., 2001]

Table 3.29 summarises some energy consumption and emission data for rendering plants. It does not state whether the installations were undertaking wet or dry rendering or, give details about the rest of the process, such as what separation techniques were used. The data applies to UK installations where, unlike other countries, separate high-pressure sterilisation is not carried out.

Energy (kWh/t of carcase or part of)	Minimum	Average	Maximum
Electricity consumed (in)	45.70	84.70	120
Electricity generated (out) ⁽¹⁾		130	
Heat consumed (in)	440	690	906
Heat recuperated/produced (out)	71.40	111	163
⁽¹⁾ Data for energy generated from on-site CHP facility Type of process and feedstock unspecified			

Table 3.29: Summary of energy data from rendering plants
[144, Det Norske Veritas, 2001]

The most efficient means of saving energy in rendering is reportedly to use heat from the evaporated water. This can be done using, e.g. heat-exchangers or multiple-effect evaporators.

Odour

Decomposition commences as soon as the animal is slaughtered. During the period from the time of death to the commencement of rendering, temperature in particular, affects the rate of decomposition. Much of the material to be processed is wet in nature and this adds to the creation of ideal conditions for rapid putrefaction. Undue delays before rendering in conjunction with inadequate temperature control, therefore, have a direct effect on the state of decomposition and on the consequent severity of any odours. [241, UK, 2002]. The biological and/or thermal decomposition of raw materials leads to the formation of odour-intensive substances, such as ammonia and amines; sulphur compounds, such as hydrogen sulphide, mercaptans, and other sulphides; saturated and unsaturated low-boiling fatty acids; aldehydes; ketones and other organic compounds. Synergistic effects can increase the odour intensity of the mixture as a whole. Measurements have shown that average odour concentrations (German) can be 80 – 800 kOU/kg of raw material. [49, VDI, 1996]. Odour emissions of 108 to 1010 odour units (Danish) per tonne of raw materials have been reported. [134, Nordic States, 2001]

The malodorous emissions arise from gaseous emissions. These include highly concentrated process gases and vapours from the cooking operation and associated ductwork transferring the gases to the odour abatement plant. Odour emissions also arise from discharges from cookers, presses and/or centrifuges receiving hot rendered material for separation and hot separated materials en route to storage. Other sources include the displacement of malodorous air from the tallow storage tanks; the cleaning of process equipment; fugitive emissions from process buildings and the operation of an odour arrestment plant beyond its design specification. They also arise from liquid effluents, including the following: accumulated liquid at the base of the raw material transport containment and on-site storage hoppers; material spillages and floor washings; cooler condensate; the by-products of abatement techniques and treatment/effluent

holding tanks. The storage and handling of animal meal and tallow can also cause odour problems. [241, UK, 2002]

Malodorous compounds may be organic or inorganic. High odour strength is not necessarily associated with high chemical concentrations. Where emissions of different odour intensity are produced within the process, the odour streams may be kept separate and treated by appropriate odour abatement plant. It is possible to build in a facility to ensure that in the event of an odour abatement plant malfunction or breakdown, malodorous air is diverted to an alternative suitable odour arrestment plant. [241, UK, 2002]

Those malodorous emissions which arise from the processing of animal by-products develop and are emitted from a variety of sources. Concentrated emissions, such as vapours and non-condensable gaseous products, are emitted directly from cookers. These are captured directly from cookers and/or by the extraction equipment over presses.

The vapour from cookers and meal presses can be extracted and ducted to air-cooled condensers. Drop-out pots situated within the ducting, upstream of the condensers, remove solid material entrained in the gas stream. The condensers reduce the temperature of the extracted vapour stream and condense out the aqueous fraction and some organic compounds. The liquid condensate is pumped to a holding tank, pending on-site treatment or disposal or is discharged direct to the WWTP. [241, UK, 2002]. Some non-condensable gases remain. The non-condensable gases and the condensate liquor have a particularly strong and offensive odour. If the odour is not destroyed at source, it can cause problems from within the installation and, for liquor, at the WWTP too. Odour problems may be exacerbated by stirring at the WWTP.

Diluted emissions include “room air”, which has a high air volume low pollutant concentration.

Considerations associated with the abatement of malodorous process gases include variations in flow; variations in the concentration of pollutants; the formation of corrosive condensate in pipework and in cold parts of the plant; oxygen content in the flow to be treated and the necessity for very high odour reduction performances. The choice of the odour abatement method will depend on the chemical composition of the gases to be treated. Capture and segregation of odours from various sources and unit operations reduces the volume of malodorous gases that might otherwise require treatment. Segregation also ensures that, where appropriate, different techniques can be provided for different emissions and tailored to take into account cross-media issues such as energy consumption and solid waste disposal. [241, UK, 2002]

Noise and vibration

New plants are usually constructed on the outskirts of towns, at least 1 km from residential areas. The reference noise levels of 60 dB(A) during the day and 45 dB(A) during the night can reportedly be achieved, without particular noise reducing measures. In existing installations close to residential areas significant noise emissions can occur. Some reported sources of noise problems are induced fans, scrubbing towers, filtration equipment and conveyors. [144, Det Norske Veritas, 2001]

Site restoration

Activities associated with rendering installations are not expected to require significant site restoration work [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001].

Data

Table 3.30 shows consumption and emission data for 4 dry rendering plants.

Consumption	
Water consumed	1590 kg/t
Electricity used	83 kWh/t
Heat/fuel used	698 kWh/t
Emission	
BOD	1630 g/t (estimated as 67 % of COD)
COD	2440 g/t
Phosphorus	unknown
Odour	< 200 OU per treatment stream
Noise	90 dB(A) max at source
Detergents	
SO ₂	40 g/t
CO ₂	132 kg/t
NO _x	390 g/t
H ₂ S	nil
HCl	10 g/t
VOCs	not measured
Dust	10 g/t (boiler exhaust only)
Condensate (effluent)	1513 kg/t (as effluent to sewer/river)
Non-condensable gases	285 kg/t
Suspended solids in effluent	400 g/t
SRM	145 kg/t
Others	
Steam produced	890 kg/t
Chemicals environment air	2.80 kg/t
Chemicals environment effluent	0.65 kg/t
Chemicals environment effluent oxygen	2.46 kg/t
Chemicals product	1.43 kg/t
Chemicals other	0.76 kg/t
Treated air for odour control	9510 kg/t
Boiler exhaust	789 kg/t
CO	30 g/t
Effluent ammonia	390 g/t
MBM/M meal to landfill	126 kg/t
Waste controlled	960 g/t
Waste filter medium	1420 g/t
Waste effluent sludge	12 kg/t
Waste effluent	13 kg/t
Waste scrap	210 g/t
Waste oil	60 g/t
Raw material handled total	1.17 t/t raw processed
Dioxins	
Nitrates	

Table 3.30: Average consumption and emission data per tonne of raw material treated - four dry rendering plants processing 515000 t/yr
[192, Woodgate S., 2001]

Table 3.31 and Table 3.32 show consumption and emission data for the dry rendering of unspecified feedstock and blood, respectively.

Figure 3.3 shows consumption and emission data for an example rendering plant. The plant operates a batch process to “Method 1” described in ABP Regulation 1774/2002/EC. The wet slurry is then dried in a continuous disc drier. In the drier, the temperature increases from 100 °C to about 130 °C. The plant has an ammonia conversion unit, where the volatile ammonia is removed from the evaporation vapours. The exhaust vapours are then condensed into acetic vapours. A solution of ammonium nitrate and urea of 28% (AHL 28) urea can be produced, by adding urea.




Figure 3.3: Consumption and emission levels for an example rendering plant [354, German TWG, 2003]

All PER TONNE of UNSPECIFIED by-product DRY rendered	Water cons. (l) (4, 28)	Waste water (l) (4, 7, 28)	Energy cons. (kWh) (4, 23)	BOD emission (kg)	COD emission (kg) (4)	Suspended solids emission (kg)	Nitrogen emission (g) (4)	Phosphorus emission (g)	Odour emission (4)	Noise emis.	Detergents	CO ₂ emis. (kg)	SO ₂ emis. (kg)	NO _x emis. (kg)
Unloading + vehicle wash		50 - 200												
Storage/chilling														
Screening/separation														
Mixing/infeed														
Cooking		600												
Drying														
Grinding and milling														
Separation														
Fat settlement														
Fat filtering														
Meal packaging														
Condensation														
Boilers														
Cleaning														
Air treatment														
Liquid effluent treatment														
Solid waste treatment														
Storage of by-product														
Storage of waste for disposal														
Total (including where individual data not available)	100 - 1600	100 - 1600	400 - 650		5		600		10 ⁸ - 10 ¹⁰⁽¹⁾					
Techniques which provide or derive benefit to or from other activities														
⁽¹⁾ Danish odour units Ranges received - operating conditions, treatments and sampling methods neither described nor submitted References: (4) [134, Nordic States, 2001]; (7) [163, German TWG Members, 2001]; (23) [144, Det Norske Veritas, 2001], (28) [353, Clittravi - DMRI, 2003]														

Table 3.31: Consumption and emission data for dry rendering - feedstock unspecified

All PER TONNE of BLOOD rendered	Water cons. (l) (4)	Waste water (l) (4, 28)	Energy cons. (kWh) (4)	BOD emission (kg) (4, 7)	COD emission (kg) (4, 7)	Suspended solids (kg) (7)	Nitrogen emission (g) (4, 7)	Phosphorus emission (g) (4, 7)	Odour (24)	Noise	Detergents	CO ₂ (kg)	SO ₂ (kg)	NO _x (kg)
Unloading + vehicle wash									Yes					
Storage/chilling														
Screening/separation														
Mixing/infeed														
Cooking		700 - 800												
Drying														
Grinding and milling														
Separation														
Fat settlement														
Fat filtering														
Meal packaging														
Condensation	600 - 700													
Boilers	200 - 250													
Cleaning														
Air treatment														
Liquid effluent treatment														
Solid waste treatment														
Storage of by-product														
Storage of waste for disposal														
Total (including where individual data are not available)	2000 - 2300	2000 - 2300	120 + 60 kg fuel oil	0.3 - 6	0.5 - 90	1.3 - 2.2	100 - 9000	< 100 - 250						
Techniques which provide or derive benefit to or from other activities														
Ranges received - operating conditions, treatments and sampling methods neither described nor submitted														
References: (4) [134, Nordic States, 2001]; (7) [163, German TWG Members, 2001]; (24) [168, Sweeney L., 2001], (28) [353, Clitravi - DMRI, 2003]														

Table 3.32: Consumption and emission data for blood rendering

3.2.2.1 Rendering of carcasses and waste

The waste water from blood processing can contain high concentrations of phosphorus.

Table 3.33 shows some achieved emission levels from the WWTPs of six German rendering plants, after unspecified biological waste water treatment, including nitrogen elimination. The starting loads are not specified.

Parameter	Single values		Average values	
	Minimum	Maximum	Minimum	Maximum
COD homogenised (mg/l)	30	125	42	65
BOD ₅ homogenised (mg/l)	1	20	3.1	6
NH ₄ -N (mg/l)	0.3	39	< 0.9	12
NO ₃ -N (mg/l)	< 0.1	52 ¹⁾	< 0.5	26
NO ₂ -N (mg/l)	0.01	4.0	0.03	1.8
inorganic N total (mg/l)	0.5	62.1 ²⁾	3.6	34
P total (mg/l)	0.05	33 ³⁾	0.15	11.9 ¹⁾
AOX (mg/l)	< 0.01	0.03	0.015	0.02
G _F - (fish toxicity)	2	2	2	2
1 1 value of 51 (= 2 %) 2 94.5 % of all results < 50 mg/l 3 Contains plant with its own blood processing unit Results from official examinations in 6 German plants – starting loads not specified				

Table 3.33: Data from 6 rendering plant WWTPs, applying nitrogen elimination
[163, German TWG Members, 2001]

3.2.2.2 Rendering of feathers and pig hair

Table 3.34 shows consumption and emission data for the rendering of feathers and pig hair.

All PER TONNE of FEATHER/HAIR rendered	Water cons. (l) (25)	Waste water (l) (7, 28)	Energy cons. (kWh) (4, 25)	BOD emission (kg) (7, 25)	COD emission (kg) (7, 25)	Suspended solids emission (kg) (7, 25)	Nitrogen emission (g) (7)	Phosphorus emission (g) (7)	Odour emission (4, 25)	Noise emis. (d(B(A))) (25)	Detergents	CO ₂ emis. (kg) (25)	SO ₂ emis. (kg) (25)	NO _x emis. (kg) (25)	CO emis. (g) (25)
Unloading + vehicle wash															
Storage/chilling															
Screening/ separation															
Mixing/infeed															
Cooking		400 - 700	165												
Drying			700 - 800												
Grinding and milling															
Separation															
Fat settlement															
Fat filtering															
Meal packaging															
Condensation															
Boilers															
Cleaning															
Air treatment															
Liquid effluent treatment															
Solid waste treatment															
Storage of by-product															
Storage of waste for disposal															
Total (including where individual data are not available)	1590	1590	814	0.2 - 8	0.33 - 12	0.83 - 2.2	100 - 2700	< 100	1.5 million *OU/m ³ \$< 200 OU/ treatment sys.	90 at source		183	0.630	0.3	70
Techniques which provide or derive benefit to or from other activities															
* Danish odour units \$??odour units Ranges received - operating conditions, treatments and sampling methods neither described nor submitted References: (4) [134, Nordic States, 2001]; (7) [163, German TWG Members, 2001]; (25) [191, Woodgate S., 2001], (28) [353, Clitavi - DMRI, 2003]															

Table 3.34: Consumption and emission data for feather/hair rendering

Feathers and hair consist mainly of keratin, a protein with a very high sulphur content. To “open” it and make it digestible, a number of very stable sulphur links in the keratin have to be broken. This results in a release of volatile sulphur compounds, including H_2S , mercaptans and a number of organic disulphides. These compounds can be found in the non-condensable gases from hydrolysis and drying. In addition, ordinary breakdown products from proteins, such as ammonia and amines, will occur. Emissions of non-condensable gases have been measured as up to 1.5 million odour units per m^3 .

At a feather rendering plant in the UK, H_2S , mercaptans, amines, amides and chlorides such as HCl are monitored in air emissions.

About 1.0 kg/pig of hair produced is rendered [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001].

3.2.3 Fish-meal and fish-oil production

Table 3.35 shows consumption and emission levels reported for fish-meal and fish-oil manufacturing.

All PER TONNE of fish treated	Fresh water cons. (l)	Seawater cons. (l)	Energy cons. (kWh)			BOD emis. (kg)	Total N emis. (g)	Total P emis. (g)	CO ₂ (kg)		SO ₂ emis. (kg)	Suspended solids emission (kg)	NO _x Emission (kg)		*DMA emission (g)	**TMA emission (g)	Dioxin (ng/m ³) – emission calculated maximum emission for 700000 t of fish/yr (26)	Odour emission For 250 tonnes of fish/hour (26)	Noise emis.
			Energy cons. (kWh) (TOTAL)	Electricity cons. (kWh)	Heat (natural gas) (kWh)				Electricity cons.	Natural gas cons.			Electricity cons.	Fuel cons.					
	(26)	(26)	(26)	(26)	(26)				(26)	(26)	(26)	(26)	(26)	(26)	(26)	(26)	(26)	(26)	
Unloading			4	4															
Storage in buffer silo																			
Cooking			138.2	0.2	138														
Pressing			1.9	1.9															
Decanting			42.7	0.7	42														
Centrifugation			1.1	1.1															
Evaporation			45.0	5.0	40														
Drying			158.5	10.5	148														
Meal cooling			1.2	1.2															
Grinding																			
Meal storage																			
Oil storage																			
Pumping seawater			3.0	3.0															
Pumping waste water			1.1	1.1															
Other pumping			1.0	1.0															
Steam production			52.6	4.6	46														
Incineration			0.5	0.5															
Room ventilation			0.2	0.2															
Compressing air			1.2	1.2															
Suction air from machinery			0.5	0.5															
Scrubbing (chemical)			0.5	0.5															
Pelletising fish- meal			4.2	4.2															
Residual			5.8	5.8															
Total (including where individual data are not available)	290	14888	464.8	50.8	414				0.0181	0.0849	0.0279	0.014	0.1698	0.426	0.6 –3	10 - 25	0.003	555000 OU/s	
Ranges received - operating conditions, treatments and sampling methods neither described nor submitted																			
*DMA = Dimethylamine * *TMA = Trimethylamine																			
References: (26) [212, Nielsen E.W., 2001]																			

Table 3.35: Consumption and emission data reported from fish-meal and fish-oil manufacturing plants

Table 3.36 shows emissions per tonne of processed raw material, from a Danish fish-meal factory. There are very large variations in the emissions, as a result of lost product, e.g. stickwater, evaporated stickwater and meal. Minimum and maximum values are shown, together with the average values.

	BOD (kg/t)	Total-P (kg P/t)	Volatile-N (kg N/t)	Kjeldahl-N (kg N/t)
Average	2.1	0.023	0.45	0.59
Maximum	8.9	0.241	1.15	1.75
Minimum	0.5	0.000	0.21	0.25
The results are based on measurements of average emissions per hour during a total of 61 hours. In practice, the emission of Kjeldahl-N is equivalent to the total nitrogen emission.				

Table 3.36: Emissions per tonne of processed raw material from a Danish fish-meal factory [155, Nordic Council of Ministers, 1997]

Air

Air emissions contain dimethylamine, trimethylamine and some hydrogen sulphide.

Water

The consumption of fresh or potable water and its subsequent discharge have been considered to play such a minor role that the issue was only recently investigated, due to the introduction of green taxes. An examination showed that the consumption of fresh water for use in the boiler was considerable in one factory, while in another factory a considerable amount of fresh water was used for cooling the hydraulics. A great deal of fresh water is also used for the cleaning of process equipment, although impure condensate from the fish-meal process is generally also used for this purpose. For example, impure condensate can be used as rinsing water for the automatic CIP of the falling film evaporators. [155, Nordic Council of Ministers, 1997]

Seawater is used as a cooling water in the scrubbers and in evaporators and for scrubbing the air before incineration.

Waste water contains organic matter, suspended solids, nitrogen, phosphorus, dimethylamine and trimethylamine. Sodium hydroxide and sulphuric acid are used as detergents.

Solid waste

The carbon filter-press used to remove dioxins from fish-oil in the oil finishing/purification process is disposed of as a hazardous waste, by incineration.

Energy

Energy is used for offloading, cooling, preserving, separating, evaporating and drying.

Fish-meal plants do not refrigerate the raw materials, but the fishermen add ice directly to the fish at sea, and the plants also receive fishery by-products as frozen or iced products from the filleting industry.

Odour

Malodorous air is produced during offloading, drying and from production rooms. It is caused by ammonia and amines in the air and water.

Noise

Offloading is a noisy operation, due to the use of pumps. The use of submersible fish pumps, such as those used on fish farms, causes less noise. These have the additional advantage of being less damaging to the fish. Their disadvantage is that they need a lot of water and this has to be treated as waste water. [267, IFFO, 2002]

3.2.4 Blood processing

Consumption and emission data for blood processing are given in Table 3.37.

Consumption & emission levels	Unloading and vehicle wash	Storage /chilling	Centrifugation /Separation	Concentration	Drying	Packing	Air treatment	Effluent treatment
Water cons. (l)	min	n/a	min	min	n/a	n/a	no	n/a
Energy used (kWh)	min	min	min	min	min	min	no	min
Odour	min	n/a	n/a	n/a	min	n/a	no	no
Noise							no	
Detergents (specify including concentration and amount)	CIP	CIP	CIP	CIP	no	no	no	no
Dust (mg/m ³)	n/a	n/a	n/a	n/a	<150 mg/Nm ³	n/a	n/a	n/a
Suspended solids in waste water (mg/l)	min	n/a	min	min	n/a	n/a	n/a	< 60mg/l
Heat emitted (°C)	n/a	n/a	n/a	n/a	90	n/a	35	n/a
BOD (mg/l)*	n/a	n/a	n/a	n/a	n/a	n/a	n/a	< 25mg/l
COD (mg/l)*	n/a	n/a	n/a	n/a	n/a	n/a	n/a	< 125mg/l
Phosphorus (mg/l) ⁽¹⁾	n/a	n/a	n/a	n/a	n/a	n/a		< 2mg/l
SO ₂ (mg/l)*	n/a	n/a	n/a	n/a	n/a	n/a		n/a
CO ₂ (ppm)*	n/a	n/a	n/a	n/a	< 500 ppm	n/a		n/a
NO ₂ (ppm)*	n/a	n/a	n/a	n/a	< 300 ppm	n/a	n/a	n/a
⁽¹⁾ Parameters subject to regulatory limits min = minimum impact n/a = not applicable no = no impact CIP = cleaning-in-place								

Table 3.37: Consumption and emission data reported from blood processing plants [190, EAPA, 2001]

Odour levels of 8 million odour units (UK) inside blood tanks, have been reported [241, UK, 2002].

The air from one installation spray drying plasma has been reported to be exhausted to atmosphere at 80 °C.

The heat treatment of protein will lead to the formation of a number of malodorous compounds (ammonia, amines, sulphur containing compounds, etc.). Spray drying and milling can result in blood dust. [134, Nordic States, 2001]

3.2.5 Bone processing

Consumption and emission data for bone processing are given in Table 3.38.

All PER TONNE of bone treated	Water consumption (l)	Waste water (l) (7)	Energy consumption (kWh)	BOD emission (kg) (7)	COD emission (kg) (7)	Suspended solids emission (g) (7)	Nitrogen emission (g) (7)	Phosphorus emission (g) (7)
Unloading + vehicle wash								
Storage/chilling								
Screening/separation								
Mixing/infeed								
Cooking		350 - 500						
Drying								
Grinding and milling								
Separation								
Fat settlement								
Fat filtering								
Meal packaging								
Cleaning								
Air treatment								
Liquid effluent treatment								
Solid waste treatment								
Storage of by-product								
Storage of waste for disposal								
Total (including where individual data are not available)				0.3 - 5	0.5 - 10	1300 - 2200	100 - 2600	< 100
Techniques which provide or derive benefit to or from other activities								
Ranges received - operating conditions Ranges received - operating conditions, treatments and sampling methods neither described nor submitted References: (7) [163, German TWG Members, 2001]								

Table 3.38: Consumption and emission data for bone processing

3.2.6 Gelatine manufacture

Delivery of lime

The continuous monitoring of stacks and silos is reported to be carried out at a gelatine manufacturing plant. Dust emissions are reportedly zero, except during loading, when they are 20 - 40 mg/m³.

Pretreatment of bones

The drying process is a high-energy consumer. A great deal of heat is emitted from the rendering vessel, which it is reported cannot be insulated due to expansion and contraction caused by the temperatures reached. Meal driers use and emit heat, and are insulated. There may be techniques available to recoup the high heat losses from this process.

De-fatting is a high-energy process which emits sufficient heat to make the metal handrails in the processing room hot to touch.

Phosphorus may be a waste water issue.

There may be odour problems from the storage of hides and/or fish skins.

Demineralisation

Thousands of m³ of water can be used daily for charging the defatted bones, hides, skins, etc., depending on the throughput of the individual plant and the degree of recycling undertaken. This water then has to be treated before it can be discharged from the WWTP.

Hydrolysis

The alkali and acid hydrolysis processes produce contaminated acid and alkali solutions respectively. Lime hydrolysis produces a soapy lime solution. Both processes are followed by thorough washing, which uses thousands of m³ of water which then have to be treated in the WWTP.

Drying

Energy consumption is high during drying of gelatine.

Dicalcium phosphate

Filters are used in dicalcium phosphate silos to reduce dust emissions. There may be dust emissions from the dicalcium phosphate drier and the lime silo and stack.

Waste water treatment

Waste water from gelatine manufacture has a high BOD. If a plant has its own WWTP, then biological treatment, incorporating nitrification and denitrification steps is required, due to the high protein levels. It can also be treated in municipal WWTPs. The chloride content of waste water is high due to its salt content.

Table 3.39 shows discharge limits for several gelatine manufacturing installations with on-site WWTPs and direct discharge to receiving waters.

	Individual maximum regulatory emission limits for gelatine manufacturers				
	COD (mg/l)	BOD (mg/l)	SS (mg/l)	Total-N (mg/l)	Total-P (mg/l)
Belgium – factory A	600	100		100	10
Belgium – factory B	200	30	100	130	3
Germany - factory A	110	25		30	2
Spain – factory A	140		50		20
France – factory A	125	30	35	60	10
France – factory B	125	30	35	50	2
Italy – factory A	150	40		40	10
Sweden - factory A	70			60	1
Limits are only valid for those factories who have a direct discharge					

Table 3.39: Waste water emission limits for individual gelatine factories
[345, GME, 2003]

3.2.7 Dedicated incineration of carcasses, parts of carcasses and meat and bone meal

The incineration has potential global and local environmental impacts.

Incineration of substances which must be disposed of as waste provides an alternative to landfilling. When incineration is combined with energy recovery it can reduce the consumption of fossil fuels and the emissions associated with their combustion. Opportunities exist for the recovery of energy in the form of both heat and power and this is now a legal requirement where WID Council Directive 2000/76/EC applies [195, EC, 2000].

WID Council Directive 2000/76/EC [195, EC, 2000] requires the control and monitoring of emissions of specified substances from incineration plants and sets ELVs and methods to ensure compliance is monitored.

Odour may arise from raw material handling; flue and scrubber gas emissions, if there is poor combustion and poor dispersion, especially if there is a condensing vapour plume; from ash handling and from WWTPs.

Compared to incinerators which do not have dedicated feedstocks, animal by-products incinerators and particularly those used for the combustion of animal meal, as opposed to raw material, have the advantage of being able to closely control their feedstock composition and feed rate, and hence the combustion conditions. Better combustion control can result in reduced flue gas treatment requirements. [293, Smith T., 2002]

3.2.7.1 Dedicated incineration of carcasses and parts of carcasses

Chlorine present in the salt in carcasses means there is a potential for dioxin formation and can also lead to HCl production. There is a potential release of particulate matter from incomplete combustion.

The emission levels in Table 3.40 have been reported for animal carcass incinerators operating in 1996 [65, EA, 1996], i.e. before WID Council Directive 2000/76/EC came into force.

Substance	Emission (mg/m ³)
NO _x	350 (average emission)
Dust	14 - 180 mg/m ³ (limited scrubbing)
SO ₂	50 mg/m ³ (limited scrubbing)
HCl	30 mg/m ³ maximum (minimum not reported) (limited scrubbing)

Table 3.40: Achieved emission levels from animal carcass incineration, before WID Council Directive 2000/76/EC [65, EA, 1996]

Table 3.41 shows some direct air emissions reported from an animal carcass incinerator.

Parameter	Emission level (kg pollutant per tonne of animal carcass incinerated)
CO ₂	< 2500
SO ₂	0.566
Dust	1.5
HCl	2.25
NO _x	< 2.5
CO	< 2.5

Table 3.41: Direct air emissions from an animal carcass incinerator (no energy recovery) [144, Det Norske Veritas, 2001]

The run-out and pooling of liquid may be a problem during the combustion of carcasses or parts of carcasses. It is less likely to be a problem during the combustion of animal meal, but it can occur. If it is not taken into account during the design, installation, commissioning, operation and maintenance of the incinerator it may be difficult to achieve good combustion. This is of particular concern when TSE or suspected TSE materials are being incinerated, because the objective to destroy the prion might not be achieved, resulting in potential pollution and public health risks. Complete combustion should ensure the reduction of microbiological risk and prevention of the formation of liquid organic and aqueous wastes.

3.2.7.2 Dedicated incineration of animal meal

Meat meal has an energy value of approximately 14.4 MJ/kg [318, EPEA Internationale Umweltforschung GmbH, 2000].

There is a potential for harmful emissions. The prevention of the formation and emission of dioxin requires particular attention. Typical chlorine contents of UK animal meal are reported to be in the range 0.4 – 0.6 %. This is high enough to lead to the formation or re-formation of dioxins if the correct combustion and cooling conditions are not maintained. Dioxin emissions are, therefore, reported to be principally dependent on the plant design and operation rather than the composition of the animal meal [293, Smith T., 2002]. Dioxins are monitored regularly and more frequently at the incinerator commissioning stage [272, Woodgate S., 2002].

It has been reported that due to the high fat content of MBM, *no particular dust emissions* were registered during unloading [164, Nottrodt A., 2001].

Some reported advantages of fluidised bed incineration include a high combustion efficiency, with uniform temperatures, which make residence time calculations more reliable. Temperatures are reported to be low enough to prevent elevated NO_x emissions. The furnace design is simple and without moving parts. The fluidised bed material provides a continuous attrition of the burning material, removing the layer of char and thereby exposing fresh material for combustion. This assists both the rate of combustion and the burnout.

High levels of phosphorus in animal meal lower the melting point of the ash, which can give rise to problems. It has been suggested that the high phosphorus content of animal meal may impair catalytic denitrification. [164, Nottrodt A., 2001]

Table 3.42 shows raw emission data for the incineration of MBM in a BFB incinerator.

Substance	Emission before FGT (g/t MBM incinerated)	Emission after FGT (g/t MBM incinerated)	Emission after FGT (mg/Nm ³)	WID Council Directive 2000/76/EC ELV –daily (mg/Nm ³)	WID Council Directive 2000/76/EC ELV – half hourly (97 %) (mg/m ³)	WID Council Directive 2000/76/EC Average value measured over 6 – 8 hours	Flue gas treatment required
VOC	80	80	8	10	10	not applicable	No
HCl	800	80	8	10	10	not applicable	Yes
HF	no info.	no info.	no info.	1	2	not applicable	?
SO ₂	1600	160	16	50	50	not applicable	Yes
NO/NO _x	1750	1750	175	200	200	not applicable	No
CO	250	250	25	not applicable	not applicable	not applicable	No
Dioxins + furans	no info.	no info.	no info.	not applicable	not applicable	0.1 ng/m ³	?

The data are reported in Normal units, i.e. (mg/Nm³ at 0 °C, 11 % O₂, dry gas)
 Typical figure of 12000 kg dry flue gas per tonne MBM (corrected to 11 % oxygen) is used

Table 3.42: Raw emission data for the incineration of MBM in a BFB incinerator
 [325, Smith T., 2002]

Table 3.43 shows consumption and emission data for an installation incinerating 50000 tonnes of MBM per year.

Parameter	Value
Water consumed	365 kg/t MBM
Electricity used	166 kWh/t MBM
Heat/fuel used	5 kWh/t MBM
BOD	0 g/t MBM
COD	0 g/t MBM
Phosphorus	unknown
Odour	< 25 OU via final exhaust
Noise	90 dB(A) max @ source
Detergents	identify
SO ₂	240 g/t MBM
CO ₂	1.9 t/t MBM
NO _x	1.2 kg/t MBM
H ₂ S	nil
HCl	120 g/t MBM
VOCs	not measured
Dust	40 g/t MBM
Condensate (effluent)	0 kg/t MBM
Non cond. gas	0 kg/t MBM
Suspended solids in effluent	0 kg/t MBM
SRM	n/a
Others	
Steam produced	4955 kg/t MBM
Chemicals exhaust gas treatment	30 kg/t MBM
Chemicals boiler	0.01 kg/t MBM
Treated air for odour control	9679 kg/t MBM
Boiler emissions to atmosphere	10509 kg/t MBM
CO	400 g/t MBM
Effluent ammonia	0 g/t MBM
MBM/Meal to landfill	n/a
Waste controlled	100 g/t MBM
Waste filter medium	n/a
Waste effluent sludge	0 kg/t MBM
Waste effluent	0 kg/t MBM
Waste scrap	40 g/t MBM
Waste oil	n/a
Raw material handled total	n/a
Dioxins	
Nitrates	
Water vapour in exhaust	
The meal comprised ~ 98.5 % dry matter and was burned as received	

Table 3.43: Consumption and emission data from an installation incinerating 50000 t/yr MBM [193, Woodgate S., 2001]

Table 3.44 shows some direct air emissions reported from an MBM incinerator.

Parameter	Emission value (kg pollutant per tonne of MBM incinerated)
CO ₂	?
SO ₂	1.5
Dust	0.89
HCl	0.45
NO _x	10
CO	6.5

Table 3.44: Direct air emissions from incinerating MBM (no energy recovery) [144, Det Norske Veritas, 2001]

Table 3.45 shows the range of amino acid residues reported in fly ashes from BFB incinerators.

	n mole amino acid/ g sample	µg amino acid/ g sample	mg amino nitrogen/ 100 g sample	mg protein/ 100g sample
Total	44.04 – 222.55	6.15 – 30.54	0.06 – 0.33	0.36 – 2.09

Table 3.45: Total amino acid residues reported in fly ashes from BFB incinerators incinerating MBM

[199, PDM Group and Wykes Engineering (Rushden) Ltd, 2000, 250, James R., 2002]

3.2.8 Burning of tallow

Odour problems may arise during tallow loading and unloading [168, Sweeney L., 2001].

Table 3.46 shows some emission data for the burning of tallow in a heavy fuel oil burner and Table 3.47 shows an analysis of the animal fat burned.

Burning tallow (from rendering plant) in a heavy oil Boiler (5.6 MW, no abatement techniques)				
	UNITS			
Boiler capacity	MW	1.95	2.5	3.19
Fuel		Tallow	Tallow	Tallow
Temperature, combustion gas	°C	206	217.9	244.5
Volume flow, combustion gas	m ³ /s	1.63	2.02	2.81
Volume flow, combustion gas (dry)	Nm ³ /s	0.83	1.04	1.32
Vapour concentration in combustion gas	%	9.7	10.1	10.2
Air coefficient		1.43	1.38	1.36
Boiler efficiency	%	89.2	88.8	87.4
Combustion gas (dry)				
O ₂	%	6.3	5.7	5.5
CO ₂	%	10.2	10.5	10.8
CO	%	0.0001	0.0002	0.0003
CO	ppm	0.8	2.2	2.9
CO concentration	mg/Nm ³	1	2.7	3.6
CO, reduced to O ₂ concentration 3 %	mg/Nm ³	1.3	3.2	4.2
CO emission	mg/MJ	0.4	0.9	1.2
CO emission	g/s	0.001	0.003	0.005
SO ₂	ppm	7.5	7	6.8
SO ₂	mg/Nm ³	21.8	20.6	20
SO ₂ reduced to O ₂ -concentration 3 %	mg/Nm ³	26.7	24.3	23.2
SO ₂ emission	mg/MJ	7.7	7	6.7
SO ₂ emission	g/s	0.018	0.021	0.026
SO ₂ (as S)	g/s	0.009	0.011	0.013
NO _x	ppm	214.8	223.3	197.5
NO _x (as NO ₂)	mg/Nm ³	440.4	457.8	404.9
NO _x , reduced to O ₂ -concentration 3 %	mg/Nm ³	539.9	539.1	470.6
NO _x emission	mg/MJ	155.1	154.9	135.2
NO _x emission	g/s	0.367	0.476	0.535
Dust	mg/Nm ³	35		29
Dust, reduced to O ₂ -concentration 3 %	mg/Nm ³	44		34
Dust emission	mg/MJ	12.6		9.8
Dust emission	g/s	0.029		0.038

Table 3.46: Emission data from burning animal fat in a heavy fuel boiler

[166, Nykänen K., 2001]

It is reported that emissions not exceeding 200 mg/m³ for NO_x and 10mg/m³ for total have been achieved for the burning of tallow [244, Germany, 2002].

ANALYSIS OF ANIMAL FAT		
	Units	Quantity
H ₂ O	%	< 0.2
Caloric value	MJ/kg	36 - 39.8
Viscosity	mm ² /s	12.4
Flash point	°C	> 250
Sulphur (S)	mg/kg	110
Density (50°C)	kg/m ³	890.1
Ash	%	0.05
Al	mg/kg	< 1
Ba	mg/kg	2
Ca	mg/kg	17
Cr	mg/kg	< 1
Cu	mg/kg	2
Fe	mg/kg	26
Mg	mg/kg	5
Mn	mg/kg	1
Na	mg/kg	31
Ni	mg/kg	1
P	mg/kg	110
Pb	mg/kg	< 1
Si	mg/kg	8
V	mg/kg	2
Zn	mg/kg	3

Table 3.47: Analysis of animal fat
[166, Nykänen K., 2001] - adapted

3.2.9 Biogas production

Air

There is a risk of an accidental release of CH₄, which is a greenhouse gas.

Water

The advantages associated with biogas production from slaughterhouse by-products include: a reduction in the concentration of impurities in waste water, low excess sludge production and the production of a biologically stable excess sludge that can be used as a fertiliser [239, Denmark, 2002].

Land

The solid residues from biogas production from animal by-products may be composted. The use of such compost is subject to the restrictions specified in ABP Regulation 1774/2002/EC.

Energy

For each unit of electricity generated from biogas, 1.5 units of heat may be produced as hot water at over 80 °C. The energy-rich gas can be used, e.g. in slaughtering or animal by-products production, as a substitute for conventional primary energy. Biogas is reported to make no net contribution to the greenhouse effect. [207, Linköping Gas AB, 1997]

Odour

Odour problems can arise from the storage and handling and processing of the raw materials and from the WWTP, if there is one.

Noise

Large-scale mechanical equipment such as compressors, used to aerate the process fluid and filtration plant may be potential sources of noise pollution. [144, Det Norske Veritas, 2001]

3.2.10 Composting**Air**

For windrow composting, the concentrations of dust and bioaerosols, such as cells and spores of bacteria and fungi, will depend on the level of moisture maintained in the material during the process. Concentrations increase when any agitation of the organic material occurs, e.g. during turning, screening or shredding. The recirculation of leachate may also release micro-organisms. Due to their microscopic size, bioaerosols can remain airborne for long periods of time. Their small size, i.e. $< 3 - 5 \mu\text{m}$, allows them to enter the lungs easily, where they can produce allergenic or pathogenic reactions. Organic wastes from animal origins, such as manure wastes, may contain human pathogens. [210, Environment Agency, 2001]

Composting inactivates pathogenic micro-organisms to a certain extent but not all viruses [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]. The deactivation of pathogens relies on good process control, especially the attainment and maintenance of appropriate temperature conditions [350, EFPA, 2003]. ABP Regulation 1774/2002/EC prohibits the composting of Category 1 material. Category 2 and Category 3 material may be composted, however, most Category 2 materials must be sterilised under specified temperature, time, pressure and size conditions first.

During composting, CH_4 emissions to air, water, and soil [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001] and NH_3 emissions to air [206, Tritt W. P. and Schuchardt F., 1992] may present a problem, especially in windrow composting. For this reason, reactor composting is increasing in popularity. [148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

VOCs can be formed during the composting process when micro-organisms break down long chain organic molecules into smaller molecules which evaporate more easily. Most of these molecules are consumed by micro-organisms, but some are released to air. The composting of sewage sludge may release high levels of VOCs. [176, The Composting Association, 2001]. It has also been reported that the main sources of VOCs are engines [210, Environment Agency, 2001].

Water

If run-off and leachate production are not prevented then contamination of water courses and groundwater may occur. Leachate may have formed during transport.

Odour

Odour problems can arise during the receipt and storage of raw materials, especially if these have been stored for some time prior to delivery. The preparation of raw material, e.g. shredding; the exhaust air from closed decomposition processes, such as in-vessel systems and anaerobic conditions in windrows or piles, may all release malodorous substances. During composting, ammonia may be released from open-air composting areas and odours may be released during the windrow forming and turning operations, especially if anaerobic conditions have been allowed to develop in the windrows. Odours may also arise from wet and dirty decomposition areas; vehicle paths and leachate which may have formed in the delivery vehicle; or from the composting process itself. [210, Environment Agency, 2001]

Low C:N ratios of below 20:1 allow the carbon to be fully utilised without stabilising the nitrogen, which may be lost as NH_3 or N_2O . This can cause odour problems. [210, Environment Agency, 2001]

Noise

Noise may be emitted by shredding, turning, screening and bagging machines; the operation of pumps for lagoons and biofilters and by site traffic. [210, Environment Agency, 2001]

Vermin

Pests such as vermin, insects or scavengers can cause nuisance problems, depending on the waste types being composted. Putrescible wastes can provide a food source and the delayed use of newly delivered materials attracts vermin. Pests can also provide vectors for disease. Covering new material with mature compost acts as a barrier. High temperatures within windrows reduce the problems from pests. [210, Environment Agency, 2001]

Pathogens

If temperatures are not maintained at or above 55 °C for up to 15 days, depending on the type of composting technology, pathogens may not all be destroyed. A temperature above 60 °C may also cause a drop in composting efficiency.

3.2.11 Animal by-products installation waste water treatment plants**Water**

A characteristic of waste water from animal by-products is that it contains organic and ammonium compounds, sometimes in high concentrations. These can be broken down in a biological waste water plant.

The high temperatures associated with waste water from animal by-products installations, affects the solubility of various pollutants and their microbial decomposition rate. In general, biological processes perform faster at higher temperatures, but this can make fat removal difficult.

Odour

Odour problems may arise, e.g. where malodorous raw materials have been treated and during sludge treatment.

Noise

Aerators associated with effluent treatment plants, which operate continuously, can produce significant noise impacts, particularly from badly maintained gearboxes and especially at night. [12, WS Atkins-EA, 2000]. The noise from fans taking malodorous air from the WWTP can also be a problem.

3.2.12 Combined processes and techniques**Slaughter with the incineration of untreated animal by-products**

Combining slaughtering and animal carcase incineration on the same site can potentially reduce overall emission levels, from both processes. The energy from incineration may be recovered for internal use, e.g. for the production of steam or hot water, in the slaughterhouse. The reduced time between slaughter and incineration means the by-products are fresher and odour problems are potentially reduced. A rapid destruction of TSE confirmed, suspected or culled cases, fallen stock, dead on arrival animals and ante mortem condemned animals can also be achieved.

Rendering with the incineration of animal meal

Figure 3.4 summarises consumption and emission data from the rendering, burning of MBM and the burning of tallow.

To directly compare the energy recovery figures for CH₄ biogas produced from animal by-products, the CH₄ generated must be converted into electricity via a gas engine, taking into account the associated engine efficiency. The energy output quoted for biogas is similar to that produced by rendering with the on-site combustion of MBM and tallow. [144, Det Norske Veritas, 2001]




Figure 3.4: Consumption and emission data for rendering with on-site energy generation
[144, Det Norske Veritas, 2001]

Biogas production with composting

Composting the solid residues from biogas production can minimise the requirement for capturing and treating the outlet air to remove odours given off as a result of the open handling of by-products and composting. If the biogas production is accompanied by a mechanical separation, e.g. pressing, then there are reported advantages of mass and volume reduction in the biogas plant. It has been reported that, taking into account the costs for disposal of solid slaughterhouse waste, the economic viability of an anaerobic plant in connection with composting could be easily achieved, even without the marketing of the composted material. [206, Tritt W. P. and Schuchardt F., 1992]

4 TECHNIQUES TO CONSIDER IN THE DETERMINATION OF BAT

This chapter describes the techniques that are considered to be most relevant for determining BAT. This chapter should be seen as the background information for the conclusions on the determination of BAT presented in Chapter 5. Moreover, it does not include every technique applied in the slaughterhouses and animal by-products industries, even if the technique has been described in Chapter 2. Techniques that are generally seen as obsolete are not included.

This chapter covers “process integrated” techniques such as prevention, control, minimising consumption, re-use and recycling procedures. “End-of-pipe” techniques applied to waste water treatment, air pollution and odour control are also included.

Each technique is presented in the format given in Table 4.1. If the information has not been submitted under any of these categories, the relevant headings have been omitted.

Heading	Type of information included
Description	Brief technical description of the technique.
Achieved environmental benefits	Main environmental impact(s) addressed.
Cross-media effects	Side-effects and disadvantages to other media caused by implementation.
Operational data	Performance data on emissions and consumption levels, including information from example plants. Any other useful information on operation, maintenance and control.
Applicability	Consideration of applicability in slaughterhouses and animal by-products industries; in new or existing plants; plant size, if relevant and factors involved in retrofitting, e.g. space availability.
Economics	Information on investment and operational costs and any savings, e.g. associated with reduced raw material consumption or waste charges. Values in currencies different than EUR have been converted if they are from countries which use the euro, otherwise the original currency and the year are quoted.
Driving force for implementation	Local conditions or requirements which have led to implementation. Information on reasons other than environmental ones for implementation, e.g. improvement in product quality, cost reduction, public health legislation or worker safety.
Example plants	Reference to the plants operating the technique in Europe and in the rest of the world.
Reference literature	Source(s) of information to the BREF.

Table 4.1: Format of information about techniques for consideration in the determination of BAT

4.1 General techniques applicable in slaughterhouses and animal by-products installations

Annex IV of the IPPC Directive lists considerations to be taken into account when determining best available techniques. The possible routes for recovery and recycling of by-products and waste are considered in this document. In recent years these routes have become increasingly regulated, largely due to BSE, culminating in ABP Regulation 1774/2002/EC [287, EC, 2002], develops and consolidates the level of regulation. Under this Regulation, some animal by-products, such as SRM, must be disposed of as waste.

The biodegradable nature of slaughterhouse by-products has a direct influence on whether they can be recovered or recycled and on the overall impact of their emissions on the environment. There are more opportunities for recovery or recycling when the by-products are fresh.

Some fresh animal by-products, such as blood, have a distinctive smell, which can lead to problems or complaints if they are not handled properly. Emissions from by-products can be prevented by storing, handling, processing and transferring materials within a suitable building; bunding tanks; using overground pipe lines and transfer lines; applying overfilling protection on bulk storage tanks and preventing rain ingress and wind entrapment [3, EPA, 1996].

Storing animal by-products over prolonged periods at ambient temperature in the open air increases the risk of direct pollution from odour and leachate. As degradation increases, so does the likelihood of the by-products needing to be disposed of as waste, as their usability significantly decreases. The environmental impacts of by-products storage, such as odour and the need to dispose them as waste, may be lessened by storage in chill units or freezers. This will, however, incur energy use and the risk of refrigerant leaks. The immediate transfer of by-products to an on-site or off-site animal by-products installation for rapid processing could minimise their impact.

MANAGEMENT OF SLAUGHTERHOUSES AND ANIMAL BY-PRODUCTS INSTALLATIONS

For the optimum performance of each technique, it is necessary for all staff to be committed to its successful operation; from the managing director, managers, supervisors and shop floor workers through to the haulage contractor delivering the animals. This requires information, training, and demonstrating to all staff the results and economic consequences of how well or badly techniques are implemented. The “human factor” impinges on all techniques. For some techniques, to successfully minimise consumption and emission levels there is a greater reliance on the responsible actions of some individuals than for others. All employees must learn what is required of them and of the process. Staff motivation is, therefore, important, as is regular feedback about the results achieved by their actions. [134, Nordic States, 2001]. Specific responsibility may be allocated to competent individuals and their performance may be monitored.

If resources such as water and energy are used sparingly, their consumption will be minimised. The pollution of waste water can be minimised by removing any waste as near to the source as possible. If by-products, such as blood, bits of meat, manure, stomach and intestinal contents are not intended to be treated together, they can be kept apart from each other and not deliberately mixed with water. The volume of waste can be minimised by measures such as, e.g. re-using by-products when possible. Consumption and emission levels can be measured; techniques can be identified to reduce both; results can be shared and techniques can be tried and tested. Action plans naming responsible individuals and setting time-scales can be drawn up and monitored. Motivating and involving staff, as well as providing training and promoting a wider understanding of the process can encourage a positive attitude to the use of BAT. [134, Nordic States, 2001]

To, e.g. manage the minimisation of water and energy use, it is necessary to monitor their consumption and to record it continuously, not only in total, but also for individual unit operations, processes and departments. To achieve this, meters need to be installed at all significant places of consumption. They must be read regularly and the results analysed and used as feedback in continuous improvement efforts. [134, Nordic States, 2001]. Direct measurements may be required for regulatory purposes. Useful estimates of consumption and emission levels may also be obtained in advance of, or in some cases instead of, direct measurements. Estimates can be obtained from calculations based on the inputs and outputs, e.g. per weight of carcase produced; the weight of animal by-products to be treated and the amount of water and energy used. Estimations by mass or energy balance will require some tracking of the material usage and the by-product and waste production. Inconsistencies in these figures may introduce some inaccuracies in the estimates but, as a minimum, should make it possible to identify those areas where priority action is required to reduce consumption and

emission levels. Infrequent, non-routine and unplanned activities, including accidents, also need to be covered.

For direct measurements, it will only be possible to record the consumption during production, cleaning and quiet periods separately, if meters are read sufficiently often. Manual reading and reporting save capital costs from automatic systems but consume labour. Some companies find it worthwhile to install equipment for the automatic monitoring and recording of consumption. [134, Nordic States, 2001]. Further information about the measurement of consumption and emission levels is contained in the *Reference Document on The General Principles of Monitoring* [278, EC, 2002].

All processes and machines need to be examined and the following questions asked. How much water/energy is used? What is it used for? How much is required in order to achieve the desired result without impairing quality or hygiene? The answers to these questions can help to identify where water or energy savings can be made. In many cases it will be found that there is a large wastage of water, because the water actually used does not form part of the process. A typical example is that there is water for showering a product that does not actually hit the product or equipment to be cleaned. Such wasteful situations need to be rectified. [134, Nordic States, 2001]

Maintenance, including preventive maintenance, is important, e.g. the regular examination of blood storage facilities, to ensure that leakage is prevented [134, Nordic States, 2001]. Where significant interruption of the process could occur in the event of a breakdown, parts need to be routinely replaced as they approach the end of their expected lifetime. To minimise interruptions and downtimes, adequate supplies of all wearing and replacement parts for both process and treatment/abatement equipment need to be kept [49, VDI, 1996].

At installations where more than one activity is undertaken, there may be opportunities for an overall management of consumption and emission levels, to the benefit of one, or more, of the activities. This may be achieved, e.g. by using steam produced by one activity in another.

The controllable characteristics of the feedstock for any process may affect the environmental performance of an installation. In such a case, the operator of the installation may make it a condition of the contract that the feedstock is supplied in the most suitable condition, for both quality and environmental performance.

4.1.1 Environmental management tools

Description

The best environmental performance is usually achieved by the installation of the best technology and its operation in the most effective and efficient manner. This is recognised by the IPPC Directive definition of ‘techniques’ as “*both the technology used and the way in which the installation is designed, built, maintained, operated and decommissioned*”.

For IPPC installations an Environmental Management System (EMS) is a tool that operators can use to address these design, construction, maintenance, operation and decommissioning issues in a systematic, demonstrable way. An EMS includes the organisational structure, responsibilities, practices, procedures, processes and resources for developing, implementing, maintaining, reviewing and monitoring the environmental policy. Environmental Management Systems are most effective and efficient where they form an inherent part of the overall management and operation of an installation.

Within the European Union, many organisations have decided on a voluntary basis to implement environmental management systems based on EN ISO 14001:1996 or the EU Eco-management and audit scheme EMAS. EMAS includes the management system requirements of EN ISO 14001, but places additional emphasis on legal compliance, environmental performance

and employee involvement; it also requires external verification of the management system and validation of a public environmental statement (in EN ISO 14001 self-declaration is an alternative to external verification). There are also many organisations that have decided to put in place non-standardised EMSs.

While both standardised systems (EN ISO 14001:1996 and EMAS) and non-standardised (“customised”) systems in principle take the *organisation* as the entity, this document takes a more narrow approach, not including all activities of the organisation e.g. with regard to their products and services, due to the fact that the regulated entity under the IPPC Directive is the *installation* (as defined in Article 2).

An environmental management system (EMS) for an IPPC installation can contain the following components:

- (a) definition of an environmental policy
- (b) planning and establishing objectives and targets
- (c) implementation and operation of procedures
- (d) checking and corrective action
- (e) management review
- (f) preparation of a regular environmental statement
- (g) validation by certification body or external EMS verifier
- (h) design considerations for end-of-life plant decommissioning
- (i) development of cleaner technologies
- (j) benchmarking.

These features are explained in somewhat greater detail below. For detailed information on components (a) to (g), which are all included in EMAS, the reader is referred to the reference literature indicated below.

(a) Definition of an environmental policy

Top management are responsible for defining an environmental policy for an installation and ensuring that it:

- is appropriate to the nature, scale and environmental impacts of the activities
- includes a commitment to pollution prevention and control
- includes a commitment to comply with all relevant applicable environmental legislation and regulations, and with other requirements to which the organisation subscribes
- provides the framework for setting and reviewing environmental objectives and targets
- is documented and communicated to all employees
- is available to the public and all interested parties.

(b) Planning, i.e.:

- procedures to identify the environmental aspects of the installation, in order to determine those activities which have or can have significant impacts on the environment, and to keep this information up-to-date
- procedures to identify and have access to legal and other requirements to which the organisation subscribes and that are applicable to the environmental aspects of its activities
- establishing and reviewing documented environmental objectives and targets, taking into consideration the legal and other requirements and the views of interested parties
- establishing and regularly updating an environmental management programme, including designation of responsibility for achieving objectives and targets at each relevant function and level as well as the means and timeframe by which they are to be achieved.

(c) Implementation and operation of procedures

It is important to have systems in place to ensure that procedures are known, understood and complied with, therefore effective environmental management includes:

(i) Structure and responsibility

- defining, documenting and communicating roles, responsibilities and authorities, which includes appointing one specific management representative
- providing resources essential to the implementation and control of the environmental management system, including human resources and specialised skills, technology and financial resources.

(ii) Training, awareness and competence

- identifying training needs to ensure that all personnel whose work may significantly affect the environmental impacts of the activity have received appropriate training.

(iii) Communication

- establishing and maintaining procedures for internal communication between the various levels and functions of the installation, as well as procedures that foster a dialogue with external interested parties and procedures for receiving, documenting and, where reasonable, responding to relevant communication from external interested parties.

(iv) Employee involvement

- involving employees in the process aimed at achieving a high level of environmental performance by applying appropriate forms of participation such as the suggestion-book system or project-based group works or environmental committees.

(v) Documentation

- establishing and maintaining up-to-date information, in paper or electronic form, to describe the core elements of the management system and their interaction and to provide direction to related documentation.

(vi) Efficient process control

- adequate control of processes under all modes of operation, i.e. preparation, start-up, routine operation, shutdown and abnormal conditions
- identifying the key performance indicators and methods for measuring and controlling these parameters (e.g. flow, pressure, temperature, composition and quantity)
- documenting and analysing abnormal operating conditions to identify the root causes and then addressing these to ensure that events do not recur (this can be facilitated by a ‘no-blame’ culture where the identification of causes is more important than apportioning blame to individuals).

(vii) Maintenance programme

- establishing a structured programme for maintenance based on technical descriptions of the equipment, norms etc. as well as any equipment failures and consequences
- supporting the maintenance programme by appropriate record keeping systems and diagnostic testing
- clearly allocating responsibility for the planning and execution of maintenance.

(viii) Emergency preparedness and response

- establishing and maintaining procedures to identify the potential for and response to accidents and emergency situations, and for preventing and mitigating the environmental impacts that may be associated with them.

(d) Checking and corrective action, i.e.:

(i) Monitoring and measurement

- establishing and maintaining documented procedures to monitor and measure, on a regular basis, the key characteristics of operations and activities that can have a significant impact on the environment, including the recording of information for tracking performance, relevant operational controls and conformance with the installation's environmental objectives and targets (*see also the Reference document on Monitoring of Emissions*)
- establishing and maintaining a documented procedure for periodically evaluating compliance with relevant environmental legislation and regulations.

(ii) Corrective and preventive action

- establishing and maintaining procedures for defining responsibility and authority for handling and investigating non-conformance with permit conditions, other legal requirements as well as objectives and targets, taking action to mitigate any impacts caused and for initiating and completing corrective and preventive action that are appropriate to the magnitude of the problem and commensurate with the environmental impact encountered.

(iii) Records

- establishing and maintaining procedures for the identification, maintenance and disposition of legible, identifiable and traceable environmental records, including training records and the results of audits and reviews.

(iv) Audit

- establishing and maintaining (a) programme(s) and procedures for periodic environmental management system audits that include discussions with personnel, inspection of operating conditions and equipment and reviewing of records and documentation and that results in a written report, to be carried out impartially and objectively by employees (internal audits) or external parties (external audits), covering the audit scope, frequency and methodologies, as well as the responsibilities and requirements for conducting audits and reporting results, in order to determine whether or not the environmental management system conforms to planned arrangements and has been properly implemented and maintained
- completing the audit or audit cycle, as appropriate, at intervals of no longer than three years, depending on the nature, scale and complexity of the activities, the significance of associated environmental impacts, the importance and urgency of the problems detected by previous audits and the history of environmental problems – more complex activities with a more significant environmental impact are audited more frequently
- having appropriate mechanisms in place to ensure that the audit results are followed up.

(v) Periodic evaluation of legal compliance

- reviewing compliance with the applicable environmental legislation and the conditions of the environmental permit(s) held by the installation
- documentation of the evaluation.

(e) Management review, i.e.:

- reviewing, by top management, at intervals that it determines, the environmental management system, to ensure its continuing suitability, adequacy and effectiveness
- ensuring that the necessary information is collected to allow management to carry out this evaluation
- documentation of the review.

(f) Preparation of a regular environmental statement:

- preparing an environmental statement that pays particular attention to the results achieved by the installation against its environmental objectives and targets. It is regularly produced – from once a year to less frequently depending on the significance of emissions, waste generation etc. It considers the information needs of relevant interested parties and it is publicly available (e.g. in electronic publications, libraries etc.).

When producing a statement, the operator may use relevant existing environmental performance indicators, making sure that the indicators chosen:

- i. give an accurate appraisal of the installation's performance
- ii. are understandable and unambiguous
- iii. allow for year on year comparison to assess the development of the environmental performance of the installation
- iv. allow for comparison with sector, national or regional benchmarks as appropriate
- v. allow for comparison with regulatory requirements as appropriate.

(g) Validation by certification body or external EMS verifier:

- having the management system, audit procedure and environmental statement examined and validated by an accredited certification body or an external EMS verifier can, if carried out properly, enhance the credibility of the system.

(h) Design considerations for end-of-life plant decommissioning

- giving consideration to the environmental impact from the eventual decommissioning of the unit at the stage of designing a new plant, as forethought makes decommissioning easier, cleaner and cheaper
- decommissioning poses environmental risks for the contamination of land (and groundwater) and generates large quantities of solid waste. Preventive techniques are process-specific but general considerations may include:
 - i. avoiding underground structures
 - ii. incorporating features that facilitate dismantling
 - iii. choosing surface finishes that are easily decontaminated
 - iv. using an equipment configuration that minimises trapped chemicals and facilitates drain-down or washing
 - v. designing flexible, self-contained units that enable phased closure
 - vi. using biodegradable and recyclable materials where possible.

(i) Development of cleaner technologies:

- environmental protection should be an inherent feature of any process design activities carried out by the operator, since techniques incorporated at the earliest possible design stage are both more effective and cheaper. Giving consideration to the development of cleaner technologies can for instance occur through R&D activities or studies. As an alternative to internal activities, arrangements can be made to keep abreast with – and where appropriate – commission work by other operators or research institutes active in the relevant field.

(j) Benchmarking, i.e.:

- carrying out systematic and regular comparisons with sector, national or regional benchmarks, including for energy efficiency and energy conservation activities, choice of input materials, emissions to air and discharges to water (using for example the European Pollutant Emission Register, EPER), consumption of water and generation of waste.

Standardised and non-standardised EMSs

An EMS can take the form of a standardised or non-standardised (“customised”) system. Implementation and adherence to an internationally accepted standardised system such as EN ISO 14001:1996 can give higher credibility to the EMS, especially when subject to a properly performed external verification. EMAS provides additional credibility due to the interaction with the public through the environmental statement and the mechanism to ensure compliance with the applicable environmental legislation. However, non-standardised systems can in principle be equally effective provided that they are properly designed and implemented.

Achieved environmental benefits

Implementation of and adherence to an EMS focuses the attention of the operator on the environmental performance of the installation. In particular, the maintenance of and compliance with clear operating procedures for both normal and abnormal situations and the associated lines of responsibility should ensure that the installation’s permit conditions and other environmental targets and objectives are met at all times.

Environmental management systems typically ensure the continuous improvement of the environmental performance of the installation. The poorer the starting point is, the more significant short-term improvements can be expected. If the installation already has a good overall environmental performance, the system helps the operator to maintain the high performance level.

Cross-media effects

Environmental management techniques are designed to address the overall environmental impact, which is consistent with the integrated approach of the IPPC Directive.

Operational data

No specific information reported.

Applicability

The components described above can typically be applied to all IPPC installations. The scope (e.g. level of detail) and nature of the EMS (e.g. standardised or non-standardised) will generally be related to the nature, scale and complexity of the installation, and the range of environmental impacts it may have.

Economics

It is difficult to accurately determine the costs and economic benefits of introducing and maintaining a good EMS. A number of studies are presented below. However, these are just examples and their results are not entirely coherent. They might not be representative for all sectors across the EU and should thus be treated with caution.

A Swedish study carried out in 1999 surveyed all 360 ISO-certified and EMAS-registered companies in Sweden. With a response rate of 50 %, it concluded among other things that:

- the expenses for introducing and operating EMS are high but not unreasonably so, save in the case of very small companies. Expenses are expected to decrease in the future
- a higher degree of co-ordination and integration of EMS with other management systems is seen as a possible way to decrease costs
- half of all the environmental objectives and targets give payback within one year through cost savings and/or increased revenue
- the largest cost savings were made through decreased expenditure on energy, waste treatment and raw materials
- most of the companies think that their position on the market has been strengthened through the EMS. One-third of the companies report increasing revenue due to EMS.

In some Member States reduced supervision fees are charged if the installation has a certification.

A number of studies¹ show that there is an inverse relationship between company size and the cost of implementing an EMS. A similar inverse relationship exists for the payback period of invested capital. Both elements imply a less favourable cost-benefit relationship for implementing an EMS in SMEs compared to larger companies.

According to a Swiss study, the average cost for building and operating ISO 14001 can vary:

- for a company with between 1 and 49 employees: CHF 64000 (EUR 44000) for building the EMS and CHF 16000 (EUR 11000) per year for operating it
- for an industrial site with more than 250 employees: CHF 367000 (EUR 252000) for building the EMS and CHF 155000 (EUR 106000) per year for operating it.

These average figures do not necessarily represent the actual cost for a given industrial site because this cost is also highly dependent on the number of significant items (pollutants, energy consumption, ...) and on the complexity of the problems to be studied.

A recent German study (Schaltegger, Stefan and Wagner, Marcus, *Umweltmanagement in deutschen Unternehmen - der aktuelle Stand der Praxis*, February 2002, p. 106) shows the following costs for EMAS for different branches. It can be noted that these figures are much lower than those of the Swiss study quoted above. This is a confirmation of the difficulty to determine the costs of an EMS.

Costs for building (EUR):

minimum - 18750
maximum - 75000
average - 50000

Costs for validation (EUR):

minimum - 5000
maximum - 12500
average - 6000

A study by the German Institute of Entrepreneurs (Unternehmerinstitut/Arbeitsgemeinschaft Selbständiger Unternehmer UNI/ASU, 1997, *Umweltmanagementbefragung - Öko-Audit in der mittelständischen Praxis - Evaluierung und Ansätze für eine Effizienzsteigerung von Umweltmanagementsystemen in der Praxis*, Bonn.) gives information about the average savings achieved for EMAS per year and the average payback time. For example, for implementation costs of EUR 80000 they found average savings of EUR 50000 per year, corresponding to a payback time of about one and a half years.

External costs relating to verification of the system can be estimated from guidance issued by the International Accreditation Forum (<http://www.iaf.nu>).

¹ (E.g. Dyllick and Hamschmidt (2000, 73) quoted in Klemisch H. and R. Holger, *Umweltmanagementsysteme in kleinen und mittleren Unternehmen – Befunde bisheriger Umsetzung*, KNI Papers 01/02, January 2002, p 15; Clausen J., M. Keil and M. Jungwirth, *The State of EMAS in the EU. Eco-Management as a Tool for Sustainable Development – Literature Study*, Institute for Ecological Economy Research (Berlin) and Ecologic – Institute for International and European Environmental Policy (Berlin), 2002, p 15.)

Driving forces for implementation

Environmental management systems can provide a number of advantages, for example:

- improved insight into the environmental aspects of the company
- improved basis for decision-making
- improved motivation of personnel
- additional opportunities for operational cost reduction and product quality improvement
- improved environmental performance
- improved company image
- reduced liability, insurance and non-compliance costs
- increased attractiveness for employees, customers and investors
- increased trust of regulators, which could lead to reduced regulatory oversight
- improved relationship with environmental groups.

Example plants

The features described under (a) to (e) above are elements of EN ISO 14001:1996 and the European Community Eco-Management and Audit Scheme (EMAS), whereas the features (f) and (g) are specific to EMAS. These two standardised systems are applied in a number of IPPC installations. As an example, there are 2 EMAS registered fish-meal and fish-oil plants in Denmark and one EMAS registered turkey slaughtering and processing plant in the UK.

In the UK, the Environment Agency of England and Wales carried out a survey among IPC (the precursor to IPPC) regulated installations in 2001. It showed that 32 % of respondents were certified to ISO 14001 (corresponding to 21 % of all IPC installations) and 7 % were EMAS registered. All cement works in the UK (around 20) are certified to ISO 14001 and the majority are EMAS registered. In Ireland, where the establishment of an EMS (not necessarily of a standardised nature) is required in IPC licenses, an estimated 100 out of approximately 500 licensed installations have established an EMS according to ISO 14001, with the other 400 installations having opted for a non-standardised EMS.

Reference literature

Regulation (EC) No 761/2001 of the European parliament and of the council allowing voluntary participation by organisations in a Community eco-management and audit scheme (EMAS), OJ L 114, 24/4/2001, http://europa.eu.int/comm/environment/emas/index_en.htm

EN ISO 14001:1996, <http://www.iso.ch/iso/en/iso9000-14000/iso14000/iso14000index.html>;
<http://www.tc207.org>

4.1.2 Training provision

Description

Giving staff at all levels, from management to shop floor the necessary training and instruction in their duties can help to improve to control of processes and minimise consumption and emission levels and the risk of accidents. This may be undertaken with in-house or external environmental advisers, but reliance should not be placed on them for ongoing environmental management of the process. Problems which can arise during start-up, shut down, maintenance, abnormal conditions and non-routine work should all be covered. Ongoing risk assessment of processes and work areas and the monitoring of compliance with identified standards and operating practices can then be undertaken by managers in partnership with shop floor employees.

Achieved environmental benefits

Reduced consumption and emission levels and reduced risks of accidents throughout the plant.

Cross-media effects

None.

Operational data

Requires an investment of time by all personnel for the provision of information, instruction, training and supervision and the operation of an assessment programme, to identify training needs and the effectiveness of training.

Applicability

Applicable in all installations.

Driving force for implementation

Routinely considering the environmental impacts can help to focus efforts to achieve lower consumption and emission levels, leading to cost savings and increasing the confidence of the regulatory authority.

Example plants

Many slaughterhouses and animal by-products installations.

Reference literature

[47, DoE SO and WO, 1997]

4.1.3 Use of a planned maintenance programme

Description

The use of a planned maintenance programme, which involves changing parts and routinely checking the function of equipment can significantly reduce consumption and emission levels. This can involve the appointment of a competent individual with responsibility for managing maintenance in co-operation with operational managers. The maintenance manager's performance can also be monitored. Records of inspections, plans, permits and other relevant information can be used to monitor improvements and anticipate required actions, such as the replacement of parts.

Achieved environmental benefits

Reduced consumption and emission levels and reduced risks of accidents throughout the plant.

Cross-media effects

None.

Operational data

Maintaining up-to-date plans of slaughterhouse drainage systems can aid the maintenance and operation of the applied waste water treatment. Management need to ensure that there are regular inspection programmes put in place to assess tank bunding, underground tanks and drain integrity and aboveground pipework. Surface water drains located next to skips containing SRM and other animal wastes can be connected to the effluent drainage system. A leak detection and repair programme can be used to save hot and cold water. Some examples of common causes of leaks include damaged pipeline connections; flanges and fittings; worn valves; flooded floats on water tanks, cistern valves and corroded pipework and tanks.

For a slaughterhouse killing 18000 turkeys per day, equating to 38 birds per minute, the following potential water savings have been reported:

1000 m³/yr with a financial saving of GBP 625/yr, for a ball valve repair on a scalding tank;
4000 m³/yr with a financial saving of GBP 2495/yr, for a ball valve repair on a tray wash and
1000 m³/yr with a financial saving of GBP 625/yr for a ball valve repair on a pressure washer.
(Costs in 1999)

If managers ensure that equipment such as boilers, are adequately maintained to perform at their maximum combustion efficiency, then emissions to air will be minimised. In general, boilers should be capable of giving a smoke colour less than or equal to shade number 1 on the Ringelmann chart, except during periods of start-up. Such-start up periods should not normally exceed 30 minutes in any 24 hour period. In addition, if a policy of selecting those fuels with the minimal polluting potential is followed this will reduce emissions further. An example is the use of low sulphur fuel oil, i.e. containing less than 1 % sulphur, by weight.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Driving force for implementation

Reduced downtime due to breakdowns and accidents. Routinely considering the environmental impacts can help to focus the efforts to achieve lower consumption and emission levels, leading to cost savings and increasing the confidence of the regulatory authority.

Example plants

At least one poultry slaughterhouse in the UK.

Reference literature

[12, WS Atkins-EA, 2000, 63, ETBPP, 2000, 67, WS Atkins Environment/EA, 2000, 167, Greek Ministry for the Environment, 2001, 214, AVEC, 2001]

4.1.4 Dedicated metering of water consumption

Description

By applying dedicated meters, water consumption can be measured at a specific unit operation level instead of only at the installation level. Areas of overconsumption due to technical and operational reasons can be identified and actions then taken to optimise the consumption. It has been suggested that frequent readings need to be taken at submetered unit operations and be logged once during every 10 minutes. The usefulness of such frequent measures depends on the complexity of the actual process and the unit operations and the size and frequency of the changes in water consumption.

Achieved environmental benefits

At one site, a comparison of actual water consumption with recommended values led to a reduction in consumption of 13 %. Consequently, the volume of waste water, which would have had to be treated was also reduced. Also, as 45 % of the water was heated to 60 °C, the energy consumption fell too.

Cross-media effects

None expected.

Operational data

A case study plant prepared a map of its water usage. Meters were fitted and some pipework was modified to enable each area's water consumption to be measured individually. Hot and cold water consumption was measured separately. The map enabled areas where improvements could be made immediately to be highlighted, for instance, the washing-down of the lairage area with hot water stopped.

Target consumption rates were set. Suppliers of equipment were asked how much water each piece of equipment should optimally use. Flow-meters were fitted and employees were instructed to maintain the pressure between preset minimum and maximum limits.

In the consultation with equipment suppliers, immediate saving potentials become apparent, e.g. it was discovered that some equipment had been fitted with 5 cm diameter intake pipes to

account for the odd occasion when the water pressure suddenly drops, but for normal day-to-day operation 2.5 cm diameter intake pipes were adequate.

The training programme for new employees was updated to cover methods to minimise water consumption. This included reporting leaks, overflows and faulty valves and on-the-job training on the use of in-line flow-meters.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Economics

In the case study installation, in 1999 the flow-meters cost GBP 200 - 300 each. Modifying the pipework and installing 20 meters cost a total of GBP 30000. This led to a reduction of around GBP 23000/yr in the company's water and effluent bill. Information about the associated energy savings is unavailable.

By 2002, it was reported that there were submeters available at a cost of approximately EUR 30 each.

Driving force for implementation

To reduce water consumption and thereby to save money.

Example plants

At least one cattle and sheep slaughterhouse and one pig slaughterhouse in the UK.

Reference literature

[52, DoE, 1994, 63, ETBPP, 2000, 307, UK, 2002]

4.1.5 Separation of process and non-process water

Description

The drainage/sewerage system can be designed to separate waste water into different categories, to collect as much waste as possible and to treat the waste correctly. This technique should complement others which minimise the amount of materials entering the waste water and thus can help to optimise the re-use of water.

Rainwater and cooling water from the refrigeration system can be discharged in the same system, as they are usually not contaminated.

Waste water from lairage and from the cleaning of lorries can be collected in a second system, as it usually contains manure. Filtered material from this system can be used for biogas production or composting.

The waste water from the production and the casing department could be channelled separately. The treatment which the entrained material will have to undergo will depend on the Category assigned to it under ABP Regulation 1774/2002/EC.

Achieved environmental benefits

Reduced water contamination, by keeping clean water separate from dirty water and consequently also a reduced energy consumption associated with the waste water treatment.

Cross-media effects

None.

Applicability

Only in new and substantially altered existing slaughterhouses.

Economics

High capital cost, however, this may be offset by the reduced running costs due to the lower requirement for waste water treatment, whether on-site, at municipal WWTPs or a combination of both.

Driving force for implementation

Reduction of long-term expenses for treating waste water and disposing of animal waste.

Example plants

Several animal by-products plants in Germany

References to literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001, 244, Germany, 2002]

4.1.6 Use of cooling water and water from vacuum pumps

Description

Water from cooling systems, which has not previously been in contact with the products, by-products or other substances and which is of drinking water quality, can be used in some applications.

Achieved environmental benefits

Reduced water consumption.

Cross-media effects

None.

Operational data

The water from sources such as vacuum pumps may have been treated with chemicals to avoid corrosion or deposits.

Applicability

Will require veterinary approval before use in slaughterhouses, where the water must be of drinking water quality. It could then be used for washing yards and lairages.

Example plants

A small Danish poultry slaughterhouse uses cooling water from the anus drill to maintain the water level in the scalding tank.

Reference literature

[134, Nordic States, 2001, 167, Greek Ministry for the Environment, 2001, 238, UECEV, 2002, 349, GME TWG members, 2003]

4.1.7 Removal of running water hoses and the repair of dripping taps and toilets

Description

Removal of running water hoses and the repair of dripping taps and toilets.

Achieved environmental benefits

The water losses listed in Table 4.2 can be saved.

Type and condition	Loss (l/h)	Loss (m ³ /yr)
<i>Leaking tap</i>		
- 10 drops per 10 second	0.7	6.1
- 30 drops per 10 second	2.1	18.4
- 1 mm run	9.0	79
- 1.5 mm run	18.0	158
<i>Water hose</i>		
- running fully open (250 days at 8 hours)		
- ½ inch (12.7 mm)	3000	6000
- ¾ inch (19 mm)	5100	10000
<i>Toilet</i>		
- running so it can only be seen with careful observation		99
- running and can be clearly seen		195
- unrest on surface		495
- pouring		3000

Table 4.2: Water losses from leaking taps, running hoses and toilets

Cross-media effects

None.

Operational data

A running ¾ inch (19 mm) water hose results in an added consumption of 195 l/t during the period the water is running at a slaughter rate of 350 pigs per hour. At lower slaughter rates the figure increases proportionally.

If a slaughterhouse has 50 water supply positions, including wash hand basins etc., with dripping taps and 10 toilets with running water, the extra water consumption can easily amount to 5000 - 6000 m³ annually. This is equivalent to DKK 75000 - 90000 (2001) running straight into the sewer.

Applicability

Applicable in all installations.

Economics

This is a cost saving measure.

Driving force for implementation

To save water.

Example plants

A pig slaughterhouse in Denmark.

Reference literature

[134, Nordic States, 2001]

4.1.8 Use of pressure cleaning throughout the installation

Description

Notwithstanding the effects of e.g. temperature and cleaning agents, the effectiveness of cleaning using hoses varies depending on the flow of the water and the applied pressure. It has been reported that a pressure of 1.5 MPa and a flow of 60 l/min per nozzle gives a good result for cleaning trucks, compared to 0.3 MPa (3 bar) and 250 l/min, i.e. a 75 % water saving is possible for the same cleaning result.

Achieved environmental benefits

A 75 % reduction in water consumption can be achieved. Consequently, the volume of waste water to be treated is also reduced. Also if the water used is heated, then there is an energy saving too.

Cross-media effects

None foreseen.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Economics

The direct economic benefit depends on the price of the water. An investment of EUR 50 - 250 per nozzle is necessary. If the existing pumps and water pipes are not fit for the desired pressure, then their replacement will increase the investment costs.

Driving force for implementation

Saving water and, therefore money.

Reference literature

[3, EPA, 1996, 240, The Netherlands, 2002]

4.1.9 Fit cleaning-hoses with hand-operated triggers

Description

Trigger control shutoffs can be fitted to cleaning hoses with no other modification, if a water heater is used to provide hot water. If a steam and water blending valve is used to provide hot water, it will be necessary to install check valves to prevent steam or water from entering the wrong line. Automatic shutoff valves are often sold with nozzles attached. Nozzles increase the water impact and decrease flow.

Achieved environmental benefits

Reduced water and energy consumption.

Cross-media effects

None.

Operational data

The energy saved was calculated for running a hose that had been fitted with an automatic shutoff valve and nozzle, using water at a temperature of 71 °C. The flowrate before installation was 76 l/min and after installation was 57 l/min. The time the hose was running was 8 h/d before installation and 4 h/d afterwards. For a water cost of USD 0.21/m³, an annual water cost saving of USD 4987 (costs in 2000) was calculated. An annual energy saving of 919 GJ has also been calculated.

For a slaughterhouse killing 18000 turkeys per day, i.e. 38 birds per minute, the potential water saving is reported as 9000 m³/yr with a financial saving of GBP 5620/yr. The investment cost quoted per hose was GBP 70. (Costs in 1999)

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Economics

If nozzles are installed without automatic shutoffs, the equipment costs are less than USD 10. An automatic trigger controlled shutoff with a nozzle costs approximately USD 90. (Costs in 2000). The payback is reported to be immediate.

Driving force for implementation

Reduced water and energy costs.

Example plants

A turkey slaughterhouse in the UK.

Reference literature

[3, EPA, 1996, 214, AVEC, 2001, 268, Ockerman H. W. and Hansen C. L., 2000]

4.1.10 Supply of pressure-controlled water and via nozzlesDescription

Where a supply of water is essential, e.g. to a slaughter-line, it can be supplied through nozzles designed and positioned for each individual unit operation and cleaning operation. For cleaning operations, the water may be supplied to a series of hoses, e.g. a ring main. The water flow at each nozzle can be set by the management, for each individual application. The water pressure can be adjusted according to the unit operation/cleaning operation requiring the highest pressure and a suitable pressure regulator can be installed at each of the other unit operations/cleaning stations which require water.

Achieved environmental benefits

Reduced water consumption. Where heated water is used the overall energy consumption can be reduced.

Cross-media effects

None.

Operational data

The pressure of the general process water can be adjusted for the process requiring the highest pressure, e.g. for slaughter equipment this has been quoted as 17 atmospheres (1.72 MPa). At the other processes a suitable pressure regulator can be installed.

Applicability

Applicable in all slaughterhouses and animal by-products installations, according to in-line, general operational and cleaning needs.

Driving force for implementation

Reduced water consumption.

Reference literature

[134, Nordic States, 2001]

4.1.11 Fit and use floor drains with screens and/or traps to prevent solid material from entering the waste waterDescription

The initial screening of waste water may be achieved by fitting grates with small mesh sizes, or a combination bridge and screen, over floor drains.

Achieved environmental benefits

Reduced entrainment of solids in waste water and consequently reduced COD, BOD and TSS loadings at the WWTP. Depending on ABP Regulation 1774/2002/EC Category of the material, the solids may be used or disposed of in a variety of ways and there may be a requirement for a screen, with a mesh size not exceeding 6 mm.

Cross-media effects

None.

Operational data

In many slaughterhouses and animal by-products installations, it is common practice for staff involved in clean-up operations to remove floor drain grates and flush solid materials, such as off cuts and meat scraps, directly down the drain. At present this may be done without thought, or in the belief that a subsequent screen or catch pot will trap all solids. However, when the solids enter the waste water stream they are subject to turbulence, pumping and mechanical screening, which breaks them down and releases high COD substances into solution, along with colloidal and suspended fats and solids. Subsequent waste water treatment and effluent disposal to the municipal WWTP can be expensive.

To reduce effluent loading, efforts can be made to keep the solids out of the waste water stream in the first place. For example, carcase dressing can be examined carefully for opportunities to intercept solid materials before they enter the drains. Similarly, cleaning staff can be encouraged to empty drain catch pots into a waste bin and replace them in the drainage point before using water to clean an area. This has the additional advantage that the solids are collected dry, so they both weigh less and are hence cheaper to transport and so that energy is not required to remove excess water.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Economics

Inexpensive.

Driving force for implementation

Reduced load at the WWTP and associated cost savings and ABP Regulation 1774/2002/EC.

Example plants

Most, but not all, slaughterhouses and animal-by-products installations have drains with screens or traps fitted.

Reference literature

[12, WS Atkins-EA, 2000, 167, Greek Ministry for the Environment, 2001]

4.1.12 Dry cleaning of installations and dry transport of by-products

Description

By-products and waste from the slaughter and animal by-products treatment processes can be transported as dry as possible and all spillages cleaned up, by sweeping or by using a squeegee, prior to wet cleaning. This reduces the entrainment of organic matter into water, which would consequently have to be treated in either an on-site or municipal waste water treatment plant.

Achieved environmental benefits

Reduced water consumption and volume of waste water. Reduced entrainment of materials in waste water and, therefore, reduced COD and BOD levels. Increased potential for the recovery and recycling of substances generated in the process. Reduced use of energy needed to heat water. Reduced use of detergents.

Cross-media effects

None.

Operational data

Some examples of dry transport methods include the transfer of feathers by screw conveyer and the transfer of offal not intended for human consumption by vacuum or compressed air. Transport in water is usually appropriate for by-products intended for human consumption, partly because of the cooling effect, although this still needs to be assessed on a case-by-case

basis, because alternatively frequent despatch of batches, to cooled areas, may remove the need for such water consumption and the associated contamination.

See also Section 4.1.31.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Driving force for implementation

Reduced energy and water use, reduced need for waste water treatment and lower detergent use and expenditure.

Example plants

Several rendering plants in Germany.

Reference literature

[167, Greek Ministry for the Environment, 2001, 244, Germany, 2002, 346, Belgian TWG member, 2003]

4.1.13 Overfilling protection on bulk storage tanks, e.g. containing blood or tallow

Description

Level detection devices can be fitted, which will automatically detect the level of liquid in a vessel and send an audible and visual signal, first to warn that the capacity is close to full and then, if no action is taken, to actually stop the tank from filling, e.g. by stopping the pump or diverting the flow.

Achieved environmental benefits

Reduced risk of accidental overfilling, which could otherwise lead, e.g. in the case of blood, to a massive increase in the COD of the waste water and a potential disabling of the on-site or municipal WWTP, or if the yard water soaks away without treatment, to potential major pollution of local water courses.

Cross-media effects

None reported.

Operational data

Overfilling protection may automatically cut off the supply of further liquids, or it could comprise a system of audible and visual alarms, to which operators respond. The choice generally depends on the hazard associated with the substance being stored. Where the substance is hazardous to the environment and/or to personnel, automated systems are generally provided and maintained. This reduces the element of risk associated with human error.

For example, the spillage of blood is potentially one of the most environmentally harmful accidents that can happen in a slaughterhouse. The blood may escape to local water courses or cause problems in an on-site WWTP, due to shock loading. The risk of this can be reduced by installing a high level alarm on the blood tank, linked to an automatic cut-off device for the blood trough pumps. For example, a mechanism using a ballcock can be used. The ballcock hits an electrical switch which then operates a solenoid and activates a valve, which prevents further filling.

Applicability

Applicable in all slaughterhouses and animal by-products installations where bulk liquids are stored, which, if released to the environment, could cause significant pollution.

Economics

Inexpensive.

Driving force for implementation

Prevention of the accidental release of liquids hazardous to the environment.

Example plants

Overfilling protection on bulk storage tanks is in widespread use throughout the chemical industry and in industries where liquids that are hazardous to the environment, including to humans, are used, e.g. in the process or for cleaning.

Reference literature

[4, EPA, 1996, 148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001, 244, Germany, 2002, 288, Durkan J., 2002, 295, HSE, 1998]

4.1.14 Bunding of bulk storage tanks containing, e.g. blood or tallow

Description

A bund wall capable of holding at least 110 % of the volume of the largest storage tank within it and of adequate strength and integrity to contain the liquid stored can be provided. This is normally considered to be sufficient to contain the contents in the event of a catastrophic failure. A smaller capacity bund may be provided, if the liquid can be directed to a separate collection area. In this case diversion walls with a minimum height of 0.5 metres can prevent the bund from overfilling.

Achieved environmental benefits

Reduced risk of accidental leakage and spillage, which could otherwise lead, e.g. in the case of blood, to a massive increase in the COD of the waste water and potential disabling of the on-site or municipal WWTP, or if the yard water soaks away without treatment, overfilling could lead to potential major pollution of local water courses and land. A typical blood tank might hold 13600 litres.

Cross-media effects

None reported.

Operational data

A bund wall should incorporate a method of removing rainwater and the need for this should be assessed regularly and in particular always after rainfall. Rainwater should be removed to ensure that the capacity of the bund is always sufficient to contain the contents of the tank, if it is required to do so. The integrity of the bund should be checked on a regular basis.

If bund walls exceed 0.6 metres in height, particular attention may be required to ensure their strength and a fixed means of escape may be required. Bund walls are usually positioned at least 1 metre away from a tank with a capacity of up to 100 m³ and 2 metres for larger tanks. Damage to bunds can be prevented by impact protection, such as crash barriers or bollards and by good traffic management.

Applicability

Applicable in all slaughterhouses and animal by-products installations where bulk liquids are stored, which if released to the environment could cause significant pollution.

Driving force for implementation

To prevent the accidental release of liquids hazardous to the environment.

Example plants

Provision of bunding on bulk storage tanks is in widespread use throughout the chemical industry and in industries where liquids hazardous to the environment, including to humans are used, e.g. in the process or for cleaning.

Reference literature

[4, EPA, 1996, 295, HSE, 1998]

4.1.15 Double skin protection of bulk storage tanks, e.g. containing blood or tallow

Description

A double skinned wall on bulk storage tanks provides some protection against a release of liquids through corrosion, wear or catastrophic damage.

Achieved environmental benefits

Reduced risk of accidental leakage and spillage, which could otherwise lead, e.g. in the case of blood, to a massive increase in the COD of the waste water and potential disabling of the on-site or municipal WWTP, or if the yard water soaks away without treatment, overflowing could lead to a potential major pollution of local water courses. A small degree of insulation from heat may be achieved, which may to a small extent reduce the rate of fermentation of blood and thereby slow down the formation of malodorous gases. A typical blood tank might hold 13600 litres.

Cross-media effects

None.

Operational data

Internal failures might remain undetected, so periodic inspections should be scheduled and undertaken. The monitoring system can use either vacuum or pressure to provide an alarm if one of the skins fails.

Applicability

Applicable in all slaughterhouses and animal by-products installations where bulk liquids are stored, which if released to the environment could cause significant pollution.

Driving force for implementation

Reduced risk of spillage.

Example plants

Provision of double-skinned blood tanks is common practice.

Reference literature

[295, HSE, 1998]

4.1.16 Implement energy management systems

Description

Improving energy efficiency can lead to significant financial savings.

Achieved environmental benefits

Reduced energy use and potential reductions in other consumption and emission levels associated with some unit operations. For example, reduced hot water consumption can result in a lower consumption of both energy and water. Adopting a formal approach to assessing consumption and identifying areas for potential improvement can help identify areas which may otherwise be overlooked, e.g. in slaughterhouses a significant proportion of the overall energy consumption is from refrigeration outside slaughtering times.

Cross-media effects

None.

Operational data

Formal methods which give a structured approach to assessing the current situation and introducing improved systems for managing ongoing improvements are available. One such method is summarised in Table 4.3. It provides a scoring system based on 6 performance criteria, which when analysed can be used to identify the organisations weak and strong points and what the priorities for improvement are. It includes reference to financial costs and savings, so it may be used to attract the attention of senior managers, for whom profitability of the organisation is likely to be a high priority. The scores obtained indicate the potential improvement for each criteria and they can be used to plan and prioritise improvements. The scoring system may be repeated periodically to monitor any improvements.

Improvements in each performance criteria may involve the provision of information, instruction and training to motivate change at all levels of the organisation.

Performance criteria						
Level	Energy policy	Organising	Motivation	Information systems	Marketing	Investment
4	Energy policy, action plan and regular review with the commitment of top management	Energy management fully integrated into management structures. Clear delegation of responsibility	Formal and informal channels of communication regularly exploited	Comprehensive system that sets targets, monitors consumption, identifies faults, quantifies savings and provides budget tracking	Marketing the value of energy efficiency and the performance of energy management both within the organisation and outside it	Positive discrimination in favour of “green” schemes with detailed investment appraisal of all new-build and refurbishment opportunities
3	Formal energy policy but no active commitment from top management	Energy manager accountable to energy committee representing all users, chaired by a member of the managing board	Energy committee used as main channel together with direct contact with major users	Monitoring and targeting reports for individual premises based on submetering, but savings not reported effectively to users	Programme of staff awareness and regular publicity campaigns	Same payback criteria employed as for all other investments
2	Unadopted energy policy set by energy manager or senior departmental manager	Energy manager in post, reporting to ad-hoc committee, but line management and authority are unclear	Contact with major users through ad-hoc committee chaired by senior departmental manager	Monitoring and targeting reports based on supply meter data. Energy unit has ad-hoc involvement in budget setting	Some ad-hoc staff awareness training	Investment using short-term payback criteria only
1	An unwritten set of guidelines	Energy management the part-time responsibility of someone with only limited authority or influence	Informal contacts between engineer and a few users	Cost reporting based on invoice data. Engineer compiles reports for internal use within technical department	Informal contacts used to promote energy efficiency	Only-low cost measures taken
0	No explicit policy	No energy management or formal delegation of responsibility	No contact between energy managers and users	No information system. No accounting for energy consumption	No promotion of energy efficiency	No investment in increasing energy efficiency in premises

Note - 0 = poor and 4 = good

Table 4.3: Energy management matrix

Applicability

Applicable in slaughterhouses and animal by-products installations.

Economics

It is reported that improved energy management could reduce the amount of money spent on energy on a national basis in the UK, by 20 %. The money saved could then be used to, e.g. fund core activities, lower operating costs/raise profits, improve products or services, or to upgrade working conditions to reduce the organisations impact on the environment.

Driving force for implementation

Reduced energy consumption and consequent costs.

Reference literature

[300, ETSU, 1998]

4.1.17 Energy management at a red meat plant

This “technique” is summarised in a case study report of an energy and water saving project carried out at an installation where cattle and sheep are slaughtered. Some deboning of meat and rendering of by-products is also undertaken at this site. The project incorporated several general techniques that may be considered for application in slaughterhouses and animal by-products installations. Some of the individual techniques will be described under separate headings. The overall project is reported for three reasons: (1) It illustrates the method used to identify those unit operations which were high consumers and/or high emitters, where improvements could be made. (2) It shows the importance of management commitment to such an initiative, in ensuring that it is implemented successfully. (3) It also shows that for this commitment to exist, managers need to understand the issues and the potential benefits to be derived from investing in pollution prevention and control techniques. Note, however, that not all of the environmental and financial benefits were calculated for each individual technique introduced.

Description

An energy saving strategy was undertaken at a red meat plant using a computerised “Monitoring and Targeting” (M & T) system. The system continuously monitors oil; electricity; hot and cold water; temperatures in chill rooms and cold working areas; whether chill room doors are open or closed; whether the chiller plant is on or off; whether the boiler is on or off and the temperatures in the fat plant and by-products plant. It is also used to obtain fuel and water consumption figures in specific areas of the installation.

Steam, hot water, cold water and electricity are individually metered in slaughter halls, deboning halls, the office block, fat plant and the by-products plant. Targets for usage are set. This is reported to have been particularly successful for hot water usage. This success appears to be due to hot water usage being the most personally attributable service and this has reportedly led to a competitive spirit among the workforce, on a departmental basis.

The electricity, fuel oil and water consumption were linked to production levels, using a computer spreadsheet program. As a result senior managers became very interested in energy reduction. Investment was made in energy saving measures. The project's success was secured by the enthusiasm engendered in the shop floor employees. The technique helped to prove the effectiveness of the energy saving measures introduced and thereby encouraged further action. The continuous monitoring of fuel and water consumption enabled anomalous readings to be investigated and addressed, thereby avoiding excessive costs.

The main technical improvements made were as follows. Sterilisation tanks were installed for knives used in slaughtering and deboning. Hand and apron cleaning cubicles were installed. Steam, water and compressed air pipework was rationalised and insulated. Override electrical

control panels were installed. Refrigeration plant time controls were installed, to take account of actual process requirements. Computer controlled isolation valves were installed for hot water and steam supplies. A computerised system was introduced for setting off alarms when chill room doors and external loading doors were left open and for measuring the length of time they were left open.

Additional energy saving actions which could have been taken include the insulation of walls and roofs against heating and cooling. Around 25 – 40 % of heat is lost through the outside walls of a poorly insulated building. Good insulation can reduce such loss by up to 75 %.

Achieved environmental benefits

Reduced energy and water consumption.

Cross-media effects

No negative environmental impacts were reported.

Operational data

The installation described in the case study reported that the reduced use of fuel oil and electricity saved 6914 GJ and 820 GJ, respectively, per year. The reduction in emissions as a consequence of reduced fuel use at the installation was approximately 561 t of CO₂ and 9.7 t of SO₂ per year and due to reduced electricity use was approximately 164 t CO₂ and 2.8 t of SO₂ at the power station. A reduction in water usage from 116000 m³ to 95000 m³, i.e. 21000m³ per year was reported. This was also reflected in a reduced effluent discharge, although this cannot be quantified as it preceded the installation of a meter for monitoring effluent, which was installed after the case study measurements were made and after a new effluent plant was installed. The new effluent plant resulting in reduced COD and suspended solids in the discharge.

Applicability

Applicable at all slaughterhouses and animal by-products installations.

Economics

The implementation costs; annual actual energy and water savings; actual financial savings and payback time are shown in Table 4.4.

	Date	Energy saving (GJ)	Water saving (m ³)	Financial saving (GBP)				Cost of implementation (GBP)	Payback period (years)
				Energy	Water	Effluent	Total		
Knife sterilisation tanks	Sep 91	2518	6435	5213	3185	1840	10238	6000	0.6
Conversion of electricity tariff to HV and bulk tariff	Oct 91 + Apr 93	-	-	53823	-	-	53823	43900	0.8
Hand and apron wash	Oct 91 - Mar 92	2035	11700	4213	5792	3346	13351	17000	1.3
Rationalisation and insulation of steam, water and air pipework	Jul 92	474	-	982	-	-	982	1100	1.1
Override control panels	Aug 92	325	-	3612	-	-	3612	13000	3.6
Refrigeration plant time control	Apr 93	269	-	3563	-	-	3563	-	-
Isolation of steam and water services	Apr 93	1891	2700	3914	1335	770	6019	15000 ⁽²⁾	2.5
Computerised M&T system	Apr 93	-	-	-	-	-	-	60000 ⁽¹⁾	-
Chill room door closing control microswitches	Oct 91 + Jul 93	226	-	3000	-	-	3000	4100	1.4
Totals		7738	20835	78320	10312	5956	94588	160100	1.7

⁽¹⁾ The total cost of the overall M&T system and the isolation of steam and water services was GBP 75000: GBP 15000 was accounted for by the isolation of steam and water services, the remainder being the cost of the computerised M&T system.

⁽²⁾ Included in the computerised M&T system costs.

Economic data from 1993

Table 4.4: Summary of costs and savings associated with environmental improvements

Driving force for implementation

As the company's energy costs increased a method of systematically reducing them was sought and identified. The method was attractive because the reduced energy costs could be both measured and related to production levels.

Example plants

A cattle and sheep slaughterhouse in the UK.

Reference literature

[52, DoE, 1994, 159, EC, 2001, 347, German TWG members, 2003]

4.1.18 Implement refrigeration management systemsDescription

It is reported that most refrigeration plants can be improved to save up to 20 % of their energy consumption. Surveying the plant can lead to the identification of technical and operational opportunities to improve energy efficiency and save money.

A plant can be reliable and still be inefficient. A plant designed and operated to be efficient, however, is inevitably more reliable; for instance, the compressor does not have to work so hard in an efficient plant, which makes it less prone to breakdown and therefore more reliable.

Increased energy efficiency can reportedly be improved by a combination of surveying the plant, adopting good housekeeping measures, and carrying out appropriate monitoring, maintenance and control.

Additional information is available in *EN 378:2000 Refrigerating systems and heat pumps – Safety and environmental requirements Part 2 Design, construction, testing, marking and documentation; Part 3 Installation site and personal protection and Part 4 Operation, maintenance, repair and recovery*.

Achieved environmental benefits

Reduced energy use. Reduced emissions of refrigerants, typically from small leaks and major accidents.

Cross-media effects

None.

Operational data**Surveying the plant**

Each component of the plant can be investigated separately, to measure/estimate its energy consumption and the associated operating costs. It may also be helpful to identify what exactly is being cooled.

The operating costs can be measured/estimated for each item of plant by either measuring the current to all meters and power consumers or, for less accurate results measuring the running times and combining these with the power rating information provided by the manufacturer. Other costs such as maintenance, refrigerant top-up, routine labour and water treatment can be included. This enables both energy and cost savings to be targeted and monitored.

Two types of cooling load can be identified: (1) product loads, i.e. the targets of the cooling and (2) parasitic loads, i.e. those not directly related to the product, e.g. heat generated by lights or motors in cooled spaces. This distinction is useful because the actions which can be taken to minimise the two types of load are different.

Good housekeeping

Good housekeeping by trained and aware personnel can lead to significant cost savings. Some examples of good housekeeping practice around the refrigeration plant and in cooled rooms, include the following:

Around the refrigeration plant

If condensers are not kept clean the condensing temperature increases. A 1 °C increase in condensing temperature can increase running costs by 2 - 4 %. The cooling capacity also drops and the required temperature may not be achieved. The warmer the air entering the condenser is, then the higher the condensing temperature will be. The condensers can be shaded, if necessary and warm air can be prevented from being recirculated. Anything obstructing the airflow can be removed.

Bubbles in the refrigerant sight-glass when the system operation is stable usually signify that the system is leaking. This is not only illegal and harmful to the environment, but it also increases the cost of running the system and the refrigerant then has to be replaced. Also, the system may not be able to provide the cooling required. Leaks thus need to be found and repaired before the system is recharged with refrigerant.

The oil level in the compressor sight-glass(es) can be checked regularly, as the compressor will be more likely to fail if the oil level is too low or too high. Neither refrigerant nor oil are used up during normal plant operation; refrigerant can only be lost because of a leak, whereas oil levels may vary because of a leak or if oil is trapped somewhere in the system.

If pipework is vibrating it is more likely to fracture, causing a major refrigerant leak. Provision of anti-vibration pipe mountings/arrangements and/or a length of flexible pipework can prevent this.

Running the plant hotter than necessary can reduce reliability and performance. The plant room can be ventilated, e.g. using an extractor fan that is switched on when the temperature gets too high.

Ensuring that the control settings for the plant are optimised, labelled and easy to find can encourage personnel to maintain efficient operating conditions.

In cooled rooms

An open door reportedly costs GBP 6/h for a freezer store and GBP 3/h for chilled storage, due to lost energy. Ice around a door indicates poor sealing, which also incurs a consequent increase in the heat load. This may mean that the system capacity cannot sustain the increased load and the store temperature may increase. Such problems may be repaired by ensuring that product is not left in the doorway and by repairing the sealing on the door. If a door has to be used regularly, strip curtains may be fitted and maintained.

Impeding the airflow over the cold store, by obstructing the evaporator airflow leads to a temperature increase throughout the store and consequently to the system consuming more power than necessary, or possibly not reaching the required temperature.

A defrost-on-demand system, which initiates a defrost when needed rather than by a timer has reportedly reduced power consumption by 30 %, in some applications. Evaporators that operate below 0 °C should be completely defrosted before ice starts to cover the fins. This may be every few hours or every few days. When the evaporator is iced-up the evaporating temperature drops. A 1 °C drop in evaporating temperature can increase the running costs by 2 - 4 %. The capacity also drops and the store may not get down to the required temperature. If the defrost elements are not working properly, then the frost build-up on the evaporator will worsen.

Other heat sources in the cold store, e.g. lights, forklift trucks, other motors and charging devices cost money due to the electricity they consume and again through running the refrigeration system to remove the heat they produce. Personnel also give off heat.

Ice formation on the floor and walls of a cold store indicate that a lot of air is entering the room, bringing with it moisture, which is condensing on the evaporator and the structure. It can also indicate a defrost problem.

Cold stores are often held at lower temperatures than necessary because of worries about failure. Having a cold store at a lower temperature than necessary makes failure more likely. A temperature 1 °C lower than necessary can reportedly add 2 - 4 % to the plant running cost.

In other areas

Refrigeration systems have to remove heat from many sources other than just the product or space intended to be cooled. These sources of heat can be minimised. Some common examples of heat sources are: pumps and fans that circulate cold air, chilled water or an anti-freeze solution. These deliver most of the power they consume as heat into the cooling load, so they need to be switched off when not required.

Cold refrigerant pipes between the evaporator and compressor, particularly the larger suction line pipes, pick up heat from their surroundings. These can be insulated and not run through hot areas.

Monitoring

Monitoring enables trends and developing faults to be detected, before they become a major and expensive problem, e.g. monitoring of refrigerant leaks.

Monitoring for very small plants

Even for small and simple plants, installing gauges to log suction and discharge pressures, daily or, at the very least, weekly can cost a few GBPs and save thousands of GBPs. Any change, such as a fall in suction pressure, indicates a problem, such as a refrigerant leak. If the discharge pressure rises and the ambient temperature does not then this may indicate a blocked condenser.

Maintaining a data log helps detect problems early and it helps the contractor to diagnose problems.

Monitoring for most plants

For most plant, more detailed monitoring may prove worthwhile. In some cases, a computerised monitoring system may be justifiable.

Maintenance schedules

Maintenance work will depend on the size and complexity of the plant, as well as on the components used. It has been reported that as a minimum, the following should be checked

Compressors	- oil level
	- suction and discharge pressures and temperatures
Condensers	- fans and pumps are working
	- fan guards are safe and secure
	- condenser is not blocked; clean condenser if necessary
Gauges	- for accuracy
Receiver	- if there is a liquid level sight glass or gauge, that it contains the right amount of refrigerant
Evaporator	- as for condensers, plus the degree of frost build-up
	- liquid-line sight-glass to see that it contains the right amount of refrigerant
Safety and efficiency	- all safety controls
	- control switches to ensure that they have not drifted from the optimum set-point
	- suction superheat to confirm that expansion valves are operating correctly
	- pressure vessels, e.g. liquid receivers, may legally need a written scheme of inspection to be carried out by a competent person (see the box on page 18)
Others	- no untoward vibration on any part of the system
	- pipework insulation is still in good condition
	- for leaks, e.g. of ozone depleting substances
	- insulation for damage, if you have a cold store or cabinet
	- cold store safety door releases.

At one example refrigeration plant, high condensing pressures were experienced, leading to increased energy usage and higher fuel bills. The condenser was cleaned, which solved the problem and a plan to replace the condenser was thus abandoned.

Control

It has been reported that keeping controls simple and getting settings right can be a big step towards making a refrigeration plant operate as efficiently as possible by, e.g. setting the thermostat to achieve the best energy efficiency for the plant without compromising reliability. Marking the normal readings on gauges helps the early detection of equipment malfunction. There are a number of low-cost controls that can be added to a plant, which give reportedly good results. Automatic controls can be used to switch off the refrigeration plant and/or lights when they are not required. Automatic switches or variable speed drives can be fitted to fans and pumps that circulate cold air, chilled water and anti-freeze solutions. Paybacks of one year or less have been reported. For plants with multiple condensers or cooling towers, these allow the minimum condensing temperature possible for the plant to be obtained and this allows cost saving advantages in cooler weather.

Case study

The refrigeration system at a small frozen and chilled food company eliminating CFCs replaced 9 old refrigeration units with a single integrated system. Energy efficiency features were incorporated. These included larger heat-exchangers, low power evaporator fans, efficient compressors, comprehensive instrumentation and heat recovery. The cold store insulation was improved and low energy lighting units were installed.

Applicability

Applicable in all slaughterhouses and those animal by-products installations which have a refrigeration plant.

Economics

It has been reported that an investment made to save up to 20 % of energy normally has a payback time of well under two years.

The savings made in the case study plant are shown in Table 4.5. The total investment was GBP 30000. The additional cost of the energy saving features was GBP 4000 (1993). The payback period for the marginal cost of the energy saving features was 9 months.

Modifications	% saving	Actual annual savings (GBP, 1999)	Annual energy savings (kWh)
Larger evaporator heat-exchangers		1500	25200
Low power evaporator fan	66	3400	57400
Efficient compressors	32	4000	6300
Low energy lighting	56	380	
Defrost use		440	
TOTAL site	23	Incomplete	Incomplete

Table 4.5: Summary of main energy saving features in a modified cold store [299, ETSU, 1999]

Driving force for implementation

Reduced energy costs.

Example plants

A chilled food distribution company in the UK.

Reference literature

[167, Greek Ministry for the Environment, 2001, 292, ETSU, 2000, 299, ETSU, 1999]

4.1.19 Control refrigeration plant running times

Description

Sequencing and time controls are used to set the refrigeration operations to match the process requirements.

Achieved environmental benefits

Reduced energy use.

Cross-media effects

No negative environmental impacts were reported.

Operational data

An annual energy saving of 269 GJ was reported in an example cattle and sheep slaughterhouse in the UK.

Applicability

Applicable in all slaughterhouses and animal by-products installations which have a refrigeration plant.

Economics

The implementation costs; annual actual energy and water savings; actual financial savings and payback time are shown in Table 4.4.

Driving force for implementation

Increased energy costs and the identification of a method of systematically reducing these in way that could be both measured and related to production levels.

Example plants

A cattle and sheep slaughterhouse in the UK.

Reference literature

[52, DoE, 1994]

4.1.20 Use of binary ice as a cooling fluid (secondary refrigerant)

Description

Binary ice can be used as a refrigerant fluid. Binary ice may be described as “liquid ice”. It comprises ice crystals of 10 – 100 µm, in suspension in water, containing antifreeze. The antifreeze is either ethanol based and containing an anti-corrosion substance, or if the binary ice is for the immersion of food, common salt (sodium chloride).

Two technologies are described for the production of binary ice. The first which is shown in Figure 4.1 is for small and medium capacity binary ice, i.e. 100 – 1000 kW. The numbers in the following text refer to Figure 4.1. The binary ice is generated with a special evaporator, called a binary ice generator (1), which is supplied with fluid by a pump (2), from a binary ice storage vessel (3). A conventional refrigeration plant (4), with a small refrigerant charge, is connected to the binary ice generator. “Natural” refrigerants such as water (not for freezing), air, carbon dioxide (still under development), ammonia and hydrocarbons can be used, as alternatives to chlorofluorohydrocarbons. A secondary pump (5) supplies binary ice at a given ice concentration into the main feed pipe (6), where pumps (7) (optional), supply binary ice to the cooling loads (8). In the case of “zero load”, but on standby, the binary ice is kept circulating in the secondary loop (6) and (10) but is passed over valve (9), which opens as soon as the cooling loads are disengaged. The return pipe (10) transports the binary ice fluid, (with or without ice crystals) back to the storage vessel (3).




Figure 4.1: Binary ice system with a conventional refrigeration plant

Medium and large capacities of binary ice, i.e. 1000 kW – 1 MW, can also be produced with a refrigeration process with “water as refrigerant”. The technology is very similar as that shown in Figure 4.1, with the exception that the conventional refrigeration plant (4) is not necessary. A water vapour compressor and suitable vacuum conditions, for binary ice typically 500 Pa (5 mbar), cause the water to evaporate in an empty vessel (evaporator) and the compressor removes the water vapour, which is eventually condensed.

Achieved environmental benefits

Under comparable conditions, the coefficient of performance for binary ice is normally better than for conventional chilling and freezing plants, i.e. less power is consumed. Smaller refrigeration units are required, so fewer materials are needed and reportedly, because they do not have to be so chemically resistant they can be simpler and better suited for recycling. As the entire plant is not filled with potentially harmful refrigerants, the probability and severity of an accidental release is reduced. Unlike other refrigerants, binary ice made from water and alcohol can normally be released to the WWTP, with the permission of the regulator. The properties of

an ice crystal's rapid phase change reportedly ensure excellent heat transfer. The surface can, therefore, either be reduced or the binary ice can be "warmer", which results in lower energy demand and less surface freezing. The product weight loss is consequently less and defrost may even be unnecessary for air chillers. Fluid coolers can reportedly also be 20 to 50 % smaller.

Cross-media effects

None reported.

Operational data

Table 4.6 compares the volumes of the refrigerants brine and binary ice required to achieve a 3 °C decrease in temperature.

Cooling process	Refrigerant	Comparable cooling ability for a given mass, to achieve a 3 °C decrease in temperature	Energy available for cooling (kJ/kg)
Chilling	Brine	1	11
	Binary ice of 10 % ice crystals	3.0	33
	Binary ice of 20 % ice crystals	6.0	66
Freezing	Brine	1	11
	Binary ice of 10 % ice crystals	3.7	33
	Binary ice of 20 % ice crystals	7.3	66

Table 4.6: Comparison between the volumes of binary ice and brine required to achieve a 3 °C decrease in temperature

For example, 4 to 7 times more refrigerant has to be circulated if brine is used as a refrigerant, compared to binary ice. It has been reported that pipe diameters can be approximately 50 % smaller and the pumping power 70 % lower, for binary ice compared to brine. It is also reported that binary ice plants commonly run throughout 24 h/d, so only a small ice making machine and storage volume is required.

In an example slaughterhouse and meat processing plant, the slaughtered cattle and pig carcasses were chilled, prior to further processing. The following binary ice plant, with a total installed capacity of 424 kW was installed provide the cooling requirements:

Total area used	3800 m ²
Number of employees	40
Production per week	500 cattle and 2000 pigs
Refrigerant	Ammonia
Binary ice system	Trade name
Number of independent refrigeration plants	2
Compressors	Gram (reciprocating)
Additional features	Heat recovery
Cooling work per day	5500 kWh/d
Full load operating hours (maximum)	13 h/d
Installed refrigerating capacity (icemakers)	230 kW
Operating hours of the Binary Ice plant (hottest summer day)	24 h/d
Binary ice storage work	1600 kWh
Binary ice storage volume	34 m ³
Binary ice fluid corrosion inhibitor	Trade name
Maximum binary ice concentration in ice storage	> 50 %
Binary ice concentration in the pipework	12 %

Applicability

Applicable in slaughterhouses.

Economics

For the slaughterhouse example referred to above, the service life was 15 years. With an interest rate of 7 % and a depreciation time of 10 years, the additional direct investment costs could reportedly be recovered in 2.2 years and the annual operating costs of the binary ice plant, including depreciation immediately recoverable. It is estimated that the payback time would be 10 to 15 years for typical Danish slaughterhouses.

It is reported that binary ice plants normally run at off-peak tariff or during times when there is a low overall electrical loading.

Driving force for implementation

The phase-out of ozone depleting chlorofluorohydrocarbons under the “Montreal protocol” and the expected pressure to reduce the use of hydrochlorofluorohydrocarbons by the “Kyoto protocol”.

Example plants

At least one slaughterhouse in Germany.

Reference literature

[360, German TWG members, 2003, 361, Pontoppidan O., 2003]

4.1.21 Chill room door closing microswitches

Description

In one example plant, 14 doors to chill rooms and external loading doors were frequently left open, thereby leading to considerable electricity wastage. Initially 3 sirens were installed and programmed to sound when the doors were left open for more than a permitted period. This encouraged personnel to close the doors. The next step was the fitting of microswitches to monitor and record the length of time the doors were left open.

Achieved environmental

There was an annual energy saving of 226 GJ.

Cross-media effects

No negative environmental impacts were reported.

Applicability

Fully applicable

Economics

The implementation costs; annual actual energy and water savings; actual financial savings and payback time are shown in Table 4.4.

Driving force for implementation

Increased energy costs and the identification of a method of systematically reducing these in a way that could be both measured and related to production levels.

Example plants

A cattle and sheep slaughterhouse in the UK.

Reference literature

[52, DoE, 1994]

4.1.22 Heat recuperation from refrigeration plants

Description

Possibilities exist for heat recuperation from large, central refrigeration installations, from, e.g. the compressed refrigerant and from condensation of the refrigerant.

Achieved environmental benefits

Reduced energy consumption. The recouped heat can be used for preheating hot water. Reduced operation of the fan for the condenser results in less noise.

Cross-media effects

None.

Applicability

Applicable at all slaughterhouses.

Economics

The payback time is 3 – 6 years.

Driving force for implementation

Reduced energy costs.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001, 333, Netherlands TWG, 2003]

4.1.23 Use of thermostatically controlled steam and water blending valves

Description

Thermostatically controlled steam and water blending valves that automatically control the water temperature can remove the risk of an untrained or over cautious operator setting water temperatures too high and consequently using excessive amounts of energy.

Achieved environmental benefits

Reduced energy consumption. Fats in the waste water, are easier to remove at lower temperatures.

Cross-media effects

None.

Operational data

If hot water is provided by blending steam with cold water at the point of use, the water temperature is often controlled by manually adjusting the steam and water blending valves. Steam pressure and water pressure may vary throughout the day, so the temperature may also vary. To ensure that minimum temperature requirements, not necessarily required by law, for wash or rinse water are met, an operator may open steam valves enough so that the water always remains above a certain temperature. This leads to unnecessarily high temperatures when the steam pressure is high or the water pressure is low. If thermostatically controlled steam and water blending valves are used, they can automatically control the water temperature and remove the responsibility from the operator to judge the correct setting.

An energy savings calculation for lowering the water temperature for cleaning at one station by installing an automatic controlled steam and water blending valve is shown below.

This calculation assumes a starting water temperature of 100 °C and a flowrate of 83.3 l/min. The target cleaning water temperature is 60 °C. Gas is used in a steam boiler at a cost of USD 0.495/therm (i.e. USD 4.67/GJ). Assuming that the efficiency of the system is 70 % and the hose is used for 2 h/d, 250 d/yr. The calculated annual saving is USD 2698 (Costs in 2000).

Another example shows the energy and cost savings when using water with an incoming water temperature of 16 °C and for lowering the temperature the water is heated to from 71 °C, to various lower temperatures. The example assumes a water use of 831 l/min, 6 h/d for 250 d/yr. Some examples of the savings are shown in Table 4.7.

New temperature setting (°C)	Energy savings (GJ/yr)	Cost savings using natural gas (USD)
68.3	7793	580
60	31160	2340
51.9	54528	4090
46.1	70104	5260
32.2	109057	8174
Cost of natural gas - USD 0.175/m ³ in 2000		

Table 4.7: Annual energy and cost savings per hose from lowering the water temperature from 71 °C

Applicability

Applicable in all slaughterhouses and animal by-products installations

Economics

The valves are reported to cost USD 450 – 700 (Costs in 2000) and the payback depends on the previous water temperature settings and the variation of the temperature above those settings.

Driving force for implementation

Reduced energy costs.

Reference literature

[268, Ockerman H. W. and Hansen C. L., 2000]

4.1.24 Rationalisation and insulation of steam and water pipework

Description

Steam, water and compressed air are widely used in various unit operations during slaughter and animal by-product recycling and disposal. An example slaughterhouse with on-site rendering removed 80 metres of steam pipes and 80 metres of water and air pipework. The pipework was divided into zones so that maintenance could be carried out in one area in isolation, without affecting the whole installation. At the same time the steam and water pipework was insulated.

Achieved environmental benefits

There was an annual energy saving of 474 GJ.

Cross-media effects

None.

Operational data

Additional benefits can be gained from eliminating leaks; regulating use and stopping misuse and by setting correct supply pressures.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Driving force for implementation

Reduced energy consumption and associated costs.

Reference literature

[52, DoE, 1994]

4.1.25 Isolation of steam and water services

Description

Isolation valves installed in fluid supply pipework for steam, hot water (at 42 °C and 82 °C) and cold water linked to a computer time control of various areas resulted in a reduction in water losses. The system enabled leaks and taps left running during non-working hours to be identified and stopped. Preventing the wastage of heated water also saved energy.

Achieved environmental benefits

An annual water saving of 2700 m³ and an energy saving of 1891 GJ.

Cross-media effects

No negative environmental impacts were reported.

Applicability

Fully applicable

Economics

The implementation costs; annual actual energy and water savings; actual financial savings and payback time are shown in Table 4.4.

Driving force for implementation

Increased energy costs and the identification of a method of systematically reducing these in way that could be both measured and related to production levels.

Example plants

A cattle and sheep slaughterhouse in the UK. Several rendering plants in Germany.

Reference literature

[52, DoE, 1994, 244, Germany, 2002]

4.1.26 Implementation of lighting management systems

Description

Existing fluorescent light fittings in rooms that are normally occupied, with either ineffective reflectors or without reflectors and using two fluorescent tubes can be reconstructed to incorporate a reflector and to use a single energy-saving tube. Energy can be saved without a reduction in the lighting efficiency.

In rooms which are not regularly occupied, such as packaging materials store and the hide room, the lighting can be sensor-controlled.

Achieved environmental benefits

Reduced energy and water consumption.

Cross-media effects

None.

Operational data

Any requirements for emergency lighting, for health and safety or fire purposes cannot be compromised.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Driving force for implementation

Reduced energy consumption and associated costs.

Example plants

At least one large Danish cattle slaughterhouse and a poultry slaughterhouse in the UK have introduced sensor operated lights in rooms which are not regularly occupied. A poultry slaughterhouse in the UK has installed reflectors fitted with a single energy-saving tube.

Reference literature

[134, Nordic States, 2001, 167, Greek Ministry for the Environment, 2001, 243, Clitravi - DMRI, 2002, 264, May G. E., 2001]

4.1.27 Short and possibly cold storage of animal by-products

See also Section 4.2.1.8 for further information about the storage of blood and Sections 4.2.2.9.11 - 4.2.2.9.16 inclusive, for information about the preservation of hides/skins.

Description

By-products destined for use or disposal can be stored in closed vessels or rooms in slaughterhouses and animal by-products installations, for as short a time as possible, before further treatment. Depending on the nature of the by-products, such as their inherent odour characteristics and how rapidly they biodegrade and create an odour nuisance, it may be prudent to also refrigerate them, particularly during warm weather and in hot climates. A temperature not exceeding 5 °C, for solids and less than 10 °C, for blood has been reported as being necessary, to prevent odour problems. This applies at both the slaughterhouse and the animal by-products installation. Although IPPC does not apply to the transport of materials between installations, by implication it is good practice to control the conditions of transport as these may have a very significant influence on, e.g. odour emissions at the by-products installation. ABP Regulation 1774/2002/EC contains some requirements for the collection and transportation of animal by-products *in sealed new packaging or covered leak-proof containers or vehicles* and for *the maintenance of an appropriate temperature throughout transport*.

Achieved environmental benefits

Reduced biological and/or thermal decomposition, which consequently leads to lower COD and nitrogen levels in the waste water at the animal by-products installation. The formation and emission of odour-intensive substances at both the slaughterhouse and animal by-products installation is minimised. Where refrigeration is required, if the storage times are also kept as short as possible, then the refrigeration capacity and the energy consumption can also be minimised.

There may be greater opportunities for animal by-products to be recovered or recycled if they remain fresh due to short storage times or refrigeration. For example, blood meal manufactured from refrigerated blood has a higher nutritional value than unrefrigerated blood and it can be fed to non-farmed animals, such as pets.

There is also a reduced risk of infestation by insects, rodents and birds.

Cross-media effects

Energy consumption may be required for refrigeration, if by-products cannot be used or disposed of before malodorous substances are produced from them, especially in summer and in warm climates.

The early despatch of animal by-products can increase the numbers of journeys between the slaughterhouse and the animal by-products installations, transporting smaller loads, and consequently lead to an increase in the environmental harm due to transport.

Operational data

To optimise the prevention of odour problems, without creating cross-media effects at either, or both, the slaughterhouse and the animal by-products installation requires co-operation between the operators of both. If the handling and storage of by-products at the slaughterhouse is not managed in such a way as to minimise odour problems beyond the actual storage time before despatch, the animal by-products installations will almost certainly have problems, even if they treat the animal by-products immediately. The odour problems associated with animal by-products do not only arise from storage before treatment. Putrescent and putrid animal by-products also produce more malodorous gaseous and liquid emissions during processing than do fresh feedstock. They consequently cause additional odour problems at WWTPs.

There may be contractual arrangements affecting the price paid to slaughterhouses for raw materials, which depend on the quality of raw material provided, if the animal by-products are destined for further use. If the materials are destined for disposal, the cost of dealing with problems, such as odour due to material not being provided fresh, may be passed on to the slaughterhouse, so investment in early despatch or refrigerated storage may be cost effective.

Table 4.8 shows the practice for the storage of animal by-products in the Flemish region of Belgium.

Animal by-product	Storage practice
Animal waste/material for destruction	Enclosed storage in a refrigerated room, awaiting daily removal
Pig hair (to be used)	Enclosed storage in a refrigerated room
Blood	Enclosed and refrigerated storage
Hides (after treatment)	Enclosed storage in a refrigerated room
Intestinal fat and mucus (for subsequent treatment)	Enclosed storage in a refrigerated room
Washed intestines (if unsalted)	Refrigerated storage
Washed intestines (if salted)	Enclosed storage
Dung, contents of stomachs, intestines and rumens	No stipulations in respect of enclosed storage, refrigerated storage or removal frequency
Sludge from grease trap	Enclosed storage (airtight packaging)

Table 4.8: Storage requirements for animal by-products in the Flemish region of Belgium

Applicability

Applicable in all slaughterhouses and animal by-products installations. There may be limitations on space in existing premises, unless the existing unrefrigerated space is used.

Economics

For a slaughterhouse killing 600 pigs per hour, it has been reported that the cost of a tank for blood and refrigeration equipment is about EUR 65000 – 70000 (2001). It has been reported that for slaughterhouses producing animal by-products that do not have a commercial value, the investment in storage facilities is not a viable option. This may be the case if the by-products are treated or removed before they cause an odour nuisance.

Driving force for implementation

Prevention of odour emissions. In Denmark, the cooling of blood at slaughterhouses was introduced due to a demand from the environmental regulatory authorities, in order to reduce the odour emissions, during the handling and transporting of blood.

Example plants

Several rendering plants in Germany. In the Flemish region of Belgium, virtually all stored animal by-products are kept under refrigeration.

Reference literature

[49, VDI, 1996, 134, Nordic States, 2001, 238, UECBV, 2002, 244, Germany, 2002]

4.1.28 Audit odour

Description

The individual sources of odour and factors which influence the rate and type of malodorous emissions are identified. All of the unit operations and the associated plant and buildings can be assessed for odour generation potential. The reception, handling, storage and preparation and the processing of raw material can be examined. The handling, storage and despatch of processed material, including separation into various products and solid, liquid and gaseous wastes can all be looked at separately. The potential impact of malodorous emissions arising from the plant should be gauged from the nature, size and frequency of operation and the distance of neighbours from the plant. In reported cases any detection of odour at the boundary fence is not acceptable. The effectiveness and appropriateness of existing odour abatement equipment and containment of emissions can be assessed.

Having identified sources of malodorous emissions these can be further characterised. Quantitative measurements may be required to determine the emission volume, flowrate, temperature, humidity, chemical analysis and the pH. A CEN standard *Air quality – Determination of odour concentration by dynamic olfactometry* [311, CEN, 2001] has become available during the late stages of the preparation of this document. Its availability may lead to more consistency in the measurement of odour concentration, within and between MSs. Much of the data currently available on odour concentrations is difficult to compare due to the diversity of the measurement techniques used to collect the data.

After emissions have been fully characterised the next step is to determine what further action, if any, is required. For example, it is necessary to look at ways of preventing the formation of malodorous substances and if this cannot be done to assess how best to contain and/or most appropriately treat the offending emissions, without incurring disproportionate cross-media effects.

Any odour abatement equipment should be selected according to the requirement of the relevant process and by taking into account the materials it will actually handle.

After installation, operator training and commissioning have been completed, the performance of the technique, including its operation and maintenance should be monitored and any further actions required can be taken as appropriate.

Achieved environmental benefits

Odour prevention and control.

Cross-media effects

None.

Operational data

For an example rendering plant of 75000 tonnes per year capacity, the following information was collected from an odour audit and the actions carried out (summary).

Sources of odour – offal intake area, main plant, finished goods area, tanker loading area, boiler outlet, carbon filter outlet, balance tank and aeration tanks.

Olfactometry – samples were taken from outlets and areas where it was identified that odours may arise. The odour concentrations (ou/m³) and the odour emission rate were measured, to model the dispersion of odour from a given source.

Dispersion modelling – emissions from point, volume and area sources were calculated across simple and complex terrain, taking into account existing abatement techniques and meteorological and local climatological data.

Assessment of further needs to meet the conditions of an IPPC permit, which required that no odour nuisance occurs beyond the boundary fence because of the site operation. – odours detectable beyond the boundary fence, were detected from the offal intake area, the processing area, the finished goods area, the WWTP and from the carbon filter. The detectable odours emanated from open areas, open doors and a carbon filter which was being renewed regularly, but which was below specification.

Additional action required – ducting and ventilation of adequate dimensions to all new abatement plant; construction of an enclosed and negative pressure delivery building; a peat supported on shell biofilter, capable of treating 60000 m³/h of air from non-condensable gases from condensers, press areas, milling areas and cooling areas, process air from the drying and sterilising production area and air from the covered balance tank; refurbishment of the carbon filter area to treat the air from the material reception area.

Post-upgrade monitoring – the modifications led to the conclusion that the odours emitted from the site would be unlikely to cause a nuisance to the people in the surrounding environment.

Application for a permit to increase the capacity of the rendering plant to 125000 tonnes of raw material per year - the odour audit was repeated and a decision was taken to prevent emissions from the additional throughput, by installing a thermal oxidiser to burn gases from all cookers, presses and sterilisers, as well as waste water, which was previously spread on land after treatment in the WWTP.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Driving force for implementation

Application for an IPPC permit.

Example plants

At least one rendering plant in Ireland.

Reference literature

[309, Sweeney L., 2002]

4.1.29 Enclose animal by-products during transport, loading/unloading and storage

Description

ABP Regulation 1774/2002/EC states that *1. Animal by-products and processed products must be collected and transported in sealed new packaging or covered leak-proof containers or vehicles. 2. Vehicles and re-usable containers, and all re-usable items of equipment or appliances that come into contact with animal by-products or processed products, must be: (a) cleaned, washed and disinfected after each use; (b) maintained in a clean condition; and (c) clean and dry before use. 3. Re-usable containers must be dedicated to the carriage of a particular product to the extent necessary to avoid cross-contamination.*

The transport of animals and animal by-products outside installations is outside the scope of the Directive and therefore their transport outside slaughterhouses and animal by-products installations is outside the scope of this document. However, whilst they remain in vehicles, whether within or outside the installation, problems associated with either spillage or leakage of any solid or liquid material or with odour, can be reduced by suitable vehicle design, construction and operation. The reception, off-loading and storage of animals and animal by-products can also be undertaken within an enclosed areas, in the case of animal by-products, operated under negative pressure, with extractive ventilation connected to a suitable odour

abatement plant. If material is tipped from the delivery vehicle, the receiving hoppers can be covered and sealed after filling.

For loading/unloading, one technique that has been applied is the construction of a tunnel/covered area large enough to accommodate the biggest despatch/delivery vehicle likely to visit the site. Odours can be contained if the tunnel has doors at either end, which make a good seal with the walls and which can be opened and shut rapidly with the minimum of effort and inconvenience. If the doors are difficult to operate there is a high probability that they will fall into disuse. High-speed plastic roller-shutter doors, which are less susceptible to damage than metal doors, are commercially available. Ensuring the integrity of the tunnel and the unloading, storage, processing and packing areas can minimise the leakage of odours. Such tunnels can be used without significantly compromising the negative pressure maintained throughout the rest of the installation. For the unloading of animals, the enclosure can also reduce the risk of noise emissions to the surrounding neighbourhood. This is important as noise can be a major problem, especially when pigs are being unloaded.

Doors to areas where animals/animal by-products are loaded/unloaded, stored or treated, can be close fitting and kept closed other than to allow pedestrian access or the movement of materials. Self-closing personnel doors can be provided and fitted with alarms, which operate if the doors fail to close within a reasonable period of time based on access requirements.

Achieved environmental benefits

Reduced odour production and emission is achieved during the loading/unloading, storage and subsequent treatment of animal by-products. The use of sealed and leak-proof containers also minimises water and soil contamination, from spillages and leaks and reduces the risk of infestation by insects, rodents and birds. Enclosure can also provide some temperature control, e.g. due to protection from direct sunlight and which can slow down the decomposition of the animal by-products. Noise emissions can also be reduced, e.g. during the unloading of pigs at slaughterhouses.

Cross-media effects

Energy is consumed in providing the ventilation to maintain a negative pressure and when extracting malodorous air to abatement equipment.

Operational data

In one case study slaughterhouse using a tunnel with roller shutter doors, problems arose which prevented their use, mainly due to the ever increasing length of the lorries collecting by-products from the site, which have resulted in the loading tunnel now being too short.

By-products can be collected and stored in covered vessels. Difficulties caused by constant or intermittent feed can be solved by conveying the material into, e.g. hoppers or chutes, instead of dropping it directly into open skips. If the skips are placed outdoors, to ease their delivery and collection, the prevention of odour and vermin problems may be achieved by maintaining e.g. conveyors and seals, to minimise both the need to open-up the equipment and the amount of downtime when it is not available for use.

Applicability

Applicable in all slaughterhouses and animal by-products installations, whether the animal by-products are inherently malodorous or if they may become so before they are either treated or removed from the premises.

A drive-through tunnel has advantages from a health and safety point of view, e.g. it eliminates reversing and it is normally applicable at loading and unloading points in slaughterhouses and animal by-products installations. Where tipping from lorries is required, there may be more restrictions, especially in many existing installations, where the availability of space may be limited. Side tipping into hoppers constructed to the equivalent length of the lorry trailer units, or individual tipping units is required.

Driving force for implementation

Driving forces include ABP Regulation 1774/2002/EC, odour control, noise reduction, hygiene and the risk of infection from animal by-products which are confirmed to be, or suspected of being, infected with transmissible diseases, such as TSE. The significance of these driving forces varies depending on the type of animal by-product and its intended use. For example, the prevention of the spread of BSE risk material by insects, rodents and birds to material intended for human consumption will make enclosure important.

Example plants

At least one pig slaughterhouse in Denmark has an enclosed area for the loading of animal by-products.

Several rendering plants in Germany have been reported to enclose materials during transport and storage and to ensure that doors are kept closed.

Reference literature

[49, VDI, 1996, 134, Nordic States, 2001, 168, Sweeney L., 2001, 241, UK, 2002, 244, Germany, 2002, 287, EC, 2002]

4.1.30 Design and construction of vehicles, equipment and premises for easy cleaning

Description

All vehicles, handling and storage equipment and premises can be smooth, impervious and designed so as not to harbour solids and liquids. Floors can have a chemical resistant finish applied, to prevent damage being caused by the chemicals used for cleaning and disinfection. Floors can be sloped to holding pits.

Achieved environmental benefits

Reduction in the consumption of water and its contamination by cleaning chemicals.

Operational data

Vehicles and equipment can be designed in such a way that eases, the movement and removal of materials, e.g. by ensuring that hoppers have sides which slope downwards, by avoiding angles where materials may stick or be difficult to dislodge and by ensuring that none of the equipment contains any “dead ends”. One way of achieving this is to follow the general principles described in CEN standard *prEN 1672-2:1997 rev Food processing machinery - Basic concepts - Part 2: Hygiene requirements* which is intended to assist compliance with *Directive 98/37/EC of the European Parliament and of the Council of 22 June 1998 on the approximation of the laws of the Member States relating to machinery*.

Applicability

Applicable in all slaughterhouses and animal by-products handling premises.

Driving force for implementation

Ease of operation, including cleaning. Reduced odour emissions.

Reference literature

[6, EA, 1997, 65, EA, 1996]

4.1.31 Frequent cleaning of materials storage areas - odour prevention

Description

Areas where by-products, raw materials and waste are stored can be cleaned frequently. The cleaning programme can cover all structures, equipment and internal surfaces, material storage containers, drainage, yards and roadways.

ABP Regulation 1774/2002/EC prescribes minimum requirements at, e.g. storage installations, rendering plants, biogas plants and composting plants, for the establishment and documentation of cleaning procedures, for all parts of the premises, containers, receptacles and vehicles.

Achieved environmental benefits

The adoption of thorough cleaning and good housekeeping, as a routine reduces malodorous emissions.

Cross-media effects

Water is consumed during the cleaning process, although the extent depends on the amount of dry cleaning carried out before water is used. There may be opportunities to re-use water from sources which have not been in contact with animals or animal by-products and from the WWTP, depending on the extent of treatment of the waste water and the final use of the by-product.

Operational data

If raw material containers are emptied and washed frequently, e.g. daily, then decomposing and malodorous materials will not accumulate over long periods of time. Delays in the despatch of animal by-products from the slaughterhouse, together with the long distances travelled, without temperature control provide sufficient time for material to deteriorate and if storage, particularly badly controlled storage, continues on a site, even briefly, odour problems will be exacerbated. Even facilities with a quick turnover of clean material can generate odour problems, if good hygiene practices are not observed.

See also Section 4.1.12.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Example plants

Several rendering plants in Germany.

Reference literature

[134, Nordic States, 2001, 163, German TWG Members, 2001, 241, UK, 2002, 244, Germany, 2002]

4.1.32 Transport blood in insulated containers

Description

Transporting blood in insulated containers can prevent the temperature from rising by more than 2 °C during the transport.

Achieved environmental benefits

Prevention of the formation of malodorous substances, by preventing rotting. By preventing rotting of the blood it is, more likely to be of a good enough quality to be used and therefore will not need to be disposed of as waste. If it is already destined for disposal it may cause fewer odour problems during processing and during the subsequent waste water treatment.

Cross-media effects

None.

Operational data

In practice liquid blood is stored in a container incorporating an air valve to exhaust any gas which might possibly be produced internally. Completely eliminating oxygen from the storage is, therefore, not possible and as a consequence if a closed, but not sealed, blood container is not refrigerated the blood will ferment within a few hours of being collected, thus leading to odours being produced. However, it has been reported that the presence or absence of oxygen makes no difference and that low temperature transport/storage preserves the blood and minimises odour problems.

Applicability

Applicable during the transport of all blood, whether for use or disposal.

Driving force for implementation

Reduction of the decomposition of fresh blood, allowing it to remain usable for the production of “high” priced products. Otherwise quality will be so low that it may have to be disposed of as waste and at a cost.

Example plants

Several rendering plants in Germany.

Reference literature

[163, German TWG Members, 2001, 244, Germany, 2002, 271, Casanellas J., 2002]

4.1.33 Biofilters

Description

Biofilters comprise an air distribution system and a carrier medium, often made from an organic material, which can support growing micro-organisms which feed on malodorous substances and thereby remove odours from the air. The malodorous substances must be caught on the micro-organism carrier, which, therefore, must have a sufficiently high surface area. As the micro-organisms also require water, the air needs to be kept moist.

The biofilter typically consists of a treatment medium supported on concrete slats above a concrete base. The extracted air is drawn through a humidifier and drop-out pot to remove entrained particulate matter. The air is then ducted to the void beneath the biofilter, which is used to distribute the extracted air uniformly beneath the filter medium, before it passes upwards through it. The filter medium must not be allowed to compact, as this will cause a pressure drop across the bed and a loss of efficiency. Typical media include a pasteurised worm compost inoculated with a selected *Pseudomonas* culture, broken pallets, bark, light expanded clay aggregate (LECA), peat and heather supported on seashells and fixed earth of a defined particle size. Insufficient information has been provided to determine the relative performances of the various media for given odour sources and concentrations.

Irrespective of the medium, it is important that the gases to be treated pass through the bed at the optimum flowrate. The residence time required to effectively abate an odour depends on the odour strength and which pollutants are present in the gas. For low intensity odours a residence time of at least 30 seconds should be aimed for, rising to up to 60 seconds for very strong odours. To maintain bio-efficiency, and to maximise the biofilter performance it is necessary to control the humidity, pH, oxygen supply and nutrients. The temperature can also affect the overall performance and operation of the biofilter. The moisture content can be maintained by an irrigation system. A high moisture content in the exhaust is beneficial for biofiltration because it reduces the amount of water required to irrigate the bed.

The technology is simple and can be operated continuously without constant supervision/attention. Maintenance is simple. It generally just comprises annually loosening and refurbishing of the filter medium. A daily visual inspection of the filter medium allows the operator to detect any compaction or the development of preferential channelling of the effluent gas, or signs of erosion by the irrigation water, all of which can reduce abatement efficiency. The retaining walls may be inspected daily for any leaks and damage that could compromise their airtight integrity. Flooding of the subfloor plenum due to inadequate drainage or due to the water table rising may occur and is usually due to improper design or installation.

Biofilters are reported to be suitable for the separation of malodorous substances which result from organic and partly inorganic exhaust air components, such as nitrogen, phosphate, etc.

Generally, the plant consists of a preliminary unit where the exhaust air is pretreated.

Leachate which seeps through the biological filtration system requires waste water treatment.

Achieved environmental benefits

Reduced odour emission. There is some disagreement about the average efficiency of biofilters. Generally, efficiency is above 90 % for the elimination of malodorous substances from the waste gases from rendering plants. This, however, depends on the composition of the feedstock, the inlet concentration, the flowrate, the number of hours in operation and maintenance of the biofilter. Used biofilter material may sometimes be used for soil improvement in gardening.

Cross-media effects

The biofilter may be an odour source. The used biofilter can sometimes be used as compost, but most of the time it has to be disposed of as waste, e.g. by incineration as chemical waste. Any leachate produced can contain organic residues of the filter material.

Energy is consumed during the transfer of the malodorous air to and through the biofilter.

It has been reported that emissions of N_2O , which is a greenhouse gas, may be a problem.

There may be problems due to noise from the fans used to transfer malodorous air to the biofilter.

There may be occupational health hazards associated with personnel entering the biofilter to visually inspect the filter medium and to water it. Remote watering systems may be provided.

Operational data

The figures in Table 4.9 show the required biofilter surface areas designed by calculation. These were found to agree with the surfaces of existing unspecified biofilters installed in rendering plants, with various raw material throughput, which were actually controlling odour problems.

Raw material throughput (t/h)	Required filtration area (m ²)	Volume flow (m ³ /h)
5	250	30000
10	500	60000
20	1000	120000
50	2500	300000

Table 4.9: Reference values for the size and rating of biofilters
[49, VDI, 1996]

Operational data for a rendering plant using an unspecified biofilter medium is shown in Table 4.10.

Operational area	Exhaust air volume flow (m ³ /h)	Odour concentration in the raw gas *(OU/m ³)	Odour concentration in the clean gas *(OU/m ³)	Decrease in odour conc. *(%)
Production	58000		226	
WWTP	1430		159	
Production	109107		197	
WWTP	3939		160	
Biofilter 1	85700	16000	242	98.5
Biofilter 2	75800	21500	236	98.9
Entire plant	16000	60000	35 - 100	99.8
*A consistent unit for odour concentration has not been agreed, these figures are provided to give an indication of the effectiveness of a biofilter				

Table 4.10: Emission reductions achieved using unspecified biofilters in a German rendering plant [163, German TWG Members, 2001]

In this case, the number of OUs, represents the volume of clean air/m³ required to dilute 1 m³ of malodorous air, to remove the smell down to the odour threshold, e.g. 80000 OU requires 80000 m³ of clean air to dilute 1 m³ of malodorous air to the odour threshold.

For **pasteurised worm compost inoculated with a selected *Pseudomonas* culture**, reduced odour emissions with an efficiency of approximately 95 – 98.4 % have been reported. This filter material is reported to be suitable for most types of ventilation air. This medium is used in an example fish-meal and fish-oil processing plant. The malodorous emissions are extracted from the processing plant, including from places where the highest intensity odours are produced such as the cooker. Fish is processed at a rate of 15 t/h, producing condensate at a rate of 0.258 t/t fish, i.e. 3.87 t/h of exhaust vapour. 60 % goes to the WWTP and 40 % evaporates, to produce 1.55 t/h of exhaust vapour.

In the example plant, before the air is transferred to the biofilter it undergoes some initial purification by passing it through water. This separates out some fats and solids. The biofilter applied has a surface area of 800 m² handling air at a rate of 100000 m³/h, with a consequent surface load of 125 m³/h per square metre and an annual operating time of 500 h/yr. It works at full load for 60 % of the time and part load for the remainder. The filter bed height is approximately 0.8 metres and the residence time of the malodorous air is approximately 15 - 20 s. During this time, the malodorous organic components of the exhaust air are organically disintegrated by micro-organisms, which include bacteria and fungi. Individual components of the malodorous air have been measured and reductions in total carbon, ammonia and other nitrogen compounds detected.

Performance data for measurements taken during a limited sampling period at the example plant, during several hours of processing under similar conditions of, e.g. temperature and pressure, are shown in Table 4.11. A scrubber is also used to reduce the odour emissions further and condensed vapours are treated in a WWTP.

Measurement 1 (09.55 – 10.55)			Measurement 2 (10.40 – 11.10)			Measurement 3 (11.15 – 11.45)		
Before biofilter (OU)	After biofilter (OU)	% odour reduction	Before biofilter (OU)	After biofilter (OU)	% odour reduction	Before biofilter (OU)	After biofilter (OU)	% odour reduction
89334	1969	97.8	94646	2481	97.4	103213	1656	98.4
See above for the definition of OU, in this case								

Table 4.11: Performance figures for a pasteurised worm compost biofilter in a fish-meal and fish-oil processing plant

Broken pallets can be used as a filter medium and it is reported that such spent filter material from a bone de-fatting plant is used as compost in gardens.

Bark can be used as a filter medium. One supplier of bark as a biofilter medium to a gelatine manufacturing plant, recommends that the bark is replaced every 3 or 4 years, but this is done annually by an example plant operator.

LECA is used as a filter medium in rendering plants. The supplier of the LECA recommends that it is periodically sterilised and re-inoculated with micro-organisms. One user with 2 plants reports that this has been unnecessary and that odour reduction efficiencies of 99 % have been achieved. A bioscrubber and chimney are also used as odour abatement in at least one of these plants.

Peat and heather supported on sea shells can also be used as a filter medium. The peat and heather provide the growing medium on which the micro-organisms grow. The shells support the medium, which would otherwise compact, thereby removing the need to periodically mix it to re-establish the growth of the micro-organisms.

Fired earth of a defined particle size is both self-supporting, i.e. it does not compact and does not biodegrade and it presents a surface area capable of supporting the biodegradation of malodorous emissions.

Applicability

Applicable in slaughterhouses and animal by-products installations. Not suited to combustion gas treatment. It has been reported that peaks of malodorous non-condensable gases may not only pass through a biofilter without any significant reduction, but they may also be inhibitory to the biological activity in the medium. Biofilters are, therefore, considered to be suitable for high volume low odour intensity air streams only, as they do not achieve 100 % odour destruction.

The requirement for a large surface area may be prohibitive if space availability is limited. Small standard modules can, however, be used for local exhausts.

Economics

The initial capital costs and running costs are relatively low. Investment costs of EUR 5000 - 20000 for a biofilter treating 1000 Nm³/h have been reported.

Pasteurised worm compost inoculated with a selected *Pseudomonas* culture.

For the fish-meal and fish-oil processing case study above, the following costs have been quoted.

2 x 58 kW exhaust fans, operating for 3000 h/yr x EUR 0.065/kWh	= EUR 22620
2 x 23 kW exhaust fans, operating for 2000 h/yr x EUR 0.065/kWh	= EUR 5980
2 x circulating pumps for the scrubber	= EUR 4875
Treatment of 60 % of the condensate in the WWTP	= EUR 39000
The filter material is changed every 4 years	= EUR 14000/yr
Maintenance	= EUR 7000/yr

Overall annual cost EUR 93475

Driving force for implementation

Reduction of odour emissions.

Example plants

Pasteurised worm compost inoculated with a selected *Pseudomonas* culture is used in a fish-meal and fish-oil product plant in Germany, as reported above.

Broken pallets are used in at least one plant bone de-fatting plant.

Bark is used in at least one gelatine manufacturing plant.

LECA is used in at least 2 rendering plants in Denmark.

Reference literature

[49, VDI, 1996, 134, Nordic States, 2001, 163, German TWG Members, 2001, 241, UK, 2002, 242, Belgium, 2002, 243, Clitavi - DMRI, 2002, 244, Germany, 2002]

4.1.34 Odour control using activated carbon filters

Description

Activated carbon has been used for odour abatement for many years. The effect is based on the very large specific surface area, in the form of micro-pores, which bind the odour molecules. The larger the molecules, the better the binding. Neither ammonia nor hydrogen peroxide are bound effectively. The efficiency for, e.g. hydrogen peroxide can, however, be improved by using specially prepared carbon. As the pores are filled, the efficiency falls and the carbon must be either replaced or regenerated.

Achieved environmental benefits

Reduced odour emission.

Operational data

The efficiency of new carbon preparations is 95 - 98 %, but it drops over time, so the average efficiency during the life cycle of the active carbon is considerably lower, possibly nearer to 80 %. Water, dust and fat aerosols can ruin an activated carbon filter. The relative humidity must therefore not exceed 80 - 90 % and particles must be effectively removed upstream of the filter.

Applicability

The technique is applicable in all slaughterhouses and animal by-products installations, providing the air is dry and does not contain dust or aerosols.

Economics

Can be expensive to maintain and replace.

Driving force for implementation

Reduced odour emissions.

Example plants

Many Danish slaughterhouses and rendering plants.

Reference literature

[134, Nordic States, 2001, 347, German TWG members, 2003]

4.1.35 Dilution of odours by capture into one or more chimneys

Description

The malodorous air is collected from various sources into one or more high chimney stacks for emission, at a suitable height to ensure sufficient dilution and dispersion of the odour, taking into account the local prevailing climate conditions.

Achieved environmental benefits

Reduced perception of odour problems in the vicinity of the slaughterhouse or animal by-products installation. No additional by-products are produced.

Cross-media effects

Reduced visual amenity due to the presence of the chimney(s). The production of the malodorous substance has not been prevented.

Operational data

The determination of stack heights for odour control is uncertain and is less precise than for other polluting discharges, because the critical feature of the emission is its olfactory rather than its chemical characteristics. Sensitivity to odours is variable and subjective. Some form of pretreatment prior to release may be required, rather than relying solely on dilution and dispersion of a discharged emission. A wet rendering plant in Denmark emits an average of 333000 Danish OU/s, from a 90 metres high chimney. 300000 m³ of air is processed per hour. The plant reports emissions of 4000 OU/m³. The air is passed through an activated sludge bioscrubber and a LECA biofilter before being directed to the chimney.

Applicability

Currently, this is the most common method employed at slaughterhouses. Pre-treatment is normally required for the types of odours produced at rendering plants.

Economics

Low cost technique.

Driving force for implementation

Odour reduction.

Example plants

A wet rendering plant in Denmark.

Reference literature

[241, UK, 2002, 243, Clitravi - DMRI, 2002]

4.1.36 Noise management

Description

Noise levels can be assessed and controlled to ensure that they do not cause annoyance to persons in the vicinity. This can be undertaken in co-operation with the regulatory authorities.

Significant stationary and mobile noise sources; those building and ground conditions which may influence noise emissions and the level and duration of each noise source can be mapped.

The consequences of noise from a planned increase in production; increased traffic to/from/at the plant; increased operational times for existing sources and from new stationary sources of noise can be evaluated.

Noise strain in the surroundings of the plant can be calculated.

A plan to reduce the noise strain in the surroundings from stationary sources and mobile sources can be prepared.

Meetings with working groups which include the participation of the neighbours can be followed by subsequent implementation of noise reducing activities. Working groups can continue to meet and review noise prevention and control measures.

Achieved environmental benefits

Reduced noise emissions.

Cross-media effects

None.

Operational data

The noise characteristics, e.g. the tone; its timing, its duration and its level, can all affect how annoying the noise is and can all be assessed to establish what controls are required.

Legislation controlling noise exposure in the workplace requires noise exposures to be controlled by means other than hearing protection, in the first instance. As a general rule, occupational noise assessments are required where the noise levels are such that people standing 2 metres apart have to raise their voices to be heard. Control of noise levels at source for occupational reasons may, therefore, significantly reduce environmental noise. Noise levels that annoy neighbours may, however, be both below occupational action levels at the ear of the person hearing the noise and/or may be high levels of noise which are not an occupational hazard due to the position, time or duration of the source of the noise.

In an example slaughterhouse, the following action was taken to combat a noise problem. A ventilating exhaust was changed; an awkwardly placed machine room was closed; the frequency control/speed of ventilators, e.g. at condensers was changed; condenser equipment was changed; heat recuperation from the cooling system was extended and selected sources of noise were shielded.

For mobile sources internal traffic routes were altered and acoustic screens were erected.

A dispensation allowing an increased noise level of + 5 dB(A) was arranged for Monday mornings.

The total noise emitted from the slaughterhouse was reduced by 12 - 13 dB(A).

It has been reported that most traffic noises arise from the way the vehicle is driven and that effective noise reduction measures include speed reduction and steady driving. Good planning before the installation is constructed can reduce noise emissions by design. This may include building structures such as embankments and walls and placing roads lower than surrounding land. Noise-reducing road surfaces can be applied, e.g. a mastic asphalt with chippings, is reportedly 2 dB(A) quieter than a rolled asphalt surface and 4 dB(A) quieter than a concrete surface. Open textured asphalt capping, known as “whispering asphalt”, can reportedly reduce noise levels by a further 3 dB(A), but has a much shorter lifetime than other road surfacing materials. It may be possible to construct the access and egress on the side facing away from, e.g. residential areas. The vehicle may also be adapted by, e.g. insulating HGV engines.

Fan noises can be transmitted over long distances, with the higher frequencies tending to die away faster. A roof-mounted fan may, therefore, be modified to produce higher-frequency noise. The connections between fans and ducts or housings can be made using elastic linkages, to minimise noise associated with vibrations.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Driving force for implementation

Good relations with neighbours and occupational health and safety.

Example plants

A Danish pig slaughterhouse

Reference literature

[189, Pontoppidan O., 2001, 224, German TWG members, 2002, 296, EA, 2002, 297, EA, 2002]

4.1.37 Reduced noise by roof extract fans - by routine maintenance

Description

Routine maintenance of roof fans reportedly resulted in a reduction of 10 dB(A).

Achieved environmental benefits

Reduced noise emissions, thus giving benefits to local residents, especially at night and weekends. For an example installation, the number of complaints about noise fell from approximately 6 per week to one in 4 months. An additional advantage reported, was the improved health and safety working environment for the employees.

Operational data

A noise survey was undertaken to determine the cause of complaints, to compare levels with standards and to advise on practical solutions to control emissions. There are 3 processing sites and a poultry rearing farm at the site. The facility operates 24 hours, 7 days per week. The survey was carried out over a 12 hour period from 15.00 to 03.00 hours.

Measurements were taken at specific predetermined positions on the site and at 3 fixed locations in the surrounding areas, as determined by the complaints.

Noise levels were recorded and compared with BS4142.1997, *Methods for rating industrial noise affecting mixed residential and industrial areas*. Measurements were taken using a CEL 573 sound level meter, set at a height of 1.5 m, for varying sample durations. Also a CEL 162 environmental noise analyser was set up in fields within 50 metres of complainant properties.

The survey indicated that the noise emissions for the site were 20 dB above the existing background noise level for the area in which the factory is situated.

The survey also identified specific sources of noise emissions. After assessment the consultants were able to recommend correction methods. As well as the effluent plant air blowers, there were emissions from refrigeration plant rooms, roof fans and lorries/trailers. The levels were greater in the tonal range of 250 to 500 hertz frequencies

Applicability

Applicable in premises with roof mounted fans.

Driving force for implementation

Regular environment meetings are held on the case study site, with representatives from the local parish council and the area environmental regulating officer. There is a register of complaints to which all incoming complaints are logged and actions taken. From these meetings and registered complaints it was decided to undertake a noise survey to try and locate any nuisance levels and to reduce these where required. The first survey to establish noise levels was undertaken in October 1999. Most of the complaints were from residents living near the further processing unit and those in a direct line with the main site and most related to the noise levels during the evenings.

Example plants

A poultry slaughterhouse in the UK.

Reference literature

[214, AVEC, 2001]

4.1.38 Reduced noise at balance lagoon blower

Description

Additional sound insulation was fitted to the effluent blower building.

Achieved environmental benefits

Reduced noise emissions.

Cross-media effects

None.

Operational data

At an example plant, noise emissions were reduced by about 15 dB(A). The benefits were felt by local residents, especially at night and at weekends. The numbers of complaints about noise fell from approximately 6 per week to one in 4 months. An additional advantage reported, was the improved health and safety environment for the employees.

Loud tonal characteristics were reduced so that they are no longer significant and at approximately 10 metres from blower sheds, the blower noise is almost inaudible against the site background noise.

A noise survey was undertaken to determine the cause of complaints, to compare levels with standards and to advise on practical solutions for controlling emissions. There are 3 processing sites and a poultry rearing farm at the site. The facility operates 24 hours a day and 7 days per week. The survey was carried out over a 12 hour period from 15.00 to 03.00 hours.

Measurements were taken at specific predetermined positions on the site and at 3 fixed locations in the surrounding areas, as determined by the complainants.

The noise levels were recorded and compared with BS4142:1997, *Methods for rating industrial noise affecting mixed residential and industrial areas*. Measurements were taken using a CEL 573 sound level meter, set at a height of 1.5 m, over varying sample durations. A CEL 162 environmental noise analyser was set up in fields within 50 metres of complaint properties.

The survey indicated that the noise emissions for the site were 20 dB above the existing background noise level for the area in which the factory is situated.

It also identified specific sources of noise emissions. After assessment the consultants were able to recommend correction methods. As well as the effluent plant air blowers, there were emissions from refrigeration plant rooms, roof fans and lorries/trailers. The levels were greater in the tonal frequencies ranging between 250 and 500 hertz.

Applicability

Applicable in installations which use a balance lagoon blower.

Driving force for implementation

Regular environment meetings are held at the case study site, with representatives from the local parish council and the area environmental regulating officer. There is a register of complaints in which all incoming complaints are logged together with the actions taken. From these meetings and registered complaints it was decided to undertake a noise survey to try and locate any nuisance levels and to reduce them where required. The first survey to establish noise levels was undertaken in October 1999. Most of the complaints were from residents living near the further processing unit and those in a direct line with the main site and most related to noise levels during the evenings.

Example plants

A poultry slaughterhouse in the UK.

Reference literature

[214, AVEC, 2001]

4.1.39 Abatement of noise from refrigeration plants by the use of insulated doors

Description

In an example slaughterhouse, the large up-and-over roller shutter doors of the refrigeration plant rooms were exchanged for insulated design doors which give 21 dB insulation, in the 63 to 4000 hertz frequency range. Where practical the doors are kept closed overnight and during the day.

Achieved environmental benefits

Reduced noise emissions, thus giving benefits to residents local to the site, especially at night and at weekends. The number of complaints about noise fell from approximately 6 per week to one in 4 months. An additional advantage was an improved health and safety working environment for the employees.

Energy is also saved, due to the reduction in heat loss.

Operational data

Safety requirements regarding ventilation need to be taken into account during the design and construction of refrigeration plant rooms.

A noise survey was undertaken to determine the cause of complaints, to compare levels with standards and to advise on practical solutions to control emissions. There are 3 processing sites and a poultry rearing farm at the site. The facility operates 24 hours a day and 7 days per week. The survey was carried out over a 12 hour period from 15.00 to 03.00 hours.

Measurements were taken at specific predetermined positions on the site and at 3 fixed locations in surrounding areas, determined by the complaints.

The noise levels were recorded and compared with BS4142.1997, *Methods for rating industrial noise affecting mixed residential and industrial areas*. Measurements were taken using a CEL 573 sound level meter set at a height of 1.5 m, over varying sample durations. A CEL 162 environmental noise analyser was set up in fields within 50 metres of complainant properties.

The survey indicated that the noise emissions for the site was 20 dB above the existing background noise level for the area in which the factory is situated.

It also indicated sources of noise emissions. After assessment the consultants were able to recommend correction methods. As well as the effluent plant air blowers, there were emissions from refrigeration plant rooms, roof fans and lorries/trailers. The levels were greater in the tonal range frequencies between 250 and 500 hertz.

Economics

The costs can be offset by energy savings.

Driving force for implementation

Regular environment meetings are held on the case study site, with representatives from the local parish council and the area environmental regulating officer. There is a register of complaints to which all incoming complaints are logged and actions taken. From these meetings and registered complaints it was decided to undertake a noise survey to try and locate any nuisance levels and reduce where required. The first survey to establish noise levels was undertaken October 1999. Most of the complaints were from residents living near the further processing unit and those in a direct line with the main site and most related to the noise levels during the evenings.

Example plants

A poultry slaughterhouse in the UK.

Reference literature

[214, AVEC, 2001]

4.1.40 Replacement of fuel oil with natural gas

Description

Fuel oil is available in various sulphur grades ($< 1\%$, $< 2\%$, $< 3\%$ and $> 3\%$). Natural gas is essentially sulphur free. If there is access to a natural gas supply, boilers can be converted to burn gas, e.g. by modifying the fuel supply system and replacing the burners. The use of natural gas is relatively easy to control and it does not require storage facilities.

Achieved environmental benefits

Due to natural gas being essentially sulphur free, lower SO_2 emissions can be achieved, without the need for abatement. The nitrogen content of natural gas is generally negligible, so fuel NO_x emissions are effectively zero.

Cross-media effects

None reported.

Operational data

Natural gas produces less energy per unit mass than fuel oil.

Applicability

Applicable in all installations using boilers and which have access to a supply of natural gas.

Economics

There will be an initial cost for modifications to the fuel supply system and the burners. The running costs for using natural gas compared to fuel oil are unlikely to be higher, although the fuel may be more expensive. The fuel cost will depend on the market in any given MS at any time and it may be higher or lower than alternative fuels. The costs of the technique will depend mainly on the prevailing fuel prices.

Driving force for implementation

Reduced SO_2 emissions.

Reference literature

[167, Greek Ministry for the Environment, 2001, 265, EC, 2001, 349, GME TWG members, 2003]

4.1.41 Replacement of boiler fuel with tallow

Description

Fuel oil is available in various sulphur grades ($< 1\%$, $< 2\%$, $< 3\%$ and $> 3\%$). Tallow is essentially sulphur free. Boilers can be converted to burn tallow by replacing the burners. Traditional uses for tallow have been restricted, as a consequence of the BSE crisis. The permitted uses and routes for disposal are defined by ABP Regulation 1774/2002/EC. In some circumstances, e.g. where there is not a readily accessible outlet for tallow, it could be convenient and/or cheap to burn it within the installation where it is produced, although this technique is currently not approved under ABP Regulation 1774/2002/EC.

Achieved environmental benefits

The need to consume fossil fuel is reduced. Also, because tallow is virtually sulphur free lower SO_2 emissions can be achieved and without the need for abatement that, e.g. sulphur-containing fuel oil requires. There is also reduced pollution associated with transport if the tallow is burned on the same site as it is produced.

Cross-media effects

None reported.

Operational data

The modifications required to enable a boiler burning fuel oil to burn tallow are very minor. It has been reported that burners are available which enable a boiler to burn tallow, natural gas, diesel or oil. If an alternative use or disposal route is not readily available, e.g. due to the grade of tallow produced, or is not considered to be economically viable, then burning the tallow in a boiler has been reported to be an easy and economic option.

Applicability

At the time of writing, this technique is not permitted in the EU, due to the fact that in ABP Regulation 1774/2002/EC, it is neither listed, nor has it been approved in accordance with the procedure referred to in Article 33(2) therein, after consultation of the appropriate scientific committee.

Economics

There will be an initial cost for modifications to the fuel supply system and the burners. The running costs for natural gas compared to fuel oil are unlikely to increase, although the fuel price may be higher. The fuel cost will depend on the market in any given MS at any time and it may be higher or lower than alternative fuels. Costs of the technique will depend mainly on the prevailing fuel prices.

Driving force for implementation

Reduced SO₂ emissions.

Example plants

Numerous slaughterhouses, rendering plants and other animal by-product (and non-animal by-product) installations throughout Europe.

Reference literature

[167, Greek Ministry for the Environment, 2001, 265, EC, 2001]

4.1.42 Installation and equipment cleaning

4.1.42.1 Management of quantities of water and detergents consumed

Description

If the consumption of water, detergents and cleanliness can be recorded on a daily basis it is possible to detect deviations from normal operation and then to monitor and plan ongoing efforts to reduce the future consumption of both water and detergents without jeopardising hygiene.

Trials can also be undertaken, e.g. using less or no detergents; using water at different temperatures; using mechanical treatment, i.e. the use of “force” in the water pressure and using scouring sponges, brushes, etc.

Monitoring and controlling the required cleaning temperatures can enable the required cleaning standard to be achieved without the excessive use of cleaning agents.

Achieved environmental benefits

Potential reduced consumption of water and detergent and of the energy required to heat the water. The reduction potential depends on the cleaning requirements at each part of the installation or equipment to be cleaned.

Cross-media effects

None.

Operational data

There are a small number of legal food and veterinary requirements which specify water consumption requirements. It is also recognised by veterinarians, operators and customers that water overuse can lead to cross contamination. Inadequate hygiene controls cause hygiene problems, which can result in product rejection or a shortened shelf life. Improvements in waterless cleaning techniques can be achieved, e.g. by using flow restrictions on the water supply and by regulating the water pressure from high-pressure wash to medium- and low-pressure for night and day cleaning, respectively. The frequency of wet cleaning can also be assessed with the objective of reducing the number of full wet cleans to one per day instead of one at every break, or as is the case in some slaughterhouses virtually constant wet cleaning, by someone who hoses down the slaughter hall approximately every 15 minutes.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Economics

The technique results in reduced water and detergent costs.

Driving force for implementation

Reduced water and detergent costs.

Reference literature

[134, Nordic States, 2001, 148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001, 241, UK, 2002]

4.1.42.2 Selection of those detergents which cause the minimum impact on the environment

Description

Certain detergents, such as nonyl phenol ethoxylate (NPE) and alkylbenzene sulphonates (LAS) pose a high risk to the environment and can be avoided in all cleaning operations. NPE has been used as a cleaning agent in slaughterhouses and animal by-products installations. Nonylphenol is a metabolite of the nonylphenolethoxylate group. It is toxic to terrestrial and aquatic organisms, in which it has exhibits hormone-like effects. It will soon be banned for use as a cleaning agent in all but a few limited circumstances by Council Directive 2003/53/EC, amending for the 26th time Council Directive 76/769/EEC and will be prohibited from use in slaughterhouses and animal by-products installations.

When choosing alternative detergents, it is necessary to first check that they can achieve an adequate level of hygiene and then to assess their potential environmental impact.

Achieved environmental benefits

Reduced damage to aquatic organisms.

Cross-media effects

These will depend on the alternative detergents chosen.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Driving force for implementation

Nonyl phenols are “priority hazardous substances” highlighted for priority action under *Directive 2000/60/EC of the European Parliament and of the Council of 23 October 2000 establishing a framework for Community action in the field of water policy*.

Reference literature

[134, Nordic States, 2001]

4.1.42.3 Avoid and reduce the use of cleaning and disinfection agents containing active chlorine

Description

Cleaning agents containing active chlorine can produce hazardous organic halogens and chlorinated hydrocarbons, which may impair or disturb the anaerobic treatment of floating matter in waste water. Substitutes for their use include, e.g. peracetic acid.

The consumption of all disinfectants can be reduced by applying an efficient cleaning before disinfection.

Achieved environmental benefits

Reduced emissions of hazardous organic halogens and chlorinated hydrocarbons, to water.

Operational data

The available substitutes for chlorine tend to be less efficient and more expensive.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Economics

The available substitutes for chlorine tend to be more expensive.

Driving force for implementation

Reduced emissions of hazardous organic halogens and chlorinated hydrocarbons, which may interfere with the operation of WWTPs.

Reference literature

[163, German TWG Members, 2001]

4.1.43 Waste water treatment

4.1.43.1 Provision of a waste water holding capacity in excess of routine requirements

Description

An emergency lagoon can be provided to intercept waste water which will exceed consent limits if it is discharged from the site. On-line monitoring of, e.g. ammonia, suspended solids and flow can be undertaken. If consent limits are exceeded the waste water can then be diverted to the lagoon and if necessary returned to the WWTP for further treatment.

The installation of mixing and equalisation tanks larger than those required for routine waste water treatment, as well as additional safety tanks, can enable plants to cope with emergencies, such as culls or occasional breakdowns. High volumes of waste water, which may also be highly loaded, can then be emptied slowly without exceeding the capacities of WWTPs.

Achieved environmental benefits

Prevention of discharge of untreated, insufficiently treated or excessive quantities of waste water to the local water course or municipal WWTP.

Cross-media effects

There may be odour problems.

Applicability

Applicable in all new slaughterhouses and animal by-products installations. For existing installations, there may not be enough space to construct a lagoon.

Economics

There is an initial high cost incurred from providing the additional storage capacity, including paying for the space this requires. This has to be balanced against the cost of contaminating local water courses, damaging the operating conditions at the local municipal WWTP and the costs of exceeding discharge ELVs.

Example plants

A poultry slaughterhouse in the UK.

Reference literature

[163, German TWG Members, 2001, 243, Clitravi - DMRI, 2002, 248, Sorlini G., 2002, 264, May G. E., 2001]

4.1.43.2 Regularly conduct laboratory analysis of the effluent composition and maintain records

Description

Regular laboratory analyses of effluent can form an important part of the management of waste water. Together with records of actual inputs, by composition and flow, the information can be used to determine how the WWTP can be operated to optimise the emission levels in the discharge to the local water courses or to the municipal WWTP.

Achieved environmental benefits

Assists with the management of the operation of the WWTP, to minimise emission levels.

Cross-media effects

None.

Applicability

Applicable in all WWTPs.

Driving force for implementation

Compliance with ELVs.

Example plants

Several rendering plants in Germany.

Reference literature

[167, Greek Ministry for the Environment, 2001, 244, Germany, 2002]

4.1.43.3 Prevention of stagnant waste water

Description

The pipes associated with the drainage and the WWTP can be laid to have sufficient gradient to avoid the stagnation of waste water. This may be done for hygiene reasons, as e.g. stagnant slaughterhouse waste water will attract flies and rats. Odour problems can also be caused by anaerobic conditions in stagnant water in drainage systems.

Achieved environmental benefits

Reduced odour and vermin.

Cross-media effects

In existing plants which have insufficient gradient, energy may need to be used to pump the waste water.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Economics

Not economically restrictive.

Example plants

Most slaughterhouses and animal by-products installations which produce waste water.

Reference literature

[134, Nordic States, 2001, 244, Germany, 2002]

4.1.43.4 Screening of solids – sieves (type unspecified)

Description

Aperture widths of 0.25 - 4 mm.

Achieved environmental benefits

Reduced suspended solids, particulate BOD and potential for the formation of malodorous gases.

Cross-media effects

Odour may be emitted from the screenings.

Operational data

Reduction rates of 50 - 90 % for the settleable solids and 10 - 40 % for the BOD₅. A BOD₅ reduction between 17 - 49 % has been reported for slaughterhouse waste water, when using a mesh size of 1 mm. It is reported that the performance can be increased significantly if the plant is operated efficiently.

If sieving is not undertaken solids get trapped in the WWTP network, where they then rot, emit odours and cause problems for complete treatment of the waste water.

If sieves and collection vessels are not enclosed there may be problems associated with freezing during winter and with odour and vermin in summer.

Applicability

Applicable in all slaughterhouses and those animal by-products installations which produce waste water.

Economics

Sieving removes the need for and therefore the cost of additional waste water treatment. It reduces the volumes of sludge produced, which would otherwise require additional costs for disposal.

Driving force for implementation

Reduced waste water treatment requirements.

Example plants

All slaughterhouses and many animal by-products installations, such as fat melting, rendering and gelatine plants.

Reference literature

[163, German TWG Members, 2001, 244, Germany, 2002]

4.1.43.5 Static wedge/curved screen

Description

In the static wedge/curved screen the waste water is pumped, or flows by gravity, to the top of the screen and then runs down a slide constructed from profile bars. The liquid drains through the screen, with the solids being collected at the bottom for separate disposal. Some screens are vibrated to facilitate particle transport. Others have cleaning nozzles for rinsing the screen from the clean side. Curved screens are supplied with slots down to 0.25 mm. Figure 4.2 shows a typical static wedge/curved screen. Figure 4.3 shows the screening and solids removal in more detail.




Figure 4.2: Curved screen
[134, Nordic States, 2001]




Figure 4.3: Static wedge screen
[12, WS Atkins-EA, 2000]

Achieved environmental benefits

A significant reduction in suspended solids and a small reduction in BOD of the waste water.

Cross-media effects

Water and detergents are consumed during cleaning.

Operational data

Static wedge screens require more maintenance than inclined screw press and rotary drum screens. In typical use, the static wedge screen can require cleaning up to three times a day using high-pressure hoses to remove the build-up of gross debris, and once a day with small amounts of cleaning chemicals, to dissolve any remaining fats.

Applicability

Applicable in all slaughterhouses and animal by-products installations which produce waste water which requires treatment.

Economics

Static wedge screens are generally cheaper than inclined screw press and rotary drum screens. The cost quoted in 2000 was GBP 10000 - GBP 12000. There are also maintenance costs associated with the regular cleaning requirement, which is necessary to prevent blinding and blocking of the mesh.

Example plants

At least one slaughterhouse in the UK.

Reference literature

[12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000, 134, Nordic States, 2001, 236, ORGALIME, 2002, 243, Clitravi - DMRI, 2002]

4.1.43.6 Inclined screw press

Description

The inclined screw press is basically a rotating screw, edged with brushes, which is located inside a cylindrical perforated screen, as shown in Figure 4.4. The whole assembly is then incorporated within a “U” shaped trough. The waste water is pumped or flows by gravity into the bottom of the trough and is moved up the cylindrical screen by the action of the rotating screw. The force of gravity and the action of the screw causes liquid to be extracted through the screen and the remaining solids are discharged from the top of the unit.




Figure 4.4: Inclined screw press
[12, WS Atkins-EA, 2000]

Achieved environmental benefits

Removal of particles and a small reduction in the BOD and suspended solids in the waste water.

Cross-media effects

There may be odour emissions, depending on, e.g. the age of the solids screened.

Operational data

The action of the screw brushes removes gross debris from the screen. Small amounts of cleaning chemicals are periodically used to dissolve any remaining fats which build up on the screen.

Applicability

Applicable in all slaughterhouses and animal by-products installations which produce waste water which requires treatment.

Economics

Inclined screw presses are generally more expensive to purchase than static wedge screens. The cost quoted in 2000 was GBP 12000.

Reference literature

[12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000, 243, Clitavi - DMRI, 2002]

4.1.43.7 Cylindrical screen

Description

The cylindrical screen comprises a rotating cylindrical drum constructed from perforated metal sheeting. The pore size in the sheeting can be as small as 1 mm. The waste water enters the drum and the liquid passes through the filter, with any particles being removed and discharged at one end, either as a result of being carried away by a screw or because of the oblique position of the cylinder. The cylindrical screen is suitable for removing materials which require tumbling to squeeze out residual liquid. The technique is illustrated in Figure 4.5.




Figure 4.5: Cylindrical screen
[134, Nordic States, 2001]

Achieved environmental benefits

Removal of particles and a small reduction in the BOD and suspended solids in the waste water.

Cross-media effects

There may be odour emissions, depending on, e.g. the age of the solids screened.

Operational data

Screens with small holes need to be rinsed periodically from the outside. This may be achieved by a mechanical or spray system, to prevent blinding and clogging of the mesh.

Applicability

Applicable in all slaughterhouses and animal by-products installations which produce waste water which requires treatment.

Reference literature

[134, Nordic States, 2001]

4.1.43.8 Rotary drum screen

Description

There are a variety of rotary drum screens available. In some systems the effluent is loaded inside the drum, but more commonly the effluent flows over the external surface of the drum. Rotary drum screens have been reported to typically have a mesh size of between 3 - 4 mm, but in some cases this can be as small as 0.25 mm. In the rotary knife system the action of the drum lifts the solids from one side of the screen to the other, where they are then removed by a spring loaded scraper for collection into a skip, as shown in Figure 4.6. The screened liquid falls through the drum and is discharged to either an on-site or municipal WWTP.




Figure 4.6: Example of a rotary drum screen
[12, WS Atkins-EA, 2000]

As well as ensuring that screening equipment is adequately maintained, it is essential to ensure that its screening capacity is capable of facilitating predictable variations in flowrates, whether on a day-to-day or a seasonal basis. At some pig slaughterhouses, there are problems when the scalding tank is emptied at the end of the working day and the waste water runs over the screen. This can remove meat scraps and debris out of the collection area. There may also be a problem in some slaughterhouses if surface water drains were routed to the waste water drainage system after the screening equipment was installed. This sometimes leads to screens being overrun during periods of heavy rainfall and meat scraps and debris being washed out of the collection area.

Achieved environmental benefits

The rotary drum screen reduces the contribution from solids to the waste water BOD level, although it does not remove the soluble fraction. It, therefore, only reduces the waste water treatment required. The proportion of the solid to the soluble fraction of the BOD depends on how the water use and the slaughter, carcase dressing and evisceration are managed in individual slaughterhouses. BOD reductions of 15 - 25 % have been reported.

Cross-media effects

None reported.

Operational data

Internal back wash spray provides self-cleaning of the rotary drum screens, which generally require less maintenance than static wedge screens.

The equipment is virtually self-cleaning and is capable of working for many weeks unaided and with little or no maintenance.

The influent to be screened is introduced into a headbox which is designed to slow down the flow and distribute it. It then overflows a sealed weir onto the cylindrical screen, which rotates at 5 – 10 rpm. The solids are retained on the outside screen surface and removed by the doctor blade. In at least one type of rotary drum screen, the screened liquid then falls through the cylinder and passes through the bottom, from the inside to the outside. This action effectively backwashes the screen openings, so the portion of the cylinder screen to be fed is always clean. The backwash operation also avoids build-up of, e.g. fatty solids inside the cylindrical screen.

Another type has a spray bar located inside the drum, which cleans the screen as the drum rotates, using water that has just been screened.

At least one type of rotary drum screen in current use is equipped with a patented high-pressure inner washing system for periodic cleaning. The frequency of such cleaning, applied to remove grease, varies depending on the climate, with hot water being used to prevent blinding by grease solidification.

The solids produced are relatively dry, which is advantageous regardless of whether they are sent for rendering, incineration or composting.

The drum is generally constructed from high grade corrosion-resistant material, which requires minimal maintenance. Wedge-shaped wire is wrapped around a supporting structure to form a helical coil, leaving free spaces as small as 0.25 mm, depending on the users specification. The wire has a trapezoidal shape, specially designed to obtain a high specific flowrate by utilising a venturi effect.

The doctor blade removes the solids trapped on the surface of the screen. It is made of special corrosion-proof material, e.g. copper and is considerably softer than the material used to make the cylinder. It is normally replaced once a year. Replacement takes a few minutes.

Correct sizing of the rotary drum to handle the volume of waste water anticipated is essential, as is the management of the rate of entry of effluent into the equipment. A number of rotary drum screens may even be constructed in series. Under-sizing, or shock-loading can cause the screen to overflow. The effect of this will vary depending on where the overflowing solids are then discharged. If yard water, including rainwater is collected separately from process water the solids can be discharged directly to the municipal WWTP. Shock-loading can result during emptying of the scalding tank, especially if this coincides with hosing down during cleaning, as both are likely to occur at the end of a shift. Provision of a balance tank may, therefore, be required.

An example slaughterhouse killing 350 pigs per hour and producing 45.5 tonnes of carcasses and handling process water only in its WWTP, uses one rotary drum screen of diameter 90 cm and length 300 cm, with a mesh size of 0.75 mm, which is capable of handling a volume of 1000m³/h and 500 kg of suspended solids. The same slaughterhouse has a back up screen of diameter 70 cm and length 180 cm, capable of handling 420 m³/h of process water. The system has been in full successful operation for 8 – 10 years.

Applicability

Applicable in all slaughterhouses and animal by-products installations which produce waste water which requires treatment.

Economics

Rotary drum screens are typically between 2 – 3 times as expensive as static wedge screens, but they have the benefit of being self-cleaning and generally require less maintenance and associated costs. The capital cost quoted in 2000 was GBP 22000 - GBP 31000.

Example plants

Slaughterhouses in Italy and the UK.

Reference literature

[12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000, 279, Leoni C., 1979, 281, Savini F., 2002]

4.1.43.9 Fat removal from waste water, using a fat trap

Description

Fat traps can capture fat, oil and grease that have been allowed to enter the waste water, by slowing down the flow of the water through the trap, which comprises a tank. If the water is hot, it is allowed to cool. As the water cools, the fat, oil and grease separate out and float to the top of the trap. The cooler water continues to flow out of the trap to the WWTP, while baffles contain the accumulated fat, oil and grease. The fat, oil and grease may be treated in a rendering plant.

The removal of the fat reduces corrosion and sedimentation in the receiving waste water pipelines and WWTPs and reduces the load requiring treatment.

Achieved environmental benefits

Removal of fat from waste water.

Cross-media effects

The correct sizing of chambers is critical to ensure proper separation and to avoid the danger of washout during high or abnormal flows. Flow diversion may be needed if inflows suffer large fluctuations. Ease of emptying and regular maintenance is essential to prevent odour problems.

Installing fat traps within processing areas can cause food safety problems. Excessively hot water can cause fats to carry through and may melt precollected fat, so it should be avoided. The baffle material and ease of cleaning need to be considered.

Odour can be a major problem, particularly during emptying.

Operational data

The size of the fat trap can vary depending on the amount of fat produced and on how often the fat trap is maintained. Fat traps may be located inside or outside the building. If they are located inside the building they tend to be smaller and they require more frequent maintenance. Traps that are located outside the building will operate differently in winter and summer and are more prone to clogging during cold weather.

If the separated fat remains in the fat trap for a long period it degrades and consequently its usability decreases and odour problems may occur during storage and processing, which can incur subsequent increased treatment costs. Automatic and continuous removal of the fats, using a scraper, can minimise these problems.

It is reported that at an example slaughterhouse, the waste water is fed into the tank via a vortex chamber. The light-weight fat, oil and grease particles go to the top of the tank and heavier material which cannot be diverted is dropped out of the bottom of the tank. The water phase then flows upwards via a submerged pipe and leaves the tank. The fat accumulated on the surface is then removed using a scraper, which guides it to a hopper and then into a storage tank. The sedimented material which accumulates in the bottom part of the tank can be removed by gravity or pump, either automatically or controlled.

It is reported that this enhanced type of mechanical fat separation guarantees on average a COD reduction of 50 % of the maximum possible COD reduction. The separation efficiency can be considerably increased if precipitants and coagulants are added. The process can be further enhanced by aeration. If a residence time of over four minutes is applied lighter materials are also retained in the sludge, reducing the settleable solids by up to 60 %.

Applicability

Applicable in all slaughterhouses and animal by-products installations.

Economics

The investment required is reportedly outweighed by the savings in waste water treatment costs and plant maintenance.

Driving force for implementation

Reduction in problems caused by fat in waste water pipelines and WWTPs and reduced loads requiring treatment.

Example plants

This technique is applied in virtually all slaughterhouses and animal by-products installations

Reference literature

[344, Brechtelsbauer P., undated]

4.1.43.10 Flotation plants

Description

Flotation plants separate the fat and solids from the waste water. Usually they are installed after a coarse filter and a sand filter. Their effect can be boosted by the addition of precipitation and flocculation agents before the waste water enters the flotation tank. Certain metal salts such as iron (III) sulphate, iron (III) chloride and aluminium sulphate, aluminium chloride and a number of polymers are used for precipitation and flocculation. The quantity and type of flocculation agents and flocculation aids can only be determined conclusively after semi-commercial trials or after the construction of a plant. It is reported that their use is not usually necessary. The application of sludge on agricultural land may be restricted after flocculation, due to metallic salt residues. For this reason, flotation without flocculation and precipitation agents can be selected for new designs, with the subsequent treatment steps dimensioned accordingly.

Achieving flotation of the solid particles requires the production of micro-bubbles. There are 3 methods for producing the bubbles. They are air flotation, i.e. aeration at atmospheric pressure; dissolved air flotation and mechanical flotation.

The floating material is removed by the use of chain conveyor scrapers.

Achieved environmental benefits

Reduction of COD, BOD, nitrogen and phosphorus in waste water and the production of sludge, after dewatering, for use in biogas manufacture. The cleaning efficiency depends on the equipment, the characteristics of the waste water and how it is operated. The solid materials may be recycled into an animal by-products installation, e.g. for composting, either on the same site, or elsewhere.

Cross-media effects

Often the dissolved air flotation water may use fresh water, thereby increasing the overall water consumption and increasing the quantity of water contaminated and thus requiring further waste water treatment.

Flotation plants are a potential source of odour problems.

The presence of metallic salts from flocculation can prevent the sludge from subsequent biological treatment being applied to land.

Operational data

In air flotation, air bubbles are formed by introducing the gas phase directly into the liquid phase through a revolving impeller or through diffusers. It is reported that aeration alone, at least for a short period, is not particularly effective in bringing about the flotation of solids.

For dissolved air flotation, air is injected while the water is under pressure. The dispersion water used, at 10 - 20 % of the flow, can be fresh water or waste water recirculated after flotation. The sludge may be scraped off the surface and sent off-site for land injection.

Table 4.12 and Table 4.13 give figures for the efficiencies of flotation plants.

		Units	COD	BOD ₅	Fat	Total Kjeldahl Nitrogen	Phosphorus
Production	Influent	mg/l	1000	498	104	36	10
	Effluent	mg/l	458	142	< 15	23	3.5
	Efficiency degree	%	54	71.5	> 86	36	65
Purification	Influent	mg/l	929	515	106	35	9.8
	Effluent	mg/l	530	237	< 15	32	5
	Efficiency degree	%	43	54	> 86	11	52

Table 4.12: Purification performance of a flotation plant during production and cleaning [163, German TWG Members, 2001]

Pollutant	% reduction
BOD	70
Total N	55
Total P	70
Fat	85

Table 4.13: Purification performance of a flotation plant using precipitation and flocculation agents [134, Nordic States, 2001]

Table 4.14 shows further operational data for a rendering plant with a flotation plant using submerged flotation aerators designed for this specific purpose.

Parameter	Influent	Effluent	% decrease
pH	9.0 - 9.5	7.7 - 11	-
Filterable solids (mg/l)	1530	570	2.7
COD total (mg/l)	5024	3416	32.0
Fat (mg/l)	1590	199	87.5
NH ₄ -N (mg/l)	943	648	31.3
Organic-N (mg/l)	119	39	66.9

Table 4.14: Influent/effluent data – for preliminary mechanical/physical-chemical waste water treatment after rendering

Another report quotes typical COD strengths of slaughterhouse waste waters ranging from between 2900 mg/l to 3800 mg/l. These can be reduced by a DAF plant, to less than 600 mg/l, prior to trade effluent discharge. Suspended solids can be reduced from about 1500 mg/l to less than 100 mg/l. [12, WS Atkins-EA, 2000]. The principal components of a DAF plant are shown in Figure 4.7.




Figure 4.7: Principal components of dissolved air flotation
[12, WS Atkins-EA, 2000]

Table 4.15 shows costs and maintenance requirements for a DAF plant treating 750 m³/d.

	Estimated capital cost	Typical maintenance requirements
Dissolved air flotation (DAF)	GBP 150000	Up to 2 hours per day cleaning and maintenance may be required.

Table 4.15: Cost and maintenance requirements for DAF treatment - (750 m³/d effluent)
[67, WS Atkins Environment/EA, 2000]

At a rendering plant using submerged aerators for flotation and a paddle to remove the floating material, with a flow of 15 m³/h and a volume of 12 m³ and surface area of 8 m², a 76 % reduction in fat content and a 42 % reduction in COD, are reported. An automatic spraying system controls the formation of foam.

At one German rendering plant the N-elimination from the high ammonia content of the waste water amounted to 10 %. At another, with higher initial ammonia levels, it amounted to approximately 30 - 40 %. This led to high ammonia levels in the air in the enclosed flotation area and occupational health risks to personnel entering the area.

High temperatures and pH values make fat separation difficult. Mechanical separation is reported to be the least sensitive to these parameters.

At an animal carcase disposal plant in Germany, flotation is undertaken using a mixing and equalising vessel designed for a constant effluent inflow of up to 8 m³/h. At this plant, a fat elimination rate of 50 % has been achieved. The COD (homogenised) is only reduced by 16 %, because the excess sludge from the biological treatment plant simultaneously reaches the flotation plant. This can lead to temporary overloading.

Applicability

Applicable in all slaughterhouses and animal by-products installations which produce waste water.

Economics

It has been reported that in many cases, the capital expenditure of a DAF plant is justified by reduced trade effluent costs.

Mechanical flotation is reported to incur lower investment and operating costs than other flotation techniques.

It has been reported that the investment cost for a flotation plant with a capacity of 60 m³/h is EUR 125000 – 150000 (2003).

Driving force for implementation

Reduction of COD, BOD, nitrogen and phosphorus in waste water.

Example plants

A poultry slaughterhouse in the UK. Slaughterhouses and rendering plants in Germany.

Reference literature

[134, Nordic States, 2001, 163, German TWG Members, 2001, 244, Germany, 2002, 346, Belgian TWG member, 2003]

4.1.43.11 Waste water equalisation tanksDescription

Storage and mixing tanks can be installed to equalise the enormous variations in the volume flow and in the concentration of the waste water.

Achieved environmental benefits

Enables downstream treatment techniques to operate at the optimum efficiency for minimising contaminated discharges to local water courses.

Cross-media effects

None reported.

Operational data

The constant use of equalisation tanks, rather than their intermittent use when the flowrate exceeds a predetermined figure, is advantageous to the WWTP, since it ensures a more consistent effluent for treatment and minimises the problems that may otherwise be caused by shock loading, e.g. from cleaning chemicals which are used once each day. The effluent quality and thickening performance of secondary sedimentation tanks following biological treatment is reportedly improved through constant solids loading. It is reported that there are advantages to be gained from locating the equalisation tank after the primary treatment and before the biological treatment. If it is located before the primary settling tank, sufficient mixing must be provided to prevent the deposition of solids, concentration variations and odour problems. It is also reported that as general rule equalisation should take place after any fat has been removed from the waste water.

At one slaughterhouse, which reportedly successfully treats process and rainwater, an equalisation tank is located after the rotary screening equipment and before a flotation tank, where fat is skimmed off and sand is removed from the bottom of the tank. Another slaughterhouse reports that it has an equalisation tank capable of holding four days worth of liquid effluent. This can have advantages in terms of creating a homogeneous feed to the WWTP, but it can also lead to odour problems.

The tanks need to be sufficiently aerated to minimise the formation of noxious and malodorous gases. They may also need to be coated to protect the concrete from corrosion by fatty acids.

Applicability

Applicable in all slaughterhouses and animal by-products installations, where the flowrate and content of the waste water varies and where this may have a detrimental effect on the other WWTP processes.

Economics

The cost of constructing and operating an equalisation tank needs to be compared with the cost savings associated with the smooth running of the downstream treatment techniques.

Driving force for implementation

To present a virtually homogeneous feed to downstream WWTP processes.

Example plants

Equalisation tanks are used in slaughterhouses in Germany, Italy and the UK and in rendering plants in Germany.

Reference literature

[163, German TWG Members, 2001, 216, Metcalf and Eddy, 1991, 244, Germany, 2002, 269, Italian TWG Members, 2002]

4.1.43.12 Minimise liquid seepage and cover waste water treatment tanks

Description

The base and sides of waste water treatment tanks can be sealed to prevent leakage into the soil and groundwater and the tops may be covered and ventilated to minimise odour problems. Drainage systems can be provided underneath tanks, to collect any seepage that does occur in the event of an accident.

Achieved environmental benefits

Prevention of soil and groundwater contamination and minimisation of odour emissions.

Cross-media effects

Energy will be required to power any ventilation equipment.

Operational data

It is standard practice to line and seal the base and sides of tanks and to construct them on a base which will settle and not stress the tank materials or cause either small or catastrophic leaks. It is also standard practice to provide a drainage system beneath tanks to collect any liquid seepage that does occur and to feed it back into the WWTP.

The ventilated gases can be drawn to an odour abatement system, either specially provided for that purpose or which treats other malodorous gases arising from other activities on the site.

Applicability

Sealing of the base and sides, applicable in all waste water treatment tanks. Covering and ventilating tanks is applicable where odour problems may arise and are not otherwise prevented.

Driving force for implementation

Minimisation of the risk of soil and groundwater contamination and reduction in odour emissions.

4.1.43.13 Minimise liquid seepage and aerate waste water treatment tanks

Description

The base and sides of waste water treatment tanks can be sealed to prevent leakage into the soil and groundwater and the contents of the tank may be aerated to prevent the development of anaerobic conditions and a consequent production of malodorous gases.

Achieved environmental benefits

Prevention of soil and groundwater contamination and minimisation of odour emissions.

Cross-media effects

Energy will be required to mix the contents of the tank and perhaps to supply oxygen.

Operational data

It is standard practice to line and seal the base and sides of tanks and to construct them on a base which will settle and not stress the tank materials or cause either small or catastrophic leaks. It is also standard practice to provide a drainage system beneath tanks to collect any liquid seepage that does occur and to feed it back into the WWTP.

Applicability

Sealing of the base and sides is applicable in all waste water treatment tanks. Aeration is applicable when anaerobic conditions which are not actually necessary for the waste water treatment arise and create malodorous gases.

Driving force for implementation

Minimisation of the risk of soil and groundwater contamination and reduction in odour emissions.

4.1.43.14 Anaerobic pretreatment using down-flow or up-flow reactors

Description

Passing waste water from slaughterhouses or rendering plants over fixed bed reactors supporting anaerobic micro-organisms on plastic rings or balls or on sintered glass, can act as a pretreatment technique to reduce the COD in waste water, prior to aerobic treatment. One particular technique operates in either a down-flow or up-flow operation, incorporating recirculation. However, the technique is unable to reduce either the COD or nitrogen content sufficiently for it to be more than just a pretreatment. It is reported to be capable of removing 73 – 76 % of COD in a rendering plant if 2 reactors are used, one operating in down-flow mode and the other in up-flow mode.

Achieved environmental benefits

Partial removal of some of the organic load from waste water, prior to further treatment on the site or at a municipal WWTP. It is reported that the biogas produced during the process contains more energy than the anaerobic plant needs to carry out the treatment.

Cross-media effects

The ammonia content released from organic nitrogen combinations during anaerobic treatment exceed the nitrogen fixation through new biomass formation, so the level of ammoniacal nitrogen increases during the treatment.

Operational data

As a rule, almost 75 % of the COD during the down-flow stage is soluble, while the remainder are solids. The dissolved COD is approximately 85 % volatile organic acids, especially ethanoic and propionic acid. Anaerobic micro-organisms convert approximately 95 % of the in-flowing organic impurities into biogas and only 3 – 5 % into new biomass. Low volumes of biomass (excess sludge) are created during the acidification or methanation stage and these can be channelled into an aerobic biological purification stage. The biogas created is 60 – 85 % CH₄, which can be used for heating and power generation.

In an example rendering plant, the specific CH_4 production is reported to reach on average $0.32 \text{ m}^3/\text{kg}$ COD input. The biogas comprises 86 – 87 % CH_4 and 0.3 – 0.7 % H_2S . The high H_2S content in the crude gas has to be removed using a desulphurisation plant to prevent emissions and corrosion.

The actual volume load achievable depends on the specific surface, free space and the biomass concentration within the reactor. The reactor configuration, the environmental conditions within the reactor, such as the temperature and pH, as well as the substrate specific decomposition ability of the micro-organisms are also important.

To treat waste water originating from rendering plants, a mesophilic method of operation at 35 – 37 °C is reported to be effective. A temperature of 32 – 42 °C can largely be maintained through the heating energy contained in the raw effluent. The residence time in the fixed bed reactor may be 11 – 30 h, depending on the biomass concentrations.

A prerequisite requirement for trouble-free operation of fixed bed reactors is to ensure the removal of solid and lipophilic substances from the effluent, in order to avoid the accumulation of materials and blockages. The anaerobic process is relatively susceptible to failure from load fluctuations, so volume and concentration equalisation of the effluent is required. A mixing and equalisation tank with a stirring device can also facilitate gradual pre-acidification. The pH needs to be maintained around neutral, to prevent inhibition of the anaerobic mixed biocoenosis. Stable CH_4 production takes place within a pH range of 6.8 – 7.8. The optimum pH for a separate pre-acidification process, depending on the substrate, is between 3.5 – 6.5.

To optimise the microbiological environmental conditions, necessary to free ammonia from the organic nitrogen compounds, an acidification dosage may be required, e.g. by the addition of hydrochloric acid or phosphoric acid. Depending on the effluent to be treated an additional dose of nutrients, e.g. phosphorus, may be required. A COD:N:P:S ratio of 800:5:1:0.5 is considered optimal. Toxicity problems may arise if there are higher ammonia or hydrogen sulphide contents. The inhibiting effects are determined by the pH, the substrate composition and the adaptation time of the micro-organisms.

Table 4.16 shows the results of anaerobic pretreatment at a rendering plant. Data are given for 2 months: February and July. It is not known to what extent the results of the treatment are due to the temperature of the anaerobic treatment or the difference in storage conditions of the raw material. The results are summarised in terms of the percentage change in each parameter. The starting loads were different.

Parameter	February			July		
	Influent	Effluent	% increase or decrease	Influent	Effluent	% increase or decrease
pH value	7.5	7.8		7.9	8.2	
Specific conductivity (mS/cm)	6.67	6.89		7.54	7.66	
Filterable solids (mg/l)	1115	532	- 61.8	2642	1011	- 62
COD total (mg/l)	4311	1156	- 73.2	9414	2208	- 76.5
BOD ₅ total (mg/l)	3433	534	- 84.5	5890	1154	- 80.4
Fat (mg/l)	370	90.8	- 75.5	717	265	- 63
NH ₄ -N (mg/l)	126	145	+ 15.1	185	208	+ 12.4
org.-N (mg/l)	57.6	30.4	- 47.2	80.2	59.4	- 25.9
P total (mg/l)	8.7	8.6	- 0.7	14.5	12.8	- 12.1
Sulphide (mg/l)	24.1	8	- 66.8	8.1	13.5	+ 65.2
Sulphate (mg/l)	39.5	11	- 72.2	65.5	22.8	- 65.2

Table 4.16: Influent and effluent data from an anaerobic waste water pretreatment plant

It is reported that the biogas from the waste water produces more energy than that used during the waste water treatment. One kg COD produces 0.5 m³ of biogas. The heating value of one m³ of biogas is about 6.4 kWh. Using a block heat and power plant, 35 % of the 6.4 kWh can be used for the generation of electricity and 55 % in producing heat.

Applicability

Applicable as a pretreatment in slaughterhouses and rendering plants, prior to aerobic treatment. Efficient removal of fat may make this step unnecessary in slaughterhouses, if the organic load is reduced sufficiently, as is the case in slaughterhouses in the Flemish region of Belgium.

Driving force for implementation

Significant removal of the COD in waste water and production of biogas.

Example plants

At least 2 rendering plants and one slaughterhouse in Germany.

Reference literature

[163, German TWG Members, 2001, 244, Germany, 2002, 346, Belgian TWG member, 2003]

4.1.43.15 Aerobic digestion combined with either intermittent or alternating denitrification under anoxic conditions

Description

Biological nitrogen elimination is described in general terms in the “Common waste water and waste gas treatment/management systems in the chemical sector” BREF.

Aerobic digestion combined with either intermittent or alternating denitrification under anoxic conditions involves the simultaneous aerobic and anoxic treatment of waste water, either in separate tanks or in a single tank. The process is controlled by monitoring the concentrations of ammonia and nitrogen oxides. Consequently, a number of aeration devices are automatically switched on or off. For example, a single tank may be divided into aerobic and anoxic zones. During the alternating operational method, individual, sequentially arranged tanks are operated alternately on an aerobic or anoxic basis which coincides with the simultaneous transfer of effluent between tanks. During the intermittent operational method, the tanks are operated in parallel.

Achieved environmental benefits

Removal of nitrogen, BOD and COD compounds from high loaded waste water streams, which have not been excluded by other means.

Cross-media effects

Odour problems may be caused. Energy is used, e.g. during aeration.

Operational data

The technique is characterised by the removal of BOD without aeration, combined with the denitrification typically required for the waste water from slaughterhouses and animal by-products installations. This offers the advantage of minimising energy consumption. It has been reported that aeration can account for 60 % of energy consumption at WWTPs.

The aeration is achieved by diffusing the air through a very large number of fine holes, to ensure that there is enough oxygen in the waste water to undertake the nitrification required for the high nitrogen loads which are typical for the waste water from this industry.

In addition, the technique is characterised by high sludge ages, which also assist the denitrification process.

At one rendering plant where the treatment is applied, it is reported that the effluent is first subjected to fat separation, solids removal using cylindrical sieves, flotation, mixing and equalisation.

The treatment is then carried out in large-volume, foil-sealed earth basins. Aeration is carried out intermittently. Full nitrogen elimination, through simultaneous nitrification/denitrification, is reportedly achieved. The main part of the BOD and COD load can be removed without aeration. The introduction of air and the circulation of the biomass are achieved using 8 aerator chains. The aerator chains consist of 7 floating aerators, each connected to the others by means of air supply hoses. The air is introduced in the form of small bubbles, over the basin floor. The required quantity of air is made available through sliding vane rotary compressors. A compressor constantly runs on base load in order to ensure a specific minimum level of circulation of the activated sludge. The connection of further compressors is regulated by a timing programme and an automatic oxidation/reduction control. By varying the rate of oxygen introduced through different chains aerobic and anoxic zones are produced. The rate of oxygen fed through the chains is altered periodically, so that over time anoxic zones are intermittently created throughout the entire basin. The intermittent creation of aerated and anoxic zones is achieved by stopping the aeration process at 33 % of the aerators at any one time.

The sludge is removed and the effluent is subjected to further aeration and sedimentation.

Dimensional and operating data of the aerobic treatment stage, at this example plant, are shown in Table 4.17.

Parameters	Values
Total volumes, aeration tank	1803 m ³
Inflow	100 m ³ /d
Mixed-liquor suspended solids in the aeration tank	3.5 g/l
BOD – load	346 kg BOD/d
NH ₄ -N – load	90 kg NH ₄ -N/d
COD:N (ratio)	5.6:1
BOD – volume load	0.19 kg BOD/(m ³ ·d)
N – volume load	0.05 kg N/(m ³ ·d)
BOD – sludge load	0.05 kg BOD/(kg TS·d)
N – sludge load	0.015 kg N/(kg TS·d)
Excess sludge	66 kg/d
Age of sludge	95 d
Specific O ₂ consumption for BOD	2.09 kg O ₂ /kg BOD
Specific O ₂ consumption for N	1.91 kg O ₂ /kg BOD

Table 4.17: Dimensional and operating data of the aerobic treatment stage at a rendering plant

Table 4.18 shows the effluent emission levels achieved in the plant described in Table 4.17 during the period 1992 to 1996.

Parameters	Influent concentration	Effluent concentration		
		Average	Minimum	Maximum
BOD ₅ homogenised mg/l	3460	3.1	1	8
COD homogenised mg/l	5040	65.4	35	125
NH ₄ -N mg/l	900	10.0	0.3	29
NO ₃ -N mg/l		2.4	0.3	7.7
NO ₂ -N mg/l		1.8	0.7	4
P total mg/l		1.8	0.3	4.3
AOX mg/l		0.015	< 0.01	0.02

Table 4.18: Influent and effluent levels achieved during the period 1992 - 1996

Further information has been reported for another example rendering plant. The WWTP is reportedly designed with a processing capacity of 580 t/d of animal carcasses and designed for full nitrogen elimination, 2 tanks are operated in parallel with intermittent aeration. The process effluent is subject to fat separation and flotation, followed by mixing with non-process waste water. It is then treated in a clarification plant and an equalisation basin (1250 m³ with a reserve of 1750 m³). It is then divided between 2 basins, each of 6240 m³ capacity. The basins contain a total of 1300 metres length of tubes, each 1.365 metres long and perforated with fine holes, for air intake and 3 stirring devices. The basins are alternately supplied with air (aerated) or are simply stirred (anoxic) in a time ratio of approximately 2:1.

At a third example plant, a slaughterhouse, a WWTP treats effluent from the slaughterhouse, which has a tripe processing plant, in which intestines and stomachs are cleaned out and prepared for further processing. Stomach and intestinal contents, as well as blood are also handled.

The slaughterhouse has a capacity of 25000 cattle per week, i.e. 5000 per slaughter day. This produces 200 litres of effluent per slaughter unit, i.e. 623 l/t cattle carcase or 1000 m³ per working day. It is reported that the daily load treated by the WWTP is BOD₅ 2020 kg, TKN 360 kg and 18 kg phosphorus. Two activation basins are used, alternating 1.5 – 2 hours denitrification with 1.5 – 2 hours nitrification. The times are controlled by monitoring NH₄-N, NO₃-N and O₂ and adjusting the pressure aeration rate.

Dimensional and operating data of the aerobic treatment stage of this plant are shown in Table 4.19.

Parameters	Values
Total volumes, aeration tank	7000 m ³
Mixed-liquor suspended solids in the aeration tank	4 – 5.3 g/l
BOD – load	2.020 kg BOD/d
TKN – load	360 kg TKN/d
pH	6.8 – 7.2
BOD – volume load	0.29 kg BOD/(m ³ ·d)
TKN – volume load	0.051 kg TKN/(m ³ ·d)
BOD – sludge load	0.072 kg BOD/(kg TS·d)
P – sludge load	0.00064 kg P/(kg TS·d)
TKN – sludge load	0.012 kg TKN/(kg TS·d)
Excess sludge	66 kg/d
Age of sludge	30 – 40 d
Mixed-liquor suspended solids in return sludge	7 – 11 g/l

Table 4.19: Dimensional and operating data of the aerobic treatment stage at a slaughterhouse

Using this method, the maximum emission levels measured between 1995 and 1997 are shown in Table 4.20.

Parameters	Influent concentration	Emission levels (Maximum ever measured 1995 – 1997) (mg/l)
COD		47
BOD ₅	2020	7
N-tot		11
NH ₄ -N		3.7
P-tot	18	0.8

Table 4.20: Data from a waste water treatment plant of a slaughtering plant in Germany

This treatment was combined with sieves, equalisation and biofiltration prior to alternating denitrification and nitrification and sedimentation and filtering afterwards.

Applicability

Applicable in slaughterhouses and rendering plants.

Economics

The technique is considered to be economically advantageous as all of the processes can be undertaken in one tank.

Example plants

At least one slaughterhouse and 2 rendering plants in Germany.

Reference literature

[244, Germany, 2002, 341, EC, 2002]

4.2 Slaughterhouses

4.2.1 Slaughterhouses - general techniques applicable at installation level

4.2.1.1 Dry scraping of delivery vehicles, prior to washing

Description

Manure and bedding are scraped into a collection area before the delivery vehicle is cleaned with water. The wash area is arranged so that as much manure as possible can be collected before the vehicle wash starts.

At a major pig slaughterhouse in Denmark, the reception area for pigs has been equipped with a system for collecting manure and bedding. After unloading the pigs the driver of the delivery vehicle scrapes the manure and bedding on to a low level belt conveyor, which carries the material to a container. The unloading of pigs and dry scraping are monitored on a video camera. This together with instructions to the drivers, ensures that the procedure is followed and complied with. After dry scraping, the vehicle is cleaned with water.

Achieved environmental benefits

Both the water consumption and the pollution burden in the waste water are reduced. This includes removal of substances difficult to degrade, e.g. sawdust. Water is still required.

Manure may be used as a fertiliser.

Cross-media effects

None.

Operational data

Water consumption levels of 78 – 130 litres per tonne of pig carcase have been reported, compared to a maximum level of 300 litres elsewhere. At one major pig slaughterhouse in Denmark, the water consumption for cleaning vehicles is approximately 110 l/t, when using dry scraping. The time for the driver to carry out dry scraping followed by washing is practically the same as when wash only is carried out.

Applicability

Applicable in all slaughterhouses.

Driving force for implementation

Reduction of water consumption and COD levels in waste water.

Example plants

At least one major pig slaughterhouse in Denmark.

Reference literature

[134, Nordic States, 2001]

4.2.1.2 Wash delivery lorries using a high-pressure trigger-operated pistol with an adjustable jet

Description

Delivery lorries can be cleaned using a high-pressure trigger-operated adjustable water jet.

Achieved environmental benefits

Reduced water consumption.

Cross-media effects

None, if combined with “Dry scraping of delivery vehicles, prior to washing”, see 4.2.1.2.

Operational data

The use of an adjustable high-pressure water pistol with a pressure of approximately 1.8 - 2.3 million Pa (18 - 25 atmospheres) can reportedly reduce the water consumption needed for washing lorries. The step-less control of the pressure and the range of the water jet makes it possible to remove dirt from both flat surfaces and corners. A saving of 130 l/t of carcase produced can be achieved due to the fact that the water flow stops when the trigger is released.

Water consumption at a Danish slaughterhouse was reduced to 6 litres per pig (78 l/t) and 25 litres per head of cattle (100 l/t) when dry scraping was used prior to washing and a trigger operated self-closing high-pressure pistol was used for the subsequent washing. The same source of information reported consumption rates of 10 l/pig and 80 l/head of cattle.

Applicability

All slaughterhouses.

Economics

The cost of a pump system with two hoses is approximately DKK 35000 (2001). If it is necessary to increase the water pressure before a pressure gun can be used, the reported cost is EUR 10000 - 14000. This reportedly covers the cost of installing high-pressure pumps for the cleaning of several lorries, normally 4, at a time. It also includes, amongst other things, piping and electrical works, hoses and spray-guns.

The reported capital cost in a pig slaughterhouse was recouped in approximately 6 months. The payback period reported in a slaughterhouse killing 40000 head of cattle annually, was 4 - 5 years, this is longer than the pig example before due to its less frequent use.

Driving force for implementation

Reduced waste water treatment costs.

Example plants

At least one Danish slaughterhouse.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.1.3 Automation of the first part of the clean slaughter-line

Description

The definition of the present process is a manual or semi-manual process, e.g. when the operator uses some auxiliary equipment, such as a rectum loosener.

Achieved environmental benefits

None reported.

Cross-media effects

Increased consumption of water, electricity and heat and consequently an increased volume of waste water. The additional wetting of carcasses and by-products, sometimes with hot water, will entrain both solids and dissolved substances and will increase the COD, BOD and nitrogen loads in the waste water.

Operational data

Operational data are shown in Table 4.21, Table 4.22, Table 4.23, Table 4.24, Table 4.25, Table 4.26, Table 4.27 and Table 4.28.

Splitting of the breast	Units	Pre-automation	Automated process	Increase
Water	l/t	6.67	45.55	38.9
Electricity (1)	kWh/t	0.0	0.53	0.53
Heating (2)	kWh/t	0.67	1.34	0.67
Total energy (1 + 2)	kWh/t	0.67	1.87	1.2

Table 4.21: Operational data for automated splitting of pig breasts

Splitting	Units	Pre-automation	Automated process	Increase
Water	l/t	Unknown	26.6	Unknown
Electricity (1)	kWh/t	Unknown	0.5	Unknown
Heating (2)	kWh/t	Unknown	1.3	Unknown
Total energy (1 + 2)	kWh/t	Unknown	1.8	Unknown

Table 4.22: Operational data for automated splitting of pig carcasses

Removal of plucks and viscera	Units	Pre-automation	Automated process	Increase
Water	l/t	0.0	39.9	39.9
Electricity (1)	kWh/t	0.0	0.13	0.13
Heating (2)	kWh/t	0.0	1.33	1.33
Total energy (1 + 2)	kWh/t	0.0	1.46	1.46

Table 4.23: Operational data for automated evisceration of pigs – existing slaughter-line

Removal of plucks and viscera	Units	Pre-automation	Automated process	Increase
Water	l/t	26.6	119.7	93.1
Electricity (1)	kWh/t	0.0	0.53	0.53
Heating (2)	kWh/t	0.67	2.67	2.00
Total energy (1 + 2)	kWh/t	0.67	3.20	2.53

Table 4.24: Operational data for automated evisceration of pigs – new slaughter-line

Removal of plucks and viscera	Units	Pre-automation	Automated process	Increase
Water	l/t	0.0	39.6	39.6
Electricity (1)	kWh/t	0.0	0.1	0.1
Heating (2)	kWh/t	0.0	1.3	1.3
Total energy (1 + 2)	kWh/t	0.0	1.5	1.5
In addition to that for the automated evisceration of pigs, shown in Table 4.24 – i.e. additional use of resources for washing 2 conveyors for transportation to existing casing department				

Table 4.25: Operational data for removal of plucks and viscera

	Units	Pre-automation	Automated process	Increase
Water	l/t	26.6	33.3	6.7
Electricity (1)	kWh/t	0.0	0.53	0.53
Heating (2)	kWh/t	0.67	1.34	0.67
Total energy (1 + 2)	kWh/t	0.67	1.87	1.2
“Back finning” is when the spinous process are cut free, this is done before the splitting to avoid damaging the loins in the splitting process. The process is used in some slaughterhouses, but not in all. In Denmark it is done in all slaughterhouses				

Table 4.26: Operational data for automated back finning of pigs

	Units	Decontamination using hot water
Water	l/t	252.7
Electricity (1)	kWh/t	2.66
Heating (2)	kWh/t	33.25
Total energy (1 + 2)	kWh/t	35.91

Table 4.27: Expected effect of installing decontamination by spraying with hot water

Rectum loosening	Units	Pre-automation	Automated process	Increase
Water	l/t	13.3	39.9	26.6
Electricity (1)	kWh/t	0.0	0.53	0.53
Heating (2)	kWh/t	0.67	1.34	0.67
Total energy (1 + 2)	kWh/t	0.67	1.87	1.20

Table 4.28: Operational data for rectum loosening pigs

Some of the most physically demanding and “unpleasant” unit operations, such as carcass splitting and evisceration are automated.

Applicability

Applicable in pig slaughterhouses.

Example plants

A few Danish slaughterhouses have implemented automation. All Danish pig slaughterhouses have implemented automated carcass splitting.

Reference literature

[184, Pontoppidan O., 2001, 243, Clitavi - DMRI, 2002]

4.2.1.4 Avoid and minimise carcase rinsing, combined with using clean slaughter techniques

Description

Skilled and careful slaughter, dressing and evisceration prevents and or minimises carcase contamination and thus improves product quality, whilst also minimising the necessity to wash the carcase after inspection by a veterinarian. Rinsing can be limited to the splitting cut, to remove bone dust from cattle, the chest cavity and the fore shanks.

Achieved environmental benefits

Reduced water consumption and contamination of water.

Cross-media effects

None.

Operational data

With a manually controlled shower head, a cattle carcase may be rinsed with 8 - 10 litres of water (approximately 30 - 40 l/t).

In pig slaughterhouses, water consumption at the slaughter and bleeding unit operations have been quoted as 10 – 50 l/t and 30 – 40 l/t respectively, with the water being supplied constantly, regardless of carcase throughput.

Applicability

Applicable at all cattle slaughterhouses.

If carcase washing is required, due to visual contamination by, e.g. hair or feathers, washing may be required. The use of water sprays mixed with compressed air can minimise the amount of water used.

Sheep can be 'safely' left unwashed, providing dressing practices are of a high standard, and the meat quality is generally better, i.e. nicer appearance, colour and improved keeping quality. Wet carcasses tend to go 'sticky' when chilled. Likewise if de-hairing of pigs and evisceration of poultry is done skilfully, washing can be avoided.

Manual washing may be preferable to automatic rinsing in cabinets, where the water consumption is often unnecessarily high. If the temperature of the water is kept to a minimum, i.e. cold water is used, fat uptake can be avoided. The use of water sprays mixed with compressed air can also lessen the amount of water used.

Economics

A spray gun costs EUR 200.

Driving force for implementation

Reduced water costs, improved product quality.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001, 217, Brindle J., 2001, 284, Leoni C., 2002]

4.2.1.5 Apply automated water start/stop controls throughout the slaughter-line

Description

Sensors such as photocells can be fitted to detect carcasses and parts of carcasses and to supply water as required. Water supplies can be turned off automatically between carcasses and during all breaks.

Achieved environmental benefits

Reduced water consumption, reduced volumes of water requiring treatment and if the pressure is regulated reduced entrainment of biological matter and contamination. It has been predicted that the savings could be up to half of the total water use during production together with the water saved during cleaning periods, by ceasing the practice of allowing it to continue to run.

Cross-media effects

Energy to pump water could be saved if the need for carcase washing was removed. Water may be wasted if clean carcasses are washed.

Operational data

Care taken during the selection, installation and maintenance of the photocells can make certain that they are reliable and their correct position ensures that carcasses are washed to the extent planned, even if they are swinging on the overhead rail, or vary in size.

Use of the technique pre-supposes that each carcasses needs to be cleaned and the technique does not distinguish between clean and dirty carcasses or dirty parts of carcasses.

If the slaughter-line is not working to its maximum capacity, the water savings are greater, if water is only supplied when there is a carcase present. This has been measured at slaughter and bleeding unit operations.

In pig slaughterhouses, water consumption at the slaughter and bleeding unit operations have been quoted as 10 – 50 l/t and 30 – 40 l/t respectively, where water has been supplied constantly, regardless of carcase throughput.

Applicability

Equally applicable to new and existing slaughterhouses.

Economics

The cost of an automated water stop/start control has been reported to be USD 255. For a pig slaughterhouse the estimated annual saving in water use was 6060 m³.

Driving force for implementation

Reduced water costs.

Example plants

A pig slaughterhouse in the US.

Reference literature

[134, Nordic States, 2001, 214, AVEC, 2001, 243, Clitravi - DMRI, 2002, 268, Ockerman H. W. and Hansen C. L., 2000, 284, Leoni C., 2002]

4.2.1.6 Continuous, dry and segregated collection of by-products along the length of the slaughter-line

See also Section 4.2.2.2.1 and 4.2.5.1.

Description

Depending on the position on the slaughter-line, drip trays/troughs can be positioned to collect liquids and solids. Drip trays/troughs can be provided for the collection of, e.g. dripping blood between the bleed hall and the scalding tank, on pig slaughter-lines; at head and hide removal stations and for blood and mixtures of solids for rendering or other by-products, which are destined for further processing. The troughs can be linked by drains, pumps or suction devices to the relevant collection vessel. The position and design of the tray/trough and the means of preventing mixing with water and the transportation of the liquids or solids depend on the unit operation, the degree of segregation of different materials desired/required and their ultimate intended use, or disposal route. Examples of materials which can be collected and transported dry include offal not intended for human consumption and feathers. For materials destined for human consumption temperature control is particularly important and some slaughterhouses transport offals in water, due to the cooling effect. This can be avoided by transferring the materials to chills quickly after they are removed from the animal.

The amount of waste is particularly large for chest opening, pluck set removal and carcase splitting operations. It is, therefore, very important to install collection systems in these areas. The removal could be done with special suction installations or pumps. In one case study slaughterhouse, all of this waste was formerly washed into the sewerage system during interval cleaning. It was found to be possible to do all the initial cleaning dry, e.g. using shovels, squeegees or vacuum suction, thereby avoiding water usage during the working period. The initial cleaning at the end of the working period can also be done without using water.

Elsewhere, when rumen is removed it is immediately transferred by dedicated pneumatic tunnel to the “dirty zone”, where it is pressed by a hopper system and unloaded into a container for composting.

Achieved environmental benefits

Reduced water consumption and less entrainment of by-products in water. If by-products are collected efficiently, the volume of water required for cleaning is reduced and consequently less energy is used to heat the cleaning water. Less detergent is also required. The amount of waste water produced and its BOD, COD, nutrient and detergent levels and CO₂ emissions are all reduced.

The segregation of liquids and solids destined for use or destruction has several advantages. If sufficient separate collection systems are provided, it reduces cross contamination between different by-products. Segregation of the by-products can, therefore, reduce potential odour problems from materials which even when fresh emit the most offensive odours, i.e. by storing/removing them separately under controlled conditions, instead of having to control a greater volume of mixed by-products. It also reduces the use of water to transport the by-products and to clean the installation (the by-products are largely confined to the drip tray/trough). In addition, cleaning may be easier.

Also, by minimising cross-contamination, segregation enables individual by-products which can be used to be used, instead of being disposed of because they are mixed with materials which cannot be used. All materials can, therefore, be used or disposed of in the most appropriate way for them.

Cross-media effects

Some energy will still be required, e.g. to operate pumps, but that energy which would have been used to heat additional cleaning water can be saved.

Operational data

At a Danish slaughterhouse, the amount of organic material collected per pig increased by 0.2 kg (2.6 kg/t pig carcass) after a trough was installed in the “clean slaughter-line”, i.e. where evisceration, splitting, weighing, cleaning and classification took place and wet suction was introduced. In addition, the pollution of the waste water was reduced by 0.52 – 0.65 kg BOD per tonne of pig carcass. Similar results would be expected using a squeegee/shovel, provided that correct procedures were consistently followed.

In another case study, the COD loading in the waste water was reduced. In a Norwegian slaughterhouse, the combination of fitting a double drain system in the bleed area and collection trays for blood under the scraping table and the evisceration area, together with a pump to the blood tank, reduced the total COD discharge by 22 %, i.e. by or more than 1.25 kg COD per tonne of pig carcass.

Some slaughterhouses use a long trough with a screw conveyor under the slaughter-line to eliminate the need for wet floor cleaning during working hours. The material can be swept or squeegeed to the screw conveyor, the mechanism of which should be inaccessible to the operator, for safety reasons.

The use of drip trays to prevent material from falling on the floor has health and safety advantages, since it can significantly reduce the risk of slipping accidents. It may also influence the downstream value and use of the by-product, if hygiene is an important consideration, e.g. if it is to be used in blood processing.

Applicability

Applicable at all slaughterhouses.

Economics

Each trough costs approximately EUR 300 per metre. If a pumping system is installed, the additional cost will be approximately EUR 3000 - 4000.

The payback period was calculated to be 8 months for a Danish slaughterhouse paying a surcharge on waste water and approximately 4 years when no surcharges are paid.

The payback time for the Norwegian example quoted above, was a little over 6 years.

Waste water treatment costs are saved.

Driving force for implementation

Reduced waste water treatment and waste disposal and the associated reduced costs.

Example plants

At least one Danish and one Norwegian slaughterhouse.

The direct collection of rumen contents for composting is undertaken in at least two cattle slaughterhouses in Italy.

Reference literature

[134, Nordic States, 2001, 167, Greek Ministry for the Environment, 2001, 183, Pontoppidan O., 2001, 239, Denmark, 2002, 244, Germany, 2002, 248, Sorlini G., 2002]

4.2.1.7 Double drain from the bleed hallDescription

The bleed hall can have a system with two drains, one to the collection tank and one to the sewer. The system is designed so that the drain to the collection tank is open during slaughtering and the drain to the sewer is closed. During cleaning the opposite is true. The maximum possible proportion of the blood can be collected without dilution with water. The discharged waste water can contain a minimum quantity of blood. Some systems incorporate an interlock system, which prevents slaughtering from starting if the drain to sewer or to a blood tanker is open.

Additionally, before hosing the bleed hall area, the blood can be scraped with a squeegee to the collection tank.

Achieved environmental benefits

Reduction of organic matter (BOD) and N in waste water.

Collected blood can be used for manufacturing blood meal.

Applicability

Applicable in all slaughterhouses.

In existing plants, it will be necessary to change the floor gradient in the bleed hall and to install a collection tank for blood. The changes can usually be made within the existing available area.

Economics

The total cost for changing the floor drain is in the order of EUR 25000 - 35000.

Driving force for implementation

The reduction of organic matter and nitrogen in waste water, thereby reducing the cost of waste water treatment and discharge.

References to literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001, 317, German TWG, 2002]

4.2.1.8 Refrigeration/cooling of blood

See also Section 4.1.27 for further information about the storage of animal by-products.

Description

Blood which cannot be processed within a very short time can be cooled to a temperature below 10 °C, at the slaughterhouse immediately after collection (and also at the installation where the blood will be received). This can reduce odour problems and waste water pollution at the blood processing plant.

A pilot scale investigation gave the values shown in Table 4.29. These relate to emissions from rendering, after 30 hours storage of blood at 4 °C and 30 °C, respectively

	4 °C	30 °C
Odour units per m³	1000	60000
ppm NH₃	200	675
ppm H₂S	200	300

Table 4.29: Reduced emissions associated with cooling of blood prior to rendering
[134, Nordic States, 2001]

Achieved environmental benefits

Prevention of offensive odours from the liquid blood, caused by the degradation of the blood at both the slaughterhouse and the installation where the blood is used or disposed of. If the blood is rendered fresh, there will also be a lower level of emission of offensive odours and waste water contamination arising from the process.

Cross-media effects

Energy consumption by the refrigeration plant.

Operational data

One company collects about 50 % of the total Spanish blood, for both processing and rendering. All of that blood is refrigerated at the slaughterhouses. Blood for plasma production is chilled at 4 °C and blood for rendering at 7 °C. The blood is refrigerated at the insistence of the blood processing/rendering company, to avoid its deterioration and subsequent bad odours at the slaughterhouses, during transport and at the processing/rendering plant. This requirement is contained in the contract between the blood processing/rendering company and the slaughterhouse, which also sets out, e.g. blood quality conditions, solid content, temperature and collection prices.

Of the remaining 50 % of Spanish blood, a further 10 % approximately is also refrigerated. Most of the 40 % which is not refrigerated is rendered on the slaughterhouse sites. Most of this blood is rendered at the slaughterhouse itself and if not it is usually coagulated in a tank, using steam. The clotted blood is rendered locally and the water goes to the WWTP of the slaughterhouse. There is a risk of odour production during these processes.

Reportedly, refrigeration is the only storage method which enables blood to be transported over long distances and for up to 5 days after being collected.

Approximately 15 % of mammalian blood is chilled prior to collection and processing, mainly to maintain the functionality of the plasma proteins for their use in pet foods.

It is reported that poultry blood is stored chilled, before being sent for further processing for disposal, e.g. rendering.

The blood is stored in closed containers fitted with an air valve, to allow the exhausting of any gas that may be produced. For this reason the European renders have asked all slaughterhouses to refrigerate their stored blood. It has been reported that if a closed, but not sealed, blood container is not refrigerated the blood will ferment within a few hours of collection and will become malodorous. It is thus recommended that blood should always be refrigerated, whether it is destined for blood processing or rendering. It has been said that maintenance of a low temperature is the single most significant factor in the prevention of odour problems.

The energy for chilling has been reported to be about 1.44 kWh/t of pig carcase. It has been reported that 30.5 kWh of electrical energy is required to cool one tonne of blood to ~ 5 °C.

It has been reported that the waste water pollution from the rendering of uncooled blood can be as high as 90 kg COD and 9 kg N per tonne of blood, compared to 20 kg COD and 2 kg N per tonne for cooled blood.

Applicability

In all slaughterhouses and animal by-products installations where blood is handled, treated or stored, except where the blood is being treated virtually immediately after bleeding. It is reported that whilst continuous refrigeration during collection is the best option, processing blood should at least be refrigerated within a maximum delay of one hour after slaughtering, and that the refrigeration of blood destined for rendering should not wait beyond the end of the slaughtering shift.

Economics

A refrigerated blood tank and associated equipment, with a capacity for a slaughter-line killing 600 pigs per hour costs about EUR 65000 - 70000.

A refrigeration cost of EUR 0.0025 per litre of blood (1997), i.e. EUR 0.11 for the blood produced by one tonne of pig carcass, has been quoted.

Driving force for implementation

Odour control at the slaughterhouse and the animal by-products installation.

Refrigeration for blood processing is primarily carried out for quality reasons, indeed one of the raw material quality checks is the smell of fresh blood.

Rendering companies reportedly ask, as a minimum requirement, that the blood be chilled. By-products companies charge more for degraded and malodorous materials, partly due to the additional environmental costs associated with odour control and waste water treatment and partly due to the fact that they have no value and have to be disposed of.

Demand from enforcement authorities to reduce odour during the handling and transportation of blood.

Example plants

Blood is refrigerated to $< 10^{\circ}\text{C}$ in Danish slaughterhouses, except when treatment is carried out very quickly after slaughter. It is also refrigerated in all Belgian, all German and approximately 55 % of Spanish slaughterhouses, whether it is destined for use or disposal. In France, it is always refrigerated in all slaughterhouses if it is destined for use but only if it is destined for disposal if it cannot be treated quickly after slaughter. In Ireland and the United Kingdom, it is refrigerated only if it is destined to be used and not to be disposed of as waste.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001, 271, Casanellas J., 2002, 272, Woodgate S., 2002, 308, Hupkes H., 2002]

4.2.1.9 Dry collection of floor waste

Description

A general principle of modern slaughterhouse operations is to minimise the amount of water that is added to animal by-products as they are collected and transported away for further processing or disposal. A lot of blood and waste falls on the floor, e.g. in the slaughter-line. The washing of this into the WWTP or sewerage system, can be avoided during the working period, by carrying out all cleaning dry. Shovels, squeegees and vacuum suction can be used. The initial cleaning at the end of the working period can also be carried out without water.

Achieved environmental benefits

Reduced water consumption and consequently a reduced consumption of energy for the later removal of the water from by-products in downstream processes, e.g. by evaporation. For recovery operations, inedible waste products such as clotted blood, bone dust and manure from the rumen and from lairages are best maintained in as dry a condition as possible.

Cross-media effects

Increased energy use if wet suction is used.

Operational data

If meat scraps are washed directly down the drain, they enter the waste water stream and they are subject to turbulence, pumping and mechanical screening. This breaks the meat down and releases high COD substances into solution, along with colloidal and suspended fats and solids.

Subsequent waste water treatment either on-site or at a municipal WWTP can then be expensive. The breakdown of suspended fats and solids is increased if the water is hot.

In an example plant, it was shown that by using wet suction in the “clean slaughter-line”, i.e. where evisceration, splitting, weighing, cleaning and classification takes place, the amount of organic waste collected in a slaughterhouse, increased by 0.2 to 0.8 kg/pig (2.6 to 10.4 kg/t of pig carcase). The pollution of the waste water decreased by 40 - 50 g BOD per pig (520 - 650 kg/t carcase).

For a slaughterhouse killing 18000 turkeys per day, i.e. 38 birds per minute, the reported potential water savings were reported to be 18000 m³/yr with a financial saving of GBP 11240/yr. (Costs in 1999)

Applicability

Applicable in all slaughterhouses.

Economics

The payback period for a Danish slaughterhouse was calculated as 8 months and 4 years respectively, depending on whether or not a surcharge is paid on the waste water.

Example plants

At least one Danish slaughterhouse.

Reference literature

[27, University of Guelph, undated, 134, Nordic States, 2001, 214, AVEC, 2001]

4.2.1.10 Use of wet suction of by-products/waste collection prior to wet cleaning

See also Section 4.2.2.2.

Description

The initial pre-cleaning of delivery vehicles can be done using wet suction. Norwegian tests have shown that it is necessary to use a vacuum system with high suction power when the mixture of manure and bedding becomes dry. The time needed for pre-cleaning is not affected. The system can also be used in the lairage area and for the collection of blood residues and soft tissues.

Achieved environmental benefits

Reduction of both water consumption and the contamination of waste water, by blood, fat, manure and other animal by-products. Water is still required for cleaning

Cross-media effects

Energy required for operation of the suction equipment. The storage of manure may cause odour problems.

Operational data

A central system, which removes the need for a mobile collection tank and trailing cables, may be advantageous in the slaughterhouse environment.

By using wet suction in the clean slaughter area, it has been reported that a pig slaughterhouse increased the amount of solid by-product it collected by 40 – 50 g BOD per pig, i.e. from 2.6 - 10.4 kg/t of carcase.

Applicability

Applicable in all slaughterhouses, for cleaning vehicles, the lairage, and the slaughter, dressing and evisceration areas.

Economics

The reported cost is in the order of NOK 170000.

The payback time for the introduction of a wet suction system in the clean slaughter area of a Danish slaughterhouse has been calculated to be 8 months, where a surcharge on waste water is paid and approximately 4 years where it is not.

Driving force for implementation

Saving money through reduced waste water treatment requirements.

Example plants

At least one Danish pig slaughterhouse.

Reference literature

[134, Nordic States, 2001]

4.2.1.11 Reduction of water consumption in poultry slaughter

Description

Water consumption can be reduced in a number of different ways. For instance, unnecessary water sprays can be removed. Manual cleaning procedures can be improved, by increasing dry cleaning, e.g. by removing solid materials and absorbing liquid spillages. The water supply flowrate can be restricted. Medium pressure washing can be carried out at night. Low-pressure washing can be carried out during the day, when required, i.e. within a cleaning schedule which replaces cleaning at every break in the process with one substantial clean per day.

Council Directive 92/116/EEC of 17 December 1992 amending and updating Directive 71/118/EEC on health problems affecting trade in fresh poultrymeat requires carcass washing after evisceration.

Achieved environmental benefits

Reduced water consumption and reduced water contamination. Minimisation of water contact with the carcasses reduces the entrainment of organic matter, such as fat and this in turn reduces the BOD levels in the waste water. A reduced uptake of faecal material may also minimise phosphorus levels in the waste water.

Operational data

Reduced water consumption, from 10 – 11 litres to 7 – 8 litres per carcass can be achieved by optimisation of manual and automated cleaning. It is reported that this will not compromise microbiological standards.

In an example poultry slaughterhouse, the number of carcass washing sprays on a poultry slaughter-line has been reduced to a minimum, i.e. to only after de-feathering and evisceration, without any increase in microbial contamination.

The operator could see no need for additional sprays, in particular, for between the scalding tanks.

With chickens, the reported reduction is from 2500 – 2750 l/t reduced to 1750 – 2000 l/t. For turkeys the reported reduction is from 2000 – 2200 l/t reduced to 1400 – 1600 l/t. These figures are much lower than the total water consumption levels reported in Table 3.4.

Applicability

Poultry processing.

Driving force for implementation

To meet the volumetric flow limit on an effluent discharge permit.

Example plants

A UK poultry slaughterhouse.

Reference literature

[241, UK, 2002]

4.2.1.12 Use pressurised water to wash the carcaseDescription

Pressurised water can be used to wash the carcase. If the pressure is kept below 1 MPa, this will reportedly avoid fat detachment and the consequent waste water contamination. A mixture of compressed air and water increases the pressure without using excess water.

Cross-media effects

Although solid fat may not be detached, there may be some entrainment of fat in suspension.

Operational data

High pressure operation may cause contamination by over-splash, thereby spreading contamination instead of removing it. High-volume/low-pressure washing is more effective than high-pressure/low-volume washing for removing wool and hair.

Applicability

Applicable in all slaughterhouses.

Reference literature

[167, Greek Ministry for the Environment, 2001]

4.2.1.13 Removal of unnecessary taps from the slaughter-lineDescription

Unnecessary taps can be disconnected from the slaughter-line to encourage and facilitate the dry collection of waste. Only essential hand and protective clothing washing facilities remain.

Achieved environmental benefits

Both the volume and contaminant burdens of waste water are reduced. Avoiding contamination of the water removes the need to clean it afterwards. Contaminants dissolve or physically break down in water into smaller fragments, thereby making their removal increasingly difficult, whether by physical, chemical or biological means. This is particularly significant with blood, blood-water, and stomach and intestinal contents from the casing department.

Operational data

Trigger-operated hoses required for wet cleaning may be needed.

Applicability

Applicable in all slaughterhouses.

Driving force for implementation

Reduced water consumption.

Reference literature

[134, Nordic States, 2001]

4.2.1.14 Insulated and covered knife sterilisers

Description

Knife steriliser boxes which are located throughout the length of the slaughter-line can be insulated and fitted with fixed covers, which have slots through which 2 knives can be placed with their blades immersed in water at 82 °C. The cover can be designed and made to suit the type of knife used at each workstation.

Achieved environmental benefits

Reduced water consumption and consequently reduced energy consumption.

Cross-media effects

None reported.

Operational data

The water consumption measured in one uninsulated knife steriliser, with constantly running water has been reported as approximately 2000 l/d. By insulating and covering the steriliser the heat loss can be reduced, so the frequency and volume of top-up water required is consequently also reduced.

Use of a 20 mm thickness of insulating material is reported to reduce the heat loss by 80 %, compared to an uninsulated steriliser, without a lid.

Applicability

Applicable at all work stations in all slaughterhouses.

Economics

Each steriliser costs approximately EUR 700 - 800. In Denmark, the payback time, for fitting new insulated steriliser boxes, has been estimated to be one year.

Driving force for implementation

Reduced water consumption and consequently reduced energy use.

Example plants

This technique is in use in at least two Danish slaughterhouses, one of which is slaughtering cattle and the other pigs.

Reference literature

[134, Nordic States, 2001, 274, Pontoppidan O., 2002]

4.2.1.15 Periodic change of water in electrically heated knife sterilisers, controlled by a timer

Description

A number of large cutting tools are used on the clean slaughter-line. For hygiene reasons, they are cleaned and disinfected several times during the working day, at the end of the day's work and before being used when they have been soiled. In small slaughterhouses, it may be possible to abandon the hot (82 °C) water system if new sterilisers with heating elements are installed and if electric heating of water is installed for major equipment. This significantly reduces heat losses from the hot water system and gives better temperature control. Water consumption can be reduced by periodically changing the water in the sterilisers, using a timer control.

Achieved environmental benefits

Less water at 82 °C is used and consequently, less energy is used to heat the water.

Cross-media effects

None reported.

Operational data

The consumption of water at 82 °C, at the clean slaughter-line of a Danish slaughterhouse has been measured to be 24 litres per pig (312 l/t of carcase). The energy consumption for heating this volume of water is in the order of 2 kWh per pig (26 kWh/t of carcase). The consumption in one uninsulated knife steriliser with constantly running water in a Danish slaughterhouse has been measured to be approximately 2000 l/d.

A periodic change of the water in the steriliser with timer control has been reported to reduce the water consumption to approximately 500 l/d.

Applicability

Applicable at all slaughterhouses.

Economics

The payback period has been reported to be between 6 months and 2 years.

Driving force for implementation

Reduction of water and energy costs.

Example plants

At least one Danish slaughterhouse.

Reference literature

[134, Nordic States, 2001, 169, EC, 1991, 183, Pontoppidan O., 2001]

4.2.1.16 Double knife sterilisation tanksDescription

It has been reported that it is a legal requirement that deboning knives are sterilised between each animal. At an example site, 55 small stainless steel sterilisers, each with 2 tanks supplied with water at 82 °C were designed and installed. Knives are placed in the tanks between each usage and used in rotation to ensure sterilisation. Special flow valves allow only a very small flow to avoid water wastage.

Achieved environmental benefits

Savings are estimated at 1 l/min at each tank. An annual saving of 6453 m³/yr has been reported.

Cross-media effects

No negative environmental impacts were reported.

Applicability

Fully applicable.

Economics

The implementation costs; actual annual energy and water savings; actual financial savings and payback time are shown in Table 4.4.

Driving force for implementation

Increased energy costs and the identification of a method of systematically reducing these in such a way that could be both measured and related to production levels.

Example plants

A cattle and sheep slaughterhouse in the UK.

Reference literature

[52, DoE, 1994, 129, McIlwaine N., 2001]

4.2.1.17 Knife sterilisation using low-pressure steam

Description

In a low-pressure steam steriliser the water is heated by an injection of steam. The water is changed manually, or controlled by a timer, as required. The water consumption is approximately 500 l/d, or less depending on how often the water is changed.

Achieved environmental benefits

Reduced energy use and reduced water consumption.

Operational data

Measurements in 1992 on knife sterilisers at Norwegian slaughterhouses showed an energy consumption of 500 kWh per day equal to 0.3 kWh per head (17 kWh/t of carcass). When the method of knife sterilisation was changed from hot water to steam, the energy consumption was reduced by 75 %, to 4.24 kWh/t of carcass.

The sterilisation is carried out at 150 kPa and after the sterilisation unit the steam pressure is reduced to 50 kPa.

The heat of condensation is used to maximum effect, which reduces the amount of water needed to maintain the sterilisation units at 82 °C.

It is reported that there is no significant risk to the operator from the steam and that the risk from the alternative, i.e. hot water, is greater because it is kept at 400 – 600 kPa.

Applicability

Applicable in all slaughterhouses.

Example plants

The technique has been applied in Norwegian sheep/lamb slaughterhouses for many years.

Reference literature

[134, Nordic States, 2001, 274, Pontoppidan O., 2002]

4.2.1.18 Hand and apron cleaning cubicles – default “water off”

Description

A slaughterman is required to wash his hands several times during the working day and each time he resumes work following a break. It is generally accepted that it is good practice to use water at 42 °C. At some workstations apron washing is also required. At an example slaughterhouse, it was customary to do this using a variety of hose pipes and wash basins, using hot water which was left running during the entire working day. This resulted in an enormous waste of water and energy, as well as leading to poor general conditions.

The hose pipes and wash basins were replaced by cubicles fitted with shower heads operated by foot pedals. The system can be a “dead mans control” design, where if the pedal is not depressed the water flow stops automatically. Alternatively, the shower head can be operated by a photoelectric system, which detects the slaughterman’s presence and turns on the water, with the default being automatic stoppage of the water.

Achieved environmental benefits

At the case study installation, there was an estimated water saving of 2 l/min at each washing point. This gave a total water saving of 11700 m³/yr. Considering the requirement for this water to be heated to 42 °C, the reduction in energy use was 2035 GJ.

Cross-media effects

No negative environmental impacts were reported.

Applicability

Applicable in all slaughterhouses.

Economics

The implementation costs; annual actual energy and water savings; actual financial savings and payback time are shown in Table 4.4.

Driving force for implementation

Increased energy costs and the identification of a method of systematically reducing these in such a way that could be both measured and related to production levels.

Example plants

A cattle and sheep slaughterhouse in the UK.

Reference literature

[52, DoE, 1994, 169, EC, 1991, 237, Italy, 2002, 243, Clitavi - DMRI, 2002]

4.2.1.19 Management and monitoring of compressed air use

See also Section 4.1.3.

Description

The main compressor for compressed air can be stopped at the end of the slaughter operations. A smaller compressor can then be used during cleaning operations. Inadequate maintenance of compressed air installations can lead to leaks developing and the consequent losses of large quantities of air. Losses of more than 30 % of the installed capacity can occur and losses of 20 - 25 % are common. With careful maintenance, losses due to leaks can be kept within 7 - 8 %. Tools operated by compressed air such as handsaws often determine the required pressure for the compressed air supplies. However, some tools are routinely operated at higher pressures than those required for the given task.

Achieved environmental benefits

By preventing leaks, the energy expended on producing unnecessary extra compressed air can potentially be reduced by 30 %. By reducing the pressure by 100 kPa, an energy saving of 6 % can be achieved.

Cross-media effects

None.

Applicability

Applicable in all slaughterhouses.

Economics

The technique will involve increased maintenance costs, but it is likely that these will be offset by the energy savings.

Driving force for implementation

Reduced energy use.

Reference literature

[134, Nordic States, 2001]

4.2.1.20 Management and monitoring of ventilation use

Description

Energy can be saved by ensuring that the filters in the ventilation system are kept clean. The pressure drop across clean filters is kept below 50 Pa. Filters can be changed at a pressure drop of approximately 100 Pa. The running time of ventilation systems can be managed. Installation of automated start and stop controls can be used to prevent unnecessary use of the system. For example, comfort ventilation might only be switched on under certain temperature conditions and only during the operation of those tasks which require it.

Achieved environmental benefits

The energy, otherwise wasted by forcing air across dirty filters and by the excessive use of the ventilation system, can be saved.

Cross-media effects

None.

Applicability

Applicable in slaughterhouses where the air is cleaned using filters before entering any part of the installation.

Driving force for implementation

Reduced energy use and expense.

Reference literature

[134, Nordic States, 2001]

4.2.1.21 Use of backward bowed centrifugal fans

Description

Many fans are of the centrifugal type with forward bowed blades. This type of fan is less efficient than the type with backward bowed blades.

Achieved environmental benefits

Reduced energy consumption.

Cross-media effects

None.

Applicability

Applicable in ventilation and refrigeration systems.

Economics

Backward bowed fans are a little more expensive than those with forward bowed blades, but the extra cost will often be repaid in less than 2 years by the savings arising from the reduced energy consumption.

Driving force for implementation

Reduced energy use and expense.

Reference literature

[134, Nordic States, 2001]

4.2.1.22 Management and monitoring of hot water use

Description

The heating and pumped circulation of water at 82 °C can be stopped automatically when slaughter operations stop, after which time only cold water and water at 60 °C needs to be available, e.g. for cleaning purposes. In a large pig slaughterhouse in Denmark, it has been reported that the temperature of the water has been reduced from 60 to 50 - 55 °C and cleaning is carried out at 1.62 kPa, instead of at a higher pressure.

Achieved environmental benefits

The energy used to heat and pump water at unnecessarily high temperatures can be saved. Fats which have not been prevented from entering waste water, are easier to remove at lower temperatures.

Cross-media effects

If water is used at a higher temperature then the amount and/or aggressiveness of the cleaning chemicals used could be lessened, but on the downside more energy would be required to heat the water to the higher temperature. Below 60 °C, the opposite could be true.

Operational data

According to Danish reports, water at 60 °C gives the best cleaning result, due to its ability to remove fat. Using water at a lower temperature requires the use of either greater quantities or more aggressive cleaning agents. Higher temperatures could reduce the use of cleaning agents, but lead to an increased energy use.

Applicability

Applicable at all slaughterhouses.

Example plants

Cleaning using water at 60 °C is undertaken in Danish slaughterhouses. Cleaning using water at 50 - 55 °C, at 1.62 kPa is undertaken in at least one large pig slaughterhouse in Denmark.

Reference literature

[134, Nordic States, 2001, 243, Clitravi - DMRI, 2002]

4.2.1.23 Installation of groundwater cooling of refrigerant

Description

Groundwater can be used to cool refrigerant gases to reduce the amount of energy used.

Achieved environmental benefits

Reduced energy consumption.

Cross-media effects

The technique can cause a rise in groundwater temperature. A system in Denmark has been closed down because of the resultant rising temperatures in neighbouring wells.

Operational data

The refrigeration system can use 40 - 70 % of the electricity consumption of a slaughterhouse. Groundwater cooling has been introduced to cool the refrigerant and to reduce the condenser operating pressure from 1.22 kPa to the 0.81 kPa which is reported to be optimal from an energy saving point of view.

Applicability

Applicable in situations where there are sufficient groundwater supplies to not cause a significant risk of raised groundwater temperatures.

Driving force for implementation

Reduced energy use.

Example plants

At least one pig slaughterhouse in Denmark.

Reference literature

[134, Nordic States, 2001, 269, Italian TWG Members, 2002]

4.2.2 Slaughter of large animals

4.2.2.1 Animal reception and lairage

4.2.2.1.1 Cessation of feeding of animals 12 hours prior to slaughter

Description

Stopping feeding the animals 12 hours prior to slaughter reduces the quantity of undigested contents in their stomachs. However, the animals are not necessarily under the control of the slaughterhouse 24 hours before slaughter, so the implementation of such a policy would require co-operation with the farmer and the haulier, taking care not to contravene any animal welfare requirements.

Achieved environmental benefits

Reduced manure, paunch and soiled bedding, which might otherwise increase the BOD of wash-water, from vehicles, the installation, the equipment and the animals and which will subsequently require waste water treatment. The risk of odour arising from the manure, paunch and soiled bedding could be reduced.

Cross-media effects

None.

Operational data

Council Directive 93/119/EC of 22 December 1993 on the protection of animals at the time of slaughter or killing states that Animals which are not taken directly upon arrival to the place of slaughter must have drinking water available to them from appropriate facilities at all times. Animals which have not been slaughtered within 12 hours of their arrival must be fed, and must subsequently be given moderate amounts of food at appropriate intervals.

Applicability

Applicable in all slaughterhouses.

Driving force for implementation

Reduced manure production and consequently reduced waste water contamination. There are hygiene benefits too, due to the decreased risk of faecal contamination of hides and carcasses.

Reference literature

[115, EC, 1993, 167, Greek Ministry for the Environment, 2001]

4.2.2.1.2 Minimise animals' time in the slaughterhouse to reduce manure production

Description

Shortening the time that animals are kept in the slaughterhouse, whilst respecting animal welfare considerations, will reduce the amount of urine and faeces produced.

Achieved environmental benefits

Reduced manure, paunch and soiled bedding, which might otherwise increase the BOD of wash-water and require waste water treatment. These materials are, however, the raw materials for biogas manufacture and composting, so any produced need to be collected as dryly as possible and with minimum mixing with other wastes to be useful.

Cross-media effects

A reduction of the amount of manure or faeces produced in the lairage will mean that the stomach and intestinal contents of the slaughtered animal will be greater. These will then have to be collected during and after evisceration.

Operational data

The implementation of such a policy would require co-operation with the farmer and the haulier, taking care not to contravene any animal welfare requirements.

Applicability

Applicable in slaughterhouses where the delivery of animals can be managed to coincide with slaughter times, therefore, minimising the time the animals are kept in the lairage.

Driving force for implementation

Efficient operation of the slaughterhouse.

Reference literature

[167, Greek Ministry for the Environment, 2001]

4.2.2.1.3 Addition of dry bedding to existing bedding, to soak up manure

Description

The addition of bedding, whether as straw or paper, on existing bedding, can reduce the potential BOD levels in waste water.

Achieved environmental benefits

Reduced BOD levels in the waste water.

Cross-media effects

There may be increased odour problems, due to the reduced frequency of changing bedding.

Operational data

Bedding levels may be topped up over a period of up to one week and then removed for, e.g. use as compost, after which the floor may be washed down.

Applicability

Applicable in all slaughterhouses where the animals require bedding.

Driving force for implementation

Reduced BOD levels in waste water.

Example plants

Some UK slaughterhouses.

4.2.2.1.4 Demand-controlled drinking water

Description

The water supply can be demand-controlled, to supply the required water ration for the animals at suitable intervals. The drinking water supply can be reduced by installing teats that can be opened directly by the animals. The use of teats instead of water troughs has the advantage that water is only supplied when the animals are drinking. Water troughs also require a system to be in place for periodic cleaning.

Achieved environmental benefits

Reduced water consumption.

Cross-media effects

None reported.

Applicability

Applicable in all large animal slaughterhouses.

Driving force for implementation

Reduced water consumption and labour requirements for cleaning.

Reference literature

[331, Italy, 2003]

4.2.2.1.5 Showering of pigs, using water saving, timer controlled nozzles

Description

Pigs are showered during hot, dry periods, for animal welfare reasons. It helps to calm them and to prevent them from becoming stressed. The shower nozzles can be designed and installed so that they are only activated when there are pigs present. The flow and the operation time are controlled automatically. Showering also improves the environment for people entering the lairage, by reducing respirable and total dust levels.

Achieved environmental benefits

Less water consumption than if manual or continuous showering is carried out.

Cross-media effects

Reduces dust by 60 %, whereas an electrostatic filter reduces both total and respirable dust by 40 - 45 %.

Operational data

In one case study slaughterhouse, the water supply is timer controlled to supply water for two minutes each half hour.

Applicability

All pig slaughterhouses.

Driving force for implementation

Less money spent on water.

Example plants

At least one pig slaughterhouse in Italy.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.2.1.6 Dry cleaning of the lairage floor and periodically cleaning it with water

Description

Cleaning of the lairage can be done by collecting manure and bedding materials, before rinsing with water. In cases where the drains are connected to a urine/slurry container, they can be transferred to the sewerage system before rinsing starts to prevent overloading of the container. Cleaning with dry scraping, using a squeegee and a shovel is normally sufficient, although it should be followed by high-pressure rinsing at least once a week.

Achieved environmental benefits

Reduced water consumption.

Cross-media effects

Infrequent wet cleaning can increase odour emissions.

Operational data

Based on Norwegian experiences in a cattle slaughterhouse, it is reported that dry scraping in a lairage where animals are kept overnight, can reduce the discharge by 700 – 800 g BOD and 7 - 8 g total P per animal (2.7 - 3.0 kg BOD/t and 26.6 - 30.4 g P/t).

In practice it can be difficult to ensure the required room/access to achieve this.

Applicability

Applied in at least one Norwegian cattle slaughterhouse.

Economics

Inexpensive

Driving force for implementation

Reduced water consumption and waste water contamination.

Reference literature

[134, Nordic States, 2001]

4.2.2.2 Bleeding

See also Section 4.2.1.

4.2.2.2.1 Optimisation of bleeding and blood collection

See also Section 4.2.1.6.

Description

The bleeding operation can be optimised to ensure that the maximum quantity of blood is collected and contained at the bleed area. This reduces the requirement to manage dripping blood along the length of the slaughter-line.

For large animals, the use of hollow knives gives a lower yield of blood collection than the more traditional method of cutting the animal's throat to initiate bleeding, which is then assisted by the animal's heartbeat and by gravity. For pigs, the blood yield has been reported to be 75 - 80 %. In most cases the time for bleeding using a hollow knife is limited to 20 - 40 seconds, because of the speed of operation of the slaughter-line and because this is reported to be the time needed to collect the highest quality blood by this method. In practice, the bleeding time with the hollow knife can be extended, to maximise the hygienic collection of blood. The animals can subsequently be hung over a blood collection trough until the amount of blood dripping from the carcase is insignificant. The second "bleed" contains clots, so it is not food/pharmaceutical grade blood and it may be sent for, e.g. rendering, biogas production or

composting. The use of the hollow knife method for the hygienic collection of blood from cattle has ceased in some countries, e.g. Denmark, because blood from ruminants is not used for human consumption, or animal feed, although it is still used in some other countries for human food and pet food.

Where the traditional method of bleeding is used, the time allowed for this may be calculated to optimise the blood collection. It has been reported that for cattle the optimum bleeding time is about 7 minutes and for pigs is 5 – 6 minutes.

It is reported that bleeding carousels can be supplied with bleeding alarms that sound if not enough blood has been drained out of the animal before it leaves the bleeding area. Bleeding carousels for hollow knife bleeding can be operated by one operator for up to 360 – 380 pigs/h, or 120 – 130 cattle/h. At higher capacities, 2 operators are required. It is also reported that during traditional bleeding, the knife disinfection required between each animal is often omitted by the operator, but that this is less likely when a bleeding carousel is used.

The hollow knife method is not relevant to poultry. The blood is not collected for food, feed or pharmaceutical use, although it can be fed to fur animals, otherwise it has to be disposed of. Nevertheless optimisation of the collection minimises the amount which ends up in the WWTP. It is reported that 90 seconds is normally sufficient time and that the blood is stored in chilled vessels to prevent odour problems.

Discussion can take place between blood plants and slaughterhouses regarding optimising blood collection for subsequent blood processing. Blood processors may stipulate that hollow knives and small drip trays are used to collect blood. Blood for rendering is usually collected in large trays or on the bleed hall floor, from where it drains away to collection tanks. Slaughterhouses sell blood to blood processing companies and renderers charge for its collection. The cost depends on the disposal method. In the UK, collection for rendering can cost twice as much as for land injection, which was practised, but is now banned by ABP Regulation 1774/2002/EC. In Italy, it costs approximately EUR 75 for the collection of one tonne of blood. The bleeding area can have drip troughs fitted above floor level, to minimise contamination. The troughs can have falls to facilitate wet suction and/or scraping of blood or coagulated blood lumps to the blood tank prior to cleaning. Some installations carry out both blood processing and rendering on the same site and the transport of blood for both activities may be easily facilitated. With the agreement of the company receiving the blood, the water from the initial washing can be collected in the blood tank.

The extension of blood collection times does not necessarily have to slow down production. A sufficient number of hollow knives can be provided in the carousel to ensure that there is enough time for the bleeding process, without a queue developing before bleeding or waiting time after bleeding. Likewise, for bleeding by the traditional cut to the throat, collection can be extended by a number of means. The bleeding trough can be extended in the bleed hall and a stainless steel collection trough/slide, which drains to the blood tank, can be installed which extends from the blood collection area all the way to the scalding tank or de-hiding area. In short bleed halls both the overhead rail, from which the carcasses are suspended and the bleeding trough can be designed to follow a circuitous route, which allows enough time for bleeding. The “circuitous route” option reportedly works well for sheep. The trough/slide can be movable, or detachable, as necessary.

Extending the blood collection facilities reduces the importance of training slaughtermen in methods to minimise drip loss along the line, e.g. not to manually shunt pigs towards the scalding tank prematurely.

Achieved environmental benefits

A higher proportion of blood is used in processes downstream of the slaughter and so consequently less ends up in the waste water, for treatment in either the on-site WWTP or the municipal WWTP. Blood contamination of water leads to elevated BOD, COD and nitrogen

levels. If blood is allowed to drip along the length of the slaughter-line, it will drain into the WWTP, as well as potentially adding to the cleaning water consumption requirements for the plant and equipment.

In addition, the collection of blood with minimal water uptake increases the yield of usable blood and reduces the energy consumption, for treatments where the blood is dried. Otherwise energy has to be expended to handle and remove the water.

Cross-media effects

Blood processing causes less contamination of waste water than blood rendering, but the energy consumption for processing is at least twice as high as that for rendering blood.

Operational data

The following blood yields have been quoted following the use of traditional bleeding methods. For cattle, 16 litres of blood can be collected in 1 minute, from a total of 18 l. In this case the kill speed is quite low and in 2 minutes practically all the blood could be collected, using a long tray. For pigs, 3.2 litres of blood can be collected in the first 40 seconds immediately after the slaughtering and 3.5 litres in 1 minute, of a total of potentially 3.8 litres.

A small slaughterhouse reportedly implemented several improvements, including increasing the bleeding time for cattle to 7 minutes; it collected and separated the blood for composting instead of dumping it in the local river; controlled inventories; reduced salt consumption and established a training programme. After less than one month, the company had reduced its water consumption by 15 %, the pollutant load in the waste water by 34 % and the consumption of salt by 60 %.

Applicability

The collection and separation of blood, instead of discharging it either to a river or to a WWTP, is applicable to all slaughterhouses. Some slaughterhouses discharge blood to their local WWTP or collect it in a tank and then send it by tanker to a WWTP which is designed to treat it.

The provision of an extended stainless steel collection trough/slide, is applicable in all slaughterhouses.

Economics

The payback time for the increased bleeding time, for composting the separated blood, controlling the inventories, reducing the salt consumption and establishing a training programme was less than one month.

The cost of the trough/slide is about EUR 300 per metre.

Driving force for implementation

The driving force for the increased bleeding time was the reduction of water consumption and high organic load in its waste water.

The driving force for provision of an extended stainless steel collection trough/slide was a reduction in waste water treatment cost.

Example plants

Extended stainless steel collection trough/slides are used in a small poultry slaughterhouse and a small pig slaughterhouse in Denmark.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001, 220, APC Europe, 2001, 248, Sorlini G., 2002, 260, EAPA, 2002, 262, United Nations Environment Programme, 2002, 271, Casanellas J., 2002, 283, Brindle J., 2002, 284, Leoni C., 2002, 308, Hupkes H., 2002]

4.2.2.2 Use of a squeegee for initial cleaning of the blood collection trough

Description

A squeegee with an offset handle can be used to remove blood from the blood trough into the blood collection vessel without using initial washdown water.

Achieved environmental benefits

Reduced consumption of water for cleaning and reduced COD and BOD levels in the waste water. Increased potential for waste minimisation. Increased potential for recovery or recycling of blood. The water previously used in the initial wash down no longer had to be handled and heated in the blood recovery process.

Cross-media effects

None.

Operational data

The system was reportedly introduced in an example pig slaughterhouse, to replace the practice of using 6 sprays along and above the bleed trough to wash some blood from the trough into the blood collection vessel. This reportedly removed 50 - 60 % of blood in the trough, but resulted in some water going to the blood collection vessel and the remainder of the blood going to the WWTP. The use of the squeegee reportedly enables 80 – 90 % of the blood on the trough to be recovered. For the example slaughterhouse, this resulted in the recovery of an additional 11.3 kg/d of blood, representing 2.3 kg BOD, which had previously been directed to the WWTP. The additional labour required was considered to be insignificant.

Applicability

Applicable in all slaughterhouses.

Driving force for implementation

Reduction of water consumption, waste water production and waste water contamination.

Example plants

At least one pig slaughterhouse in the US.

Reference literature

[268, Ockerman H. W. and Hansen C. L., 2000]

4.2.2.3 Pig scalding

4.2.2.3.1 Condensation/steam scalding of pigs (vertical scalding)

Description

Scalding with steam is an alternative to scalding in hot water. This procedure operates using moist air heated to approximately 60 - 62 °C. The pig carcasses are conveyed through a tunnel. The moist air is extracted in the upper part of a tunnel by ventilators and circulated in exterior channels, where it is moistened and heated by steam. Ventilators then blow the hot moist air back into the lower section of the scalding tunnel. Air deflection plates guide the air over the carcasses, where some of it condenses and produces the scalding effect. The technique is illustrated in Figure 4.8.




Figure 4.8: Outline of a condensation scalding tunnel
[163, German TWG Members, 2001]

Achieved environmental benefits

Reduced water and energy consumption. The lungs can be used.

Cross-media effects

The carcasses will have to be washed prior to scalding. If there is any dirt on the skin, this will prevent the steam from contacting the skin and will result in poor scalding of the dirty part.

Operational data

This process can be maintained at a constant temperature and 100 % humidity under varying loads, which is crucial for a good scalding performance.

The producers' information about consumption values of different scalding methods is listed in Table 4.30.

	Circulation method	Condensation/steam scalding method
Energy demand (Revolving pumps/ventilators)	4 x 7.5 kW x 8h/d = 240 kWh/d 240 kWh/d x 200 d/yr = 48000 kWh/yr	4 x 5.5 kW x 8 h/d = 176 kWh/d 176 kWh/d x 200 d/yr = 35200 kWh/yr
Heating demand (1 kWh = 3.6 MJ) (fuel oil: 1 kg = 1.2 l)	3270 kWh/d x 200 d/yr = 654000 kWh/yr 654000 kWh/yr x 3.6 MJ/kWh = 2354400 MJ/yr 2354400 MJ/yr / 40 MJ/kg = 58860 kg/yr 58860 kg/yr x 1.2 l/kg = 70632 l/yr fuel oil	2020 kWh/d x 200 d/yr = 404000 kWh/yr 404000 kWh/yr x 3.6 MJ/kWh = 1454400 MJ/yr 1454400 MJ/yr / 40 MJ/kg = 36360 kg/yr 36360 kg/yr x 1.2 l/kg = 43632 l/yr fuel oil
Water demand	14000 l/d + 5 l/pig x 2400 pigs/d = 26000 l/d 26000 l/d x 200 d/yr = 5200000 l/yr	0.7 l/pig x 2400 pigs/d = 1680 l/d 1680 l/d x 200 d/yr = 336000 l/yr

Table 4.30: Comparison of consumption data of different scalding methods (producers' information)
[163, German TWG Members, 2001]

Operational consumption levels for “water circulation spray scalding” and “condensation/steam scalding” are shown in Table 4.31 for plants with a capacity of 350 pigs per hour or 600000 pigs per year.

	Water circulation spray scalding	Condensation/steam scalding
Energy demand	4 pumps x 5 kW x 8h x 255 days = 40800 kWh/yr	4 ventilators x 4 kW x 8h x 255 days = 32640 kWh/yr (0.0544 kWh/pig)
Heat consumption	To heat the water-bath	
	1450 kWh x 255 days = 369750 kWh	Not applicable
	To heat the pigs	
	3.116 kWh/pig x 600000 = 1869600 kWh/yr	2.5 kWh/pig x 600000 = 1500000 kWh/yr
Water demand	Daily water-bath	
	25 m ³ x 255 days = 6375 m ³	Not applicable
	Leaking loss	
	11.625 l/pig x 600000 = 6975 m ³	1 l/pig x 600000 = 600 m ³

Table 4.31: Comparison of actual consumption data of “water circulation spray scalding” and “condensation scalding”
[163, German TWG Members, 2001]

Unpublished results from tests of steam scalding indicate that the water consumption can be reduced to 3 - 5 litres per pig (40 - 65 l/t pig carcase) and the energy consumption to approximately 0.4 kWh per pig (5.2 kWh/t pig carcase), for a slaughterhouse of unspecified throughput. These energy consumption levels are lower than those shown in Table 4.31, whereas the water consumption levels are higher, nevertheless they are both lower than the levels shown for water circulation spray scalding, also in Table 4.31. Table 4.32 reports that both methods consume less water than using a scalding tank.

	Scalding tank	Water circulation spray scalding	Condensation/steam scalding
Water consumption	8440000 l/yr	5200000 l/yr	336000 l/yr

Table 4.32: Comparison of water consumption data for different scalding methods (producers' information)

Applicability

It has been reported that measurements of hair and toenail loosening have shown that the scalding quality of the condensation/steam condensation system is comparable to that of a traditional scalding tank. Furthermore, condensation/steam has a number of advantages over a traditional scalding tank, i.e. hygiene, no water gets in the lungs or the sticking wound; it has a short start-up time and a reduced risk of over-scalding during stops on the slaughter-line.

The replacement of an existing scalding tank system with a condensation/steam system is not considered to be profitable, based on the water and energy savings alone. The method is, however, considered to be applicable in connection with large alterations, extensions or new buildings.

Economics

Expensive.

Driving force for implementation

Reduction of water and energy costs.

Example plants

At least one pig slaughterhouse in Germany.

Reference literature

[12, WS Atkins-EA, 2000, 134, Nordic States, 2001, 163, German TWG Members, 2001, 183, Pontoppidan O., 2001, 237, Italy, 2002, 243, Clitravi - DMRI, 2002]

4.2.2.3.2 Insulation and covering of pig scalding tanks

See also Section 4.2.3.3.2.

Description

The scalding tank can be insulated to reduce the heat loss through the sides and covered to reduce evaporation and heat loss from the water surface. The surface may be covered with plastic balls.

Achieved environmental benefits

Energy savings are associated with preventing radiated heat losses and the loss of hot water. There is also a reduced water consumption.

In addition, less ventilation will be required, so less energy will be consumed.

The reduced evaporation will also result in less odour.

Cross-media effects

None.

Operational data

For a scalding tank with a capacity to handle 210 pigs per hour, with the dimensions of: length approximately 43 meters, area of sides and bottom about 100 m² and surface area 22 m², the following data has been reported: heat loss of about 370000 kJ (103 kWh) per hour, of

which 53 % is lost through the sides and bottom and 47 %, from the surface. The heat loss can be reduced from 1.73 to 1.35 kWh per pig (from 22.5 kWh/t to 17.2 kWh/t of pig carcase) by applying insulation and covering of the scalding tank.

Applicability

Applicable in all new pig slaughterhouses. A cover can be installed on existing tanks and they can be insulated.

Economics

Insulation of a scalding tank used for about 360 pigs per hour costs EUR 55000. There are conflicting reports about the applicability in existing slaughterhouses. One view is that the payback time for the insulation of tanks is 1 to 3 years. Another view states that existing scalding tanks can be insulated, but the cost will normally only be recouped in connection with the replacement or alteration of the system.

Driving force for implementation

Reduced energy costs.

Reference literature

[57, DoE, 1993, 134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.2.3.3 Water level control on pig scalding tanks

Description

The spare distance from the water level to the top of the tank and to the overflow pipe can be sufficient to avoid overflow due to water displacement when the tank is filled with carcasses.

Achieved environmental benefits

Energy and water saving, by preventing the loss and need for replacement of water heated to approximately 60 °C.

Cross-media effects

None.

Operational data

The control of the water level can be achieved through the fitting of an automatic level control, or by the operator filling the tank to a marked upper limit, in a tank that is sufficiently deep to contain sufficient water and the pig carcasses. Automation of the level control, if properly maintained, will remove the responsibility from the operator.

According to a Danish example, correct control of the water level can save approximately 5 m³/d.

Applicability

Applicable at all pig slaughterhouses.

Economics

The capital cost is low and the payback is almost immediate.

Driving force for implementation

Reduced spending on water.

Example plants

At least one pig slaughterhouse in Denmark.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.2.4 Pig hair and toenail removal

4.2.2.4.1 Recirculation of water within pig de-hairing machines

Description

The water used in pig de-hairing machines can be recirculated, after it has been reheated by steam injection to the temperature required for de-hairing. The water is collected in a tank, in which steam is injected to raise the temperature to that required. For food hygiene reasons the whole system is enclosed and the water collection and recirculation is carried out under hygienic conditions. The system is discharged, cleaned and disinfected at least once a day.

Achieved environmental benefits

Reduced water consumption and energy use.

Cross-media effects

None reported.

Operational data

Water which is entrained with the pigs as they leave the system is replaced with fresh water. This has been reported to occur at a rate of 0.7 – 1 m³/h for a slaughterline producing carcasses at a rate of 55 – 60 t/h. Most of the water is heated from 50 – 55 °C to a de-hairing temperature of 55 – 60 °C. In the past the water was heated to 80 – 90 °C.

The operation is shown in Figure 4.9.




Figure 4.9: Recirculation of water for de-hairing pigs

The use of cold water at temperatures less than 10 °C has been reported. The water has to be cooled, otherwise the temperature rises to 30 – 35 °C, due to the heat from the freshly slaughtered carcasses. Less energy is required to chill the carcasses later in the process and the risk of bacterial contamination is less in the colder water.

Applicability

Applicable in all pig slaughterhouses.

Economics

The costs of additional water are saved by recirculating the water. In the case where water was previously heated to 80 – 90 °C, the money which was required to both supply and heat that water is saved.

Driving force for implementation

Reduced water and energy costs.

Example plants

At least one pig slaughterhouse in Italy.

Reference literature

[269, Italian TWG Members, 2002, 347, German TWG members, 2003]

4.2.2.4.2 Replace irrigation pipes at the top of de-hairing machines, with nozzles

Description

The irrigation pipes at the top of the de-hairer can be replaced with flat jet nozzles, which direct the flow of water at the pigs. At the same time, the spray to transport the hair away, can be moved to just under the pig, because the water in this area will no longer be sufficient by itself, for removing the hair. The water can be controlled so that it is only running when there is a pig in the machine. It is unnecessary to add water to the gambrelling table.

Achieved environmental benefits

Reduced water consumption.

Cross-media effects

None.

Operational data

The water use can be reduced from 16 litres per pig to 6 litres per pig (208 l/t carcass to 78 l/t carcass).

Applicability

Applicable in all pig slaughterhouses.

Economics

Payback is almost immediate.

Driving force for implementation

Reduced water costs.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.2.5 Pig singeing

4.2.2.5.1 Re-use of cooling water from the singeing kiln

Description

Cooling water can be collected from the singeing kiln and distributed to, e.g. the scalding tank, if used, or the scraping and polishing section. Additionally, instead of irrigation pipes, nozzles can be fitted and directed to the pigs. A schematic diagram of the system is shown in Figure 4.10. The water can also be used for cleaning.




Figure 4.10: The Grinsted system re-using cooling water from a singeing kiln
[134, Nordic States, 2001]

Achieved environmental benefits

Reduced water consumption, by 780 l/t of carcase.

Cross-media effects

None.

Operational data

The system can reduce the water consumption from more than 100 litres per pig to 20 - 30 litres per pig (from more than 1300 l/t to 260 - 390 l/t pig carcase).

Applicability

All slaughterhouses which currently use a particular very thorough surface treatment, which is considered to be necessary for carcasses to be used for bacon curing.

Economics

The capital cost for a Danish slaughterhouse has been calculated to be approximately DKK 210000, giving a repayment period of less than 6 months.

Driving force for implementation

Reduced water costs.

Example plants

The system is used at all of the larger Danish pig slaughterhouses.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.2.5.2 Heat recovery from pig singeing exhaust gases, to preheat water

Description

In pig slaughterhouses, the heat of the exhaust of the singeing unit can be recovered to heat water, e.g. to maintain the scalding tank temperature.

Achieved environmental benefits

Reduced energy use to heat water for, e.g. scalding or cleaning and reduced odour, by stopping the direct emission of hot singeing gases.

Cross-media effects

None reported.

Operational data

Temperatures in the singeing unit can be as high as 900 - 1000 °C and if heat is not recovered gases can be emitted at 600 - 800 °C. A heat recovery system, such as that shown in Figure 4.11, can be used to heat the water. In the case study shown in Figure 4.11, water is heated to 70 °C and is then used to clean the slaughterhouse.

After singeing, the exhaust contains approximately 58 % of the energy used to heat it. By installing a heat recuperation unit, 40 - 45 % of the applied energy can be recovered.




Figure 4.11: Heat recovery from pig singeing gases

Applicability

Applicable in all pig slaughterhouses.

Economics

Two differing reports state that, based on Danish conditions, the payback time is either approximately 6 months or 3 - 4 years. A payback time of 1 to 3 years is reported from the UK.

Driving force for implementation

Reduced energy costs.

Example plants

The technique is used in Finnish slaughterhouses and in at least one Italian pig slaughterhouse.

Reference literature

[57, DoE, 1993, 134, Nordic States, 2001, 148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001, 183, Pontoppidan O., 2001, 280, Savini F., 2002]

4.2.2.5.3 Post singeing showering with flat jet nozzlesDescription

Showering can be done with flat jet nozzles instead of shower heads. The water supply can be arranged so that water only flows when a carcass is present.

Achieved environmental benefits

Reduction in water consumption, of 65 l/t carcass.

Cross-media effects

None.

Operational data

The water consumption can be reduced from 3000 - 4000 l/h to approximately 400 l/h, depending on the throughput of carcasses per hour.

Applicability

Applicable in all pig slaughterhouses.

Driving force for implementation

Reduced water consumption.

Reference literature

[134, Nordic States, 2001]

4.2.2.6 Rind treatment**4.2.2.6.1 Replace irrigation pipes with flat jet nozzles**Description

All irrigation pipes can be replaced with flat jet nozzles, which have considerably lower water consumption. Nozzles with diameters below 2 mm block frequently. In some installations it may be necessary to install a pressuriser to increase the water pressure.

Achieved environmental benefits

Reduced water consumption.

Cross-media effects

None.

Operational data

The water consumption for rind treatment has been reduced from approximately 100 litres per pig to 20 - 25 litres per pig (from 1300 l/t to 260 - 325 l/t carcass) as a result of this and other techniques.

Applicability

Applicable in all slaughterhouses with rind treatment lines.

Economics

The estimated cost for nozzles is about EUR 500. The payback time is very short.

Driving force for implementation

Reduced water costs.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.2.7 Evisceration

See also techniques for fat separation from water after evisceration in Section 4.2.2.9.

4.2.2.7.1 Saw sterilisation in a cabinet with automated hot water nozzles

Description

Chest opening saws can be sterilised in a cabinet with nozzles supplying water at 82 °C, instead of in running water in a vat at the same temperature. The water supply can be turned on and off, as required.

Achieved environmental benefits

Reduced water consumption, by 130 - 195 l/t carcase.

Cross-media effects

None.

Applicability

Applicable in all large animal slaughterhouses.

Driving force for implementation

Reduced water consumption and consequent energy use.

Reference literature

[134, Nordic States, 2001]

4.2.2.7.2 Regulation and minimisation of water use for moving intestines

Description

Water may be supplied to slides, intestine conveyors and intestine elevators, only when required. The required water quantity can be determined and the setting can then be locked.

Achieved environmental benefits

Reduced water consumption and reduced water entrainment of high BOD material, especially intestine contents.

The intestines can be used for sausage casings or pet food.

Cross-media effects

None.

Applicability

Applicable in all slaughterhouses.

Economics

Reduced water consumption, therefore, lower expenditure for water and waste water treatment.

Driving force for implementation

Reduced water consumption.

Reference literature

[134, Nordic States, 2001]

4.2.2.8 Chilling**4.2.2.8.1 Blast-chilling/shock-cooling tunnel - for chilling pigs**Description

Blast-chilling uses the fact that an increase of the boundary layer air velocity at the carcass surface leads to an increase in the heat transfer coefficient. This increases the extraction of heat from the carcass. This, combined with a low air temperature, causes the surface temperature to drop. The blast-chilling process is built into a tunnel with a conveyor, evaporators and fans. The air velocity is high, i.e. 3 – 4 m/s.

Cross-media effects

The low chilling temperature, increases the energy consumption of the compressor operation and also the capacity required.

Operational data

The advantage of using blast-chilling is the low shrinkage and the small tunnel dimensions. Low process temperatures cause surface freezing, which kills all non-cold tolerant bacteria and improves food safety. The black bone problem, which is a discolouration of the backbone due to incorrect chilling, can be caused by surface freezing. This can be eliminated by a short tempering zone at the end of the chilling process, which will cause the surface temperature to rise to the equalisation room temperature.

The temperatures in the shock-cooling tunnel lie between -15 °C and -20 °C. The contact time in the shock-cooling tunnel is 60 - 90 minutes. After leaving the shock-cooling tunnel, the carcasses are subjected to secondary cooling in an equalisation cooling room until they have a core temperature of +7 °C.

Operational data for blast-chilling/shock-cooling and mist-cooling are compared in Table 4.33.

	Blast-chilling/shock-cooling	Water spraying/mist-cooling
Weight loss after 24 hours	1.3 - 1.7 %	0.4 – 1.0 %
Temperature in the core of the ham after 18 hours	5.4 °C	5.8 °C
Surface freezing	On the entire surface	NONE
Bursting of small blood vessels	Often in the bones and in the fat	NONE
Bacteriological quality	Reduction by 2 log units	Increase by 2 log units
Air temperature in the cooling tunnel	-25 to - 8°C	+5 to –5°C
Energy consumption	16.3 – 21.7 kWh/t carcass	6.5 – 13.0 kWh/t carcass
Water consumption	0 l/t carcass	Unknown
Maintenance and repair requirements	High	Very low
Cleaning frequency	2 - 4 times each month	Daily
Wall insulation	Thickness 160 mm	Thickness 80 mm
Space requirements (ratio)	1	2

Table 4.33: Consumption data for shock-cooling and mist-cooling
[163, German TWG Members, 2001, 342, Pontoppidan O., 2003]

For a slaughterhouse killing approximately 300 pigs/h, the installed cooling capacity of the shock-cooling tunnel is about 1000 kW. The temperature of the ammonia refrigerant is -35 °C.

Applicability

It is reported that this technique cannot be applied in Italy, when carcasses are destined for the production of typical Italian cured products and are cut beyond the standard cuts, before chilling.

Reference literature

[163, German TWG Members, 2001, 237, Italy, 2002]

4.2.2.8.2 Water-spraying/mist-cooling as a method of cooling pigs

Description

The entire surface of the split carcass is sprayed with water at the same time as it is swept over by air at moderate velocity and temperature. The cooling effect is achieved by evaporation of the spray-water on the surface of the carcass. Fine droplets with a size of 10 - 100 µm are evaporated by the warmth of the carcasses. When these droplets evaporate, the carcass surfaces remain very moist and this prevents the meat from parching. As soon as the droplets are evaporated, the spraying is repeated until the desired cooling has been achieved. For this cyclical treatment, the pig halves are conveyed through water spraying cabins, which are installed in the cooling tunnel. During a cooling period of 3 hours the pig halves may, e.g. be conveyed through 30 - 35 cabins. In each cabin, the spraying with sterile water lasts only 1 - 3 seconds. As the carcass surface temperature is highest at the beginning of the process, the spraying cabinets are placed close together in the first part of the tunnel. The entire spraying time during a 3 hour cooling period, therefore, adds up to a treatment of 50 - 100 seconds.

Achieved environmental benefits

Consumption data for the shock-cooling technique and the water-spray-cooling technique are compared in Table 4.33, within the shock-cooling technique information in Section 4.2.2.8.1.

Reduction in energy consumption for cooling and ventilation, compared to conventional cooling methods, which require cooler air and a greater airflow.

Cross-media effects

High water consumption.

Operational data

It was anticipated that the weight loss would be 0.9 %, compared to 1.1 % for conventional cooling, and also that the reduction in the weight loss would have an environmental benefit, because the specific cooling energy for each carcass is lower than for conventional cooling. The energy efficiency would, therefore, be higher. However, in a slaughterhouse using this technique the anticipated reduction in weight loss did not occur, but there were energy savings. In a Dutch slaughterhouse each carcass required 1.5 kWh instead of 3.3 kWh.

At a processing volume of 1 million pigs/year, the annual electricity savings amount to 1800 MWh/yr. This is equivalent to 510000 m³ of natural gas, with a heating value of 31.65 MJ/m³, assuming an average power plant efficiency of 40 %.

Two advantages of using water-spray chilling are the low carcass shrinkage and the high process temperature. At high process temperatures it is possible to avoid surface freezing.

Two disadvantages are that the process is very slow and it needs huge tunnel dimensions. If there is water on the carcass surface when it leaves the tunnel, it could cause an increased bacterial growth. Water consumption is high and it must be of drinking water standard.

Purifying water with a chloride compound is not allowed in many countries. The wet surface increases the black bone problem.

Operational data for blast-chilling/shock-cooling and water-spraying/mist-cooling are compared in Table 4.33, in Section 4.2.2.8.1.

Applicability

Applicable in all large animal slaughterhouses, although it may be difficult to retrofit the system in an existing slaughterhouse due to the large space requirements. It is reported that this technique cannot be applied in Italy, when carcasses are destined for the production of typical Italian cured products and are cut beyond the standard cuts, before chilling.

Economics

In the case study reported, the overall investment for the new tunnel amounted to NLG 1.8 million (1996). At an electricity price of NLG 0.142/kWh, the annual savings are NLG 256000, which yields a payback period of about 7 years. (If the expected reduced cooling losses had taken place, this would have saved an additional NLG 452000 and the payback period would have been 2.5 years.)

Example plants

The technique is reportedly used in several French slaughterhouses, at least one slaughterhouse in the Netherlands and at least one slaughterhouse in Germany.

Reference literature

[53, IEA OECD, 1996, 163, German TWG Members, 2001, 237, Italy, 2002]

4.2.2.8.3 NOT showering carcasses before they are chilled in a chilling tunnel

Description

The need for carcasses to be showered prior to entering a chilling tunnel should be examined as not all slaughterhouses do it. Generally, following scalding, pig carcasses don't require further cleaning, although they are cooled with water after singeing.

Achieved environmental benefits

Reduced water consumption.

Cross-media effects

None.

Operational data

If the carcasses need to be washed before chilling, it can be done with nozzles, rinsing the required areas only, i.e. the belly at the first skin incision, parts of the front legs and the neck. The water supply can be controlled to ensure that water flows, only when the carcasses are in the correct position in relation to the nozzles, or it can be controlled by handheld trigger-operated nozzles.

The washing of carcasses should not take place before they have been through the routine official veterinary inspection, because visible contamination may be washed away and make microbiological contamination difficult or impossible to detect.

Applicability

Applicable in all slaughterhouses. It is reported that this technique cannot be applied in Italy, when the carcasses are destined for the production of typical Italian cured products are cut prior to chilling.

Reference literature

[134, Nordic States, 2001, 237, Italy, 2002]

4.2.2.9 Associated downstream activities - viscera and hide and skin treatments

See also techniques for fat separation from the water, after evisceration in Section 4.2.2.7.

4.2.2.9.1 Removal of chopping blades from a by-product washer

Description

The blades may be removed from an animal by-product washer so that the manure is collected with the intestines, etc. and, e.g. sent for rendering.

Achieved environmental benefits

It allows the further recovery and recycling of substances. It also permits a substantial reduction in BOD, suspended solids, and other pollutants going to the WWTP. Reduced energy use for running the chopping blades and the WWTP.

Cross-media effects

These depend on the use or disposal route for the by-products. Additional pollution is associated with transport of the solids to the animal by-products installation.

Operational data

At a pig slaughterhouse, the by-product washer drain was the largest contributor of pollution load from the kill floor. Intestines and large quantities of other solid materials were washed into the by-product washer from various parts of the kill floor. Blades slashed the intestines, to enable the water to wash away the intestinal contents. The objective was to send the fat and meat solids for inedible rendering and the waste water to the WWTP. The separation of solids and liquid was inefficient, so large quantities of solids ended up in the WWTP, causing an extremely high load in terms of, e.g. BOD solids, grease, and other pollutants.

After the chopping blades were removed from the by-product washer, the unit functioned only as a dewatering device. The large and small intestines and their contents remained intact and were sent to inedible rendering. This increased the quantity of meat scrap and material for rendering by an average of 3856 kg/d.

Table 4.34 and Table 4.35 show pollution and cost savings as a result of the removal of the washer blades.

	Pollution load (parts per thousand per week, by weight)		Net reduction (parts per thousand per week, by weight)	Total for plant (kg/day)
	Before change	After change		
Flow	No change	No change	-	-
BOD	2.70	0.6498	2.050	1337
SS	2.35	0.324	2.020	1318
Grease	2.83	0.255	2.625	1712
TKN	0.23	0.134	0.096	63
COD	6.80	1.581	5.219	3404

Table 4.34: Reduction in production shift waste water contamination, due to removal of the washer blades

	Pollution reduction	Saving (USD–2000)
Flow savings	None	None
BOD savings	334110 kg/yr	23518
SS savings	329540 kg/yr	19179
Total annual savings		42697
Cost of modification		275
Based on 250 d/yr; USD 1.48/m ³ ; USD 0.07/kg BOD; USD 0.06/kg SS - costs in 2000		

Table 4.35: Annual cost savings associated with removal of the washer blades

Applicability

Applicable in all slaughterhouses.

Economics

In the US, the value to the slaughterhouse for additional material going to rendering was USD 488.75/d. This accounted for additional income, because in spite of it being of lower quality the additional quantity was worth more. In the EU, if the material was sent for rendering there would be a cost to the slaughterhouse. There would, however, be savings in WWTP operation charges, due to the decreased load. Figures are not available to compare the costs and savings.

Driving force for implementation

Financial savings.

Example plants

A pig slaughterhouse in the US.

Reference literature

[268, Ockerman H. W. and Hansen C. L., 2000]

4.2.2.9.2 Dry emptying of stomachs

Description

The stomachs can be cut open in a machine. The contents fall into the base of the machine, from where they are pumped away for use in, e.g. biogas production or composting. Machines are available which can empty the stomachs without using water, apart from the amount used to clean the knife for cutting the stomachs.

Achieved environmental benefits

Reduced water consumption and consequently a reduced volume and BOD loading of waste water.

The stomachs can be used as human food, e.g. ox tripe, or for pet food.

Cross-media effects

None.

Operational data

Modifying old machines from double rinse to single rinse halves the water consumption.

Applicability

For a Danish slaughterhouse, the capital cost for a new pig stomach emptying machine can be repaid in approximately 5 years. Applicability may, therefore, be limited to new or refurbished casing cleaning departments. Old stomach emptying machines with a double rinse can, however, be altered to single rinse machines, at low cost.

Economics

The cost, including for a new stomach machine is approximately EUR 28000. The cost of modification of an old stomach machine is approximately EUR 16000.

Driving force for implementation

Reduced water consumption and treatment costs.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001, 317, German TWG, 2002]

4.2.2.9.3 “Dry” collection of the contents of small intestines

Description

The content of pigs’ small intestines which are to be used as casings can be collected dry. The first stage in the cleaning involves emptying the intestines by pulling them over a pair of rollers. The content can then be collected in a tray and pumped to a container for manure, stomach content, etc. The edge must be kept wet to avoid damaging the intestines, but a minimum amount of water can be used in order to limit the dilution of the intestinal content. The wetting can be done with nozzles, and the water supply can be stopped when no intestines are present. The content of the small intestines is an easy flowing, slimy mass. It is, therefore, important to ensure that there is no drainage from the collection container.

Achieved environmental benefits

Reduced water consumption and consequently a reduced volume and BOD loading of waste water.

The intestines can be used for sausage casings or pet food.

Cross-media effects

None.

Operational data

The importance of collecting the stomach and intestinal contents dry is illustrated by the high contribution to overall waste water contamination from wet emptied stomach and intestinal contents, as reported in Section 3.1.2.12.

Applicability

Applicable in all pig slaughterhouses.

Economics

In a slaughterhouse slaughtering 400 - 600 pigs per hour, the cost will be approximately EUR 10000 - 15000 for collecting the stomach contents and EUR 20000 for small intestine contents. If only one of the items is installed the cost will be higher.

Driving force for implementation

Reduction of pollution and its costs.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.2.9.4 “Dry” emptying of pig intestines, which are not to be used for casings

Description

Condemned intestines and their contents can be separated prior to rendering. The intestines are cut to enable them to be separated from their contents during centrifugation. In principle, the centrifugation can be done without the use of water, other than that required for cleaning the

centrifuge. Water is, however, often added, to make the content so thin that it can be pumped with a simple pump system, to the manure silo. Selecting a suitable pump type and screw conveyor can eliminate the requirement for adding water.

Achieved environmental benefits

Reduced water consumption and consequently a reduced volume and BOD loading of waste water. The water used is warm so there are also energy savings.

The reduced water content of the condemned intestines also reduces the energy costs associated with driving off the water at the rendering plant.

The manure can be used as fertiliser, after gas production in a biogas plant.

Applicability

Applicable at all slaughterhouses where intestines are emptied.

Economics

For a Danish slaughterhouse, the payback period for the required capital cost is calculated to be approximately one year.

Driving force for implementation

Reduced water use and costs. The separation of the by-products into intestine material and contents enables them to be put to different uses, depending on the current market.

Example plants

Applied in at least one Danish slaughterhouse.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.2.9.5 Use of nozzles instead of showers to flush out large intestines (pigs)

Description

When large intestines are flushed out, showers or nozzles are used to wet the surfaces to ensure that the intestines slide easily and are not damaged. Shower heads can be replaced by nozzles and the water supply can be controlled, so that it is only running when there are intestines present. The water supply can be controlled by a photocell.

Achieved environmental benefits

Reduced water consumption, from 3.8 litres per pig intestine with a shower running continuously to 1.0 litre per pig intestine with a nozzle running only when the pipe is activated.

Applicability

The payback time for replacing shower heads with nozzles has been calculated to be approximately 6 months.

Reference literature

[134, Nordic States, 2001]

4.2.2.9.6 Control of water consumption for small and large intestine washing

Description

The water supply for the small and large intestine lines can be strictly regulated and valves can be equipped with nozzles and automatic stop controls.

Achieved environmental benefits

Reduced water consumption and reduced water contamination.

Cross-media effects

None.

Operational data

Water consumption in a pig slaughterhouse has reportedly been reduced from 70 litres to 40 litres per gut set. On the small intestine line in a Danish pig slaughterhouse, water savings of 844 l/t carcass have been reported.

Example plants

A slaughterhouse in Denmark.

Reference literature

[134, Nordic States, 2001]

4.2.2.9.7 Use of a mechanised fat trap for removing fat from water

Description

The warm outlet from the cleaning of small intestines and the water from centrifuges contain high levels of fat and protein and can be pre-cleaned in an automatic fat removal unit, prior to discharge. Allowing the temperature to fall first and then adding flocculants maximises the fat and protein separation. Passing the fat through a sieve cleaned with cold pressurised water also prevents the fat from dissolving and makes its collection easier.

A mechanised fat trap is normally constructed as a rectangular or circular stainless steel tank. The water is retained in the tank until the fat is separated onto the surface, where a mechanical scraper system transfers it to a storage container.

Achieved environmental benefits

Reduction of BOD and N in waste water.

The fat can be used for rendering.

Cross-media effects

None.

Operational data

Figures of 80 % fat retention and collection of about 360 g of fat per pig (4675 g/t of carcass) have been reported.

Applicability

Applicable in most slaughterhouses, since the fat trap does not require a lot of space.

Economics

A fat trap costs approximately EUR 35000 - 40000.

Driving force for implementation

Reduction of pollution and cost of waste water treatment and/or discharge.

Example plants

Several German rendering plants.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001, 244, Germany, 2002]

4.2.2.9.8 Collection of the mucosa from small intestines (pigs)Description

Mucosa is the mucous membrane of the small intestine. It is removed during the cleaning process. It has a very high BOD and can be collected without being mixed into the waste water. Mucosa can be pressed out and then collected, by pumping it to a tank. The material is pulpy, so it is essential that the pump is reliable, to prevent blockages from occurring.

Achieved environmental benefits

Reduction of organic matter (BOD) in the waste water.

Mucosa can be used by the pharmaceutical industry, for manufacturing heparin or it can be rendered or used in biogas installations.

Cross-media effects

None.

Operational data

Approximately 1.8 kg of mucosa can be collected per pig (23 kg/t of carcase).

Economics

The cost for a pump and control system for pumping the material to the manure tank is approximately EUR 12000 - 16000.

If the material is to be used for the manufacture of heparin, it will be necessary to install a tank and equipment for preservation. The total cost will be then be about EUR 40000.

Driving force for implementation

Reduction of organic pollution of waste water and the costs of treating or discharging it.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.2.9.9 Minimise water usage during rinsing of tongues and heartsDescription

The rinsing of tongues, sweetbread and neck meat is sometimes done to remove blood splashes. Tongues can be rinsed without using running water. A timer control can be fitted to the water supply, to ensure that water is used in the required time only, or with intervals. Tongues can also be hung on a Christmas tree (multiple hook) or placed in a trolley with perforations and then rinsed lightly before being stored in a chill room. The rinsing of hearts can be done with a handheld shower head after hanging them on a rack. It can be limited to only rinsing away possible blood drips.

Achieved environmental benefits

Reduced water consumption and contamination. Drums for washing tongues and other by-products have a very high water use. Up to 50 litres per head (192 l/t cattle carcase) have been measured.

The tongues and hearts can be used for human food or for pet food.

Cross-media effects

None.

Applicability

Applicable in all cattle slaughterhouses.

Driving force for implementation

Reduced water consumption and reduced waste water volume.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

4.2.2.9.10 Trimming of all hide/skin material not destined for tanning immediately after removal from the animal

Description

Trimming consists of cutting away from the edges of hides and skins, all unwanted material such as legs, tails, face, udders, testicles, etc. to give the raw material a better shape.

This operation is performed manually, using the appropriate knives, ideally carrying it out as early as possible in the production process of hides and skins, to prevent material which is not intended for tanning from being processed unnecessarily. The operation is usually done in the slaughterhouse, although it is sometimes carried out in tanneries. Special knives can be used, depending on the appropriate standard for each type of hide or skin.

Achieved environmental benefits

The trimming of hides directly after hide removal optimises the alternative uses for trimmings, e.g. in pet food, gelatine or cosmetic production, thereby reducing waste production, both at the slaughterhouse and at the tannery. It also removes contaminants which could otherwise lead to the putrefaction of hides and skins.

It also minimises the consumption of substances used in the preservation processes, at both the slaughterhouse and the tannery. For example, at the slaughterhouse, if salt is used to preserve the hide, the amount used will be less. This also reduces the contamination of waste water by salt.

It is reported that trimming to ISO standards can give a 7 – 10 % reduction in the amount of waste produced in the leather industry.

There is a reduction in the amount of water and process chemicals used during tanning operations.

Odour problems are reduced due to the removal of putrescible trimmings.

Cross-media effects

Additional waste may be produced at the slaughterhouse compared to the tannery. This may however have the advantage that it is not contaminated with those substances used for preservation or tanning and may consequently have a lower environmental impact.

Operational data

It is reported that approximately 120 kg/t of trimmings can be recovered from bovine hides at the slaughterhouse and that this can serve as a valuable raw material for other industries or for the production of biogas. Trimmings can be collected in batches, as appropriate, depending on their intended use. There are published standards for trimming hides and skins. Each batch can be monitored and records can be kept. If suppliers and buyers discuss the records regularly, they can plan continuous improvements in the operation of the technique.

It is reported that if fully trimmed hides and skins are delivered to the tannery, total water consumption there can be reduced by about 5 %. Total process chemicals are about 500 kg/t of hides or skins. The reduction in the consumption of substances used in tanning is directly proportional to the weight of the trimmed material. The contamination of waste water is also subsequently reduced.

The technique does not require any special equipment.

It is important that during hide or skin removal and trimming, damage is not caused which will lead to waste aggravated by the mechanical process during tanning.

If the animals are not washed and/or clipped before slaughter the trimming process may expose the operator to a risk of infection from, e.g. *Escherichia coli* 0157.

Applicability

Applicable in all large animal slaughterhouses where hide or skin removal is undertaken.

Economics

It is reported that no capital investment is required and that an average sized slaughterhouse can normally perform the technique without supplementary personnel. Some investment will be required for training.

Trimming may generate income of EUR 0.01/kg, if sold for further processing.

Driving force for implementation

The commercial driving forces are improved earnings from the sale of better shaped hides and skins and better by-product quality. Customer satisfaction is also improved.

The environmental driving forces are the improved waste management. There is a reduced waste of raw materials and consumption of process chemicals and water.

Reference literature

[332, COTANCE, 2003]

4.2.2.9.11 Storage of hides/skins at 10 - 15 °C

Description

Hides and skins may be stored in hygienic conditions at 10 - 15 °C, in the short term, if they are processed within 8 – 12 hours.

Achieved environmental benefits

Compared to alternative preservation techniques, the use of salt and its subsequent contamination of waste water at the slaughterhouse and the tannery, as well as disposal of salt residues are avoided. The energy which would be required for refrigeration and/or ice making is also saved. Although it is not considered within IPPC, the environmental impact of long distance refrigerated transport, possibly with the added weight of ice can also be avoided.

Cross-media effects

It has been reported that more biocides are needed when processing fresh hides and skins. This is because the cooling process takes several hours and bacterial growth may develop in this time.

Operational data

Hides and skins may be cooled by spreading them on a clean marble floor with the flesh side in contact with the cold floor, or by passing them through a tank of cooled water.

The opportunities for using untreated hides and skins stored between 10 – 15 °C are limited by the possibilities of processing them within 8 – 12 hours, which depends on the proximity of tanneries and their demand for hides/skins.

It has been reported that the quality and yield from fresh hides/skins is better than that from those that have been salted.

Applicability

Applicable where hides and skins can be processed within 8 – 12 hours.

Driving force for implementation

There are reduced costs associated with the purchase of salt, careful addition of salt, ice making, refrigeration and transport.

Reference literature

[273, EC, 2001]

4.2.2.9.12 Drum salting of hides and skins

Description

Hides and skins can be taken from the slaughter-line directly to a drum, similar to a concrete mixer, where clean salt that is free from, e.g. blood and rust is added.

Achieved environmental benefits

Water cooling is not required. The quantity of salt used is reduced by 30 - 50 %, compared to a salting table. All of the salt is used, compared to the addition of salt at a salting table which results in significant spillage, much of which inevitably ends up in the waste water. The hide/skin quality is at least as good as before. The need for energy use to chill the hide room is avoided.

Cross-media effects

Salt can reduce the efficiency of the WWTP and unless there is a naturally saline water course for receipt of the treated waste water the salt content can have adverse effects on plant growth.

Operational data

Hide/skin salting with this method can be done without water cooling, thereby saving 5 litres per head (278 l/t carcass). There was no residual salt, saving approximately 0.7 kg per head (0.039 t/t carcass). When salting large animal hides, an amount of salt equivalent to about 35 % of their weight is used. For example, for a hide weighing 28.5 kg, use 10 kg of salt. For sheepskins this ratio depends on whether the animals are sheared before slaughter, if not then an amount of salt equivalent to about 150 % of the skin weight, i.e. excluding the wool, is required.

Applicability

Drum-salting has been implemented at the majority of Norwegian sheep/lamb slaughterhouses. For storage times longer than 8 days, e.g. if hides/skins have to be transported overseas, then salting remains the preferred option, due to the weight of ice and the energy consumption required for ice production and for refrigeration.

Driving force for implementation

Reduction in salinity of waste water treatment and associated problems with the efficiency of the WWTP.

Example plants

The majority of Norwegian sheep/lamb slaughterhouses.

Reference literature

[134, Nordic States, 2001, 216, Metcalf and Eddy, 1991, 273, EC, 2001]

4.2.2.9.13 Drum salting of sheep/lamb skins - with added boric acid

Description

Sheep/lamb skins can be taken from the slaughter-line directly to a drum, similar to a concrete mixer, where clean salt that is free from, e.g. blood and rust is added. The addition of boric acid prevents the growth of halophilic bacteria, known as “red heat”.

Achieved environmental benefits

Water cooling is not required. The quantity of salt used is reduced by 30 - 50 %, compared to a salting table. All of the salt is used, compared to the addition of salt at a salting table which results in significant spillage and where much of the salt inevitably ends up in the waste water. The skin quality is at least as good as before. The need for energy use to chill the hide room is avoided.

Cross-media effects

Salt can reduce the efficiency of the WWTP and unless there is a naturally saline water course for receipt of the treated waste water the salt content can have adverse effects on plant growth. A small amount of boric acid (1 - 2 %) may be added to the salt, although it is argued that if preservation is carried out properly the use of biocides should not be required. Biocides are specifically mentioned in Annex III of the Directive.

Operational data

Skin salting with this method can be done without water cooling, thereby saving 5 litres per head (278 l/t carcase). There was no residual salt, saving approximately 0.7 kg per head (0.039 t/t carcase).

Applicability

Drum-salting has been implemented at the majority of Norwegian sheep/lamb slaughterhouses. For storage times longer than 8 days, e.g. if hides/skins have to be transported overseas, then salting remains the preferred option, due to the weight of ice and the energy consumption required for ice production and for refrigeration.

It has been reported that some tanneries in the UK have been unable to use boric acid because of limits on the amount they are permitted to discharge.

Driving force for implementation

Reduction in salinity of waste water treatment and associated problems with the efficiency of the WWTP.

Reference literature

[134, Nordic States, 2001, 216, Metcalf and Eddy, 1991, 273, EC, 2001, 332, COTANCE, 2003]

4.2.2.9.14 Dry collection of salt residues from hide, skin or fur preservation

Description

Salt residues from hide, skin and fur preservation can be re-used or if they are excessively contaminated they can be collected and disposed of dry. Excessive contaminated salt is disposed of by waste incineration.

Achieved environmental benefits

The quantity of salt used is reduced, so there is less contamination of the waste water.

Operational data

Techniques for the removal or recovery of salt from waste water in slaughterhouses have not been reported. High salinity can disrupt biological WWTPs and even after dilution, it may still

cause corrosion damage. Prevention of waste water contamination appears, therefore, to be not only the preferred option, but actually the only option for controlling the salt content of waste water. It has been reported that techniques such as ion exchange and reverse osmosis are not suitable for salt removal from slaughterhouse waste water, both of which would produce concentrated brine. Brine can be naturally dried, in hot climates.

If dissolved salt is discharged to water courses it can have a significant environmental impact, especially for rivers with a low flowrate and during periods of low water levels. The high conductivity has an effect on the flora and fauna.

Dry collection may be achieved in vessels, such as trays and troughs, positioned beneath salting drums and tables, to collect overspill associated with, e.g. careless loading or spreading of salt. Floor spillages may have to be swept up, due to the corrosive properties of salt and the problems this may cause for a vacuum system.

Applicability

Applicable in all slaughterhouses where hides and/or skins are salted.

Economics

Inexpensive and in any case cheaper than the recovery of a disrupted WWTP. The costs are associated with the labour for handling the salt and payment for its disposal, if it cannot be re-used.

Driving force for implementation

Trouble-free waste water treatment.

Reference literature

[163, German TWG Members, 2001, 273, EC, 2001, 282, Palomino S., 2002, 347, German TWG members, 2003]

4.2.2.9.15 Preservation of hides and skins by refrigeration

Description

Cattle hides are washed and refrigerated at approximately 2 °C.

Achieved environmental benefits

The use of salt is avoided, so potential problems due to the salt at the slaughterhouse and the tannery are prevented. One problem with salt is that it can reduce the efficiency of the waste water treatment plant and unless there is a naturally saline water course for receipt of the treated waste water the salt content can have adverse effects on plant growth.

Cross-media effects

Energy consumption for refrigeration. Washing hides/skins involves the consumption and contamination of water.

Operational data

Washing can lead to contamination and deterioration of the hides/skins.

Applicability

If the time between the de-hiding and the processing in the tannery is no more than 5 – 8 days, after draining the blood, it is possible to cool the hides/skins, to a temperature of 2 °C by refrigeration. The cooling chain must not be interrupted during transport and storage. If hides/skins can be delivered to a tannery and processed within 8 – 12 hours after slaughter then they generally don't require any treatment. They can be preserved satisfactorily by chilling, if they are to be processed within 5 - 8 days. For longer storage times, e.g. if they have to be

transported overseas, then salting remains the preferred option, due to weight of ice and the energy consumption required for ice production and refrigeration.

Economics

The capital investment required for chilling units and cold stores exceeds that for one of the alternatives, i.e. ice making machinery.

It is, however, reported that investment in cooling equipment is not prohibitive and that, e.g. many hide markets and tanneries have invested in cooling systems with good results on quality and total cost.

Example plants

The chilling of cattle hides and sheepskins is undertaken in some slaughterhouses in the UK. Nearly all slaughterhouses in Germany that manufacture leather from cow hides practise preservation by refrigeration. This is because the tanneries are within 300 km of the slaughterhouses, so the costs for refrigerated transport are not excessive.

Reference literature

[244, Germany, 2002, 273, EC, 2001]

4.2.2.9.16 Preservation of hides and skins by cooling with flaked or crushed ice

Description

Cattle hides are washed and then preserved in flaked ice at approximately 2 °C.

Achieved environmental benefits

The use of salt is avoided, so problems due to salt at the slaughterhouse and the tannery are prevented. Salt can reduce the efficiency of the waste water treatment plant and unless there is a naturally saline water course for receipt of the treated waste water the salt content can have adverse effects on plant growth.

Cross-media effects

Energy and water consumption, for ice making. Washing hides/skins involves the consumption and contamination of water.

Operational data

Washing can lead to contamination and deterioration of the hides/skins.

Applicability

If the time between de-hiding and processing in the tannery is no more than 5 – 8 days, after draining the blood, it is possible to cool the hides/skins, to a temperature of 2 °C, using flaked or crushed ice. The cooling chain must not be interrupted during transport and storage. If hides and skins can be delivered to a tannery and processed within 8 – 12 hours after slaughter they generally don't require any treatment. They need to be chilled if they are processed within 5 - 8 days. For longer storage times, e.g. if they have to be transported overseas then salting remains the preferred option, due to the weight of ice and the energy consumption required for its production and for the refrigeration.

Economics

The capital investment required for ice making machinery is less than that required for chilling units and cold stores.

Reference literature

[273, EC, 2001]

4.2.3 Slaughter of poultry

See also Sections 4.1 and 4.2.1.

4.2.3.1 Reception of birds

4.2.3.1.1 Re-use of crate washing water

Description

The system is designed to make the most economical use of water by adding clean water from the final wash to the early stages. Any gross debris are filtered-out and top-up water is added to maintain water levels in the system.

Achieved environmental benefits

Reduced detergent use.

Cross-media effects

Significant increases in water consumption.

Operational data

The crates are removed from their transport container and passed to the bird unloading stage. After emptying they are washed. The transport container goes to a separate washing system, after which it rejoins the cleaned crate for replacement on to the lorry.

Crate washing is achieved by the use of potable water at ambient temperature. The crate passes through a spray wash section. The water passes over a wire wedge screen and is then returned to a collection bath, for recirculation. A float operated water make up system maintains a constant water supply to the system. After leaving the washer the crate is immersed in a dip tank and travels approximately 6 m, after which it is raised into a final spray washer. The overflow from the washer feeds into the immersion section and also into the first wash.

The last stage is a final rinse using clean water plus a quaternary amine compound detergent/disinfectant. This is added by an automated dosing system at a concentration of 15 mg of chemical per litre of water volume used.

The transport container passes to an inline spray booth and the water is recirculated via a wire wedge screen to remove gross debris. Clean water is added to maintain the water level and this is controlled by a float valve. Detergent/disinfectant is added at a rate of 0.5 l/h.

The clean crates are assembled in the transport containers. Before leaving the system for reloading on the vehicle they are rinsed again in clean water dosed at a concentration of 15 mg of detergent/disinfectant per litre of water volume used.

In an example slaughterhouse, the system was installed in a new building. The water consumption increased by an average of 400 – 450 m³ per 5 day week. This led to an equivalent increase in the amount of water being processed in the WWTP over a 7 day period and the slaughterhouse requiring an increase in its volume consent, from the environmental regulatory authority.

Applicability

Applicable in poultry slaughterhouses.

Driving force for implementation

In an example company, all of the water consumed on a given site is purchased from a local supply company and treated in an on-site WWTP, before being discharged to a river. The discharge volume is set by the regulatory authority. When the live bird handling system was

installed, it was necessary to limit the increase in water to enable the installation to operate within the consent limits.

The system was also introduced for bird welfare reasons, i.e. to prevent potential contamination/diseases being transported between farms and factories.

Disinfecting the crates and transport containers reduces the spread of food poisoning organisms between the birds and the human population, which can be carried on the trays.

Example plants

At least one poultry slaughterhouse in the UK.

Reference literature

[291, Rodgers K., 2002]

4.2.3.1.2 Dust abatement at bird reception, unloading and hanging stations - fabric filters

Description

During the unloading and hanging of birds up to and during slaughter and bleeding, high airborne dust levels are generated from the feathers. This is caused by the movements of the birds, especially by their flapping wings. The dust levels can be abated by the use of exhaust ventilation. The dust can be collected in a fabric filter. The air may be collected using either local exhaust ventilation or by general ventilation, although the former is more effective. The airstream is passed into a large chamber and through a filter fabric. When the airstream passes through the filter fabric, the dust particles are trapped in the fabric. As more particles are trapped, they in turn trap other particles from the airstream. Separation is carried out by sieve action, direct collision or attraction. The filter fabric can be fitted in various configurations, such as bags or screens. Compressed air or mechanical vibration is used to remove the separated dust from the fabric. The dust drops to the bottom of the chamber and is removed.

Achieved environmental benefits

Reduced dust emissions to air.

Cross-media effects

Captured dust has to be disposed of as waste.

Operational data

An emission level of 5 mg/Nm³ can be achieved from starting levels of the order of g/Nm³. Dust bags have to be disposed of and replaced approximately every 5 years.

Applicability

Applicable in all poultry slaughterhouses.

Economics

A fabric filter requires an investment of EUR 1000 - 4500/1000 Nm³/h, depending on the housing design. Operating costs are approximately EUR 2800/1000 Nm³/h each year.

Driving force for implementation

Primarily occupational health at the hanging station, but also reduction of dust emissions to the environment, particularly in residential areas.

Reference literature

[333, Netherlands TWG, 2003]

4.2.3.1.3 Dust abatement at bird reception, unloading and hanging stations – wet scrubber

Description

During the unloading and hanging of birds up to and during slaughter and bleeding, high airborne dust levels are generated from the feathers. This is caused by movement of the birds, especially by their flapping wings. The dust levels can be abated by the use of exhaust ventilation. The air may be collected using either local exhaust ventilation or by general ventilation, although the former is more effective. The dust can be collected in a wet scrubber. The exhausted airstream is passed through a water spray to ensure intimate contact with the scrubbing water, causing the dust particles to be trapped in the droplets. For increased efficiency, the gases can be passed through a venturi collar in which water is atomised, either with-the-flow or as a counter-flow. The increased efficiency is achieved due to the high speeds in the venturi collar and the intensive contact between the gas stream and the water mist. Alternatively a mist may be created by internal static vanes.

Achieved environmental benefits

Reduced dust and odour emissions to air.

Cross-media effects

Using a scrubber requires water and energy. The sludge produced from the dust in water, has to be concentrated and disposed of as waste.

Operational data

It is reported that dust emissions can be reduced by 99 % and that the average efficiency is 50 - 90 %.

Scrubbers can be used for air flows of up to 100000 Nm³/h.

Applicability

Applicable in all poultry slaughterhouses.

Economics

A scrubber requires an investment of about EUR 5000/1000 Nm³/h at a capacity level of 10000 Nm³. Operating costs are approximately EUR 2600/1000 Nm³/h each year.

Driving force for implementation

Primarily, occupational health at the hanging station, but also reduction of dust emissions to the environment, particularly in residential areas.

Reference literature

[333, Netherlands TWG, 2003]

4.2.3.1.4 Dust abatement at bird reception, unloading and hanging stations – washable metal mesh

Description

During the unloading and hanging of birds up to and during slaughter and bleeding, high airborne dust levels are generated from the feathers. This is caused by movement of the birds, especially by their flapping wings. The dust levels can be abated by the use of exhaust ventilation. The air may be collected using either local exhaust ventilation or by general ventilation, although the former is more effective. The dust can be collected using a washable metal mesh inserted in extract ventilation ducts.

Achieved environmental benefits

Reduced dust and odour emissions to air.

Cross-media effects

Using an extractor requires energy. The washings have to be disposed of as waste.

Operational data

In an example plant, the extract system is mounted at ground level with grills to prevent large material being drawn into the duct before it is collected in a 1 m³ tank/low-velocity zone, via an internal baffle plate and a washable metal mesh filter. It is reported that the system is linked to an air intake providing a minimum of 30 air changes per hour and that either disposable cartridge filters or washable metal mesh filters need to be fitted to the air inlet.

Applicability

Applicable in all poultry slaughterhouses.

Driving force for implementation

Primarily, occupational health at the hanging station, but also reduction of dust emissions to the environment, particularly in residential areas.

Reference literature

[336, BPMF, 2003]

4.2.3.2 Stunning and bleeding

See also techniques described in Sections 4.2.1 and 4.2.2.2.

4.2.3.2.1 Using inert gases for poultry stunningDescription

Inert gases can be used for stunning/killing chickens and turkeys, whilst they are in their in transport containers. Mixtures of (a) argon, nitrogen or other inert gases, or any mixture of these gases, in atmospheric air with a maximum 2 % oxygen by volume or (b) any mixture of argon, nitrogen, or other inert gases with atmospheric air and CO₂ provided that the CO₂ concentration does not exceed 30 % by volume and the oxygen concentration does not exceed 2 % by volume, can be used.

Achieved environmental benefits

Reduced dust emissions during unloading, hanging and bleeding. It has also been reported that improved quality and yield have led to a reduced by-product destined for disposal as waste. The increase in yield in turn leads to a tendency to store more of the slaughterhouse output, in conditions which will not cause spillage or odour problems.

Reduced energy consumption due to reduced refrigeration time and space requirements, since it is no longer necessary to mature the carcasses.

Cross-media effects

The reduced energy consumption, due to reduced refrigeration requirements may be offset by installations using a nitrogen separation plant for processing atmospheric air.

Operational data

A reduction in dust levels, from 11.1 – 29.6 mg/m³ to 9.0 mg/m³, has been reported.

A proprietary system has 12 draws per module, each with a capacity of around 24 broiler chickens per draw, giving a total of 288 birds per module. A typical poultry processing line operates at 8000 birds per hour, thereby killing around 70000 birds per line, per day.

The system is reported to have the following advantages. It does not impede blood loss, therefore, residual blood in the carcase meat is low. In comparison with electrical stunning, it reduces the number of birds with broken bones and the number of broken bones per bird; this is important as broken wish and collarbones frequently cause haemorrhaging in breast fillets and tender loins. It greatly reduces the incidence of haemorrhaging, not associated with broken bones, in the breast and leg muscles and this improves the yield and the value of products.

Research during 2001 indicated that the adoption of a gas mixture consisting of 80 % by volume nitrogen and 20 % by volume argon, is considered to be better than the carbon dioxide-argon mixture from bird welfare and meat quality points of views.

Applicability

Applicable in poultry slaughterhouses.

Economics

At a cost of GBP 1200 per module (1995), the maximum investment on modules alone works out to be around GBP 288000. To this module cost, around GBP 200000 must be added for the standard plant handling equipment plus approximately a further GBP 200000 for the stunning equipment. Total equipment costs for a complete installation on one processing line are therefore estimated to be about GBP 700000.

Slaughterhouses using the system from 1995 - 1999, used a mixture of 30 % CO₂ and 60 % argon in air (leaving 8 % nitrogen and 2 % oxygen from residual air). Carbon dioxide and argon were stored in separate silos at the processing plant and mixed prior to supply into the stunning unit. Changing the gas silos to store nitrogen and argon led to additional costs.

The stunning unit is designed and built to accommodate gases which are heavier than air, and to minimise the gas loss. Maintaining 25 - 30 % CO₂ and 1.5 - 2.0 % residual oxygen in argon in the unit, at a throughput rate of 7000 birds per hour, the gas consumption is estimated to be 17 litres of mixed gas per bird. In 1995, based on UK prices, the cost of stunning with this mixture was estimated to be between GBP 0.8 - 1.0 per 100 birds. The implementation of a mixture of 80 % nitrogen and 20 % argon in 2001, is estimated to have reduced the cost to between GBP 0.3 - 0.5 per 100 birds.

Driving force for implementation

The main driving force is reported to be animal welfare.

Some of the major welfare concerns associated with the water-bath electrical stunning systems, which reportedly cause stress, trauma and pain, are removed. These include, e.g. removing birds from their transport containers; shackling; conveying birds upside-down on a shackle line; giving birds an electric shock before being stunned (pre-stun shocks); cutting the necks of birds which miss being stunned adequately, due to wing flapping at the entrance to the water-bath stunners and the recovery of consciousness during bleeding due to inadequate stunning and/or an inappropriate neck cutting procedure.

Example plants

There are at least 4 companies in the UK using a predominantly nitrogen based gas mixture for killing chickens and turkeys.

Reference literature

[253, Raj A. B. M., 2002]

4.2.3.3 Scalding

4.2.3.3.1 Steam scalding of poultry

Description

Poultry can be scalded whilst hanging by being passed through steam.

Achieved environmental benefits

Steam scalding of poultry can reportedly reduce both energy and water consumption by at least 25 %, compared to scalding using hot water.

Example plants

Steam scalding of poultry is used at one Danish turkey slaughterhouse.

Reference literature

[243, Clitravi - DMRI, 2002]

4.2.3.3.2 Insulation of scalding tanks

See also Section 4.2.2.3.2.

Description

Insulation of the scalding tank can reduce heat loss by approximately 0.5 kW/m² of surface.

Achieved environmental benefits

Reduced energy consumption.

Cross-media effects

None.

Applicability

When a company has to replace an old scalding tank, the new one could be insulated.

Economics

The payback period for insulating an existing tank is estimated to be approximately 10 years.

Reference literature

[134, Nordic States, 2001]

4.2.3.4 De-feathering

4.2.3.4.1 Use of nozzles instead of irrigation pipes

Description

It is possible to use nozzles instead of irrigation pipes, to supply water in the de-feathering machine. They can also be used, supplemented with beater straps, for showering poultry after de-feathering.

Achieved environmental benefits

Reduced water consumption and more efficient washing.

Operational data

The water can be directed better with nozzles, so its consumption can be reduced.

Reference literature

[134, Nordic States, 2001, 243, Clitravi - DMRI, 2002]

4.2.3.4.2 Use of recycled water, e.g. from scalding, for the carriage of feathers

Description

The feathers are collected in a trough under the plucking machine. They are then transported with recirculated water to a screen with water passing through it, before they are collected.

Achieved environmental benefits

Reduced water consumption.

Cross-media effects

None.

Applicability

Applicable in all poultry slaughterhouses.

Reference literature

[134, Nordic States, 2001]

4.2.3.5 Evisceration

4.2.3.5.1 Water efficient and fewer shower heads

Description

An evisceration line with a total of 32 shower heads has a reported water use of approximately 600 l/h. Changing from domestic style shower heads, to an alternative form of spray nozzle, e.g. orifice plates, which have an estimated flowrate of 500 l/h, can save water. Additional savings may be achieved on new lines by reducing the number of shower heads.

Achieved environmental benefits

Reduced water consumption, reduced waste water volume for treatment and reduced entrainment of, e.g. blood and fat in the waste water.

Cross-media effects

None.

Operational data

For a slaughterhouse killing 18000 turkeys per day, i.e. 38 birds per minute, the reported potential water saving is 8000 m³/yr with a financial saving of GBP 5000/yr. The cost quoted per shower head is GBP 15. (Costs in 1999)

Applicability

Applicable in all poultry slaughterhouses.

Economics

Combined with other projects a payback time of 1 month was reported.

Driving force for implementation

Reduced water consumption and consequent cost savings for waste water treatment, within permitted discharge volume limits.

Example plants

A turkey slaughterhouse in the UK.

Reference literature

[214, AVEC, 2001]

4.2.3.6 Chilling

4.2.3.6.1 Air-chilling

Description

Air-chilling is generally used where the carcasses are for sale fresh. Chilling can be carried out by batch in a chill room or by a continuous air blast method.

Achieved environmental benefits

Greatly reduced water consumption, compared to immersion/spin chilling or spray chilling.

Tests have shown that air-chilling can reduce the food contamination rate by up a third of that after immersion chilling. Food contamination caused by immersion chilling is not only intrinsic to the process, which involves the same birds passing through common water, but it depends on the effectiveness of the pre-chilling wash. During immersion chilling, carcasses take up water and in some MSs microbial contamination is controlled by chlorination, within potable water limits.

Likewise, preventing water contamination depends to some extent on how well the birds are prepared, e.g. to prevent heads and feet breaking off during chilling.

Cross-media effects

The energy consumption is higher than that required for cooling water or for making ice for immersion/spin chilling, or water for spray chilling. The refrigeration plants operate continuously. The condensing units, compressors and cooling towers associated with refrigeration can be a source of noise.

Operational data

Air-chillers can be designed to accommodate up to 3 layers of birds. This can save energy and space.

Applicability

All chicken slaughterhouses producing fresh poultry meat.

Economics

Air-chilling is more expensive than immersion/spin chilling.

Driving force for implementation

Food hygiene.

Example plants

Most chicken slaughterhouses.

Reference literature

[12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000, 308, Hupkes H., 2002]

4.2.3.6.2 Controlling the supply of water to the immersion/spin chiller

Description

Immersion/spin chillers can be the biggest users of process water for chilling, compared to other methods.

The volume of water supplied can be controlled, so that the required amount is maintained and not exceeded. Supplying water only according to the number of slaughtered chickens can ensure this.

Achieved environmental benefits

Reduced water consumption, water contamination and waste water treatment. Reduced energy consumption for cooling water.

Operational data

For a slaughterhouse killing 18000 turkeys per day, i.e. 38 birds per minute, the reported potential water saving is 16000 m³/yr with a financial saving of GBP 9995/yr. The cost quoted per spin chiller is GBP 200. (Costs in 1999)

Applicability

Applicable in all poultry slaughterhouses applying spin chilling.

Economics

The reported payback time is one month.

Driving force for implementation

Reduced water consumption and consequent cost savings for waste water treatment, within discharge volume limits.

Reference literature

[134, Nordic States, 2001, 214, AVEC, 2001]

4.2.4 Slaughterhouse cleaning

Techniques for the prevention of spillage, which minimise the need for cleaning and waste water contamination are described elsewhere, e.g. in Sections 4.2.1 and 4.1.

4.2.4.1 Use of detergents using enzymes

Description

Biochemical cleaning agents containing naturally occurring enzymes can be used for cleaning equipment, floors and walls and for disinfection.

Achieved environmental benefits

They are less harmful to the environment than some alternatives. They can be used at lower temperatures, so there are energy savings. They produce an effluent with a lower COD than other chemicals. They are non-corrosive.

Cross-media effects

There may be potential occupational health problems, as is the case with many traditional cleaning chemicals.

Operational data

A major poultry processor tested a biochemical cleaning product in an area soiled with faeces, blood, urine, grease, fat and feathers, which was difficult to clean with NaOH. The biochemical cleaning product tested removed all traces of organic matter more efficiently. There was a reduction in odour and less damage to equipment. Less hot water was required.

Open handling and the use of detergents containing enzymes may result in unpredictable respiratory sensitisation in susceptible individuals.

Applicability

Applicable in poultry slaughterhouses.

Driving force for implementation

The use of detergents containing enzymes instead of tensides, can reduce the problems associated with the use of the latter. Tensides can reduce the separation performance of fat separators and flotation plants.

Reference literature

[61, ETBPP, 1998, 163, German TWG Members, 2001]

4.2.4.2 Pre-cleaning blood and meat juice contamination with cold waterDescription

In areas where the dominant by-product is blood and meat juice, the initial pre-cleaning can be carried out with cold water. Hot water makes blood stick to the surfaces being cleaned. Hot water only needs to be used in areas with fatty waste.

Achieved environmental benefits

Reduced energy consumption for heating the water for the initial rinsing and for a subsequent cleaning, which would be required due to the adherence of materials to surfaces being cleaned. Reduced use of detergents and contamination of waste water by detergents.

Applicability

Applicable in all slaughterhouses.

Economics

There is an immediate cost saving.

Driving force for implementation

Reduced energy costs.

Reference literature

[134, Nordic States, 2001, 167, Greek Ministry for the Environment, 2001]

4.2.4.3 CIP (Cleaning-in-place)Description

CIP systems are cleaning systems that are incorporated into equipment and can be set to use only the required quantities of detergents and water at the correct temperature (and sometimes pressure) conditions, for that equipment and the substance it is being used for. Incorporation of a CIP system can be considered at the equipment design stage and installed by the manufacturer. Retrofitting a CIP system may be possible, but is potentially more difficult and expensive. CIP systems can be improved by incorporating the internal recycling of water and chemicals, optimising programmes, using water efficient spray devices and by removing product and gross soiling prior to cleaning. Equipment correctly designed for CIP cleaning should have spray balls located so that there are no “blind spots” in the cleaning process.

Achieved environmental benefits

A reduction in the consumption of water, detergents and the energy needed to heat the water are achievable because it is possible to set the consumption levels, specifying the use of only that required for the surface area to be cleaned. It is possible to recover and re-use water and chemicals within the system.

Cross-media effects

Possible energy considerations associated with pumping the water and detergent.

Applicability

Applicable in closed/sealed equipment through which liquids can be circulated, comprising, e.g. pipes and vessels.

Economics

The capital cost is high.

Driving force for implementation

Automation and ease of operation. Reduced requirement to dismantle and reassemble equipment.

Reference literature

[61, ETBPP, 1998, 134, Nordic States, 2001, 163, German TWG Members, 2001]

4.2.4.4 Use of cyclonic vacuum cleaners

Description

Table 4.36 gives the specifications of two sizes of vacuum cleaner in use. They are used to remove blood and viscera from slaughterhouse floors prior to washing.

	Large size	Medium ⁽¹⁾ size
Suction tool	Curved - with open front attached to rubberised, smooth-bore hose (7.6 cm diameter)	Open-ended - attached to rubberised smooth-bore hose (5 cm diameter)
Ease of cleaning	60 litre stainless steel drum that can be lifted out	35 litre stainless steel drum that can be lifted out
Method of emptying drum contents	Rubberised, smooth-bore drain hose (10 cm diameter)	Tipping chassis
Approximate dimensions	1.1 m high by 0.6 m wide	0.9 m high by 0.5 m wide
Voltage	240 or 110 volts	240 or 110 volts
Approximate cost (2000)	GBP 800	GBP 650

⁽¹⁾ Also available as a battery powered unit

Table 4.36: Cyclonic vacuum cleaner specifications

Achieved environmental benefits

Reduced water contamination.

Cross-media effects

Increased use of energy compared to simply hosing down, or using a squeegee.

Operational data

In an example cattle slaughterhouse, a cyclonic vacuum cleaner was used to remove blood and offal from the slaughter hall floor areas, during the day, prior to wash downs. The separation between blood and cleaning water was also improved by constructional changes and a number of taps and showers were equipped with automatic switches and timers and the water flowrate was adjusted. These measures reduced the slaughterhouse's water consumption by 170 litres per animal, i.e. 680 l/t, which was equivalent to a 15 % saving in water use. The waste water COD was reduced by 0.4 kg, which was equivalent to a reduction of 7 %.

Cyclonic vacuum cleaners can be designed for easy emptying. If they are not emptied and cleaned regularly the risks of odour and infestation problems can increase.

Applicability

Applicable in all slaughterhouses.

Economics

The investments costs for medium and large cyclonic vacuum cleaners were GBP 650 and GBP 800, respectively in 2000.

Example plants

Several UK slaughterhouses and a Danish slaughterhouse.

Reference literature

[63, ETBPP, 2000]

4.2.5 Storage and handling of slaughterhouse by-products

4.2.5.1 Segregated storage and handling of different kinds of by-products

See also Section 4.2.1.6.

Description

By-products can be collected, handled and stored separately or in categories, depending on their further use or disposal route and on the potential environmental consequences of mixing them. If, e.g. they are the same material but at different stages of degradation and one causes an odour problem, then mixing them would lead to an increased volume of malodorous material and make the whole volume less usable.

Achieved environmental benefits

Reduced odour emissions associated with the storage of malodorous by-products, both at the slaughterhouse and at animal by-products installations.

The segregation of liquids and solids destined for use or destruction offers several advantages. If sufficient separate storage systems are provided, it reduces cross contamination between different by-products. The segregation of by-products can reduce potential odour problems from those materials which even when fresh emit the most offensive odours. They can be stored or removed separately under controlled conditions. If by-products which require refrigeration are separated from those that do not, the refrigeration capacity required will be less.

Also, by minimising cross-contamination, segregation enables individual by-products to be used instead of disposed of. Each by-product can potentially be used or disposed in different ways.

Applicability

Applicable in all slaughterhouses.

Driving force for implementation

Reduced waste disposal costs.

Reference literature

[148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

4.2.6 Slaughterhouse waste water treatment

4.2.6.1 Treatment of slaughterhouse waste water at municipal WWTPs

Description

The degree of waste water treatment undertaken at the slaughterhouse before discharge to either a water course or to a municipal WWTP varies between installations and in some MSs is governed by local legislation or practice.

Instead of the slaughterhouse reducing the BOD level of its waste water to levels acceptable for discharge, it may, usually after primary treatment, be transferred to a local municipal WWTP. Gross solids are generally removed at the slaughterhouse and in the case of slaughterhouses handling Category 1 and 2 material, the sieved material is also deemed to be Category 1 and 2 material, as required by ABP Regulation 1774/2002/EC. Fats are also removed because these can cause serious problems with the operation of the biological treatment processes. The municipal WWTP must be designed to be able to treat the volume and load received from the slaughterhouse.

To run a waste water treatment plant with complete denitrification (nitrogen removal) it is necessary for sufficient carbon to be present. The ratio between carbon and nitrogen (the C:N ratio) of the incoming waste water normally needs to be a minimum of 5:1 for denitrification. Household waste water almost meets this requirement, but the inclusion of even only a small amount of badly compounded waste water, e.g. from industry, can disturb this ratio, with the result that complete denitrification is not obtained. Some plants add methanol or strong carbonaceous by-products like treacle to the waste water. In towns with slaughterhouses, this type of problem seldom occurs because waste water from slaughterhouses contains easily degradable organic matter with a favourable C:N ratio.

In some countries, e.g. Denmark and the Flemish part of Belgium, taxes on waste water removal make it profitable for the slaughterhouse to pre-clean its waste water so that the tax they pay is reduced or discontinued. Pre-cleaning at the slaughterhouse is usually done by flotation. With flotation, the C:N ratio decreases to approximately 5:1. This results in lower waste water costs for the slaughterhouse since discontinuation of the tax they pay will normally fully make up for the expenses associated with running the flotation plant and for the return on investment in the new plant. The pre-cleaned waste water from the slaughterhouse still has a high enough C:N ratio that it can be completely denitrified, but the local authorities will now need the additional contribution of carbon to denitrify the rest of the waste water.

Achieved environmental benefits

Treatment of municipal waste without the need to add a carbon source.

Cross-media effects

Transferring untreated waste water to the municipal WWTP introduces a risk of accidental discharge between the slaughterhouse and the WWTP.

Operational data

The slaughterhouse waste water contains high concentrations of nitrogen and phosphorus compounds. Discharge of this water to the municipal WWTP places extra burdens on it, which may require additional treatment techniques to be introduced, in order to achieve low concentrations of nitrogen and phosphorus in the final effluent.

Applicability

Where the municipal WWTP is sufficiently close to the slaughterhouse and has the capacity and willingness to accept and treat the waste water.

Economics

Local arrangements determine how much the slaughterhouse has to pay.

Driving force for implementation

The slaughterhouse waste water may be a useful source of carbonaceous organic matter for the municipal WWTP. The slaughterhouse does not have to install or operate an on-site WWTP.

Example plants

Several Danish and German slaughterhouses.

Reference literature

[186, Pontoppidan O., 2001, 240, The Netherlands, 2002, 244, Germany, 2002, 277, EC, 1991]

4.2.6.2 Use of sequencing batch reactors (SBR) in slaughterhouse waste water treatment

Description

The SBR process is an activated sludge process which treats waste water through a timed sequence of operations within one or more reactor tanks. The system allows equalisation, COD removal, nutrient removal and clarification to be achieved using a SBR. The cycle comprises a timed sequence of operations and is divided into the following main stages: filling, reaction, settling, discharging and idle.

Before the SBR treatment, the waste water needs to be screened using a 0.5 – 1 mm mesh and then degreased. If there is only one reactor, it is then collected in an equalisation tank prior to filling.

Filling stage

The SBR is filled with a quantity of waste water. The filling can be static, aerated, anoxic and/or anaerobic and adjusted to the particular waste water by simply modifying parameters in the control unit. This adaptability reportedly improves nutrient removal and prevents bulking problems. The filling velocity can also be controlled and this affects the effectiveness of the final settling stage.

Reaction stage

The reactor is mixed and aerated in sequence to optimise the final removal of COD and nitrogen. These can be controlled with dissolved oxygen or oxidation-reduction potential monitoring to ensure the desired efficiency with the minimum consumption.

Settling stage

The biomass is separated from the treated water by sedimentation in the reactor. The clarification is very effective since there is no countercurrent flow of the treated water. The length of the sedimentation period can be modified during operation to improve the clarification.

Discharging stage

The treated clarified liquid is discharged by a floating device at an appropriate height to ensure that neither settled solids nor floating debris are discharged. Finally, the settled biomass is pumped away from the bottom of the reactor, to prevent a build-up of excess sludge.

Idle stage

When there is no waste water to be treated, the SBR is switched to an idle phase. During this stage, it is not necessary to run the aeration systems at the same rate as during a normal cycle.

Another technique has been reported which is similar and which uses separate reactor vessels for aerobic, anoxic and anaerobic treatments.

Environmental benefits

The COD reduction efficiency is reported to be as high as 95 %, thereby resulting in a low oxygen depletion potential in receiving waters. Compared to other waste water treatment processes, the energy consumption is reported to be low, as there is no need for recirculation between tanks, since all the operations are carried out in the same tank. There is no requirement to use chemicals and consequently there is no chemically contaminated sludge. The sludge can be used, e.g. in composting.

Cross-media effects

Most of the carbonaceous contamination ends up as CO₂ emissions, which eventually contribute to global warming. The nitrates output is higher than the input, because all of the TKN nitrifies into nitrates. This is compensated for by the TKN output being very much lower than the input.

Operational data

COD emission values of 22 mg/l have been reported from an SBR plant for a chicken slaughterhouse without total blood recovery. An achieved sludge waste value of 0.05 kg SS/kg COD has been reported.

As slaughterhouse waste water contains nitrogen and phosphorus there is an associated risk of the eutrophication of receiving waters. Emission levels as low as 0.2 mg/l of ammonium and < 1 mg/l of nitrates have been measured after SBR waste water treatment in chicken slaughterhouses, although it is reported that in practice the average levels in a plant with optimal operation is around 1 – 2 mg/l of ammonium and 5 – 15 mg/l of nitrates.

SBRs can alternate anoxic periods with aerobic periods, thereby removing nitrogen from the waste water. The length of the anoxic periods can be adjusted to create anaerobic conditions which facilitate up to about 40 % phosphorus removal.

It is reported that odour is not a problem if the biological reactor and the equalisation tank are well aerated.

It is reported that there is a low risk of accidents, since the plant works automatically and requires very little control by personnel.

It is reported that a de-foaming agent is the only chemical required and only during the first week of starting-up, due to blood in the waste water.

Table 4.37, Table 4.38, Table 4.39 and Table 4.40 show data for a pilot plant and for three existing SBR WWTPs in poultry slaughterhouses.

Reference	Pilot plant (23 August 2001 – 2 August 2002)					
Waste water	Poultry slaughterhouse with < 85 % blood recovery					
Design	HRT = 3 days					
Pretreatments	Equalisation (HRT = 1 day) + 0.5 mm screening					
Net sludge production	0.1 kg SS/kg COD					
Parameters	pH	Conductivity (mS/cm)	COD (mg/l)	TKN (mg/l)	NH ₄ ⁺ (mg/l)	NO ₃ ⁻ (mg/l)
Inlet	6.5 - 8	3 - 4	3500	350		10
Outlet	7 - 8	3 - 4	< 125		< 5	< 20
Minimum value			17		0.4	8.4

Table 4.37: Operational data for a SBR at a poultry slaughterhouse pilot plant

Reference	Slaughterhouse A					
Waste water	Poultry slaughterhouse					
Flow	40 m ³ /d					
Design	HRT = 3 days					
Pretreatments	0.6 mm screening + degreasing DAF unit + aerated equalisation (HRT = 1.5d)					
Net sludge production	0.06 kg SS/Kg COD					
Parameters	pH	Conductivity (mS/cm)	COD (mg/l)	TKN (mg/l)	NH ₄ ⁺ (mg/l)	NO ₃ ⁻ (mg/l)
Inlet (equalisation tank)	7 - 8	3.0 - 4.5	2800 – 4200	300 – 475		5
Outlet	7 – 8	1.8 – 2.3	< 200		< 5	< 30
Minimum value			42		0.4	14.6

Table 4.38: Operational data for a SBR at a 40 m³/d poultry slaughterhouse

Reference	Slaughterhouse B					
Waste water	Poultry slaughterhouse					
Flow	100 m ³ /d					
Design	HRT = 2 days					
Pretreatments	1 mm screening + equalisation tank + DAF primary unit					
Net sludge production	SBR = 0.023 kg SS/kg COD Primary flotation approx. 4000 l/day at 4 % dryness					
Parameters	pH	Conductivity (mS/cm)	COD (mg/l)	TKN (mg/l)	NH ₄ ⁺ (mg/l)	NO ₃ ⁻ (mg/l)
Inlet (equalisation tank)	6.4 – 8.2	3.3 - 4.5	2900 – 7250	200		2.5
Outlet	6.8 – 8.5	2.5 – 3.5	< 100		< 25	< 10
Minimum value			22		0.2	0.8

Table 4.39: Operational data for a SBR at a 100 m³/d poultry slaughterhouse

Reference	Slaughterhouse C					
Waste water	Poultry slaughterhouse					
Flow	470 m ³ /d					
Design	HRT = 1.25 d x 2 SBR = 2.5 d					
Pretreatments	0.3 mm screening + degreasing DAF unit					
Net sludge production	0.21 kg SS/kg COD					
Parameters	pH	FOG (mg/l)	COD (mg/l)	TKN (mg/l)	NH ₄ ⁺ (mg/l)	NO ₃ ⁻ (mg/l)
Inlet (equalisation tank)	5.8 – 6.4	400 - 725	3300 – 3820	227		
Outlet	6.1 – 7.4	1 – 35	< 150		< 20	< 5
Minimum value		0.8	93		0.4	< 1

Table 4.40: Operational data for a SBR at a 470 m³/d poultry slaughterhouse

The SBR is automated and controlled using a PLC. The main controls are for the cleaning of the screens and the degreasing units rather than for the operation of the technique. The operation of the SBR is monitored by the periodic measurement of V₃₀ values, i.e. by measuring the volume of a 1 litre sludge from the reactor after 30 minutes sedimentation time.

The cycle can be adjusted easily at the touch panel of the PLC and as required by the properties of the inlet waste water, e.g. if the COD:N changes or if there is a problem due to the appearance of filamentous bacteria, which create bulking.

The sludge is normally dried in a decanter, to achieve a 95 % reduction in volume.

SBRs are reported to provide low maintenance secondary treatment, as they use less electromechanical equipment than other biological treatments.

Applicability

Applicable in all slaughterhouses.

The technique is reported to have the advantages of not requiring much space and not requiring a clarification system (sedimentation or flotation units) or separate anoxic treatment for denitrification or phosphorus removal. It operates at a high solids concentration (MLVSS = 4000 – 5000 mg/l), so low volumes are required.

Economics

Investment costs

SBR is reported to be the cheapest secondary treatment, because the treatment can be carried out in one vessel.

The reported selling prices of some slaughterhouse SBR treatment plants are shown in Table 4.41.

Name	Flow (m ³ /d)	COD effluent (mg/l)	Price not including VAT (EUR)	Observations
Slaughterhouse A	40	200	63106	Civil works not included.
Slaughterhouse B	200	160	96162	Civil works not included.
Slaughterhouse C	570	160	280524	Civil works and sludge line included. Stainless steel tanks and centrifuge decanter sludge line.
Slaughterhouse D	1500	*1750	187305	Civil works and sludge line included. Galvanised tanks and centrifuge decanter sludge line. Existing pretreatment.
Slaughterhouse E	160	160	75685	Civil works not included.
Slaughterhouse F	200	160	110115	Civil works partially included.
* COD value required by local permit, before treatment at a municipal WWTP				

Table 4.41: Reported selling prices of SBR treatment plants in 6 slaughterhouses

Operational costs

The range of electrical costs reported is EUR 0.12 – 0.25/m³, for a EUR 0.06/kWh cost for electricity. There are no chemical reagent costs.

Driving force for implementation

The main driving force for the use of SBR in slaughterhouses is its capacity for removing nitrogen contents with a high efficiency and low investment and running costs. The technique is flexible and conditions such as the length and frequency of anoxic periods, filling velocity, settling time and anaerobic periods can be easily altered using a PLC. The technique does not require a lot of space.

Example plants

At least 3 poultry slaughterhouses in Spain, one ostrich slaughterhouse in Cyprus and several pig, poultry and cattle slaughterhouses in the Netherlands. There are plans for the technique to be installed in a pig slaughterhouse and a poultry slaughterhouse in Cyprus.

Reference literature

[302, Jiménez Rodríguez J J., 2002, 306, Hydrotech Water and Environmental Engineering Ltd, 2001, 333, Netherlands TWG, 2003]

4.2.6.3 Moving bed trickling filter - for the treatment of air, water and air/water mixtures

Description

The moving bed trickling filter (MBTF) is a sludge-on-carrier aerobic biological filter for the treatment of waste water, waste gases and air and air/water mixtures. It is possible to treat waste water and air simultaneously.

The MBTF comprises a vertical cylindrical tank filled with plastic spheres. The spheres, which are made of durable material, act as a carrier material for micro-organisms. The waste water is fed into the filter at the top, whilst the air flows through the filter parallel or countercurrently to the water. Intensive mixing takes place in the filter and the contaminants in the water and air are broken down by the micro-organisms. A special feature is the fact that a number of the micro-organism-carrying spheres are periodically removed from the bottom of the filter and cleaned. The micro-organisms removed from the spheres are thickened to a compact sludge in the cone of the filter. The cleaned spheres are returned to the top of the filter. This unique integrated cleaning procedure makes it possible to control the amount of micro-organisms and makes clogging of the filter impossible.

The MBTF is shown in Figure 4.12.




Figure 4.12: Diagram of a moving bed trickling filter designed to treat waste water and air emissions
[147, DHV, 1999]

Achieved environmental benefits

Low energy consumption. COD levels and nitrogen compounds are reportedly reduced by 90 % and 55 %, respectively.

Operational data

Compared to other systems for the treatment of air/gas or waste water, the MBTF is characterised by a high efficiency and a high capacity. Depending on the concentrations and flows, a reactor with a diameter of 4 metres could treat a waste gas flow of 30000 Nm³/h of air while simultaneously treating 20 m³/h of waste water. For highly concentrated flows or with very strict effluent requirements other gas:liquid ratios are feasible.

MBTF has proven to be relatively insensitive to suspended solids and fats in the waste water stream. This often makes the use of coagulants or flocculants in the pretreatment unnecessary.

Applicability

Applicable at slaughterhouses and animal by-products installations.

Economics

Filter costs are compensated for by the reduced waste water charges. With combined treatments there is no need to invest in separate air/gas treatment techniques.

Example plants

A poultry slaughterhouse in the Netherlands.

Reference literature

[147, DHV, 1999, 240, The Netherlands, 2002]

4.2.7 Slaughterhouse waste treatment

4.2.7.1 Microbiological treatment of slaughterhouse waste

Description

A biological treatment system using a tailored microbial culture has been reported. Three waste streams from a slaughterhouse, i.e. wash-water, stomach contents and blood are combined and treated in a two-stage, aerobic digestion process. The technology is reportedly applicable to other wastes with a high blood and/or fat content.

The sludge produced by the digesters is dewatered on a belt press, to give a biomass with a commercial value as a fertiliser. Analysis of the biomass shows that it contains elevated levels of the major plant nutrients nitrogen, phosphorus, potassium, magnesium and sulphur.

Liquid from the belt press undergoes a final biological polishing and is either collected in a tanker for land spreading, or used for belt washing. The final effluent is reportedly suitable for yard washing, after veterinary approval.

This two-stage, biological system has been shown to be capable of treating high-strength wastes with a COD content of over 100 g/l and of adapting to a wide range of pollutant loads.

The process is shown in the Figure 4.13.




Figure 4.13: Schematic of the biological treatment process for high-strength slaughterhouse wastes [56, ETBPP, 1997]

Achieved environmental benefits

Waste water treatment producing water and solids which can be used instead of needing to be disposed of. Although not within the scope of IPPC, environmental benefits from the reduced transportation of by-products may be reported.

Cross-media effects

Some energy use for the operation of the process and odour from the biomass.

Operational data

The combined influent to the treatment plant consists of 67 % wash-water, 20 % macerated stomach contents and 13 % blood. These waste streams vary in COD and suspended solids content owing to changes in slaughterhouse throughput and the type of animal slaughtered. The average COD content of the combined influent is 60 g/l, although levels of over 100 g/l can occur.

From the collection sump, the combined waste streams are pumped to a balance tank at a rate of approximately 45 m³/d. The balance tank, which is aerated, provides a buffer against extremely high pollutant loads entering the biological stage of the process and ensures a steady feed to the first digester. Dried microbial culture is regularly added to the balance tank. The modular design of the two-stage aerobic digestion process allows for operational flexibility and variable capacity. The process requires no external heating or cooling.

The sludge produced during the biological treatment process is dewatered in batches in a belt press, to which a proprietary polyelectrolyte is added to aid dewatering. The resulting biomass, which contains approximately 30 % dry solids, is discharged to a skip and stored on-site prior to use or sale.

The average COD content of the final, treated effluent is 1 g/l, giving an average COD removal efficiency of greater than 98 %. With further polishing, lower levels have been achieved.

It has been reported that in Italy, COD levels have been reduced from 4000 – 7000 mg/l to < 160 mg/l.

Applicability

Applicable in all slaughterhouses.

Economics

The large volumes of waste with a high blood and fat content generated by slaughterhouses can be expensive to dispose of. At the time the case study was reported, stricter legislative controls were also expected to increase the costs of transporting and disposing of these wastes.

In 1996, the throughput of cattle, lambs and pigs at a slaughterhouse in the UK resulted in the production of nearly 11400 m³ of effluent with a high COD and suspended solids content. This high-strength waste had previously been tankered off-site, for disposal by a specialist waste disposal contractor at an annual cost of over GBP 128000. Faced with rising waste disposal costs, a decision was taken to install a biological treatment system that would eliminate the need for expensive off-site waste disposal and that would allow for increases in production capacity.

The benefits of this innovative biological treatment system include annual cost savings of over GBP 130000 and the elimination of the need for off-site disposal of high-strength waste.

The commercial value of the biomass produced was estimated at GBP 50 per tonne. Based on the production of 10 tonnes per week, i.e. approximately 500 tonnes per year of biomass, the potential revenue from sales of the biomass was GBP 25000 per year (1997). It has been reported that in Italy the spreading of biomass produced in a WWTP according to Council Directive 86/278/EEC costs approximately EUR 20/t.

In the example installation, prior to the installation of the biotechnology plant, the high-strength effluent was tankered off the site for 32 weeks of the year for disposal by a waste management contractor. This disposal method cost GBP 128000 per year, i.e. GBP 17.7/m³ for 45 m³/d of effluent (1996 prices). For the remaining 18 weeks of the year, the waste was spread on land at the site, at an estimated cost of GBP 3000 per year. The need to tanker high-strength waste off the site for disposal was thus eliminated.

With equipment costs of GBP 350000 (1996 prices), the net cost savings of over GBP 130000 per year led to a payback time of 2.7 years. This period would be significantly shorter if the cheaper option of land spreading had not been available, because it would have replaced a more expensive alternative.

At the time the case study was reported, municipal WWTPs were being upgraded to comply with the requirements of the *Council Directive 91/271/EEC of 21 May 1991 concerning urban waste water treatment* [277, EC, 1991]. This may have led to increased charges to the slaughterhouses for their waste water treatment. This new technology may, therefore, produce significant cost savings for slaughterhouses discharging effluent to sewer.

Table 4.42 shows the annual operating costs, capital costs and savings for biological treatment at the slaughterhouse described in the case study.

	Costs, savings and payback (GBP)
Annual operating costs	
Microbial culture	3200
Polyelectrolyte	4380
Water	1050
Specialist maintenance	2500
Electricity	9200
Labour ⁽¹⁾	5000
Total annual operating costs ⁽²⁾	25330
Annual savings:	
Biomass value	25000
Waste disposal	131000
Total annual savings	156000
Net annual cost savings	130670
Total capital costs	350000
Payback period	2.7 years
⁽¹⁾ Estimate for one person working half a day, 5 days a week and for 50 weeks a year.	
⁽²⁾ Based on treating 45 m ³ /day of effluent for 5 days a week and for 50 weeks a year.	

Table 4.42: Economic analysis of biotechnological treatment of slaughterhouse waste

Driving force for implementation

Rising costs for the off-site disposal of waste.

Example plants

One slaughterhouse in the UK and one in Belgium.

Reference literature

[56, ETBPP, 1997, 237, Italy, 2002, 248, Sorlini G., 2002, 346, Belgian TWG member, 2003]

4.3 Animal by-products installations

4.3.1 Animal by-products installations - general techniques applicable at installation level

4.3.1.1 Continuous and segregated collection of by-products throughout animal by-products treatment

See 4.2.1.6 for a description of another technique also applicable in animal by-products installations.

4.3.1.2 Maintenance of negative pressure in storage, handling and processing areas

Description

Material can be stored in hoppers or on open floors in buildings which are well sealed and kept under a slight negative pressure, whilst ensuring that the air is changed sufficiently frequently for the health and welfare of personnel. Storage times can also be kept to a minimum.

The process building can be subdivided internally into functional areas, by using full-height, solid walls, to control and manage air movement. All buildings can be designed and

constructed so that they are well sealed to separate different processing areas, such as the raw material reception, storage, cooling and end-product storage areas. The ventilation provided can be capable of maintaining negative pressure and preventing an uncontrolled escape of malodorous air to outdoors. The areas from which ventilation is provided can be connected to suitable odour abatement plant.

Achieved environmental benefits

Reduced odour and dust emissions.

Cross-media effects

Energy is used to move large volumes of air. There may be cross-media effects associated with the odour abatement plant.

Operational data

See also Section 4.3.8.14.

Applicability

Applicable at all slaughterhouses and animal by-products installations where malodorous animal by-products are handled.

Driving force for implementation

Prevention of odour emissions, beyond the site boundary.

Example plants

A rendering plant and a fat melting plant in the UK. Two animal carcase incinerators in Italy. A slaughterhouse and several rendering plants in Germany.

Reference literature

[47, DoE SO and WO, 1997, 164, Nottrodt A., 2001, 241, UK, 2002, 248, Sorlini G., 2002]

4.3.1.3 Sealed storage, handling and charging of animal by-products

Description

Hoppers can provide a storage method, which is relatively easy to control and may be combined with automated, fully enclosed, transfer and handling equipment. Material can be delivered in, e.g. bulk tipper lorries and transferred directly to an unloading hopper, either mechanically via conveyors/augers or pneumatically.

The storage, handling and possibly size reduction equipment, can be sealed or maintained under negative pressure and the air extracted can either be used to provide oxygen in a combustion process, such as incineration, see Section 4.3.8.15, or can be directed to an odour abatement system.

Achieved environmental benefits

Animal by-products installations can use fully enclosed feed systems to minimise biological risk and fugitive emissions, e.g. of malodorous substances.

Cross-media effects

None.

Operational data

In an example incinerator, carcasses and parts of carcasses are tipped into a hopper, from which they are immediately transferred to a storage vessel which has been designed and constructed to hold the maximum quantity of material likely to be delivered to the site.

A cover may be provided for the initial hopper into which the animal by-products are tipped, as they are received from the slaughterhouse, to reduce odour emissions. If the animal by-products are received fresh and are not inherently malodorous, e.g. if the incinerator is on the same site as the slaughterhouse, the material comprises fresh condemned carcasses and bones and the material is then fed into the storage vessel immediately, a cover may not serve an odour reduction purpose, but it may reduce problems arising from, birds and vermin.

Storage hoppers are covered and sealed. The final feed to the continuously running rotary kiln furnace is always sealed by a fully charged screw conveyor.

Applicability

Applicable in all animal by-products installations where the materials can be stored, handled and treated in enclosed equipment and where odour and vermin problems may arise. This may include, e.g. in fat melting, rendering, fish-meal and fish-oil processing, blood processing, bone processing, gelatine manufacture, incineration and biogas production.

Economics

It is inexpensive to seal equipment upstream of the incinerator, to prevent air ingress during charging.

Driving force for implementation

Enclosure of raw materials reduces vermin and odour problems.

Example plants

Sealed handling, including hopper charging of whole carcasses and parts of carcasses is undertaken at least two animal carcasses/parts of animal carcass incinerators in Italy.

Reference literature

[6, EA, 1997, 269, Italian TWG Members, 2002, 293, Smith T., 2002]

4.3.1.4 Use of fresh refrigerated raw materials

Description

If raw materials are handled as fresh as possible, the quantity of compounds that end up in the waste water or the air can be reduced. For example, by cooling warm waste, such as soft waste from the slaughter-line and casing-cleaning department, the formation of air and water pollution can be reduced. Consequently, the energy consumption for waste water and air cleaning is also reduced. If it is not possible for the processing to take place within the time it takes for odour problems to develop after slaughter or intermediate treatment, materials may be refrigerated. Cooling can take place, if necessary, at the slaughterhouse, in transit or at the animal by-products installation. The refrigeration period may be kept to a minimum, sufficient to simply prevent odour/quality problems without delaying treatment of the animal by-products. Good co-operation between the operators of the slaughterhouse, the haulier and the animal by-products installation minimises the need for refrigeration and the time required, if refrigeration is needed at all.

Achieved environmental benefits

Reduced COD, BOD, sediments, nitrates and phosphate in waste water and reduced odour emissions from storage and processing.

Cross-media effects

An increased energy consumption if refrigeration is necessary.

Operational data

It may be appropriate to refrigerate animal by-products due to extreme operational difficulties, such as a long distance between the source of the materials, which makes quick treatment

impossible. An additional or alternative reason may be high ambient temperatures, which cause materials to rapidly decompose and produce malodorous emissions. High temperatures may be seasonal in the north of Europe or permanent in countries with warmer climates.

A British investigation showed that the COD levels in rendering condensate from completely fresh raw materials, raw materials stored in winter and raw materials stored in summer was 2.7, 10 and 50 g/l, respectively.

A German study comparing waste water contamination in summer and winter illustrates the effect that the storage temperature for raw materials can have on the contamination loads of waste water, see Table 3.24.

Applicability

Applicable at all animal by-products installations where there is a risk of odour emissions which are likely to cause offence and that cannot be prevented without the use of refrigeration.

Driving force for implementation

By-products companies charge more for degraded and malodorous materials, partly due to the additional environmental costs associated with odour control and waste water treatment and partly due to the fact that they have no value and have to be disposed of. This, therefore, provides the incentive for the slaughterhouse to keep the storage of by-products to as short a time as possible and even where further treatment is not possible, but before degradation and the formation of malodorous substances occurs, to refrigerate them.

Example plants

Six rendering plants in Germany.

Reference literature

[134, Nordic States, 2001, 244, Germany, 2002, 272, Woodgate S., 2002]

4.3.1.5 Multiple-effect evaporators

See also Section 4.3.2 and 4.3.4.

Description

Multiple-effect evaporators are used in, e.g. fat melters, rendering systems, fish-meal factories and gelatine plants, to remove water from liquid mixtures. In rendering, raw materials typically contain about 60 % water. Multiple-effect evaporators operate at relatively low temperatures and this prevents scorching of the animal by-products being treated. Removing water by evaporation is an energy-intensive process, and low-pressure evaporators are more efficient at this than open kettles or other systems operating at atmospheric pressure. At 50.7 kPa (0.5 atmospheres), water boils at 81.5 °C. Evaporators can be made to operate at much lower pressures than 50.7 kPa, therefore, vapour just above 100 °C can be used as the heat source for the evaporators.

An effective use of the evaporative heat can be achieved in a multiple-effect evaporator. After the separation of the raw materials into a solid and a liquid phase in a continuous system, by either pressing, centrifugation, or a combination of both, the liquid phase can be dried in a multiple-effect evaporator. The heating-medium is the steam raised from the drying of the solid phase and from the evaporation in the other stages of the vacuum drier. The Atlas process of mechanical dewatering is an example of such a process. The heat consumption in this process is 400 - 450 kWh/t of raw materials.

Achieved environmental benefits

Reduced energy use for evaporation, i.e. by re-use of the heat from the evaporated water.

Cross-media effects

None.

Operational data

A multiple-effect evaporator is shown in Figure 4.14. In theory, the efficiency of evaporation can be almost doubled by each doubling of effects, i.e. twice as much liquid can be evaporated per quantity of live steam or vapour consumed in the steam jacket. In a multiple-effect evaporator system, vapour from an effect is condensed in the steam jacket of a succeeding effect. This is possible because the succeeding effect will be operated at a lower pressure and thus a lower temperature.




Figure 4.14: Multiple-effect evaporator

The efficiency of evaporators can be improved by providing more heat transfer surface than that given by simply jacketing the boiling chamber. The evaporators often consist of vertical tube bundles with the heating medium on the outside of the tubes and the product boiling on the inside. Product is either moved up through the tubes, i.e. in what is described as a “rising film”, or down-ward through the tubes, in which case the evaporator is called a “falling film” evaporator. The product is fed into these evaporators in such a way and at such a flowrate that facilitates the formation of a thin film covering the inside of the tubes. This results in high heat transfer coefficients and a tremendous amount of water can be boiled off within a relatively small area of equipment.

Applicability

Applicable in fat melting, rendering, fish-meal production and gelatine manufacture treating more than 50000 - 100000 tonnes per year.

Economics

The capital cost of such continuous installations is reportedly higher than that of conventional systems and they are reported to be only suited for plants with a relatively high level of raw material supplies, i.e. more than 50000 - 100000 t/yr.

Driving force for implementation

Reduced energy consumption and consequently reduced costs.

Example plants

All rendering plants in Denmark.

Reference literature

[249, GME, 2002, 268, Ockerman H. W. and Hansen C. L., 2000]

4.3.2 Fat melting

See also Sections 4.1 and 4.3.1.

4.3.3 Rendering

See also 4.1 and 4.3.1.

4.3.3.1 Totally enclosed rendering line

Description

The transfer of materials throughout the entire processing line, including the conveyance of process gases and liquid effluents, can be undertaken within totally enclosed and sealed handling systems designed, constructed and maintained to prevent leakages from occurring. If occasional access is required, e.g. to remove tramp metal from a magnet positioned at the beginning of the line, then a hinged cover interlocked to the mechanism can be provided.

Achieved environmental benefits

Reduced liquid and solid leakage and reduced emissions to air, including odour.

Cross-media effects

None.

Applicability

Applicable at all rendering plants.

Economics

Inexpensive.

Driving force for implementation

Reduced odour.

Reference literature

[49, VDI, 1996]

4.3.3.2 Size reduction of animal carcasses and parts of animal carcasses before rendering

See also Section 4.3.8.4.

Description

ABP Regulation 1774/2002/EC prescribes the maximum particle sizes for rendering animal by-products. Depending on the process to which the materials will be subject and based on their Category and further processing destination, the size varies between 20 – 150 mm. Size reduction can also yield processing advantages, e.g. increased weight capacity and throughput performance. Very finely ground raw material can be pumped through closed pipelines.

Achieved environmental benefits

Less energy for complete processing of smaller particles than for whole carcasses or large particles.

Cross-media effects

Energy is consumed in the size reduction operation.

Operational data

With good mixing the increased surface area can make complete processing easier. It is reported that pre-cutting of the raw material should be carried out just before treatment is started, to minimise any decomposition and associated quality and odour problems.

Grinders equipped with knives or crushing teeth are used. They often represent critical points during processing, because they are particularly prone to wear and tear, so maintenance is important.

Applicability

Applicable in all plants rendering solid animal by-products.

Example plants

Six German rendering plants.

Reference literature

[244, Germany, 2002]

4.3.3.3 Continuous rendering of, e.g. fresh raw feathers and hairDescription

The processing of feathers and hair in as fresh a state as possible can minimise emissions to air and waste water. Hydrolysis in a continuous installation using direct steam, followed by mechanical dewatering in a decanter and evaporation of the liquid phase from the decanter in a multiple-effect evaporator can save significant heat energy.

Achieved environmental benefits

Potential savings of 40 - 50 % of the heat energy for the process, if large amounts of raw materials are available and a waste steam evaporator is used.

Reduced storage times can lead to reduced odour emissions from storage, processing and waste water treatment.

Cross-media effects

Additional journeys may be required between the slaughterhouse and the rendering plant to ensure that the feathers are rendered in as fresh a state as possible, hence transport may involve part loads and consequently the environmental impact of transport may be higher than if only full loads are transported.

Operational data

This technique requires a large amount of raw materials and access to a waste steam evaporator.

Applicability

Applicable where there is a feather feedrate of at least 2 t/h and usually no more than 5 t/h. Continuous rendering is also applicable for other animal by-products destined for rendering if their feedrates match the capacity of a continuous rendering plant, i.e. synchronised slaughter and rendering.

Driving force for implementation

By-products companies charge more for degraded and malodorous materials, partly due to the additional environmental costs associated with odour control and waste water treatment and partly due to the fact that they have no value and have to be disposed of. This, therefore, provides the incentive for the slaughterhouse to store by-products for as short as time as possible. Where further treatment is not possible, before degradation and the formation of malodorous substances occurs, they may be refrigerated, to minimise degradation.

Reference literature

[134, Nordic States, 2001, 272, Woodgate S., 2002]

4.3.3.4 Removal of water from blood, by steam coagulation, prior to rendering or spray drying

See also Section 4.3.5.

Description

Blood contains more than 800 kg of water per tonne, i.e. approximately 80 %. A lot of energy is required to remove this. To minimise the amount of energy required to remove the water, during, e.g. rendering or spray drying, a proportion of this can be done in advance, using steam coagulation. This is common practice in the majority of plants.

The blood is coagulated by direct steam injection. The coagulated blood is then separated in a decanter, in which the blood is separated into a grax containing 50 - 55 % water and blood water containing 70 - 75 % of the original water content. The blood water is treated in the WWTP. The grax is sterilised and finally dried in a dry rendering cooker or another drier, such as a spray drier. Alternatively, the blood can be mixed with other raw materials and processed with them.

Achieved environmental benefits

Reduced energy consumption.

Cross-media effects

The heat treatment of protein leads to the formation of a number of malodorous compounds, such as ammonia, amines and sulphur containing compounds.

Operational data

The energy consumption in an energy saving installation has been measured to be approximately 60 kg fuel oil and approximately 120 kWh electricity per tonne raw materials. Of the electricity consumption, 72 kWh are used for the processes and 48 kWh, for air and waste water cleaning.

The energy consumption can be reduced from 700 – 800 kWh/t of blood to 350 – 400 kWh/t, depending on the type of drier used.

The water consumption has been measured as 2000 - 2300 litres of water per tonne of raw materials. Of this 600 – 700 litres are used for condensation and 200 – 250 litres are used in the boilers.

2000 litres of waste water is produced per tonne of raw materials. 700 - 800 litres of this is water condensed from the raw materials. This contains a number of dissolved compounds. To a large extent, the waste water composition depends on the freshness of the processed blood and on the process itself. Discharge figures of the order of 5 – 6 kg BOD, 0.6 - 0.8 kg N and 0.20 - 0.25 kg P per tonne raw materials, have been reported.

Applicability

If only small quantities of blood have to be processed, the investment in energy saving equipment is not profitable.

Driving force for implementation

Reduced energy consumption.

Example plants

Very widely applied.

Reference literature

[134, Nordic States, 2001, 243, Clitravi - DMRI, 2002, 244, Germany, 2002]

4.3.3.5 Single effect evaporatorDescription

Evaporators are used in rendering systems to remove water from liquid mixtures. They operate at relatively low temperatures and this prevents scorching of the animal by-product being treated. Removing water by evaporation is an energy-intensive process, and low-pressure evaporators are more efficient at this than open kettles or other systems operating at atmospheric pressure. At 50.7 kPa (0.5 atmospheres), water boils at 81.5 °C. Evaporators can be made to operate at much lower pressures than 50.7 kPa, therefore, vapour just above 100 °C can be used as the heat source for the evaporators.

Achieved environmental benefits

Reduced energy use for evaporation, i.e. by re-use of the heat from the evaporated water.

Cross-media effects

None.

Operational data

Figure 4.15 illustrates a single-effect evaporator and a typical method of operation. The condensation of live steam or cooker/drier vapour in the steam jacket provides the heat source to drive the evaporator. Vapour produced from the liquid being evaporated is condensed by the cool water sprayed into the condenser chamber. Water leaving the condenser flows through a barometric leg into an open tank. The water level in the barometric leg is higher than that in the open tank so it creates a vacuum within the evaporator, approximately equal to 74 mm Hg (9.87 kPa) per metre of water in the barometric leg. A pump may be used in place of the barometric leg to maintain the vacuum. The function of the vacuum pump is to remove non-condensable gases, such as air, from the evaporator.




Figure 4.15: Single effect evaporator

Applicability

Applicable in fat melting, rendering and fish-meal production.

Driving force for implementation

Reduced energy costs.

Example plants

Low temperature rendering systems in the US.

Reference literature

[268, Ockerman H. W. and Hansen C. L., 2000]

4.3.3.6 Ammonia stripping of exhaust vapour condensates from rendering

Description

The following example of a stripping plant for the exhaust air treatment in a biofilter describes the purification performance. The stripping plant consists of two columns which are dimensioned as follows:

Influent to the stripping plant:	75 m ³ /d
Filling body height:	~8 m
Throughput of column 1:	2100 l/h
Throughput of column 2:	3000 l/h
Column entry temperature:	~60 °C
Recirculating air stream:	5100 Nm ³ /h
NaOH demand:	~5 k/kg (nitrogen eliminated)
Ammonium nitrogen (influent):	~2000 mg/l
Guaranteed value (effluent):	150 mg/l

The exhaust vapour condensate, which is at a temperature of 60 - 80 °C, is conveyed into a container of 3 m³ volume. To prevent the emergence of foams, a defoaming agent, on a silicone base, is dosed onto the stripping input pipeline, which feeds the columns. The pH value is raised by the addition of NaOH. Air saturated with steam is fed countercurrently from the press room at a temperature of approximately 30 °C and with a waste water:air ratio of 1:1000. Neutralisation of the effluent does not occur immediately after the stripping, but only after the reconvergence with the other waste water part-streams. The exhaust air from the stripping is then conveyed through a biofilter system at a maximum rate of 122400 m³/d. The reported alternative routes for disposal of the ammonia-laden air are incineration, catalytic oxidation and acid absorption.

Achieved environmental benefits

Removal of NH₃ from exhaust vapour condensates.

Cross-media effects

These depend on how the exhaust air is treated.

Operational data

Table 4.43 shows performance data for a winter and a summer month.

Parameter	February			July		
	Influent	Effluent	% increase/ decrease	Influent	Effluent	% increase/ decrease
pH value	7.6	12.1		5.7	12.5	
Specific Conductivity (mS/cm)	3.67	8.45		6.08	14.8	
COD total (mg/l)	6168	5553	- 10	14016	12780	- 9
NH ₄ -N (mg/l)	647	64.3	- 90	931	95.4	- 90

Table 4.43: Data of a stripping plant for ammonium (average values - daily mixed samples)

Example plants

At least 2 rendering plants in Germany.

Reference literature

[163, German TWG Members, 2001, 244, Germany, 2002]

4.3.3.7 Ammoniacal-N removal from rendering condensate by ammonia conversion

Description

Ammoniacal nitrogen can be removed from exhaust vapour condensates (EVCs) by ammonia conversion. Ammonia is conveyed with the EVCs into a washing tower (converter) in a countercurrent to a nitrous solution of 50 - 60 % strength. These react producing a solution of ammonium nitrate. The concentrated ammonium nitrate solution is pumped through a filter tower in the converter. The ammonium nitrate is extracted from the tower when the desired concentration has been reached. The exhaust vapours, now freed of ammonia, are then condensed in a condenser into acid exhaust vapours.

By adding urea, the ammonium nitrate solution gained in this way can be turned into a 28 % ammonium-nitrate urea solution, which can be used in agriculture as a high nitrogen ratio fertiliser.

For the operation of such a converter, it is a requirement that the exhaust vapours do not carry any solids. Cyclones or other suitable means of separation must therefore be installed upstream of the converters. Volatile carbon acids in the exhaust vapours are mainly caused by high temperatures ($> 130\text{ }^{\circ}\text{C}$) during the drying process.

Achieved environmental benefits

Removal of ammoniacal nitrogen from the condensates produced from rendering.

Example plants

At least 3 rendering plants in Germany.

Reference literature

[163, German TWG Members, 2001, 244, Germany, 2002]

4.3.3.8 Bioscrubber – general

Description

Biological scrubbers work through the microbial decomposition of air pollutants absorbed in the scrubbing medium. The absorbent is a scrubbing medium containing a high concentration of micro-organisms, such as activated sludge. The bioscrubber can be operated in several stages, using absorbents of different pH values to absorb components of differing chemical composition, thereby achieving decomposition to as great an extent as possible.

The micro-organisms can also be established as a filter film on built-in elements or on packing, i.e. trickle bed reactors.

Nutrients for the microbes are added to the absorbents in controlled quantities.

Achieved environmental benefits

Can reduce odour emissions by 70 - 80 %.

Cross-media effects

The requirement for water and air to be circulated makes this abatement technique relatively energy intensive.

Sludge is produced which then needs to be thickened, dehydrated and removed. The waste water produced needs to be sluiced to prevent scaling and to prevent it from inhibiting microbiological activity.

Operational data

The gas to be treated is passed countercurrent against a flow of water containing a population of microbes suitable for oxidising the malodorous pollutants. The treatment is undertaken within a “tower” containing a packing medium on which the microbial growth is supported. Bacteria from activated sewage sludge can be used to seed the packing. The water is circulated through the absorber and nutrients are added as required. The pH and nutrient balance are particularly important to prevent biomass from accumulating within the packing and causing a reduced circulation and flow and ultimately a blockage, if not periodically removed.

Fluctuations in the conditions of the airstreams can have a large impact on the performance.

The performances in Table 4.44 have been reported.

Pollutant	Concentration at 15 - 40 °C and atmospheric pressure	Performance (% removal)
Volatile organic compounds	400 – 1000 mg/m ³	80 - 95
Odour	> 20000 OU/m ³	70 - 90
H ₂ S	50 – 200 mg/m ³	80 - 95
NH ₃	100 – 400 mg/m ³	80 - 95
Mercaptans	5 – 100 mg/m ³	70 - 90

Table 4.44: Reported performance data for a biotrickling installation

Applicability

Unsuitable for toxic and high concentrations of acidifying substances. The technique is not suitable for very poorly soluble components.

Economics

Investment costs of EUR 5000 – 15000 for a biofilter treating 1000 Nm³/h have been reported. Running costs are relatively high, due to the energy requirements for the water circulation.

Example plants

A rendering plant in Denmark.

Reference literature

[241, UK, 2002, 242, Belgium, 2002, 266, Tauw, undated]

4.3.3.9 Wet scrubbing – general

Description

The concentration of malodorous substances in waste gases can be reduced by means of a waste gas scrubbing process using a scrubbing fluid (absorption agent). The absorption of a substance by the scrubbing fluid is a balance reaction which depends on the solubility and vapour pressure of the substance under the prevailing temperature and pressure conditions; the contact area; the residence time and the ratio of the gas flowrate to the liquid flowrate. The process can be optimised by atomising the scrubbing fluid and by coating absorbers on support material to maximise the surface area exposed.

Water is frequently used as a preliminary scrubbing fluid to remove dust and droplets of fat, which could otherwise interfere with the activity of the absorbent, as well as to remove some of the nitrogenous compounds. The use of water alone, even in several stages, is not sufficient to reduce odour emissions to acceptable levels. It is, therefore, usually followed by exposure to acid or alkali oxidising streams.

Gas absorbers are essentially gas-liquid contacting devices where vapours and gases are absorbed from a contaminated exhaust stream into chemical solutions. This liquid phase is generally recirculated, with a small quantity being continually bled off and an equal amount of fresh reagent being added. Malodorous pollutants are absorbed into appropriate chemical solutions-oxidants.

Achieved environmental benefits

Odour reduction.

Cross-media effects

Waste water is generated. Generally in installations there is inadequate separating capacity and a lack of suitable means of feedback control for the metering of chemicals. In Germany, there have consequently been no new investments in chemical scrubbers for the past several years, not even for use in old plants.

The use of oxidants can lead to the formation of malodorous compounds and poor liquid effluent management and can create a secondary odour source.

Applicability

The cost effectiveness of absorbers is reduced, if the exhaust gas to be treated has a high moisture content, due to their preferential absorption of water vapour.

Reference literature

[49, VDI, 1996, 241, UK, 2002]

4.3.3.10 Thermal oxidiser for combustion of vapour, non-condensable gases and room air

Description

The direct combustion of malodorous gases can be undertaken for a few seconds at 850 °C. The running cost of doing this is high in terms of the energy consumption, so expensive heat-exchange systems need to be used to minimise this.

An example thermal oxidiser comprises a 3 unit system and consists of a combustion chamber, where the gases are heated to e.g. 950 °C; a retention chamber, where the temperature is maintained for the required time, e.g. 1 - 2 seconds and a steam boiler which uses the heated gases to produce steam, which can be used. The excess heat is passed through a heat-exchanger to preheat the air and vapour going into the combustion chamber.

The system deodorises the non-condensable gases and some process air and ventilation air. It can also treat the water evaporated from raw materials and then discharge the water into the air as clean water vapour. However, there will still be some water requiring treatment in a WWTP, e.g. the washing water, some of which will come from washing the oxidiser equipment, such as in-line filters.

Achieved environmental benefits

Reduced emissions of low volume/high intensity and high volume/low intensity odours to almost 100 % efficiency and the elimination of whole vapour, thus removing the need for it to be treated in the WWTP.

Cross-media effects

A feature of the combustion systems is that they produce the greenhouse gases CO₂ and NO_x and can give rise to SO_x emissions.

The amount of NO_x emitted may be high if the raw materials are not fresh, especially in warm weather if degradation is not first prevented, i.e. by the rapid treatment or preservation of raw materials by, e.g. cooling. The continuous measurement of NO_x may be required, to monitor the combustion conditions.

Fuel is required to run the thermal oxidiser.

Operational data

Generally it is the concentrated process gases that are incinerated, particularly those containing non-condensable gases. Complete combustion must be achieved, as partially oxidised organic matter might still produce malodorous substances. The effective destruction of malodorous

emissions is achieved by paying particular attention to the temperature in the combustion chamber, keeping it at 850–950 °C, with a residence time of 1–2 s and employing turbulence/mixing and sufficient oxygen.

The sizing of the combustion chamber is important. The combustion chamber length and design is determined by the length of the flame and the requirement to achieve the required residence time and effective mixing of the gas stream with combustion air. Process gases and vapours are extracted directly from the cooker and meal presses and conveyed, via stainless steel pipework, to a collector. Dropout pots situated within the pipework remove any air-entrained solid matter within the gas stream.

Room air from other malodorous areas may also be extracted, after first being filtered to remove entrained particulate matter. It may then be preheated by an economiser and used as combustion air within the combustion chamber. See also Section 4.3.8.15, regarding the ducting of air from an incinerator installation in the incinerator.

Operation of the thermal oxidiser is managed by a PLC control system. Temperature is continuously measured in the combustion chamber and variable speed fans ensure balanced rates of combustion, extraction of process gases and steam production. There is a strong relationship between the thermal destruction requirement and the demand for steam. This includes steam venting arrangements at process shutdown and the provision of steam during periods of process start-up and downtime return.

During thermal oxidation, the objective is to completely oxidise the combustible gases. This leads to the production of pollutants such as CO₂, NO_x and possibly SO₂ and/or chlorides, plus water.

As the process destroys all of the odour from the cookers, including by destroying the non-condensable gases, the need to provide an alternative means of disposal or to treat a highly malodorous effluent is removed. If, in addition, waste water is also subject to a thermal destruction, the generation of liquid effluent is greatly reduced and even potentially removed.

The achievable emission release levels met by any installation are affected by baseline combustion conditions pertaining to the fuel being used and the character of the process gas needing to be destroyed. Additional levels of substances such as NO_x, arise from the destruction of substances present in the process air fed into the combustion chamber. The principal factor affecting the magnitude of NO_x releases is the level of NH₃ present in the process gases, which is directly related to the storage history of the raw material prior to the rendering. In order to minimise releases of ammonia and NO_x some degree of control over the raw material storage, handling and transfer at the source and at the animal by-products installation, can ensure that the materials are processed in as fresh a state as possible.

A waste heat recovery boiler integrally connected to the thermal oxidiser can use heat from the combustion gases to provide steam for use in the cooking/rendering operation.

There is some opposition to the use of this technique on the grounds of high energy consumption and capital expenditure, which may limit the feasibility of this technique to small quantities of air and/or heavily polluted air.

Case study

For a case study, a new plant was studied. It treats poultry offal in a continuous drier, followed by a screw press and a centrifuge for purification of the fat. It also hydrolyses feathers in a continuous hydrolyser, which is also used for sterilising/pressure cooking pig offal. A thermal oxidiser was installed and tested. The flue gas analysis showed that emissions were below the permitted levels. Odour emissions were not measured.

The plant has a potential throughput of 13 – 15 t/h of raw material.

The operational data in Table 4.45 was reported:

Maximum vapour flow		10000 kg/h
Maximum non-condensable gases flow	1930 m ³ /h	2500 kg/h
Maximum combustion airflow (air to be deodorised)	10800 m ³ /h	14000 kg/h
Working temperature		900 °C
Residence time		> 1 s
Steam production*		11500 kg/h, 12 Pa
* As a general rule, the amount of steam used to dry render a given raw material is 10 x x %, where x is the raw material water content, 10 x x kg of steam are used. For example, if the raw material contains 75 % water, then at least 750 kg of steam will be used.		

Table 4.45: Operational data for a case study rendering plant using a thermal oxidiser

Applicability

The equipment suppliers have concluded that the system is most suited for conventional rendering systems which do not use waste heat evaporators or similar heat recovery systems.

Economics

The equipment suppliers have calculated investment and running costs for such a system built into various conventional systems. Their calculations are shown in Table 4.48. The economy of the system is reported to be substantially improved if new investments in a conventional boiler, condensing unit and waste water treatment plant can thus be avoided.

Table 4.48 shows comparative costs for 3 different rendering processes replacing their existing boiler with a thermal oxidation system. In each case the thermal oxidiser is designed to cope with the whole vapour, including the non-condensable gases and a proportion of room extraction air from the process and to provide 100 % of the steam required by the process. The information is referenced to a throughput of 12.5 t/h of raw material, comprising 25 % dry solids, 12 % fat and 63 % water.

The total cost given is the additional annualised cost of running the thermal oxidiser system compared with retaining the existing system of steam raising boiler, condenser system and waste water treatment system. It is made up of the elements shown in Table 4.46.

Element name	Definition
Investment	The capital cost of the new thermal oxidiser
Extra fuel	The additional fuel required by the thermal oxidiser compared to that required by the existing boiler, to process those vapours that would not be processed by the boiler
Waste water saved	The amount of process vapour that is no longer condensed, but passes directly to the thermal oxidiser
Capital cost	The investment cost annualised over a 4 year period with an interest rate of 5 %
Fuel cost	The annualised cost of the extra fuel based on an oil price of EUR 200/t
Waste water	The savings in effluent treatment/disposal costs of the vapour that is no longer condensed, based on a waste water treatment cost of EUR 2/t

Table 4.46: Cost elements for replacing an existing boiler with a thermal oxidiser

The use of recuperative or regenerative heat recovery systems can improve the efficiency of the process and reduce the running costs. The comparative costs of the thermal oxidation system can also be improved if its installation prevents the need to invest in new, or replacement, boiler plant, condensers or waste water treatment facilities.

OIL price (EUR/t)	200
Waste water (EUR/t)	2
Production period(h/yr)	5000
Interest (%/yr)	5
Depreciation period (yr)	4

Raw material		
DS	25 %	3125 kg/h
F	12 %	1500 kg/h
W	63 %	7875 kg/h
Total	100 %	12500 kg/h

Reference

Wet rendering		
Steam heater		
1620 kg/h		
Steam drier		
5210 kg/h		
Total steam		
6830 kg/h		
Total condensate		
6440 kg/h		
Vapour from 1 effect		
1130 kg/h		
Oil thermal oxidiser	Load	
490 kg/h	100 %	
Oil normal boiler	Load	
0 kg/h	0 %	
Oil normal boiler	Load	
427 kg/h	100 %	

Dry rendering		
Total steam		
10910 kg/h		
Evaporation cooker		
7680 kg/h		
Oil thermal oxidiser	Load	
767 kg/h	100 %	
Oil normal boiler	Load	
0 kg/h	0 %	
Oil normal boiler	Load	
682 kg/h	100 %	

WHD		
Steam heater		
1620 kg/h		
Steam drier		
5160 kg/h		
Total steam		
6780 kg/h		
Total condensate		
6740 kg/h		
Vapour from 1 effect		
840 kg/h		
Oil thermal oxidiser	Load	
487 kg/h	100 %	
Oil normal boiler	Load	
0 kg/h	0 %	
Oil normal boiler	Load	
424 kg/h	100 %	

Reference	Plant with standard boiler and additional thermal oxidiser in addition (Capacity = 100 % load)				
Investment (EUR)	52500		575000		525000
Extra fuel (kg/h)	63		85		63
Waste water saved (kg/h)	1130		7680		840
Capital cost (EUR/yr)	141006		154435		141006
Fuel cost (EUR/yr)	63432		85229		63377
Waste water (EUR/yr)	-11300		-76800		-8400
Total (EUR/yr)	193138		162864		195983

Table 4.47: Consumption, emission and economic data for a thermal oxidiser for the combustion of vapour, non-condensable gases and room air in rendering [194, EURA, 2000]

Driving force for implementation

Elimination of intense malodorous gases, especially the non-condensable gases produced during rendering.

Example plants

Rendering plants in Ireland, Spain and the UK.

Reference literature

[134, Nordic States, 2001, 168, Sweeney L., 2001, 194, EURA, 2000, 241, UK, 2002, 310, Oberthur R., 2002]

4.3.3.11 Burning malodorous gases, including non-condensable gases, in an existing boiler

Description

Malodorous gases, including non-condensable gases produced during rendering may be burned in an existing boiler in the installation. Steam collected from cookers, driers and evaporators is first passed through a cyclone, to separate out the solid material. It then passes through a heat-exchanger, in which the steam is cooled. The moist air is then dewatered. The water is discharged to a WWTP and the air containing the malodorous substances, including air from the premises, is finally burned.

Achieved environmental benefits

Reportedly highly efficient and if properly operated, as efficient at eliminating odours, including intense odours, as other burning methods.

Cross-media effects

Fuel consumption is raised slightly, due to reduced boiler efficiency. It may be necessary to keep the boiler running during rendering, even when there is no demand for steam, otherwise strong odours may escape, e.g. via a biofilter, which may be only capable of treating low intensity odours. Keeping the boiler running incurs an additional fuel use.

Operational data

If the installation does not have a boiler capable of running continuously to burn the malodorous gases in places where there is a demand for abatement, an alternative treatment system may be required. The flowrate needs to be controlled to ensure complete combustion of the malodorous gases.

Applicability

Applicable to low volume high concentration odours.

Economics

High running costs can be reduced by heat recovery. The running costs can be reduced if the inevitable reduction in boiler efficiency can be minimised and provided that the installation is properly designed and built to minimise the effects of the corrosive gases treated.

Driving force for implementation

Reduction in odour emissions.

Example plants

At least one rendering plant in the Netherlands and one in the UK.

Reference literature

[167, Greek Ministry for the Environment, 2001, 200, Widell S., 2001, 243, Clitravi - DMRI, 2002, 333, Netherlands TWG, 2003]

4.3.3.12 Chlorine dioxide scrubber generated from sodium chlorite - odour abatement

Description

An alternative or complementary technique to burning malodorous rendering gases is to pass the outlet air and water through a recirculating scrubber system. In this case, the scrubber water can be treated with a chemical oxidant to remove offensive contaminants, such as H₂S, mercaptans and ammonia-based compounds, such as amines. Chlorine dioxide is effective as a chemical oxidant for controlling decomposition products generated from rendering operations, i.e. products formed by the action of putrefactive bacteria on nitrogenous matter.

A technical sodium chlorite solution can be applied through a chlorine dioxide generation system.

Cross-media effects

Chlorinated amines and AOX can be formed.

Operational data

This technique is reported to be less efficient than burning the malodorous gases.

Chlorine dioxide is reported to be more attractive than chlorine, because it does not react with the ammonia and primary amines, instead only reacting with the malodorous secondary and tertiary amines.

Reference literature

[200, Widell S., 2001, 243, Clitravi - DMRI, 2002, 347, German TWG members, 2003, 348, Austrian TWG member, 2003, 350, EFRA, 2003]

4.3.3.13 Chlorine dioxide scrubber generated from sodium chlorate - odour abatement

Description

A sodium chlorate based chlorine dioxide technology can be used as an alternative or complementary technique to burning malodorous rendering gases. The outlet air and water can be passed through a recirculating scrubber system. In this case the scrubber water can be treated with a chemical oxidant to remove offensive contaminants, such as H₂S, mercaptans and ammonia-based compounds, such as amines. Chlorine dioxide is effective as a chemical oxidant for controlling decomposition products generated from rendering operations, i.e. products formed by the action of putrefactive bacteria on nitrogenous matter.

The sodium chlorate system is claimed to have advantages over the sodium chlorite system because of its chlorine-free nature. The chlorite process reportedly adds chlorine to the system, as an unreacted agent.

Achieved environmental benefits

Odour abatement.

Cross-media effects

Chlorinated amines and AOX can be formed.

Operational data

This technique is reported to be less efficient than burning the malodorous gases.

Reference literature

[200, Widell S., 2001, 243, Clitravi - DMRI, 2002, 347, German TWG members, 2003, 348, Austrian TWG member, 2003, 350, EFRA, 2003]

4.3.3.14 Use of H₂O₂ to remove H₂S from waste water in feather rendering plants

Description

For waste water with high sulphide concentrations, e.g. from feathers processing, the reduction of the H₂S concentration is a high priority. Concentrations from about 80 - 100 mg/l of sulphide will impair the activated sludge biocoenosis and thus the biological treatment process in the downstream biological stage.

Hydrogen peroxide can be added to the waste water to oxidise the sulphide.

Operational data

To oxidise 1 kg of sulphide stoichiometrically, approximately 13 litres of 30 % hydrogen peroxide are needed. The reaction takes approximately 10 minutes. If surplus hydrogen peroxide is used the reaction time will be less, e.g. at a 50 % surplus the reaction takes approximately 5 minutes.

Example plants

A German rendering plant.

Reference literature

[163, German TWG Members, 2001, 244, Germany, 2002]

4.3.3.15 Biological waste water treatment using overpressure in conjunction with ultrafiltration

Description

The effluent, from an example animal carcase rendering plant, is initially treated by means of pressure relaxation flotation and subsequently by means of aerobic biological purification.

The effluent passes over a rotary drum screen and then to a type of pressure relaxation flotation, during which fats and lipophilic substances are largely separated out. This is done without the use of chemicals, so that the substances can be recycled back into the rendering process together with the coarse material from the rotary drum screen.

The mechanically treated effluent then undergoes an aerobic biological treatment, which is reportedly well suited for the treatment of heavily laden effluent. The solids are separated using a bag filter and the effluent is pumped to a series of 3 “activation reactors”. Activation takes place at 300 kPa, thus facilitating oxygen use. The biological treatment consists of a denitrification reactor phase, followed by 2 subsequent nitrification reactor phases. Carbon compounds (BOD₅, COD) and nitrogen compounds (N-org.; NH₄-N; NO₃-N; NO₂-N) are biologically converted into biomass, CO₂, N₂ and H₂O. Phosphoric acid and caustic soda are provided for the micro-organisms. The plant has a cooling tower, through which heat is removed from the system. The temperature in the activation reactors, is maintained at a level of 35 – 37 °C.

The process reportedly has a high operational stability, even if the effluent conditions change. In contrast to conventional biological effluent purification processes, the separation of bacterial matter from the purified liquid takes place by means of membrane filtration during an ultrafiltration process. Solids down to a particle size of 0.05 µm can be removed. Bacteria and hazardous substances adsorbed in the activated sludge are retained within the system. The formation of bulking sludge in the bioreactor can be controlled through the use of membranes.

The process is characterised by a comparatively low increase in sludge, resulting in a high sludge age being achieved, which significantly promotes the adaptation of the micro-organisms

to the effluent. In this closed system, a biomass concentration is achieved which resembles that of a conventional activation plant.

The sludge concentrate retained in the ultrafiltration unit is continuously channelled back into the activation reactor as residue. The flowrate of the residue aids mixing. Mixing in the reactor is also assisted by the injection of air into the system.

After biological purification, the effluent is channelled into a municipal sedimentation plant. The effluent can be used for scrubbing the exhaust air from the system. The water is then passed through the biological treatment process again and the exhaust air is treated in a biofilter.

The technique is summarised in Figure 4.16.




Figure 4.16: Flow diagram of biological waste water treatment using overpressure in conjunction with ultrafiltration

Achieved environmental benefits

The biological treatment reportedly achieves a COD reduction of greater than 97 % and a nitrogen reduction of greater than 90 %.

Cross-media effects

Odour emissions require abatement. In an example installation, a biofilter is used. Noise is emitted from pumps and compressors.

Operational data

Cleaning chemicals such as citric acid, nitric acid and caustic soda are used for cleaning membranes, thereby avoiding the use of complexing agents. The cleaning chemicals are channelled back into the biological treatment plant.

On average, the energy consumption for the plant is 40 kWh/m³.

The average annual water consumption for the cooling tower and for cleaning the membrane unit is approximately 1800 m³.

The excess sludge from the biological treatment has an organic content of over 90 % and it can be transported into the digestion tower of a municipal sedimentation plant or to a biogas plant. At a dry matter content of approx. 18 – 20 g/l the volume of sludge produced is in the region of 1500 m³/yr. The ultrafiltration unit can concentrate the excess sludge down to a dry matter content of approximately 35 – 38 g/l, thereby reducing the disposal volumes. It is possible to reduce the sludge disposal volume by as much as 50 % of the produced excess sludge volume.

The pumps and the compressors for supplying the air are the main sources of noise at the plant. The plant room noise level is reported to be 80 – 85 dB(A); dropping to < 45 dB(A) at a distance of 50 metres.

Applicability

Applicable for waste water which contains a high organic load, such as that from rendering plants. The breaks for maintenance and cleaning represent only 5 % of the operating time. The process has particularly low space requirements compared to other WWTPs. As a result, it is possible to reduce construction costs substantially.

Economics

The operational costs for effluent treatment are approximately EUR 8.20/m³ of effluent or EUR 7.38/t of processed raw material.

The low space requirements, compared to other WWTPs, mean that construction costs are relatively low.

Driving force for implementation

Compact plant technology, minimal space requirements, high operational reliability, high availability, safe compliance with restrictive discharge parameters and low personnel expenditure through fully automated operation.

Example plants

An animal carcase rendering plant in Germany. Some data are shown in Table 4.48 and Table 4.49.

Month	2001 financial year		
	Monthly averages processed raw materials (t)	Water volume (m ³)	Specific water volume (m ³ /t)
January	2339.8	2295	0.981
February	2309.2	1966	0.851
March	3195.3	2267	0.709
April	5065.1	3050	0.602
May	5458.5	2341	0.429
June	2359.5	2146	0.910
July	2331.2	2384	1.023
August	2804.7	1489	0.531
September	2689.5	2852	1.060
October	2735.2	2549	0.932
November	2942.4	1909	0.649
December	2579.0	1870	0.725
Average	3067.5	2260	0.784
Total	36809.4	27118	

Table 4.48: Effluent production during the 2001 financial year

Month	Effluent concentrations						
	Monthly averages						
	Inflow		Outflow				
	COD (mg/l)	NH ₄ -N (mg/l)	COD (mg/l)	NH ₄ -N (mg/l)	NO ₃ -N (mg/l)	NO ₂ -N (mg/l)	P total (mg/l)
January	4935	995	55	5.0	45	3.0	0.15
February	4136	975	58	4.5	48	4.2	0.20
March	4832	838	65	2.2	52	5.3	0.30
April	7490	1067	75	3.8	50	6.5	0.20
May	8000	1015	68	3.2	43	5.8	0.25
June	8650	1250	72	3.8	46	8.2	0.32
July	11750	1540	75	4.2	56	9.3	0.34
August	6700	1311	71	4.6	53	8.4	0.45
September	6200	1137	68	4.3	68	7.6	0.30
October	5720	917	55	4.8	65	5.8	0.35
November	3800	802	58	4.1	63	5.2	0.45
December	4445	1012	61	3.8	58	5.3	0.25
Average	6388	1072	65	4.0	54	6.2	0.30

Table 4.49: Average effluent concentrations

Reference literature

[301, German TWG, 2002]

4.3.4 Fish-meal and fish-oil production

See also Sections 4.1 and 4.3.1.

4.3.4.1 Use of fresh low total volatile nitrogen (TVN) feedstock

Description

Fish can deteriorate under the anaerobic conditions present during storage on the fishing vessel and in the raw material silos in the factory. The deterioration causes the formation of a large number of strong-smelling compounds. Besides NH_3 , TMA and other volatile basic compounds, various volatile sulphur compounds, such as mercaptans and the highly toxic and strong-smelling H_2S gas, are formed.

Achieved environmental benefits

Reduced nitrogen and sulphide content and consequently reduced odour emissions during storage, processing and waste water treatment.

Cross-media effects

None reported.

Operational data

A decrease in raw material quality (increase in TVN) results in a considerable increase in the levels of the nitrogen compounds evolved. It is reported that statistical analysis shows that even with low concentrations of phosphorus, e.g. from over-boiling, much larger increases in condensate nitrogen levels were recorded than expected from just a consideration of the nitrogen and phosphorus content of the stickwater and evaporated stickwater.

Several investigations have been carried out on the deterioration of the raw material and on odour emissions from fish-meal factories. The investigations included examinations of the odour emitted during the unloading, transport, storage and processing of industrial fish in relation to the freshness/quality of the raw material. Plots of the raw material TVN contents against time give almost straight lines which have a strong dependence on the storage temperature. Several investigations have shown that the rate of TVN formation roughly doubles for each 6 °C temperature rise.

Investigations indicate that H_2S formation starts at a raw material TVN content of approximately 50 - 100 mg N/100 g of fish. H_2S is released from the fish during mechanical handling. It has been shown that at both 6 °C and 12 °C an exponential decrease in the H_2S content (the released amount) takes place. It has also been shown that extending the storage by 4 to 5 days results in roughly a tenfold increase in odour, irrespective of the temperature.

To summarise, the results of the odour measurements show that the higher the storage temperature, the faster the odour development and the stronger and more unpleasant the odour is, at an equal odour concentration. That is, odour formed at high temperature has a more powerful and worse smell than the same “odour quantity” formed at low temperature.

Minimising the TVN at the fish-meal and fish-oil processor installation, therefore, depends on the fish being stored in the fishing vessels at low enough temperatures and for the shortest time possible, to minimise degradation and the formation of strong and intensively malodorous substances.

Fish-meal and fish-oil processors do not generally refrigerate raw materials, but ice is added on the fishing vessels. The amount depends on the temperature of the seawater and on how long the fish have to be stored in the boat before landing. In the late summer period, up to 25 % ice can be added to the fish; in the winter 10 % is considered to be sufficient. On average 15 % ice is added to all fish caught. To cool the fish down to 0 °C, ice is added at a ratio of 1.25 %, by weight of fish caught. For example, if the temperature of the fish is 4 °C, then $4 \times 1.25\% = 5\%$,

by weight of ice is added, i.e. 5 t ice/100t fish. If the temperature is 16 °C then $16 \times 1.25 = 20$ t ice/100 t fish is added. If the fish has to be stored for longer than 1 – 2 days then more ice is required to keep the temperature down to 0 °C. The energy consumption for producing 1 tonne of ice is 60 kWh. The average energy consumption per tonne of industrial fish by adding 0.15 tonne of ice would be 9 kWh. The addition of ice to the fish means that more energy must be used to remove the water, which in turn has to be treated in a WWTP.

The use of fresh raw material, leads to the production of a higher quality product, as well as a reduction in odour and waste water treatment problems.

It is reported that it is not possible to totally avoid odours, even by using fresh materials, so the use of abatement techniques will always have to be considered.

Applicability

Applicable in all fish-meal and fish-oil processing plants.

Economics

There are economic advantages associated with the production of a higher quality product from fresher, i.e. lower TVN, raw material.

Driving force for implementation

Reduced odour problems during storage, processing and waste water treatment and improved product quality.

Example plants

The 3 largest Danish fish-meal factories.

Reference literature

[155, Nordic Council of Ministers, 1997, 303, Minck F., 2002]

4.3.4.2 Use of heat from vapour from drying fish-meal in a falling film evaporator, to concentrate stickwater

Description

The waste heat from the drying of press cake, grax and evaporated stickwater can be used in a falling film evaporator, for the concentration of stickwater, to form evaporated stickwater.

In the installation which reported this technique, the specification for the air/vapour mix from the drier is a temperature of at least 87 °C and for the mix to be saturated with vapour. A 1:1 mix of air:vapour gives an acceptable energy source with suitable heat transfer properties.

Figure 4.17 and Figure 4.18 are schematic representations of two different evaporator types. The evaporator shown in Figure 4.17 is an older self-circulating evaporator, where the stickwater/evaporated stickwater circulates up through the heat-exchanger as a result of heating and vapour formation. This circulation is not shown in the figure. It shows the main steam and liquid flows. The seawater flow through the barometric condenser is typically in the order of 200 m³/h, while the evaporation rate is about 5 to 20 m³/h. The self-circulating evaporator is heated with steam from the factory boiler. This is a very common evaporator type in the fish-meal industry. This type of evaporator typically contains very large quantities of liquid and uses high temperatures in its first stage, where boiling temperatures of 120 – 130 °C are normal. The large quantities of liquid lead to long average retention times and this, together with the high boiling temperatures, causes the stickwater/evaporated stickwater to be exposed to a severe heat load.




Figure 4.17: Schematic representation of a 4-stage self-circulating evaporator [155, Nordic Council of Ministers, 1997]




Figure 4.18: Schematic representation of a falling film surplus heat evaporator [155, Nordic Council of Ministers, 1997]

The evaporator shown in Figure 4.18 is a falling film evaporator. It shows the main steam and liquid flows. The seawater flow through the barometric condenser is typically around 250 m³/h, while the evaporation rate is about 10 to 30 m³/h. The stickwater/evaporated stickwater is recirculated and then pumped to the top of the heat-exchanger. Here, the liquid is dispersed into a large number of tubes where it runs as a film down the inner walls of the tubes to the bottom of the heat-exchanger. Part of the liquid evaporates. At the bottom of the evaporator, the liquid and vapour mixture is separated. This evaporator type is typically heated with surplus steam from the driers but it can also be heated with steam from the boiler. The evaporator typically contains very small quantities of liquid and this results in short average retention times. Normally, relatively low temperatures, typically 55 – 60 °C in stage 1 and 40 - 50 °C in the last stage, are used when the evaporator is supplied with surplus vapour from the normal atmospheric pressure driers. The product is submitted to a much lower temperature in this type of evaporator than in the self-circulating evaporator, so it has a better quality.

In the falling film evaporator, a correlation has been reported between the performance of the evaporator and the amount of carry-over in the impure condensate. It is, therefore, possible to reduce carry-over by controlling the output of the evaporator. The carry-over reported at moderate output from a falling film evaporator is reported to be slightly lower than the best results from a self-circulating evaporator. No severe boiling-over was observed from the falling film evaporator.

A self-circulating evaporator, in relation to a falling film evaporator, contains very large quantities of stickwater and evaporated stickwater which remain in the evaporator during temporary stoppages. As stickwater and evaporated stickwater are very unstable, even very short stoppages can result in changes in the product great enough to have a negative effect on the discharge from the evaporating process on restarting the evaporator.

The large volume of the self-circulating evaporator requires very large amounts of water and NaOH for cleaning, which subsequently leads to large amounts of waste water.

It is claimed that use of falling film evaporators in the evaporating process of the fish-meal industry improves the product, as well as reducing the environmental impact. The quality of evaporated stickwater from a falling film evaporator is reported to be considerably higher than that of evaporated stickwater from a self-circulating evaporator, due to the much lower temperatures to which the product is submitted in the falling film evaporator.

Achieved environmental benefits

Reduced energy consumption, due to using the vapour from the drier and by operating at lower temperatures. Less water contamination by product loss and cleaning substances than when a self-circulating evaporator is used.

Cross-media effects

Seawater is discharged at approximately 10 - 15 °C.

Operational data

The secondary impure condensate received little contamination due to boiling-over from the self-circulating evaporator, until unidentified technical problems occurred in the evaporator. In spite of this, the results of a statistical analysis suggest that the phosphorus content had a significant influence on the degree of pollution in the condensate. A similar effect was not seen for the secondary impure condensate of the falling film evaporator, even though it often contained as much phosphorus as the samples from the self-circulating evaporator.

The quality of the evaporated stickwater from a falling film evaporator is considerably higher than that of evaporated stickwater from a self-circulating evaporator, because of the much lower temperatures to which the product is submitted in the latter. The fish-meal extracted from the press cake, grax and evaporated stickwater, is also consequently of a higher quality.

Applicability

Applicable in all fish-meal and fish-oil factories.

Driving force for implementation

Reduced energy consumption and improved product quality.

Example plants

A fish-meal and fish-oil factory in Denmark.

Reference literature

[155, Nordic Council of Ministers, 1997, 213, Nielsen E.W., 2001]

4.3.4.3 Incineration of malodorous air, with heat recovery

Description

An installation has been described where 80000 m³/h of air is incinerated in each of 3 incinerators. The majority of the air is from the press cake, grax and evaporated stickwater drier. Other sources include air from offloading, which contributes about 5000m³/h. The air is passed through a scrubber before it is incinerated and the liquid effluent from the scrubber is treated in a WWTP.

Achieved environmental benefits

Odour abatement by 99.5 %.

Cross-media effects

High energy consumption, i.e. 1 m³ of natural gas per tonne of fish treated. It is reported that 90 - 95 % of the heat is recovered and used to heat air.

Operational data

It is reported that it is impossible to avoid malodorous air during the production of fish-meal and fish-oil, even if fresh ingredients are used. Malodorous emissions are produced during drying and evaporation. Those associated with the raw material can be reduced if the fish is processed fresh.

The inlet air is passed through one of 3 ceramic heat-exchangers at 40 - 50 °C and the outlet air is passed through one of the other 2, at a temperature of 90 - 100 °C. The air is forced through the incinerator by suction. The direction of the flow is changed about every 30 seconds, so that all 3 heat-exchangers operate in the cycle.

When the plant is running at a maximum fish throughput capacity, i.e. 250 t/h fish, the driers generate 50 t of dry air and 50 t of water vapour. Most of the water vapour condenses in the waste heat evaporator.

The incineration conditions are 850 °C for 1 second.

Non-condensable gases can reportedly be destroyed by increasing the temperature of the ceramic incinerator. It has been stated that using scrubbers with seawater will only reduce the odour problem by 50 %.

Applicability

Applicable in fish-meal and fish-oil processing factories where odour problems cannot be eliminated.

Economics

The investment costs are reported to be EUR 10000 - 15000/1000 m³/hr.

Driving force for implementation

Odour reduction.

Example plants

A fish-meal and fish-oil factory in Denmark.

Reference literature

[212, Nielsen E.W., 2001, 213, Nielsen E.W., 2001, 303, Minck F., 2002, 333, Netherlands TWG, 2003]

4.3.4.4 Washing of air with condensate instead of with seawater

Description

At one installation it was found that when condensate air was washed with seawater, it was unsuitable for treatment in a WWTP (in the installation reported, this would have been a municipal WWTP) and was discharged back to the sea, still containing the contaminants from the condensate.

The system was changed so that the air was washed/scrubbed with condensate and could consequently be directed to the WWTP. The operators of the installation chose to send a proportion of the effluent to the WWTP, thereby reducing the BOD, nitrogen and phosphorus emissions to the sea.

Achieved environmental benefits

Reduced emissions of nitrogen, phosphorus and BOD to sea. Reduced consumption of seawater.

Cross-media effects

Additional waste water treatment required.

Operational data

Table 4.50 and Table 4.51 show actual reductions in emissions of nitrogen, phosphorus and BOD to sea made possible by substituting condensate for seawater in an air scrubber. This made treatment of the scrubbing liquor in a WWTP an option.

Recipient	N (g/t fish)	P (g/t fish)	BOD (g/t fish)
Sea	137 (160)	0.68 (2)	131 (230)
WWTP	213 (condensate)	1.04 (condensate)	838 (condensate)
	25 (flotation)	5.59 (flotation)	137 (flotation)
Total	375	7.31	1106

Table 4.50: Contamination loads in waste water from a fish-meal/fish-oil factory, before substitution of seawater by condensate in an air scrubber

Recipient	g/t fish						Condensate (m ³ /t fish)	
	Before	After	Before	After	Before	After	Before	After
	N	N	P	P	BOD	BOD		
Sea	137	19	0.68	0.62	131	53	0.230	0.185
WWTP	238	356	6.63	6.69	975	1053	0.770	0.815

Table 4.51: Reductions in emissions to sea from a fish-meal/fish-oil factory, due to substitution of seawater by condensate in an air scrubber

Reference literature

[212, Nielsen E.W., 2001]

4.3.5 Blood processing

See also Sections 4.1, 4.3.1 and 4.3.3.4.

4.3.5.1 Concentration of plasma, prior to spray drying - reverse osmosis

Description

Liquid blood plasma contains a very low proportion of solids, i.e. around 8 % and a high proportion of water, which means that it requires a lot of energy for direct drying. Reverse osmosis concentrates the initial liquid plasma by filtering its water through a set of membranes until the solid content reaches 24 - 28 %.

Achieved environmental benefits

Reduced energy consumption.

Cross-media effects

Electricity consumption.

Operational data

The concentration process, by reverse osmosis, removes approximately 75 % of the initial water contained in the liquid plasma.

Applicability

Applicable to any liquid plasma.

Economics

The final drying cost of the liquid plasma is reduced by 75 %. Cleaning and maintenance of the filtering membranes is expensive.

Driving force for implementation

Reduced energy costs.

Reference literature

[271, Casanellas J., 2002]

4.3.5.2 Concentration of plasma, prior to spray drying - vacuum evaporation

Description

Liquid blood plasma contains a very low proportion of solids, i.e. around 8 % and a high proportion of water, which means that it requires a lot of energy for direct drying. Evaporation under vacuum concentrates the initial liquid plasma by filtering its water through a set of membranes until the solid content reaches 24 - 28 %.

Achieved environmental benefits

Reduced energy consumption.

Cross-media effects

Steam production and use of cooling water to condense the evaporated water from the liquid plasma.

Operational data

The vacuum evaporation process removes approximately 75 % of the initial water contained in the liquid plasma.

Applicability

Applicable to any liquid plasma.

Economics

The cost of drying the liquid plasma is reduced by 75 %.

Driving force for implementation

Reduced energy cost.

Reference literature

[271, Casanellas J., 2002]

4.3.6 Bone processing

See also Sections 4.1 and 4.3.1.

4.3.7 Gelatine manufacture

See also Sections 4.1 and 4.3.1.

4.3.7.1 Insulation of bone de-fatting equipment

Description

The bone de-fatting process emits heat in quantities sufficient to make the equipment and associated metalwork, such as walkways and handrails, hot to touch. The equipment can be insulated to minimise such heat losses and to reduce energy consumption.

Achieved environmental benefits

Reduced energy consumption.

Cross-media effects

None.

Applicability

Applicable in all gelatine manufacturing plants.

Driving force for implementation

Employee comfort.

Example plants

A gelatine manufacturing plant in Belgium.

4.3.8 Dedicated incineration of carcasses, parts of carcasses and animal meal

See also Sections 4.1 and 4.3.1.

4.3.8.1 Enclosing buildings for the delivery, storage, handling and processing of animal by-products

Description

Unloading, storage and handling can be undertaken in totally enclosed equipment (see Section 4.3.8.14) and in buildings with lockable, self-closing doors, which can be insect rodent and bird proof. The building can incorporate extraction fans through filters to prevent any dust generated from escaping and to minimise local odour problems. Material can be delivered in bulk tipper lorries and transferred directly to an unloading hopper, within an enclosed area (see Section 4.1.29). Extracted air can be burned in the incinerator to reduce odour emissions.

Achieved environmental benefits

Reduction of airborne dust and odour emissions. A reduction in the risk of spreading potential biohazards by insects, rodents and birds.

Cross-media effects

None.

Operational data

Some animal meal will break down and become dusty, but that left at the bottom of stockpiles for long periods can become compacted into large lumps which will have to be broken up sufficiently for handling and for effective combustion.

Applicability

Applicable at all installations.

Driving force for implementation

Environmental regulator permits.

Reference literature

[82, EA, 1998]

4.3.8.2 Cleaning and disinfection of delivery vehicles and equipment after each delivery

Description

After being emptied, and at the end of each working day, delivery vehicles and transport skips can be wet-cleaned and disinfected with calculated optimal amounts of sodium hydroxide or sodium hypochlorite. Wash-water can be collected and inactivated on the site, e.g. by being fed into the incinerator.

Achieved environmental benefits

Reduced odour and pest infestation.

Cross-media effects

Subsequent treatment of wash-water required, e.g. by incineration with associated emissions, or by waste water treatment also with associated problems. Sodium hypochlorite contains active chlorine. Disinfection with sodium hypochlorite, followed by incineration of the waste water provides a source of chlorine for emissions to air.

Driving force for implementation

The original driving force was lack of confidence in the sterilisation of animal meal received from numerous sources, some of them unknown. ABP Regulation 1774/2002/EC requires that *vehicles and re-usable containers, and all re-usable items of equipment or appliances that come into contact with animal by-products or processed products, must be: (a) cleaned, washed and disinfected after each use; (b) maintained in a clean condition; and (c) clean and dry before use.*

Reference literature

[164, Nottrodt A., 2001]

4.3.8.3 Carrying carcasses (not dragging)

Description

Carcasses can be carried, preferably enclosed to prevent floor contamination. Individual small carcasses may be transported in wheeled bins with hinged lids.

Achieved environmental benefits

Reduced requirement for washing with water and consequently reduced waste water treatment requirements. Reduced potential for odour from the material which would be spread throughout the installation by the dragging action.

Cross-media effects

None.

Operational data

Small quantities of carcasses and parts of carcasses can easily be transported in closed sealable bins. Larger quantities can be moved in sealable covered skips or tipper lorries and then tipped directly into feed hoppers at the incineration installation. It has been reported that carriage is very easy, even when the incinerator is on the same site as the slaughterhouse. It is possibly easier than dragging.

Applicability

Applicable to all installations handling carcasses and parts of carcasses.

Economics

Inexpensive.

Driving force for implementation

Efficiency in the movement of carcasses and parts of carcasses and prevention of contact between personnel and carcasses, especially in the case of the carcasses of diseased animals, including those from TSE confirmed or suspected animals.

Example plants

At least two slaughterhouses with on-site incinerators in Italy.

Reference literature

[65, EA, 1996, 269, Italian TWG Members, 2002]

4.3.8.4 Size reduction of animal carcasses and parts of animal carcasses before incineration

See also Section 4.3.3.2.

Description

Animal carcasses and parts of carcasses may be reduced in size to increase the surface area and to facilitate burning, particularly in an incinerator which operates in such a way that the material is suspended or regularly turned.

Achieved environmental benefits

Reducing the size of the material fed to the incinerator helps to stabilise combustion conditions which, in turn, has the following main benefits. The improved burnout that is achieved aids the destruction of organic material indicative of potential the potential presence of TSE. and improves the overall solid residue quality. There are reduced peak and overall CO emissions; reduced production of combustion related pollutants, e.g. VOCs, NO_x, dioxins and furans. There is a reduced requirement for support fuels.

Cross-media effects

Energy is consumed in the size reduction operation. There may also be increased odour emissions. The additional use of water and cleaning and disinfection agents is required.

Operational data

An example plant reported that their success in achieving good combustion of SRM, comprising cattle heads and vertebral columns, was due to the fact that they grind all material to a maximum diameter of 30 mm. Trials involving grinding the material twice did not yield any significant advantage, so a one grinding cycle is now undertaken.

The same plant reported “autothermic” conditions during the continuous incineration of parts of carcasses, at a rate of 5 t/h, but nevertheless it uses CH₄ at rate of 12 m³/h to maintain the furnace temperature, as a precaution against inconsistencies in the calorific value of the feedstock. The feedstock comprises cattle heads and vertebral columns. It is reported that considerably less CH₄ is used than would otherwise have been used to heat water in the co-located slaughterhouse if the incinerator had not been there.

Grinders equipped with knives or crushing teeth are used. They often represent critical points during processing, because they are particularly prone to wear and tear, so maintenance is important.

Size reduction may increase the risk of odour problems particularly if the equipment is not part of an enclosed and exhausted continuous system. Additional cleaning and disinfection is required.

Applicability

Applicable in all incinerators burning animal carcasses and parts of animal carcasses.

Driving force for implementation

Good combustion of the feedstock, which in the case study plant is SRM.

Example plants

At least two incinerators in Italy, burning animal carcasses and parts of animal carcasses.

Reference literature

[269, Italian TWG Members, 2002]

4.3.8.5 **Restriction of feedstock to exactly that tested during trials**

Description

Animal meal varies in terms of its calorific value, particle size range, fat and moisture content. Calculations can clearly take the type of material to be burned into account to ensure that only material which has been demonstrated to burn successfully in the trials is burned. In practice this may include a range of feedstocks, with a variety of fat:moisture:ash contents and calorific values. Permits can specify this in their authorisation conditions.

Achieved environmental benefits

Operation of the incinerator and any flue gas treatment techniques only within their design constraints, as demonstrated during trials, thereby minimising consumption and emission levels.

Cross-media effects

None.

Applicability

Applicable to all incinerators.

Driving force for implementation

Trouble free incineration, within the design constraints of the incinerator and its associated flue gas treatment techniques. Minimal consumption and emission levels.

Reference literature

[82, EA, 1998]

4.3.8.6 **Agreeing the fat:moisture:ash content of animal meal, with the renderer**

Description

If the fat:moisture:ash content of animal meal is agreed with the renderer supplying the incinerator, the conditions can be set for the optimum combustion of a consistent feedstock. This can be done within the constraints of ABP Regulation 1774/2002/EC and WID Council Directive 2000/76/EC. Calculations can clearly take the type of material to be burned into account to ensure that only material which has been demonstrated to burn successfully in the trials is burned. In practice this may include a range of feedstocks, with a variety of fat:moisture:ash contents and calorific values.

Achieved environmental benefits

Consistent and controlled incineration reduces emissions and does not place variable burdens on the flue gas treatment equipment.

Cross-media effects

None.

Operational data

Compared to incinerators which do not have dedicated feedstocks, animal by-products incinerators and particularly those used for the combustion of MBM, as opposed to raw material, have the advantage of being able to closely control feedstock composition and feed rate, and hence combustion conditions.

Driving force for implementation

The incinerator should not be used for the combustion of materials which have not been subject to trials first and which have been included in the authorisation permit from the environmental regulatory authority. A known and consistent feedstock helps to facilitate trouble-free incineration.

Reference literature

[293, Smith T., 2002]

4.3.8.7 Agreeing a specification with the renderer, regarding receipt of material manufactured to the optimal physical characteristics for incineration and associated handling and storage

Description

Co-operation between renderers and incinerator operators can take account of the risks associated with handling animal meal and the facilities available at both sites, especially for existing premises. Agreements can be made, e.g. about whether the meal should be delivered to the incinerator in tankers or bags, or whether it should be ground or pelletised.

Achieved environmental benefits

Reduced dust emissions at rendering installations and at incinerators.

Cross-media effects

If meal needs to be ground, this will require the use of energy at either the rendering installation or at the incinerator.

Driving force for implementation

Reduced dust emissions.

Reference literature

[164, Nottrodt A., 2001]

4.3.8.8 Handling and burning of animal meal as pellets

Description

Animal meal can be received, handled, stored and burned in pellet form.

Achieved environmental benefits

Reduction of airborne dust and odour emissions, at the pre-combustion stages.

Cross-media effects

Energy consumption of pelletising process.

Reference literature

[164, Nottrodt A., 2001]

4.3.8.9 Handling and burning of packaged MBM

Description

Animal meal can be received, handled, stored and burned packaged, e.g. within sealed sacks. For instance, meal may be supplied in, e.g. bags, with the intention that it is burned in those bags, e.g. for occupational health reasons to minimise exposure to material infected or suspected to be infected with TSE or to minimise exposure to dust. If so, the potential environmental impact of burning the packaging should be assessed and also taken into account.

Achieved environmental benefits

Reduction of airborne dust and odour emissions.

Cross-media effects

If the packaging material is not carefully selected, e.g. to avoid PVC, environmental harm may be caused by its combustion. See also Section 4.3.8.10. Dust emissions may increase during handling, if material is received unpackaged, unless alternative arrangements have been made to control them.

Applicability

Some rendering plants used to put animal meal in bags for distribution as animal feed, before its use in feed was banned.

Reference literature

[164, Nottrodt A., 2001]

4.3.8.10 Avoid receipt of material for incineration in PVC packaging

Description

Conditions can be stipulated by incinerator operators, demanding that material for incineration is not supplied in PVC packaging.

Achieved environmental benefits

Reduced emissions of hydrogen chloride and consequently reduced consumption of reagents for HCl control and also reduced residue accumulation from flue gas treatment.

Cross-media effects

Dust emissions may increase during handling, if material is received unpackaged, unless alternative arrangements have been made to control them.

Applicability

Applicable in all animal by-products incinerators.

Driving force for implementation

Reduced hydrogen chloride emissions, reagent consumption and flue gas treatment residue production.

Reference literature

[6, EA, 1997, 65, EA, 1996, 82, EA, 1998, 164, Nottrodt A., 2001]

4.3.8.11 Auger feed of parts of carcasses or animal meal

Description

A closed mechanical feed system which avoids the opening of the furnace during charging will prevent emissions from the furnace, the ingress of excess air and cooling. Material can be passed through a pre-breaker or shredder and then fed into the furnace using an auger.

Achieved environmental benefits

Reduced odour emissions. Reduced emissions from the furnace and reduced ingress of air, thereby potentially reducing NO_x production. Reduced fuel consumption to maintain the temperature of the combustion chamber. Improved combustion stability and control.

Cross-media effects

Energy used by the feed system.

Applicability

Widely applied in the continuous incineration of animal by-products and other materials.

Driving force for implementation

Maintenance of a consistent continuous feed to the incinerator and consequent stable incineration conditions, which the operator can control easily, possibly without supplementary fuel and which do not exceed the capacities of the flue gas treatment plant. Compliance with WID Council Directive 2000/76/EC will also lead to a system of closed feedstock loading.

Example plants

Widely applied in the continuous incineration of animal by-products and other materials.

Reference literature

[6, EA, 1997, 82, EA, 1998]

4.3.8.12 Pumping of parts of carcasses or animal mealDescription

A closed mechanical feed system which avoids the opening of the furnace during charging will prevent emissions from the furnace, the ingress of excess air and cooling. Material can be passed through a pre-breaker or shredder and then, if it is sufficiently moist, pumped into the furnace.

Achieved environmental benefits

Reduced odour emissions. Reduced emissions from the furnace and reduced ingress of air, thereby potentially reducing NO_x production. Reduced fuel consumption to maintain the temperature of the combustion chamber. Improved combustion stability and control.

Cross-media effects

Energy used by the feed system.

Applicability

Widely applied in the continuous incineration of pasty materials.

Driving force for implementation

Maintenance of a consistent continuous feed to the incinerator and consequent stable incineration conditions, which the operator can easily control, possibly without supplementary fuel, and which do not exceed the capacities of the flue gas treatment plant. Compliance with WID Council Directive 2000/76/EC will also lead to a system of closed feedstock loading.

Example plants

Widely applied in the continuous incineration of pasty materials.

4.3.8.13 Incineration of incinerator waste waterDescription

Waste water from the incineration installation and from the washing of delivery vehicles can be incinerated. The organic content of the waste water can be destroyed by incineration and the water can be evaporated.

Achieved environmental benefits

Destruction of pathogens. Reduced sewer disposal.

Cross-media effects

Increased energy may be required to support combustion when the additional moisture load from the waste water is significant and combustion is not self supporting. If sodium hypochlorite is used as a disinfectant there may be increased hydrogen chloride emissions from the incinerator.

Operational data

In an example incinerator burning SRM, all water used for the cleaning of storage and handling facilities is collected in a tank and then automatically dosed to the incinerator at a rate proportionate to the material being incinerated. The water can be used to control combustion temperatures.

If increased energy is required to incinerate the waste water, this may provide an incentive to manage the use of water and to encourage reduced wastage.

ABP Regulation 1774/2002/EC sets requirements for the collection of animal material when treating waste water from Category 1 and Category 2 processing plants and other premises in which specified risk material is removed. Incineration of the water ensures that the animal materials are incinerated too, if they are not collected separately, e.g. in sieves and gratings.

Applicability

Applicable in all animal by-products incinerators.

Economics

There may be additional costs if extra fuel is required to assist combustion. There may also be savings if the need for waste water treatment is removed.

Driving force for implementation

Confidence that all TSE risk material is destroyed. For a site dedicated to incineration, a WWTP would not be required.

Example plants

At least two slaughterhouses in Italy burning SRM incinerate all their waste water in this manner.

Reference literature

[6, EA, 1997, 82, EA, 1998, 269, Italian TWG Members, 2002]

4.3.8.14 Sealed storage, handling and charging of animal by-products to incinerators

Description

Hoppers can provide a storage method, which is relatively easy to control and which may be combined with automated, fully enclosed, transfer and handling equipment. Material can be delivered in, e.g. bulk tipper lorries and transferred directly to an unloading hopper, either mechanically via conveyors/augers or pneumatically.

The storage, handling and possibly size reduction equipment, can be sealed or maintained under negative pressure and the air extracted can be used to provide oxygen for the incineration process, see Section 4.3.8.15.

Animal by-products can be introduced to the furnace without the entrainment of ambient air if the feed mechanism is designed so that it is always filled with the next batch of feedstock or the next quantity that will be drawn into the furnace. Examples of charging mechanisms include a screw conveyor feeding directly into the combustion chamber; feeding into a chute, which feeds into the combustion chamber, either directly or via either a ram mechanism, or a conveyor or by pumping.

Achieved environmental benefits

Plants burning animal meal are able to use fully enclosed feed systems to minimise biological risk and fugitive emissions. The same feed systems are able to closely control the composition and mass flowrate of the feedstock to ensure that stable combustion conditions are maintained. Sealing the process also reduces the risk of malodorous emissions from animal by-products, which may be stored for a number of days. In an example incinerator, on the same site as a slaughterhouse, the slaughterhouse slaughters cattle 5 days a week, from Monday to Friday, but the incinerator operates continuously, so material fed into the incinerator on Monday may have been in storage for up to 3 days, during which time the animal by-products can degrade and become malodorous.

Sealed charging of animal by-products contributes to providing very stable and controllable combustion conditions, due to the stable air supply and the temperature profiles. Preventing air from entering the furnace via the charging system is reported to be effective in reducing emissions from the furnace, e.g. by reducing the potential for the production of NO_x . It is also claimed that it reduces fuel consumption, by preventing the ingress of cold air, which would otherwise lead to a need for additional fuel use to maintain the temperature of the combustion chamber.

Cross-media effects

None.

Operational data

In an example incinerator, carcasses and parts of carcasses are tipped into a hopper, from which they are immediately transferred to a storage vessel which has been designed and constructed to hold the maximum quantity of material likely to be delivered to the site.

A cover may be provided for the initial hopper into which the animal by-products are tipped when they are received from the slaughterhouse, to reduce odour emissions. If the animal by-products are received fresh and are not inherently malodorous, e.g. if the incinerator is on the same site as the slaughterhouse, then typically the material will comprise fresh condemned carcasses and bones. If this material is fed into the storage vessel immediately, the cover may not serve an odour reduction purpose but it will still reduce problems arising from birds and vermin.

Storage hoppers are covered and sealed. The final feed to the continuously running rotary kiln furnace is always sealed by a fully charged screw conveyor or chute or pumped supply.

Applicability

Applicable in all incinerators burning animal by-products, whether they be carcasses, parts of carcasses or animal meal.

Economics

There is a relatively low cost associated with sealing equipment upstream of the incinerator, to prevent air ingress during charging.

Driving force for implementation

Ease of operation; maintenance of stable combustion conditions and maintenance of autothermic conditions, by preventing air from entering at ambient temperature and thereby avoiding the requirement for supplementary fuel to maintain combustion temperatures. The enclosure of raw materials can also reduce odour problems.

Example plants

Sealed hopper charging of whole carcasses and parts of carcasses is undertaken in at least two animal carcasses/parts of animal carcass incinerators in Italy.

Reference literature

[6, EA, 1997, 65, EA, 1996, 269, Italian TWG Members, 2002, 293, Smith T., 2002]

4.3.8.15 Ducting of air from the installation and the pre-combustion equipment to the combustion chamber

Description

Storage, handling and possibly size reduction equipment, can be sealed or maintained under negative pressure and the air extracted can then be used to provide oxygen for the incineration process. Air can also be ducted to the incinerator from the building in which the storage handling and grinding equipment are situated. The amount of air which can be fed to the

combustion chamber will be limited to the optimum oxygen requirements for the incineration process. An odour assessment can help to identify the areas which are most likely to lead to odour emissions and these can be selected as the highest priority for capture of air, for incineration.

The amount of air which passes through the incinerator can also be controlled. Excess air fed into the incinerator adds an additional burden on the flue gas treatment equipment. The use of small storage buildings with small openings/air inlets increases the effectiveness of capturing malodorous air.

Achieved environmental benefits

Enclosure of the process combined with continuous extraction of the air in the storage and handling equipment reduces the risk of malodorous emissions from animal by-products, which may be stored for a number of days. In an example incinerator, the incinerator is situated on the same site as a slaughterhouse, where cattle are killed 5 days a week, from Monday to Friday. The incinerator operates continuously, so material fed into the incinerator on Monday may have been in storage for up to 3 days. Without the extraction of air from the storage, handling and grinding equipment, odour problems would almost certainly arise.

Cross-media effects

None.

Operational data

At one case study site, there are two air inlets at the top of the storage vessel. The air from the vessel, as well as that from the other handling and grinding equipment between the storage vessel and the furnace, is drawn into the furnace to provide oxygen for the combustion process. This is the only source of oxygen for combustion. The furnace is in continuous operation, so this method of providing oxygen for combustion maintains the negative pressure within the storage vessel and prevents malodorous air from escaping. The air inlets to the storage vessel are protected by grills, to prevent the access of rodents and birds.

When the incinerator is shut down, especially if this is unplanned, it may be necessary to extract malodorous air from the installation and equipment to alternative treatment systems. For planned shutdowns the receipt of feedstock may be temporarily stopped, e.g. to prevent odour emissions.

This technique is not restricted to incinerators and can be used for any site that has combustion equipment installed.

Applicability

Applicable at all incinerators burning malodorous material and at other installations with combustion equipment.

Economics

There will be a cost for the ducting required to draw the air from inside the building and through the pre-combustion storage and handling equipment. The cost will depend on whether the installation has been designed so that the pre-combustion equipment is situated close to the incinerator or not. Some redesign and or sealing of air inlets at areas from where the air is extracted may also be required, to improve the effectiveness of the air capture.

Driving force for implementation

Odour reduction.

Example plants

This technique is widely used in incinerators and co-incinerators throughout Europe.

Reference literature

[269, Italian TWG Members, 2002, 350, EFPPA, 2003]

4.3.8.16 Combustion temperatures alarmed and interlocked to charging mechanisms

Description

The maintenance of adequate combustion temperatures at all times when animal by-products are in the furnace is one of the conditions required to ensure good combustion and for materials potentially infected with TSEs, the destruction of the prion.

WID Council Directive 2000/76/EC requires, amongst other things, the following *Each line of the incineration plant shall be equipped with at least one auxiliary burner. This burner must be switched on automatically when the temperature of the combustion gases after the last injection of combustion air falls below 850 °C or 1100 °C as the case may be. It shall also be used during plant start-up and shut-down operations in order to ensure that the temperature of 850 °C or 1100 °C as the case may be is maintained at all times during these operations and as long as unburned waste is in the combustion chamber.*

ABP Regulation 1774/2002/EC requires *Incineration or co-incineration plants must be designed, equipped, built and operated in such a way that the gas resulting from the process is raised in a controlled and homogeneous fashion, even under the most unfavourable conditions, to a temperature of 850 °C, as measured near the inner wall or at another representative point of the combustion chamber as authorised by the competent authority, for two seconds. and that Each line of high-capacity incineration plants must be equipped with at least one auxiliary burner. This burner must be switched on automatically when the temperature of the combustion gases after the last injection of combustion air falls below 850 °C. It must also be used during plant start-up and shut-down operations to ensure that the temperature of 850 °C is maintained at all times during these operations and as long as unburned material is in the combustion chamber.*

The combustion temperatures can be interlocked to the incinerator charging mechanism, to ensure that if the temperature falls charging is automatically halted.

Gas temperatures in the primary combustion zone and at the point of exit from the secondary combustion chamber can be continuously monitored and recorded. Audible and visual alarms can be triggered when the temperature falls below the minimum specified. The charging of the system can be interlocked with the temperature at the exit from the secondary combustion chamber.

The term “zone” in this context is described as “the volume after the last injection of combustion air where adequate turbulent conditions exist”. For example, it may be the space above the freeboard in a fluidised bed combustor, or a secondary chamber in the case of a rotary furnace”.

Achieved environmental benefits

Maintaining combustion temperatures ensures the good combustion of gases and therefore reduces emissions of products of incomplete combustion.

Cross-media effects

The operation of auxiliary burners increases fuel consumption.

Operational data

The maintenance of stable temperatures together with constant flowrate and consistent material composition creates stable combustion conditions and reduced emissions to air.

Stable temperatures reduce the amount of damage to the combustion chamber, due to thermal expansion and contraction. This in turn reduces the amount of downtime for maintenance and repair.

Applicability

Applied in virtually all incinerators.

Economics

Reduced maintenance requirements and minimal downtime lead to reduced costs.

Driving force for implementation

Legislative requirements, i.e. *Directive 2000/76/EC of the European Parliament and of the Council of 4 December 2000 on the incineration of waste* and ABP Regulation 1774/2002/EC.

Example plants

Virtually all incinerators.

Reference literature

[6, EA, 1997, 82, EA, 1998]

4.3.8.17 Bubbling fluidised bed (BFB) incineration of animal by-products

Description

The disposal of crushed animal carcasses and animal meal as waste, by incineration, can be undertaken in a BFB incinerator.

The furnace may be sensitive to the size, fat content and moisture content of the feedstock, so pretreatment may be important. Fluidised bed furnaces are usually designed with the gas residence time built into the top of a single furnace instead of in a secondary chamber.

The process, showing incineration of MBM, is summarised in Figure 4.19.




Figure 4.19: 40 MW twin stream MBM fluid bed combustion facility
[199, PDM Group and Wykes Engineering (Rushden) Ltd, 2000]

The MBM is taken from storage, or directly from a rendering plant and ground to an optimum size for burning.

Conditioning liquor is then added to the MBM, to make a sludge, to ensure that the MBM does not flash-off before it is properly combusted. The conditioning liquid may be water and/or it may include effluent from rendering, which comprises waste water and liquid condensate. The amount added will depend on the condition (fat:moisture:ash) of the MBM. If too much water is added the MBM fuses and builds up on the incinerator wall.

The velocity of the combustion air through a preheated bed of inert particles causes the bed to fluidise and gives the appearance of a boiling liquid. At a pre-determined bed temperature the MBM is fed into the top of the BFB at a controlled rate. Due to the fluidising motion the MBM particles are evenly distributed throughout the bed and are rapidly combusted.

Achieved environmental benefits

For untreated animal by-products, the following environmental benefits have been reported. Reduced microbiological risks due to good combustion. This has in part been achieved by preventing the formation of liquid organic and aqueous wastes and by preventing run-out and the pooling of liquid (fat and water), during combustion. This in turn improves the potential for the residues to be recycled. Both WID Council Directive 2000/76/EC and ABP Regulation 1774/2002/EC require the residues to be *minimised in their amount and harmfulness* and to be *recycled, where appropriate*.

Low CO emissions have also been reported and considering the high N-content in animal carcasses, low NO_x emissions were reportedly achieved. The NO_x emissions were reported to be lower than for the wood chips they replaced in the trial described under “Operational data” below.

It has been reported that consultant experts in incinerators involved in a project where 60 % of the feed was minced animal by-products, have sufficient evidence to believe that a BFB incinerator specifically built for the incineration of animal waste will be able to incinerate 100 % animal waste and that such incinerators could work autothermically [298, Widell S., 2002].

For MBM, the following environmental benefits have been reported. Destruction of TSE-risk materials has been claimed, by destroying proteins and producing an inert inorganic ash suitable for disposal to landfill. The ash is also reported to have a potential commercial use. Emissions of gases and dust are reported to be within the limits prescribed in WID Council Directive 2000/76/EC. When the MBM starts burning it becomes self-combusting, so supplementary fuels are not required.

The conditioning liquid added to the MBM, to make a sludge before incineration, may include effluent from rendering, which comprises waste water and liquid condensate, which would otherwise have to be treated using another technique.

BFB incinerators reportedly operate at temperatures at which a proportion of acid gases such as SO₂ and HCl can be absorbed into the alkaline bed material, i.e. the bone ash.

For both animal carcasses and animal meal incineration, the heat generated can be used to produce electricity, hot water or steam and these can be used either in on-site associated activities, or off-site. Malodorous process gases and air can be burned, at no additional cost. The granulated bed provides continuous attrition of the burning material, removing the char as it forms and exposing fresh material for combustion. This assists with increasing the speed and completeness of combustion.

Cross-media effects

Emissions to air SO₂, HCl, NO_x and CO and additional energy use due to the requirement for the destruction of protein to destroy BSE prions and to fluidise the bed.

Operational data

The technique is more established for the dedicated incineration of animal meal than untreated carcasses and parts of carcasses, nevertheless it has been demonstrated to be effective in the treatment of carcasses if they are reduced in size before incineration.

Trials have been carried out for the incineration of animal carcasses, including one where wood chips were replaced with animal waste material, mainly consisting of fallen stock crushed into a pulp. There was no addition or removal of contents, such as water and no pretreatment was undertaken. A 10 - 11 MW BFB incinerator was used. As the feedstock was intended to be injected continuously into the boiler, a nozzle was developed which could inject the material in a proper way. An optimal particle size of the material was crucial for a proper injection. The technical staff responsible for the trial claimed that a substitution of up to 100 % is technically possible using a BFB boiler specifically designed for animal fuel combustion, taking into consideration the humidity of the fuel.

The suspension of the finely divided material in the fluidised bed allows it to be burned without run-out and pooling of liquid, which could result in insufficient combustion and the requirement for the material to be returned to the incinerator.

In an example plant burning MBM, the BFB bed is constantly fed and topped up by ash produced by the incineration process. To avoid it becoming too heavy the excess is removed. The air from the fluidising fan pushes the fines upwards and the heavier bed ash particles drop down. These are inorganic bone particles and they are transferred to store, pending disposal to landfill.

Malodorous air from storage areas and handling equipment can be used as an oxygen source. The BFB incineration temperature can also destroy the malodorous compounds.

CaCO₃, in the form of limestone, can be added to the BFB, to reduce the emission levels of NO_x, SO_x and HCl.

The hot gas generated in the combustion process is transferred into a specially designed waste heat recovery boiler. The waste heat from an installation burning 4750 tonnes per week in 2 incinerators is used to produce steam with a pressure of 4.5 million Pa (45 bar). Alternatively, it can produce 17 tonnes of steam per hour and 3.5 MW of electricity, or alternatively again it can be used exclusively for power generation, i.e. to generate 7 MW of electricity.

The hot gas carries minute particles of entrained ash from the BFB. Some of this ash will deposit on the outside of the vertical boiler tubes, within which water evaporation is taking place. A specially designed system periodically blows off this “fly ash” into a collecting hopper.

The fly ash laden air is then passed through sodium bicarbonate, to neutralise the flue gases and to remove HCl and SO₂.

The fly ash content of the air is then reduced using special-texture membrane filters which reduce the emitted dust levels to less than 10 mg/m³. The filter banks self-clean automatically and the resultant fly ash, which has the consistency of talcum powder, is collected and transferred to storage. The ash is then mixed with sodium bicarbonate and water and sent for landfill.

In-line continuous computerised emission monitoring equipment, with fail-safe alarms, is fitted between the filters and the final exhaust stack.

Several dedicated MBM incinerators operate in the UK. Emission data both before and after flue gas treatment are shown in Table 3.42. Further data are given in Table 3.43.

Table 4.52 shows the reported performance of the example plant incinerator compared with those prescribed in WID Council Directive 2000/76/EC [195, EC, 2000].

Releases to air		Performance associated with BAT ⁽³⁾	
		Typical	Monitoring
SO ₂	(mg/m ³)	< 30 ⁽²⁾	Continuous
HCl	(mg/m ³)	< 10 ⁽²⁾	Continuous
HF	(mg/m ³)	n/a	
NO _x	(mg/m ³)	< 175 ⁽²⁾	Continuous
CO	(mg/m ³)	< 25 ⁽²⁾	Continuous
VOCs	(mg/m ³)	< 10 ⁽²⁾	Periodic
Dust	(mg/m ³)	< 10 ⁽²⁾	Continuous
Dioxins and furans	(ng/m ³)	< 0.1 ⁽⁴⁾	Periodic
Heavy metals total (Cd, TI)	(mg/m ³)	< 0.05 ⁽⁵⁾	
Heavy metals (Hg)	(mg/m ³)	< 0.05 ⁽⁵⁾	
Heavy metals total (Sb, As, Pb, Cr, Co, Cu, Mn, Ni, V)	(mg/m ³)	< 0.5 ⁽⁵⁾	
NH ₃	(mg/m ³)	< 10	
Residence time	> 850 °C	3.5 s	
Oxygen	(minimum after last injection)	9 %	Continuous
Pressure, Temperature, Water vapour; Volumetric flow			Continuous
Ash - (total carbon)		< 1 % ⁽⁶⁾	Periodic
Ash – (total protein) (Aqueous extract) (mg/100g)		0.3 – 0.6	Periodic
⁽²⁾ Releases control – “95 % percentile <u>hourly</u> average over 24 hours”. Measurements at 273 K (temp.), 101.3 kPa (pressure) and 11 % O ₂ dry gas			
⁽³⁾ Actual performance results operating a dry flue gas-cleaning system with bag filters and injected reagents			
⁽⁴⁾ Values measured over a sample period of a minimum of 6 hours and a maximum of 8 hours expressed as toxic equivalents in accordance with Annex 1 of the Waste Incineration Directive			
⁽⁵⁾ Values measured over a sample period of a minimum of 6 hours and a maximum of 8 hours			
⁽⁶⁾ Total organic carbon			
Note: Protein analysis is not relevant to the dedicated incineration of poultry by-products			

Table 4.52: Emission levels associated with the dedicated incineration of MBM in a fluidised bed incinerator

[199, PDM Group and Wykes Engineering (Rushden) Ltd, 2000] (adapted)

Some examples of the results of analyses of fly ash and bed ash, for amino acid concentrations are shown in Table 4.53 and Table 4.54.

Amino Acid	nanomole amino acid/g sample	µg amino acid/g sample	mg amino nitrogen/100g sample	mg protein/100g sample
Aspartic acid	2.78	0.37	0.004	0.02
Glutamic acid	Trace < 2.1	Trace < 0.31	Trace < 0.003	Trace < 0.018
Serine	Trace < 2.3	Trace < 0.25	Trace < 0.003	Trace < 0.020
Glycine	3.94	0.30	0.01	0.03
Histidine	N D < 0.4	N D < 0.06	N D < 0.002	N D < 0.011
Arginine	N D < 3.2	N D < 0.56	N D < 0.018	N D < 0.113
Threonine	N D < 2.4	N D < 0.28	N D < 0.003	N D < 0.021
Alanine	Trace < 3.3	Trace < 0.29	Trace < 0.005	Trace < 0.029
Proline	Trace < 1.1	Trace < 0.12	Trace < 0.001	Trace < 0.009
Tyrosine	N D < 2.0	N D < 0.37	N D < 0.003	N D < 0.018
Valine	Trace < 1.8	Trace < 0.21	Trace < 0.003	N D < 0.016
Methionine	N D < 2.3	N D < 0.35	N D < 0.003	N D < 0.020
Isoleucine	2.80	0.37	0.004	0.02
Leucine	2.54	0.33	0.004	0.02
Phenalanaline	28.98	4.79	0.04	0.25
Lysine	N D < 2.7	N D < 0.39	N D < 0.007	N D < 0.047
Total	41.04	6.15	0.06	0.36

Table 4.53: Analysis of fly ash from BFB incineration of MBM for amino acids [199, PDM Group and Wykes Engineering (Rushden) Ltd, 2000]

Amino Acid	nanomole amino acid/g sample	µg amino acid/g sample	mg amino nitrogen/100g sample	mg protein/100g sample
Aspartic acid	4.62	0.62	0.01	0.04
Glutamic acid	Trace < 2.1	Trace < 0.31	Trace < 0.003	Trace < 0.018
Serine	5.36	0.56	0.01	0.05
Glycine	9.22	0.69	0.01	0.08
Histidine	0.97	0.15	0.004	0.03
Arginine	Trace < 3.2	Trace < 0.56	Trace < 0.018	Trace < 0.113
Threonine	Trace < 2.4	Trace < 0.28	Trace < 0.003	Trace < 0.021
Alanine	3.58	0.32	0.01	0.03
Proline	2.64	0.30	0.004	0.02
Tyrosine	N D < 2.0	N D < 0.37	N D < 0.003	N D < 0.018
Valine	2.47	0.29	0.003	0.02
Methionine	Trace < 2.3	Trace < 0.35	Trace < 0.003	Trace < 0.020
Isoleucine	2.22	0.29	0.003	0.02
Leucine	3.38	0.44	0.005	0.03
Phenalanaline	27.23	4.50	0.04	0.24
Lysine	4.26	0.62	0.01	0.07
Total	65.94	8.79	0.10	0.63

Table 4.54: Analysis of bed ash from BFB incineration of MBM for amino acids [199, PDM Group and Wykes Engineering (Rushden) Ltd, 2000]

Applicability

BFB incinerators can be used to burn animal carcasses, if the feedstock is reduced in size to enable it to be injected into the fluidised bed, suspended and burned. They can also be used to burn animal meal.

Driving force for implementation

ABP Regulation 1774/2002/EC and consequently WID Council Directive 2000/76/EC.

Example plants

Several BFB incinerators dedicated to the incineration of MBM operate in the UK.

Reference literature

[82, EA, 1998, 164, Nottrodt A., 2001, 199, PDM Group and Wykes Engineering (Rushden) Ltd, 2000, 200, Widell S., 2001, 325, Smith T., 2002]

4.3.8.18 Circulating fluidised bed incineration of animal by-productsDescription

In circulating fluidised beds, the feedstock is introduced to the fluidised bed, together with recirculated bed material, from the cyclone at the exit of the combustion chamber. High air velocities carry the granulated bed material and the feedstock up through the combustion zone to the top of the combustion chamber, i.e. the freeboard. The material then passes through a hot cyclonic collector. Hot gases pass through the cyclone and the majority of solids drop to the bottom of the cyclone and are reinjected into the bed of the furnace. Uncirculated flue gases pass to heat recovery and flue gas treatment processes.

The feedstock is introduced between the cyclone and the reactor bed, via a screw conveyor, from a holding silo. No atomisers or special nozzles are required to introduce the waste. A combustion air fan provides air to the bed for fluidisation and combustion. The furnace draft is maintained by an induced draft fan downstream of the cyclone.

The retention time of the material in the furnace is controlled by controlling the discharge from the ash cooler. Not all of the cyclone bottom ash is recirculated. Some is removed via an ash conveyor. The speed of this conveyor determines the rate of removal of material, so decreasing the speed increases the retention time. This feature can, in appropriate circumstances, allow lower combustion temperatures, with consequent lower supplementary fuel requirements and less refractory damage and maintenance.

Achieved environmental benefits

For animal meal, it has been claimed that TSE-risk materials can be destroyed, by destroying proteins. The heat generated can be used to produce electricity, hot water or steam, which can be used either in on-site associated activities, or off-site.

Cross-media effects

Emissions of SO₂, HCl, NO_x and CO to air and additional energy use due to the requirement for the destruction of protein to destroy BSE prions and to fluidise the bed.

Operational data

At an example plant, a trial was undertaken using 100 % animal meal, with a calorific value in the range 17 – 21 MJ/kg, a thermal load of approximately 9 – 12 MW and a throughput performance of 1550 to 2550 kg/h. It is reported that if in the same fluidisation bed, the throughput was changed to 2500 – 7500 kg/h, then a thermal output of 4.8 – 9.7 MW would be achieved.

The incineration in the circulating fluidised bed was carried out at a minimum temperature of 850 °C. The gas residence time was controlled to approximately 4 s, by setting the ash removal rate. The measuring system for testing the prescribed minimum dwell time of 2 s and the temperature requirements was located between the two return cyclone separators specifically, between the top of the furnace head and the inlet to the boiler.

The hot flue gases were directed from the cyclone, where they were separated from the heavier solid matter. SNCR was used for NO_x removal, by injecting urea into the flue gas stream between the return cyclone and the waste heat boiler, at a temperature of > 850 °C. The boiler was used for heat recovery. Further cooling plus inorganic chlorine and sulphur dioxide

removal was achieved using a scrubber containing calcium hydroxide in suspension. Carbon was injected to remove dioxins, furans and heavy metals. A fibrous filter was used for dust removal. Prions were not detected in the ash and it was therefore deduced that the proteins had been destroyed.

The achieved emission levels from this trial with 100 % animal meal incineration are illustrated in Table 4.55.

Parameter	Average annual measured levels (mg/m ³)	WID Council Directive 2000/76/EC limits	
		Daily average value (mg/m ³)	Half-hourly average value (mg/m ³)
Total dust	0.34	10	30
Gaseous and vaporous organic substances, expressed as total organic carbon	0.032	10	20
Hydrogen chloride (HCl)	2.83	10	60
Sulphur dioxide (SO ₂)	24.22	50	200
Nitrogen monoxide (NO) and nitrogen dioxide (NO ₂), expressed as nitrogen dioxide ⁺	120.13	200	400
CO*	17.95		
Hg and its compounds, indicated as Hg	0.0004	0.03	0.05 average determined through relevant sampling
⁺ Until 1 January 2007 and without prejudice to relevant Community legislation the emission limit value for NO _x does not apply to plants only incinerating hazardous waste. *The following emission limit values of carbon monoxide (CO) concentrations shall not be exceeded in the combustion gases (excluding the start-up and shut-down phase): - 50 milligrams/m ³ of combustion gas determined as daily average value; - 150 milligrams/m ³ of combustion gas of at least 95 % of all measurements determined as 10-minute average values or 100 mg/m ³ of combustion gas of all measurements determined as half-hourly average values taken in any 24-hour period. Exemptions may be authorised by the competent authority for incineration plants using fluidised bed technology, provided that the permit foresees an emission limit value for carbon monoxide (CO) of not more than 100 mg/m ³ as an hourly average value.			

Table 4.55: Emissions incinerating 100 % animal meal in a circulating fluidised bed

Example plants

A trial dedicated to the incineration of 100 % animal meal was carried out at one circulating fluidised bed incinerator in Germany.

Reference literature

[244, Germany, 2002, 334, Brunner C. R., 1996]

4.3.8.19 Rotary kiln incinerator design

Description

Incineration in a rotary kiln is normally a 2 stage process, consisting of a kiln and a secondary combustion chamber. The kiln is a cylindrical shell lined with a refractory substance, which is inclined downwards from the feed end and rotates slowly about its cylindrical axis. The rotation moves the material through the kiln with a tumbling action, so as to expose fresh surfaces to heat and oxygen. Structures may be added within the kiln, to aid turbulence and to slow the passage of liquid wastes.

If a rotary kiln furnace incorporates structures which slow down the passage of liquids along the inclined structure then run-out, which could result in incomplete combustion, should not arise. Nevertheless it is normal practice to provide a burnout chamber to ensure that combustion is sufficiently complete.

Achieved environmental benefits

Conversion of “problematic” waste animal by-products into useful energy.

The opportunity to co-incinerate offensive liquid waste products and effluents.

Adequate combustion reduces microbiological risk and prevents the formation of liquid organic and aqueous wastes, by preventing run-out and the pooling of liquid (fat and water) during combustion. This in turn improves the potential for the residues to be recycled. Both WID and ABP Regulation 1774/2002/EC require the residues to be *minimised in their amount and harmfulness* and to be *recycled, where appropriate*.

Cross-media effects

Emissions to air and energy consumption to turn the kiln.

Operational data

Air velocity, which depends on the fans, burners and furnace diameter and rotational speed is important for minimising dust emissions and to achieving good burnout. The furnace length needs to be long enough to minimise the load on the secondary chamber, which in turn should be designed to ensure adequate turbulence.

Table 4.56 shows the analysis of ashes from a rotary kiln incinerator dedicated to the incineration of SRM comprising cattle heads and vertebral columns.

Analysis	Value	Units	Detection limit	Method
Total solid	78.6	g/100g		
Dry matter	78.2	g/100g		
Total volatile solid (organic substances)	< DL	g/100g	0.5	
Heavy metals:				
As	0.181	mg/kg		ICP/MS
Cd	< DL	mg/kg	0.05	ICP/MS
Cr	2.04	mg/kg		ICP/MS
Fe	171	mg/kg		ICP/MS
Mn	2.29	mg/kg		ICP/MS
Hg	< DL	mg/kg	0.05	ICP/MS
Ni	2.54	mg/kg		ICP/MS
Pb	0.962	mg/kg		ICP/MS
Cu	2.46	mg/kg		ICP/MS
Zn	2.47	mg/kg		ICP/MS

Table 4.56: Analysis of ashes from a rotary kiln incinerator dedicated to the incineration of SRM comprising cattle heads and vertebral columns

Applicability

Rotary kilns are suitable for the incineration of animal carcasses, parts of animal carcasses and animal meal.

Economics

This information concerns an incinerator on a cattle slaughterhouse site, for which some public funding was provided.

For an effective incinerator capacity of 0.5 t/h, i.e. 4380 kg/yr, an investment of EUR 2300000 has been reported. This has been quoted as being equivalent to EUR 0.525/kg. It has been

estimated that the cost of a 1 tonne capacity incinerator would be more than twice the cost of a 0.5 t/h incinerator.

Payback, for the case study incinerator, is reported to be difficult to measure because of public investment, but is estimated to be 4 years.

Driving force for implementation

ABP Regulation 1774/2002/EC and consequently WID Council Directive 2000/76/EC.

Example plants

At least 2 carcase incinerators at 2 cattle slaughterhouses in Italy.

Reference literature

[82, EA, 1998, 248, Sorlini G., 2002, 269, Italian TWG Members, 2002]

4.3.8.20 Continuous incineration

Description

Continuous incineration involves the continuous operation of an incinerator without the repeated heating and cooling associated with batch processes.

Achieved environmental benefits

The main environmental benefit of continuous incineration is that it avoids the emission peaks associated with start-up and shutdown. When a combustion temperature is reached and maintained with a steady supply of feedstock, the emissions to air are more uniform. Consequently, the emissions per tonne of feedstock are lower. Abatement equipment can be designed and run to lower emissions, with a consequent lower energy use and chemical consumption. Less supplementary fuel is required for continuous incineration than for batch incineration, since the feedstock continues to act as a fuel to maintain the combustion temperature. For batch incineration, as the feedstock is consumed additional fuel is required to complete the combustion process.

Continuous incineration may provide a faster disposal route for animal by-products and may reduce odour problems associated with the storage and handling of putrescent materials. Incineration before malodorous substances are formed may be achievable, e.g. at incinerators located on the same site as slaughterhouses.

A method of treating malodorous air, i.e. the incinerator, is always available, except when the incinerator is stopped for, e.g. maintenance.

Cross-media effects

None reported, compared with batch processes.

Operational data

Maintenance problems associated with damage to the equipment, e.g. the refractory lining of the incineration chamber, caused by frequent heating and cooling during batch incineration are avoided.

Applicability

Applicable when sizing new incinerators to process anticipated feedstock throughputs. Existing incinerators may maximise their inputs of animal by-products required to be incinerated to achieve their full capacity and to run on a continuous basis.

Economics

Reduced maintenance costs.

Driving force for implementation

Reduced emissions, increased stability of operation and reduced maintenance time and expense.

Example plants

Numerous incinerators burning a wide variety of feedstocks, including rotary kilns burning animal carcasses and BFB incinerators burning MBM.

4.3.8.21 Provision of an ash burnout chamberDescription

Burnout of solid waste is important to ensure the destruction of microbiological hazards and dioxins. It also prevents biological attack of the ash afterwards, e.g. in a landfill site. Adequate combustion also assists in ensuring that the residues *shall be minimised in their amount and harmfulness*, thus increasing their potential for recycling, where appropriate, which is a requirement of both WID Council Directive 2000/76/EC and ABP Regulation 1774/2002/EC.

Achieved environmental benefits

Reduced biohazard risk from, e.g. TSE prions.

Cross-media effects

None.

Operational data

The requirement for an ash burnout chamber will depend on the reliability of the main combustion zone in achieving adequate combustion for the designated throughput. They are usually provided as part of the rotary kiln incinerator system and are not generally required as part of BFB incinerators.

A “loss on ignition” test involving taking an ash sample, heating it to combustion temperature in the presence of air and measuring the weight loss can be used to monitor good performance.

Applicability

Applicable in all incinerators where reliable combustion cannot be achieved in the main combustion zone.

Driving force for implementation

Compliance with WID Council Directive 2000/76/EC and ABP Regulation 1774/2002/EC.

Reference literature

[65, EA, 1996]

4.3.8.22 Automated continuous de-ashingDescription

De-ashing can be enclosed and automatic for continuous systems. The combustion zone, therefore, is then reserved for the adequate incineration of the feedstock. The sealed system prevents the ingress of air during de-ashing and thereby allows continued stable combustion conditions to be maintained. This results in reduced emissions to air and/or, a lower requirement for flue gas treatment systems.

Achieved environmental benefits

Minimal airborne dust emissions.

Cross-media effects

Energy consumption associated with the operation of the automated de-ashing system.

Operational data

A screw conveyor can transfer the ash directly to a covered collection vessel. An example continuously operating rotary kiln furnace has a screw conveyor fitted to remove ash, which has first been cooled by quenching.

Applicability

Applicable at all continuous incinerators.

Driving force for implementation

Occupational health and reduced airborne dust emissions.

Reference literature

[82, EA, 1998]

4.3.8.23 Vacuum cleaning of ash - not sweeping

Description

The vacuum collection of ash, during de-ashing or cleaning up spillages, can be done using a high efficiency particle filter, instead of sweeping and can prevent dust from becoming airborne.

Achieved environmental benefits

Reduced dust emissions.

Cross-media effects

Energy consumption associated with the operation of the vacuum system.

Operational data

If the material is adequately burned out and allowed to cool and all de-ashing operations are enclosed and made directly into an enclosed transport skip this will reduce the risk of dust becoming airborne. Forced cooling causes dust to become airborne.

Applicability

Applicable in batch incinerators.

Driving force for implementation

Possibly occupational health and reduced airborne dust.

Reference literature

[6, EA, 1997, 82, EA, 1998]

4.3.8.24 Wet quenching of ash

Description

Collecting ash, in a quench bath, or passing it through a quenching spray can prevent dust from becoming airborne.

Achieved environmental benefits

Reduced dust emissions.

Cross-media effects

Increased water consumption.

Operational data

Dust quenching sprays can be designed and operated so that they moisten and agglomerate the surface of the ash without causing a run-off or leachate problem. They can use non-potable water. Alternatively, the ash can be collected in a quenching bath.

Wet ash can be held at an intermediate point to ensure that it is fully drained before it is transferred to the vessel which will be used to transfer it from the site. This will prevent the water from draining during transportation or at the place it is finally disposed of. The water which is drained can be returned to the quenching system.

Applicability

Applicable in all incinerators.

Driving force for implementation

Possibly occupational health and reduced airborne dust.

Reference literature

[65, EA, 1996]

4.3.8.25 Monitoring regime for emissions, including a protocol for monitoring burnout, including biohazard from TSE prions, in ash

Description

A monitoring regime can be used to measure the actual environmental performance of an animal by-products incinerator, to both establish the achievable performance and to monitor compliance with emission limit values. As a minimum, the monitoring regime should meet the requirements of WID Council Directive 2000/76/EC, notwithstanding the possibility that the achievable emission levels may be significantly lower than those required by the legislation.

Further information on monitoring is available in the “Reference Document on The General Principles of Monitoring”.

Both WID Council Directive 2000/76/EC and ABP Regulation 1774/2002/EC require that the residues *shall be minimised in their amount and harmfulness*. A protocol for monitoring burnout, including biohazard from TSE prions in ash after animal by-product incineration, can be used to double check that all of the procedures and safeguards in use are operating correctly. The *Monitoring protocol - ash and particulate testing methods and frequency (for analysis of carbon, nitrogen and amino acid content)* and the *Environment Agency - Bovine trials group, Notes on sampling of ash* are reproduced in Section 10.1.

An incinerator burning SRM in Italy measures organic nitrogen in ash, as a way of monitoring prion destruction. The residual nitrogen is measured at 105 °C. The detection limit is 0.5 g nitrogen/100 g ash.

Continuous monitors should have battery back-up to ensure that they can still record in the event of a power failure.

Achieved environmental benefits

By monitoring emissions the effectiveness of the chosen incineration equipment and associated processes, including “end-of-pipe” techniques, can be checked to see whether they are effectively preventing or controlling emissions to the environment as a whole. Underperformances can thereby be detected and rectified.

Cross-media effects

None.

Operational data

None.

Applicability

The monitoring of emissions to air is applicable in all incinerators, including those burning animal by-products. A protocol and regime for monitoring burnout, is also required and this should include a means of checking for any residual biohazard associated with TSE prions in ash.

Driving force for implementation

The legislative requirements of WID Council Directive 2000/76/EC and ABP Regulation 1774/2002/EC and the destruction of TSE prions.

Example plants

Virtually all incinerators are required by WID Council Directive 2000/76/EC, to monitor their emissions and those that are excluded from that particular legislation, do so to meet the permitting requirements of environmental regulators.

Reference literature

[6, EA, 1997, 82, EA, 1998, 278, EC, 2002]

4.3.8.26 Regular cleaning and disinfection of installations and equipment

Description

A regular, e.g. weekly, thorough cleaning of installations and equipment where animal by-products are handled will reduce the risk of diseases being spread by insects, rodents and birds and will help control the formation of malodorous substances.

Achieved environmental benefits

Reduced odour emissions. Insect, rodent and bird control.

Cross-media effects

Detergents, including disinfectants are used.

Operational data

The following example of a cleaning routine has been reported at an installation incinerating animal carcasses and parts of carcasses, including SRM. First rinse, then apply an alkaline detergent, follow with another rinse, then disinfect with 2 % chlorine solution, for at least one hour. At the same installation, the enclosed storage, handling, grinding and charging equipment is cleaned periodically and usually before maintenance, by passing wood chips through the system and then incinerating them.

Applicability

Applicable at all installations, storing, handling and treating animal by-products, except perhaps where there is long-term storage of animal meal.

Economics

Cheaper and more convenient than dealing with odour and infestation.

Driving force for implementation

ABP Regulation 1774/2002/EC. Prevention of odour and infestation by insects, rodents and birds. Prevention of the spread of TSEs and in particular BSE.

Example plants

At least 2 animal carcase incinerators in Italy.

Reference literature

[6, EA, 1997, 82, EA, 1998, 248, Sorlini G., 2002, 287, EC, 2002]

4.3.8.27 Operation of odour arrestment techniques when the incinerator is not working

Description

Technical or operational odour controls can be provided to prevent odour emissions at times when the incinerator is not working and is consequently unavailable for odour destruction using malodorous air as furnace air.

For planned shutdowns, materials destined for incineration may, depending on, e.g. the refrigerated storage capacity at the incinerator, be directed to other incinerators or if suitable facilities exist at the slaughterhouse or animal by-products installation, they may be stored there. For incinerators operating on a batch system, the downtime is generally more frequent and longer than for continuously operating incinerators.

If it is foreseeable that putrescent materials will be stored when the incinerator is not available for the combustion of malodorous air. Alternative odour abatement plant, such as biofilters, chemical scrubbers or carbon filters may be provided. Shock loading on a chemical scrubber would produce inefficient treatment during the initial stages, so this may not be a suitable technique for intermittent use. The energy used to transfer air to such equipment would replace that used to transfer it to the incinerator.

For breakdowns, arrangements for the use of alternative operational or technical means for preventing odour emissions can be put place, in case the problem cannot be rectified immediately by a readily available supply of spare parts and labour.

Achieved environmental benefits

Reduced odour emissions.

Cross-media effects

Any cross-media effects will depend on the action taken, e.g. there may be an energy use for refrigeration of any putrescent materials.

Applicability

Applicable in all incinerators burning inherently malodorous and/or putrescent materials.

Driving force for implementation

Reduced odour emissions.

Reference literature

[65, EA, 1996]

4.3.8.28 Biofilter for odour abatement when the incinerator is not operating

Description

Odours may be produced when the incinerator is not operating and available for odour abatement. The use of a biofilter may be effective for controlling low intensity odours from inherently malodorous and/or putrescent materials. Further information is available in Section 4.1.33.

Achieved environmental benefits

Odour abatement.

Applicability

Biofilters require a high surface area.

Reference literature

[65, EA, 1996]

4.3.8.29 Carbon filter for odour abatement when the incinerator is not operating

Description

Carbon filters can be used for odour abatement, especially when the total quantity of organic compounds is small. However, they can lead to a significant solid waste, which has to be disposed of. If it cannot be recovered it may be burned in the incinerator. This destroys the malodorous compounds and recovers the energy content of the carbon.

Achieved environmental benefits

Odour abatement.

Cross-media effects

There may be energy consumed during the regeneration of the carbon.

Operational data

Carbon filters can be sized according to the needs of the installation and do not require a large ground space. They are not especially sensitive to intermittent use, or shock loading, so they are relatively easy to use effectively at short notice.

Applicability

Applicable in all incinerators burning inherently malodorous and/or putrescent material.

Driving force for implementation

Reduction of odour emissions.

Reference literature

[65, EA, 1996]

4.3.9 Land spreading/injection

See also Sections 4.1 and 4.3.1.

Techniques for the land spreading of manure are described in the *Reference Document on Best Available Techniques for Intensive Rearing of Poultry and Pigs* [304, EC, 2002].

4.3.9.1 Land spreading of sludge from gelatine and leather glue manufacture

Description

The sludge from waste water treatment from gelatine and leather glue manufacture is reported to be an excellent fertiliser and soil improver. It can be applied to agriculturally utilised soil, both as a wet sludge or it can be thickened and pressed.

Achieved environmental benefits

Application of the by-products of gelatine production as fertiliser, when suitable agricultural land is available. The sludge contains calcium, nitrogen and phosphorus.

Cross-media effects

Iron, aluminium and manganese may be present and it may therefore be prudent to analyse for these.

Applicability

Applicable when soil requirements match the nutrient level of the sludge.

Economics

Cheaper than paying for landfill.

Example plants

Sludge from all gelatine and leather glue manufacturing WWTPs in Germany.

Reference literature

[244, Germany, 2002, 351, UK TWG Members, 2003]

4.3.9.2 Land spreading of solid residues from biogas productionDescription

The solid residues from biogas production may be applied as soil improvers.

Achieved environmental benefits

Utilisation of the nitrogen and phosphorus as an odourless sanitised fertiliser, in addition to the utilisation of the energy potential from slaughterhouse waste (gastro-intestinal contents, manure, material screened from waste water, fat from fat traps, sludge from sedimentation tanks and sludge from flotation tanks).

Cross-media effects

Iron, aluminium and manganese may be present and it may therefore be prudent to analyse for these.

Applicability

The application to pasture land of organic fertilisers and soil improvers, other than manure, is prohibited by ABP Regulation 1774/2002/EC. The Regulation contains the definition “*Organic fertilisers*” and “*soil improvers*” mean materials of animal origin used to maintain or improve plant nutrition and the physical and chemical properties and biological activity of soils, either separately or together; they may include manure, digestive tract content, compost and digestion residues.

Economics

Cheaper than landfill or incineration.

Driving force for implementation

Recovery of the nutrients in the by-products after use of the energy content to produce biogas.

Example plants

The land spreading of biogas residues is practised in Denmark.

Reference literature

[134, Nordic States, 2001, 287, EC, 2002, 351, UK TWG Members, 2003]

4.3.10 Biogas production

See also Sections 4.1 and 4.3.1.

4.3.10.1 Biogas production from slaughterhouse by-productsDescription

Organic matter is degraded to CH₄ under anaerobic conditions. The releases to air, water, and land from the process can be well controlled.

Recent advances in anaerobic digestion technologies have made it possible to treat an increasing diversity of by-products and waste waters. Not only can slaughterhouse waste water undergo anaerobic treatment, but manure, slaughterhouse waste, including blood, fat, and the contents of stomachs and viscera and residues can also be treated.

The co-digestion of manure and slaughterhouse waste is sometimes undertaken with industrial organic wastes.

Achieved environmental benefits

CH₄ can be recovered and used in energy production, to replace fossil fuels and thereby to reduce CO₂ emissions. Most of the nutrients remain in the treated material and, as in composting, materials can be recovered for agricultural purposes.

Cross-media effects

CH₄ and CO₂ produced during biogas production may be accidentally released to atmosphere, if adequate controls are not in place. CH₄ has a global warming potential 30 times greater than that of CO₂.

Applicability

Widely applicable. The application to pasture land of organic fertilisers and soil improvers, other than manure is prohibited by ABP Regulation 1774/2002/EC. The Regulation contains the definition “*Organic fertilisers*” and “*soil improvers*” mean materials of animal origin used to maintain or improve plant nutrition and the physical and chemical properties and biological activity of soils, either separately or together; they may include manure, digestive tract content, compost and digestion residues.

Economics

It is reported that a medium sized plant using 2000 tonnes per week of feedstock comprising 50 % poultry slaughterhouse by-products and 50 % manure could generate approximately GBP 500000/yr in gate fees at GBP 10/t and could sell around GBP 700000 of electricity per year. Such a plant would cost GBP several million to construct. (2001 costs)

Driving force for implementation

Recovery of the energy content of animal by-products and reduction of waste disposal costs.

Example plants

There are plants in Denmark and one plant treating the slaughterhouse waste, in Sweden.

Reference literature

[148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001, 222, Gordon W., 2001, 305, Porteous A., 2000]

4.3.10.2 Biogas from manure and fat containing waste

Description

Danish plants

The plants digest animal manure together with small amounts of fat-containing waste, to produce biogas. The biogas is burned in a motor/generator unit (CHP unit), to produce CO₂-neutral energy. The energy is then sold directly to electricity networks and the heat produced as a consequence of cooling the motor, is used for on-site heating, including in the biogas production process.

The plant comprises a highly efficient anaerobic digester unit; a biogas storage unit; a cleaning unit; a CHP production unit with a power interface with the local electricity utility and a heat accumulation tank.

An Italian plant

In an Italian plant 400 – 500 m³ manure and waste water sludge is mixed in a reactor vessel every day. Water, which has been heated to 90 °C using biogas, is added to maintain a temperature of 33 °C. The total volume of 8000 m³, of which 2400 m³ is added water, is mixed. After 15 – 20 days the mixture and CH₄ produced are pumped to a 4000 m³ reactor, for 10 – 15 days and from which the CH₄ is continuously bled to a 600 m³ gasholder. The gas is used to heat water and to generate energy at a rate of 250 kWh/m³ CH₄, in a 400 kV generator. At the example plant there is insufficient capacity to use all of the CH₄ produced and the excess is burned in a stack.

The residues are pumped from the base of the second reactor, mixed with polyelectrolyte and then, depending on the demand, spread directly on land or sent for composting.

Accidents are reportedly prevented by operator training and by prohibiting smoking and naked flames. The gas pipework and the gasometer water seal are inspected once every 3 months.

There are plans to modify the plant to substitute homogenised and pasteurised blood for approximately 18 % of the manure and to produce 30 - 40 % more CH₄, at a rate of 400 m³/h and to use all of this. There are also plans to pass the exhaust air, after pasteurisation, through a hot NaOH solution to remove NH₃ and then through a peat biofilter to remove malodorous substances. It is anticipated that the use of blood will increase the COD in the waste water from 1000 ppm to 2000 ppm and that the sludge will continue to be spread on land.

The CO₂ will be removed from the biogas, using water to produce H₂CO₃. Although the operators report that they do not expect the amount of H₂S produced to increase, it will be removed using FeCl₂.

German studies

German studies have been carried out on the treatment of certain wastes from fat separation or food processing in anaerobic treatment facilities at sewage treatment plants. The results for fat were considered to be “very good”, even improving the overall efficiency of the anaerobic process and producing a better yield of gas.

Achieved environmental benefits

Production of CO₂-neutral energy; the production of fertiliser from the digested manure, which can then replace chemical fertilisers; reduction of odour emissions from animal manure and the reduction of nitrogen leakage to the subsoil water.

The biogas production process favours the use of high moisture content feedstock. Other treatments use a lot of energy to remove water.

Cross-media effects

The CH₄ and CO₂ produced during biogas production may be accidentally released to atmosphere if adequate controls are not in place. Methane has a global warming potential 30 times greater than that of CO₂.

Operational data

Table 4.57 shows actual and anticipated figures for biogas, heat and power production from manure and fat containing waste. It also shows the actual or anticipated energy and fuel savings resulting from the process.

Manure (m ³ /yr)	Fat containing waste (t/yr)	Biogas produced (or anticipated) (m ³ /yr)	Electricity produced (kWh/yr)	Heat produced (kWh/yr)	Electricity saved on site (kWh/yr)	Heating oil saved on site (kWh/yr)	Straw saved (t/yr)
14600	750	750000	1400000	1960000	542900	178000	
10950	550	520000	1430000	1716000	300000	80000	
4380	550	350000	1000000	1200000	150000		125
23000	800	1000000	2600000	3120000	430000	120000	
9125	850	750000	1650000	2310000	278907		
6570	550	536100	1533246	1839895	157223		
12000	900	831420	2377420	2853433	324000	72000	40

Table 4.57: Energy, heat and economic data for biogas/CHP units using (or planning to use) manure and fat containing waste on Danish farms

Applicability

The plants referred to in Table 4.57 produce more than 75 % of the biogas from Danish farm biogas plants. The application to pasture land of organic fertilisers and soil improvers, other than manure is prohibited by ABP Regulation 1774/2002/EC. The Regulation contains the definition “*Organic fertilisers*” and “*soil improvers*” mean materials of animal origin used to maintain or improve plant nutrition and the physical and chemical properties and biological activity of soils, either separately or together; they may include manure, digestive tract content, compost and digestion residues.

Economics

Payback times for the Danish plants have been reported as 5 - 6 years. The costs of disposal are saved.

Driving force for implementation

Financial savings through electricity sales and hot water generation. Production of fertiliser from the biogas residues.

Example plants

In Denmark, more than 75 % of the biogas produced is from manure and fat containing waste. There is at least one plant in Italy. There are power stations in the UK and Germany fired by biogas produced from manure.

Reference literature

[218, Dansk Biogas A/S, undated, 287, EC, 2002]

4.3.10.3 Re-use of heat during biogas production

Description

Heat-exchangers can be used to extract heat from the material leaving the digester and this can be used to warm the incoming material.

Achieved environmental benefits

Reduced energy use to heat the raw materials for biogas production or pasteurisation.

Cross-media effects

None.

Operational data

If the material is Category 3 material as defined in ABP Regulation 1774/2002/EC, the incoming material needs to have a maximum particle size of 12 mm and needs to be heated for

pasteurisation at 70 °C, for 60 min. For the actual anaerobic digestion, the by-products are heated to a temperature approximately in the range 33 - 37 °C. The heat from the materials leaving the pasteurisation plant or the digester can be used to warm the incoming material.

Applicability

Applicable in all biogas production plants.

Driving force for implementation

Reduced energy use.

Reference literature

[222, Gordon W., 2001]

4.3.11 Composting

See also Sections 4.1 and 4.3.1.

4.3.11.1 Sufficient drainage capacity for windrow composting on a hard standing

Description

The site can be designed to prevent the ingress of rain to the windrow and to minimise the volume and load of leachate formed. Even with careful management of the addition of water, some leachate will be formed. An impermeable site surface, correctly sloped to drainage and with sufficient piping and drainage collection capacity to contain the maximum run-off anticipated, can be provided. The drainage collection vessel can be separate from those collecting rainwater and other liquid effluents. The liquid may be recirculated to moisten the compost especially early in the process, when the composting is most active. If it is recirculated, it can be stored very close to the windrow.

Slopes with gradients as low as 1:200 have been reported to be sufficient for drainage, without causing problems with vehicle movement.

Achieved environmental benefits

Preventing contamination of water courses with leachate and run-off, both of which potentially contain dissolved substances and suspended solids, which may cause pollution, or which will require waste water treatment. Leachate contains a higher concentration than run-off, because it seeps through the pile. The leachate can be recirculated and used in the process.

Cross-media effects

None.

Applicability

Applicable at all windrow composting sites.

Driving force for implementation

Prevention of leachate and run-off polluting local water courses.

Example plants

Widely applied.

Reference literature

[176, The Composting Association, 2001]

4.3.11.2 Hard standing – concrete

Description

Concrete has been described as the strongest and most durable surface that can be used. The introduction of a layer of geotextile material gives the formation more strength, helps hold the sub-base together and spreads the load on to the fill. Care needs to be taken when choosing the material between slabs to allow for the expansion and contraction and differential movement of the slabs.

Joints can be filled with material which permits expansion and contraction and prevents the passage of surface water or leachate down through the joint. Joint sealing compounds offer good adhesion to the concrete; flexibility without cracking; resistance to flow and temperature changes and are also durable and waterproof.

Achieved environmental benefits

Prevention of seepage of contaminated leachate and run-off into groundwater. Reduction in waste water contamination and treatment requirements.

Cross-media effects

None reported.

Operational data

Concrete is reported to be suitable for high volume sites on poor ground.

Economics

Rigid concrete pavement built over prepared sub-grade (e.g. soft clay/alluvium) has a reported cost of GBP 27 - 32 per square metre (2001).

Driving force for implementation

Prevention of leachate and run-off from polluting local water courses.

Reference literature

[176, The Composting Association, 2001, 210, Environment Agency, 2001]

4.3.11.3 Hard standing - asphalt or macadams

Description

A dense bitumen macadam base course has been reported to give a high grade impermeable surface with a good wearing capacity. Bitumen macadams gain their strength from using an interlocking aggregate bound by bitumen.

Asphalt surfaces are not totally impermeable and some concerns have been expressed about their use. The temperatures reached by the composting material may affect the asphalt over time. The asphalt surface may become brittle and there may be a risk of contamination of the composting material.

Achieved environmental benefits

Reduction in seepage of contaminated leachate and run-off into groundwater. Reduction in waste water contamination and treatment requirements.

Cross-media effects

Asphalt surfaces are not totally impermeable.

Operational data

Asphalts and macadams are reported to be less durable and to have a higher permeability than concrete. Storage and delivery areas may need thicker layers or concrete to withstand the action of mechanical loading shovels.

The temperatures reached by the compost may make the asphalt brittle and there are fears that asphalt residues may contaminate the compost.

Economics

Flexible asphalt pavement built over prepared sub-grade, e.g. stiff clay soil, has a reported cost of GBP 15 - 20 per square metre (2001)

Driving force for implementation

Cheaper than concrete.

Reference literature

[176, The Composting Association, 2001]

4.3.11.4 Windrow composting of animal by-productsDescription

A windrow is a long pile of composting materials, usually shaped as an elongated triangular prism. They are constructed on a hard standing and drainage is provided to collect any leachate. Water is added to the windrows as and when required for the composting process. Material being composted is turned sufficiently frequently to ensure the maximum sanitation and degradation of the total material and to keep the process fully aerobic.

Achieved environmental benefits

Furthering of recovery and recycling of the substances generated and used in the process and of waste, where appropriate.

Cross-media effects

Odour emissions from decaying inherently malodorous and putrescent animal by-products. ABP Regulation 1774/2002/EC requires most Category 2 materials to be sterilised under specified temperature, time, pressure and size conditions, before being composted. This requires energy.

Operational data

An example composting plant using slaughterhouse by-products uses 50 % slaughter sludge and rumen contents mixed with 50 % wood, by volume, to improve the structure of the windrows. It is reported that that this mixture of products allows the production of good windrows which reach a core temperature of 70 °C during the bio-oxidation step. This process reportedly produces a good quality compost which could, however, benefit from the addition of more phosphorous.

Reportedly windrow composting may potentially carry, but not necessarily so, a greater risk of odour and pest problems than in-vessel composting.

Applicability

The composting of animal by-products in windrows is applicable for by-products from slaughterhouses, e.g. lairage bedding, manure, stomach contents, intestinal contents, blood and feathers; from waste water treatment, e.g. screenings, flotation tailings and sludge; solid residues from biogas production; sludge from blood processing and sludge from WWTPs.

Economics

Composting plants dedicated exclusively to slaughterhouse by-products are reported to be simpler and cheaper than traditional composting plants. The dedicated aspect represents an effective source separation. The dedicated plants do not tend to contain the plastic, glass, or other foreign bodies in the raw material that municipal wastes contain, so technologies for compost purification are not required. A dedicated composting plant for 30000 tonnes of biomass reportedly costs approximately EUR 3000000.

The investment, operational and maintenance costs for windrow composting are lower than those for in-vessel composting. Windrow composting also requires greater levels of knowledge and skill and more labour than in-vessel composting. It also requires a greater land area.

Driving force for implementation

Reduced disposal of slaughterhouse by-products to landfill, as waste.

Example plants

There is at least one free-standing plant in Italy and one on a slaughterhouse site in the UK.

Reference literature

[148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001, 176, The Composting Association, 2001, 210, Environment Agency, 2001, 269, Italian TWG Members, 2002]

4.3.12 Manufacture of fertiliser from meat and bone meal

See also Sections 4.1 and 4.3.1.

4.3.13 Alkaline hydrolysis of animal carcasses and parts of animal carcasses at elevated temperature

See also Sections 4.1 and 4.3.1.

Description

The heated alkaline hydrolysis process effectively digests and disposes of animal carcasses and reportedly inactivates BSE agents. The animal and microbial tissues are converted into a reportedly sterile, neutral aqueous solution, which, after cooling, is discharged to an anaerobic digestion process for further treatment. The anaerobic digestion produces CH₄ gas which can be used to generate electricity or steam.

Achieved environmental benefits

Destruction of microbial risk during alkaline hydrolysis. Energy production from anaerobic digestion.

Cross-media effects

Consumption of water, although it does not need to be potable and consumption of alkali, usually 50 % solutions of NaOH or KOH. A steam raising capacity is needed to heat water, at a rate of 1 kg steam/kg feedstock. Electricity is required at a rate of 17 kW for every 4.5 tonnes of feedstock.

Operational data

Alkaline hydrolysis at elevated temperature is undertaken in insulated, steam-jacketed, stainless steel tissue digesters with lids which can either be manually or hydraulically clamped. The vessel contains a basket for the retention of bone remnants. The tissue digesters are manufactured in a range from 36 kg - 4.56 t. Animal carcasses are generally treated without any prior size reduction, without any reported reduction in effectivity of the technique.

Raw material handling arrangements reportedly depend on the scale of operation and range from manual handling to systems of rails, conveyors and chutes.

For larger scale operations a series of digesters can be installed. The process operates at 150 °C, for 3 hours and > 400 kPa pressure. It is automated during the process cycle.

The process converts proteins, nucleic acids and lipids of all cells and tissues, as well as infectious micro-organisms, to a sterile aqueous solution of small peptides, amino acids, sugars and soaps. The alkali is consumed in the process, by generating the salts of the hydrolysis products. Ash comprising the mineral constituents of the bones and teeth of vertebrates, is produced and represents approximately 3 % of the weight of original carcase/tissue. This is easily crushed by hand and can reportedly be recovered as calcium phosphate powder.

A heat-exchange for heating water can be built into the system design.

The digestion residue is discharged directly to the balance tank of the anaerobic digestion system. It has been suggested that the residues from anaerobic digestion could be used as follows: crushed bone from non-BSE risk animals as fertiliser, liquid residue from non-BSE risk animals as fertiliser. The liquid residue from BSE risk animals could possibly be evaporated to minimise the solid residue and then be disposed of to landfill or by incineration, according to relevant legislation.

For an example digester of 4.5 t capacity, the following consumption and emission levels are reported:

To the 4.5 t of animal material, between 50 - 100 % equivalent weight of water, i.e. 2.25 – 4.5 t is added. The amount depends on the animal material. The addition of alkali to the tissue digester is 14 %, for NaOH and 21 % for KOH, of the weight of the animal carcase/tissue material to be processed. 4.5 kg of raw material requires 4.5 kg of steam. The electricity requirement is 11.1 kW/t of raw material.

Applicability

At the time of writing, this technique is not permitted in the EU, due to the fact that in ABP Regulation 1774/2002/EC, it is neither listed, nor has it been approved in accordance with the procedure referred to in Article 33(2) therein, after consultation of the appropriate scientific committee.

The process is being marketed in the red and white meat and rendering industries, in preparation for potentially receiving approval under the procedures prescribed in ABP Regulation 1774/2002/EC, both in terms of BSE type risk and non-infected by-product treatment and disposal, as an alternative to, e.g. landfill.

It can reportedly be applied to a range of plant sizes, from small to very large, with the installation of multiple units being appropriate for large scale operations, for which there is a reported economy of scale. The technique may be applied as an integrated system for on-site treatment and disposal, thereby saving on transport costs and environmental damage.

Economics

A 4.5 t capacity alkaline hydrolysis tissue digester is reported to be capable of processing 18 t of animal carcase waste material per 24 hour period. If it operates 7 days per week, 52 weeks per year, the annual throughput will, therefore, be 6570 t.

The capital investment cost for a 4.5 t capacity tissue digester is calculated at EUR 20.9/t of material processed, if the capital cost is assumed to be spread over 10 years, ignoring interest charges.

The operating cost for the tissue digester is calculated at EUR 41/t of material processed.

The capital and operating costs of combined alkaline hydrolysis and anaerobic digestion systems are to some extent offset by the income from energy generation.

Driving force for implementation

The need to destroy BSE agents, without the use of incineration. The pretreatment of waste prior to landfill, to satisfy the requirements of *Council Directive 1999/31/EC of 26 April 1999 on the landfill of waste*.

Example plants

Alkaline hydrolysis is reportedly in full scale use in the US, for disposing of TSE infection risk sheep, elk and deer. Pharmaceutical research companies and medical/veterinary university research units have also installed tissue digesters for the disposal of animal and human material. They are in use in Canada for the disposal of TSE wastes. No plants are in operation in the EU, due to the current lack of approval of the technique as required by ABP Regulation 1774/2002/EC. Such approval is currently being sought.

The anaerobic digestion plants incorporated with this technique are currently applied in 100 full scale operational installations in Europe and Asia.

The combined technologies have not yet been installed on an integrated site.

Reference literature

[294, Waste Reduction Europe Ltd, 2002]

4.4 Integrated same-site activities

See also Sections 4.1, 4.2.1 and 4.3.1.

4.4.1 Integrated site - slaughterhouse and rendering plant

Description

A rendering plant may be operated on a slaughterhouse site. The by-products of the slaughter process and on-site waste water treatment may be treated on a continuous basis, thereby minimising the need for collection and transport, for use or disposal off-site, and the need for storage.

Achieved environmental benefits

Reduced energy consumption, reduced production of malodorous substances and reduced need for energy required for their treatment.

Cross-media effects

None in addition to those associated with slaughtering and rendering.

Operational data

Heat in the system can be recovered in the form of hot water and used, e.g. as cleaning water in the slaughterhouse.

The use of the tallow as a fuel, in theory could make the installation largely self-sufficient in terms of heating. At the time of writing, this is not permitted in the EU, due to the fact that in ABP Regulation 1774/2002/EC, it is neither listed, nor has it been approved in accordance with the procedure referred to in Article 33(2) therein, after consultation of the appropriate scientific committee.

Putrescible materials are used quickly, so there is minimal raw material degradation. The waste water treatment plant is not required to treat the products of decomposition and the odour problems associated with such treatment are thus avoided. The need for either a frequent

collection service, or other means of preventing odour problems such as chilling is also avoided. There are consequent energy savings.

Category 1, 2 and 3 animal by-products can either be treated in separate rendering units or in combination, although mixtures containing Category 1 materials are deemed to be Category 1 and mixtures of Category 2 and 3 materials are deemed to be Category 2 and must be treated as such, as prescribed in ABP Regulation 1774/2002/EC.

Continuous rendering minimises the storage times and ensures that the existing boiler is available for the destruction of the non-condensable gases produced during rendering.

Applicability

Applicable in all slaughterhouses.

Economics

The costs of separate collection and disposal of the various ABP Regulation 1774/2002/EC categories of animal by-products are saved. The investment and running costs of odour prevention and treatment techniques are minimised, during storage, processing and waste water treatment.

Payback periods of 2 - 3 years have been reported, for installing a rendering system in on a slaughterhouse site. The calculations included savings achieved by minimising the costs of collection, processing, cooling and concentration. They also took account of the value of saleable end-products, minus variable operating costs. Cost savings on transport, environmental protection and energy were also identified.

Driving force for implementation

Cost savings.

Example plants

Integrated slaughterhouses and rendering plants exist in 3 locations in Belgium, 1 in the Netherlands and 1 in France.

Reference literature

[321, RenCare nv, undated]

4.4.2 Integrated site - slaughterhouse and animal carcase incinerator

See also the information about rotary kiln incinerators in 4.3.8.19. The information here concerns the integration of slaughtering with incineration.

Description

Slaughterhouses with a capacity over 50 t/d can have an on-site incinerator for the destruction of TSE and SRM material.

Achieved environmental benefits

Recovery of energy for internal use, e.g. for the production of steam or hot water for use in the slaughterhouse or for other associated activities on the site, such as blood processing and meat processing. Reduced time between slaughter and incineration, therefore, the by-products are fresher and odour problems are potentially reduced. Rapid destruction of TSE confirmed, suspected or culled cases, fallen stock, dead on arrival animals and *ante mortem* condemned animals. Reduced packaging wastes. Reduced whole environmental impact associated with the transport of untreated SRM, from the risks associated with the SRM and from transport (transport between installations is outside the scope of the Directive).

Cross-media effects

None in addition to those associated with slaughtering and incineration.

Operational data

One case study incinerator, with a capacity of 1 t/h, is reportedly capable of destroying all of the SRM produced by a slaughterhouse killing 1100 carcasses daily, five days a week. The heat recovered, using a reportedly under capacity boiler, raises 2000 kg of steam per day.

Applicability

Applicable in slaughterhouses where there is sufficient space for an incinerator which can be adequately separated from the slaughterhouse to meet the requirements of ABP Regulation 1774/2002/EC.

Economics

This information concerns an incinerator on a cattle slaughterhouse site, for which some public funding was provided.

For an effective incinerator capacity of 0.5 t/h, i.e. 4380 kg/yr, an investment of EUR 2300000 has been reported. This has been quoted as being equivalent to EUR 0.525/kg. It has been estimated that the cost of a 1 tonne capacity incinerator would be more than twice the cost of a 0.5 t/h incinerator.

Payback, for the case study incinerator, is reported to be difficult to measure because of the public investment, but is estimated to be 4 years.

Driving force for implementation

Significant reduction in the amount of waste produced in the slaughterhouse requiring off-site treatment. Reduced risk of cross contamination by different sources of materials destined for rendering to make animal meal.

Example plants

Two cattle slaughterhouses in Italy have on-site rotary kiln incinerators for the direct and dedicated incineration of some of their SRM.

Reference literature

[269, Italian TWG Members, 2002]

4.4.3 Integrated site – rendering plant and animal meal incinerator

See also the information about BFB incinerators in 4.3.8.17. The information here concerns the integration of rendering with incineration.

Description

At an example site, a rendering plant and a BFB incinerator are situated on the same site. The rendering plant provides the feedstock for the incinerator. The incinerator is capable of burning malodorous gases from the rendering process, and the steam and electricity produced by the incinerator can be used for the rendering process.

Achieved environmental benefits

Integrating the rendering plant with the incinerator provides a convenient and reportedly effective means of destroying malodorous gases. These arise in rooms, storage vessels and from pretreatment and handling equipment and they include non-condensable gases which have the most intense and offensive odours, which are produced during rendering. These malodorous gases would otherwise require an alternative means of destruction. To ensure that all of the malodorous non-condensable gases are destroyed, the incinerator needs to be running all of the time when they are being produced. Many incinerators operate continuously.

The steam and electricity produced by the incineration process can be used directly in the rendering plant.

Off-site transport is not regulated under IPPC, however, by removing the requirement to transfer animal meal from the rendering site to the incinerator the environmental impact associated with transport, which is usually carried out by road, is also removed.

Data was provided for what is reported to be a typical rendering plant with on-site incineration of MBM.

Cross-media effects

Only those associated with rendering and incineration. No additional cross-media effects due to the integration of the processes have been reported.

Operational data

Figure 4.20 shows some consumption and emission data for rendering 1 tonne of animal by-products and the subsequent on-site incineration of MBM.




Figure 4.20: Consumption and emission data for rendering with on-site burning of MBM [199, PDM Group and Wykes Engineering (Rushden) Ltd, 2000] – adapted

* At the time of writing, burning tallow in a boiler is not permitted in the EU, due to the fact that in ABP Regulation 1774/2002/EC, it is neither listed, nor has it been approved in accordance with the procedure referred to in Article 33(2) therein, after consultation of the appropriate scientific committee.

The malodorous air from rendering plant rooms can be used as the incinerator air supply, because the BFB temperature can also incinerate the malodorous compounds.

Applicability

Applicable in slaughterhouses where there is sufficient space for an incinerator and in particular where the animal meal being produced has to be incinerated or co-incinerated to comply with ABP Regulation 1774/2002/EC. The rendering treatments and Categories of material used to produce animal meal which must be incinerated are summarised in Table 2.3.

Driving force for implementation

The BSE crisis in the UK.

Example plants

There is at least one BFB incinerator burning MBM on the same site as a rendering plant in the UK.

Reference literature

[199, PDM Group and Wykes Engineering (Rushden) Ltd, 2000]

5 BEST AVAILABLE TECHNIQUES

In understanding this chapter and its contents, the attention of the reader is drawn back to the preface of this document and in particular the fifth section of the preface: “How to understand and use this document”. The techniques and associated emission and/or consumption levels, or ranges of levels, presented in this chapter have been assessed through an iterative process involving the following steps:

- identification of the key environmental issues for the sector; these include energy consumption, water contamination, odour and the destruction of transmissible spongiform encephalopathy related risk materials, in line with the *Regulation (EC) No 1774/2002 of the European Parliament and of the Council of 3 October 2002 laying down health rules concerning animal by-products not intended for human consumption* [287, EC, 2002]
- examination of the techniques most relevant to address those key issues
- identification of the best environmental performance levels, on the basis of the available data in the European Union and worldwide
- examination of the conditions under which these performance levels were achieved; such as costs, cross-media effects, main driving forces involved in implementation of the techniques
- selection of the best available techniques (BAT) and the associated emission and/or consumption levels for this sector in a general sense, all according to Article 2(11) and Annex IV of the Directive.

Expert judgement by the European IPPC Bureau and the Slaughterhouses and Animal By-products TWG has played a key role in each of these steps and in the way in which the information is presented here.

On the basis of this assessment, techniques, and as far as possible emission and consumption levels associated with the use of BAT, are presented in this chapter that are considered to be appropriate to the sector as a whole and in many cases reflect the current performance of some installations within the sector. Where emission or consumption levels “associated with best available techniques” are presented, this is to be understood as meaning that those levels represent the environmental performance that could be anticipated as a result of the application, in this sector, of the techniques described, bearing in mind the balance of costs and advantages inherent within the definition of BAT. However, they are neither emission nor consumption limit values and should not be understood as such. In some cases it may be technically possible to achieve better emission or consumption levels but due to the costs involved or cross-media considerations, they are not considered to be appropriate as BAT for the sector as a whole. However, such levels may be considered to be justified in more specific cases where there are special driving forces.

The emission and consumption levels associated with the use of BAT have to be seen together with any specified reference conditions (e.g. averaging periods).

The concept of “levels associated with BAT” described above is to be distinguished from the term “achievable level” used elsewhere in this document. Where a level is described as “achievable” using a particular technique or combination of techniques, this should be understood to mean that the level may be expected to be achieved over a substantial period of time in a well maintained and operated installation or process using those techniques.

Where available, data concerning costs have been given together with the description of the techniques presented in the previous chapter. These give a rough indication about the magnitude of the costs involved. However, the actual cost of applying a technique will depend strongly on the specific situation regarding, for example, taxes, fees, and the technical characteristics of the installation concerned. It is not possible to evaluate such site-specific

factors fully in this document. In the absence of data concerning costs, conclusions on economic viability of techniques are drawn from observations on existing installations.

It is intended that the general BAT in this chapter are a reference point against which to judge the current performance of an existing installation or to judge a proposal for a new installation. In this way they will assist in the determination of appropriate "BAT-based" conditions for the installation or in the establishment of general binding rules under Article 9(8). It is foreseen that new installations can be designed to perform at or even better than the general BAT levels presented here. It is also considered that existing installations could move towards the general BAT levels or do better, subject to the technical and economic applicability of the techniques in each case.

While the BAT reference documents do not set legally binding standards, they are meant to give information for the guidance of industry, Member States and the public on achievable emission and consumption levels when using specified techniques. The appropriate limit values for any specific case will need to be determined taking into account the objectives of the IPPC Directive and the local considerations.

In order to complement this general introduction, the paragraphs below introduce the sector-specific issues and the assessment of BAT and they explain the structure of the chapter.

The main environmental issues for slaughterhouses are water consumption, emission of high organic strength liquids to water and the energy consumption associated with refrigeration and heating water.

For animal by-products installations the main issues are related to the energy consumption associated with drying animal by-products; emission of high strength organic liquids containing ammoniacal compounds to water; infectivity, especially related to the controlling, handling and destruction of TSE material and odour.

Measures to prevent and control consumption and emission levels are very much influenced by planning each process technically and operationally at each unit operation level. BAT have, therefore, been identified at this level of detail. Where consumption and emissions cannot be avoided, BAT is to reduce their impact on the environment, by the application of both technical and operational techniques.

For example, there are opportunities to avoid the unnecessary use of water at many unit operations and sometimes these can also result in energy savings, e.g. reducing the consumption of hot water not only reduces water use, but also the energy that would otherwise be needed to heat it. Avoiding unnecessary contact between water and carcasses and animal by-products and carrying out dry cleaning, minimises water contamination.

The quick treatment of animal by-products can prevent or minimise odour problems during storage and processing, which would otherwise develop due to their decomposition over time.

ABP Regulation 1774/2002/EC specifies requirements for the handling, storage, transport and processing of animal by-products and describes the disposal routes allowed for TSE risk material. BAT does not conflict with legal requirements relating to, e.g. public health, food safety, animal welfare or health and safety at work. In the case of animal welfare, the avoidance of stress and harm to the live animal, that could result in wounds/injuries from, e.g. forks, slippery ramps or jagged fences, in turn reduces the risk of damage to the products, e.g. the hide and skins, so less waste is produced at the slaughterhouse and losses are prevented in the value chain.

The assessment of techniques is dependent on the information provided and assessed by the TWG. For many techniques there is only limited technical and economic data available.

In the remainder of this chapter the BAT options for slaughterhouses and animal by-products installations are reported. Firstly, general BAT which apply to all installations are presented. In addition to the general BAT there are some BAT which only apply to individual activities or to several activities. These are reported for slaughterhouses and where appropriate, divided between large animal slaughterhouses and poultry slaughterhouses. BAT for all animal by-products installations are then presented, followed by the additional BAT which apply in individual types of installations.

To assist the reader, the way the BAT conclusions are presented is shown in Figure 5.1. In Figure 5.1, the BAT conclusions are presented in tiers. The top tier shows the sections listing BAT for all slaughterhouses and animal by-products installations; the second is divided between additional BAT for slaughterhouses and BAT for animal by-products installations and the third is divided further showing the sections listing additional BAT for individual types of slaughterhouse and animal by-products installation.




Figure 5.1: How the BAT conclusions are presented for slaughterhouses and animal by-products installations

The BAT in this chapter are numbered to make them easier to read and to refer to in discussions. The numbering does not infer any hierarchy.

5.1 Slaughterhouses and animal by-products installations

For all slaughterhouses and animal by-products installations, BAT is to do all of the following:

5.1.1 General processes and operations

For all slaughterhouses and animal by-products installations, BAT is to do all of the following:

- 1 use an environmental management system (see Section 4.1.1 and 5.1.1.1)
- 2 provide training (see Section 4.1.2)
- 3 use a planned maintenance programme (see Section 4.1.3)
- 4 apply dedicated metering of water consumption (see Section 4.1.4)
- 5 separate process and non-process waste water (see Section 4.1.5)
- 6 remove all running water hoses and repair dripping taps and toilets (see Section 4.1.7)
- 7 fit and use drains with screens and/or traps to prevent solid material from entering the waste water (see Section 4.1.11)
- 8 dry clean installations and transport by-products dry (see Section 4.1.12), followed by pressure cleaning (see Section 4.1.10) using hoses fitted with hand-operated triggers (see Section 4.1.9) and where necessary hot water supplied from thermostatically controlled steam and water valves (see Section 4.1.23)
- 9 apply overfilling protection on bulk storage tanks (see Section 4.1.13)
- 10 provide and use bunds for bulk storage tanks (see Section 4.1.14)
- 11 implement energy management systems (see Sections 4.1.16 and 4.1.17)
- 12 implement refrigeration management systems (see Section 4.1.18)
- 13 operate controls over refrigeration plant running times (see Section 4.1.19)
- 14 fit and operate chill room door closing switches (see Section 4.1.21)
- 15 recuperate heat from refrigeration plants (see Section 4.1.22)
- 16 use thermostatically controlled steam and water blending valves (see Section 4.1.23)
- 17 rationalise and insulate steam and water pipework (see Section 4.1.24)
- 18 isolate steam and water services (see Section 4.1.25)
- 19 implement light management systems (see Section 4.1.26)
- 20 store animal by-products for short periods and possibly to refrigerate them (see Section 4.1.27)
- 21 audit odour (see Section 4.1.28)
- 22 design and construct vehicles, equipment and premises to ensure that they are easy to clean (see Section 4.1.30)
- 23 clean materials storage areas frequently (see Section 4.1.31)
- 24 implement a noise management system (see Section 4.1.36)
- 25 reduce noise at, e.g. roof extract fans, balance lagoon blowers and refrigeration plants (see Sections 4.1.3, 4.1.36, 4.1.37, 4.1.38 and 4.1.39)
- 26 replace the use of fuel oil with natural gas, where a natural gas supply is available (see Section 4.1.40)
- 27 enclose animal by-products during transport, loading/unloading and storage (see Section 4.1.29)
- 28 where it is not possible to treat blood before its decomposition starts to cause odour problems and/or quality problems, refrigerate it as quickly as possible and for as short a time as possible, to minimise decomposition (see Section 4.2.1.8) and
- 29 export any heat and/or power produced which cannot be used on-site.

5.1.1.1 BAT for environmental management

A number of environmental management techniques are determined as BAT (see Section 4.1.1). The scope (e.g. level of detail) and nature of the EMS (e.g. standardised or non-standardised) will generally be related to the nature, scale and complexity of the installation, and the range of environmental impacts it may have.

BAT is to implement and adhere to an Environmental Management System (EMS) that incorporates, as appropriate to individual circumstances, the following features: (see Chapter 4)

- definition of an environmental policy for the installation by top management (commitment of the top management is regarded as a precondition for a successful application of other features of the EMS)
- planning and establishing the necessary procedures
- implementation of the procedures, paying particular attention to
 - structure and responsibility
 - training, awareness and competence
 - communication
 - employee involvement
 - documentation
 - efficient process control
 - maintenance programme
 - emergency preparedness and response
 - safeguarding compliance with environmental legislation.
- checking performance and taking corrective action, paying particular attention to
 - monitoring and measurement (*see also the Reference document on Monitoring of Emissions*)
 - corrective and preventive action
 - maintenance of records
 - independent (where practicable) internal auditing in order to determine whether or not the environmental management system conforms to planned arrangements and has been properly implemented and maintained.
- review by top management.

Three further features, which can complement the above stepwise, are considered as supporting measures. However, their absence is generally not inconsistent with BAT. These three additional steps are:

- having the management system and audit procedure examined and validated by an accredited certification body or an external EMS verifier
- preparation and publication (and possibly external validation) of a regular environmental statement describing all the significant environmental aspects of the installation, allowing for year-by-year comparison against environmental objectives and targets as well as with sector benchmarks as appropriate
- implementation and adherence to an internationally accepted voluntary system such as EMAS and EN ISO 14001:1996. This voluntary step could give higher credibility to the EMS. In particular EMAS, which embodies all the above-mentioned features, gives higher credibility. However, non-standardised systems can in principle be equally effective provided that they are properly designed and implemented.

Specifically for slaughterhouses and animal by-products installations*, it is also important to consider the following potential features of the EMS:

- giving consideration to the environmental impact from the eventual decommissioning of the unit at the stage of designing a new plant
- giving consideration to the development of cleaner technologies
- where practicable, sectoral benchmarking on a regular basis, including energy efficiency and energy conservation activities, choice of input materials, emissions to air, discharges to water, consumption of water and generation of waste.

5.1.2 Integration of same site activities

For slaughterhouses and/or animal by-products installations, operating on the same site, BAT is to do the following:

- 1 re-use heat and/or power produced in one activity in other activities (see Sections 4.4.1, 4.4.2 and 4.4.3) and
- 2 share abatement techniques, where these are required, e.g. WWTPs.

For rendering and incineration on the same site, BAT is to do the following:

- 1 burn non-condensable gases produced during rendering in a same site incinerator (see Sections 4.4.2 and 4.4.3).

5.1.3 Collaboration with upstream and downstream activities

The operations of those involved in the supply of animals to slaughterhouses, including the farmers and the hauliers, can have environmental consequences in the slaughterhouse. The suppliers of feedstock to animal-by-products installations and other downstream users can also influence the environmental impact of those installations. Their impact can be affected by the properties of the feedstock, e.g. the freshness, degree of separation of different materials and the specification.

BAT is to seek collaboration with upstream and downstream partners, to create a chain of environmental responsibility, to minimise pollution and to protect the environment as a whole, (see, e.g. Sections 4.2.2.1.1, 4.2.2.1.2, 4.1.27, 4.3.1.4, 4.3.4.1, 4.3.8.7 and 4.2.2.9.10).

5.1.4 Installation and equipment cleaning

For the cleaning of slaughterhouses and animal by-products installations, BAT is to do the following:

- 1 manage and minimise the quantities of water and detergents consumed (see Section 4.1.42.1)
- 2 select those detergents which cause minimum impact on the environment (see Section 4.1.42.2), without compromising the efficacy of cleaning
- 3 avoid, where possible, the use of cleaning and disinfectant agents containing active chlorine (see Section 4.1.42.3) and
- 4 where the equipment is suitable, operate a cleaning-in-place system (see Section 4.2.4.3).

5.1.5 Treatment of waste water

Waste water treatment is an “end-of-pipe” treatment which is required because waste water is produced from various sources. These include water from vehicle, equipment and installation cleaning and from the washing of carcasses and animal by-products. Waste water also arises as a

by-product of some of the treatment and disposal processes for animal by-products, where water may be either evaporated, leached or run-off. WWTPs consume energy and produce residues which in some cases are used in further treatments and which in others are disposed of.

“Process-integrated” BAT which minimise both the consumption and the contamination of water should be applied. The selection of waste water treatment techniques can then be made, based on the capacity required to treat the waste water produced after BAT minimising its quantity and load have been applied.

No conclusions were reached about whether it was better to treat waste water from slaughterhouses and/or animal by-products installations on-site or at a municipal WWTP.

For the treatment of waste water from slaughterhouses and animal by-products installations, BAT is to do the following:

- 1 prevent waste water stagnation (see Section 4.1.43.3)
 - 2 apply an initial screening of solids using sieves (see Section 4.1.43.4) at the slaughterhouse or animal by-products installation
 - 3 remove fat from waste water, using a fat trap (see Section 4.1.43.9)
 - 4 use a flotation plant, possibly combined with the use of flocculants, to remove additional solids (see Section 4.1.43.10)
 - 5 use a waste water equalisation tank (see Section 4.1.43.11)
 - 6 provide a waste water holding capacity in excess of routine requirements (see Section 4.1.43.1)
 - 7 prevent liquid seepage and odour emissions from waste water treatment tanks, by sealing their sides and bases and either covering them or aerating them (see Sections 4.1.43.12 and 4.1.43.13)
 - 8 subject the effluent to a biological treatment process. Aerobic and anaerobic treatments which are applied to waste water from slaughterhouses and animal by-products installations are described in Sections 2.3.1.2, 2.3.2.1.3, 4.1.43.14, 4.1.43.15, 4.2.6.2, 4.2.6.3 and 4.3.3.15
 - 9 remove nitrogen and phosphorus. Some information is given in Section 2.3.1.2
 - 10 remove the sludges produced and subject them to further animal by-product uses. These routes and their conditions of application are regulated by ABP Regulation 1774/2002/EC
 - 11 use CH₄ gas produced during anaerobic treatment for the production of heat and/or power
 - 12 subject the resulting effluent to tertiary treatment and
 - 13 regularly conduct laboratory analyses of the effluent composition and maintain records (see Section 4.1.43.2). Further information on monitoring techniques is available in the current “Common Waste Water and Waste Gas Treatment/Management Systems in the Chemical Sector” BREF [341, EC, 2002].
- Note the emission levels given in Table 5.1 are generally considered to be appropriate for protecting the water environment and are indicative of the emission levels that would be achieved with those techniques generally considered to represent BAT. They do not necessarily represent levels currently achieved within the industry but are based on the expert judgment of the TWG.

Parameter	COD	BOD ₅	SS	Nitrogen (total)	Phosphorus (total)	FOG
Achievable emission level (mg/l)	25 - 125	10 - 40	5 - 60	15 - 40	2 - 5	2.6 - 15

Table 5.1: Emission levels associated with BAT for minimising waste water emissions from slaughterhouses and animal by-products installations

5.2 Additional BAT for slaughterhouses

In addition to the general measures in Section 5.1, for all slaughterhouses BAT is to do all of the following:

- 1 dry scrape delivery vehicles (see Sections 4.2.1.1) and prior to cleaning with a high-pressure hose (see Section 4.2.1.2)
- 2 avoid carcase washing and where this is not possible to minimise it, combined with clean slaughter techniques (see Section 4.2.1.4)
- 3 continuously collect by-products dry and segregated from each other, along the length of the slaughter-line (see Section 4.2.1.6), combined with optimising bleeding and the collection of blood (see Section 4.2.2.1) and segregating the storage and handling of different kinds of by-products (see Section 4.2.5.1)
- 4 operate a double drain from the bleed hall (see Section 4.2.1.7)
- 5 collect floor waste dry (see Section 4.2.1.9)
- 6 remove all unnecessary taps from the slaughter-line (see Section 4.2.1.13)
- 7 insulate and cover knife sterilisers (see Section 4.2.1.14), combined with sterilising knives using low-pressure steam (see Section 4.2.1.17)
- 8 operate hand and apron cleaning cubicles, with a “water off” default (see Section 4.2.1.18)
- 9 manage and monitor compressed air use (see Section 4.2.1.19)
- 10 manage and monitor ventilation use (see Section 4.2.1.20)
- 11 use backward bowed centrifugal fans in ventilation and refrigeration systems (see Section 4.2.1.21)
- 12 manage and monitor the use of hot water (see Section 4.2.1.22) and
- 13 trim all hide/skin material not destined for tanning immediately after removal from the animal, except if there is no outlet for the use/valorisation of the trimmings (see Section 4.2.2.9.10).

5.2.1 Additional BAT for the slaughter of large animals

In addition to the general measures in Sections 5.1 and 5.2, for all large animal slaughterhouses, BAT is to do all of the following:

- 1 stop feeding animals 12 hours prior to slaughter (see Section 4.2.2.1.1), combined with minimising the animals’ time in the slaughterhouse to reduce manure production (see Section 4.2.2.1.2)
- 2 apply demand-controlled drinking water (see Section 4.2.2.1.4)
- 3 shower pigs using water saving timer controlled nozzles (see Section 4.2.2.1.5)
- 4 dry clean the lairage floor and to periodically clean it with water (see Section 4.2.2.1.6)
- 5 use a squeegee for the initial cleaning of the blood collection trough (see Section 4.2.2.2.2)
- 6 steam scald pigs (vertical scalding) (see Section 4.2.2.3.1)
- 7 in those existing slaughterhouses, where it is not yet economically viable to change to steam scalding, insulate and cover pig scalding tanks (see Section 4.2.2.3.2) and control the water level in those tanks (see Section 4.2.2.3.3)
- 8 re-use cold water within pig de-hairing machines (see Section 4.2.2.4.1) and replace irrigation pipes with flat jet nozzles (see Section 4.2.2.4.2)
- 9 re-use cooling water from pig singeing kilns (see Section 4.2.2.5.1)
- 10 recover heat from pig singeing exhaust gases, for preheating water (see Section 4.2.2.5.2)
- 11 shower pigs after singeing, using flat jet nozzles (see Section 4.2.2.5.3)
- 12 replace irrigation pipes with flat jet nozzles for rind treatment in pig slaughterhouses (see Section 4.2.2.6.1)
- 13 sterilise chest-opening saws in a cabinet with automated hot water nozzles (see Section 4.2.2.7.1)

- 14 regulate and minimise the water used for moving intestines (see Section 4.2.2.7.2)
- 15 use either water-spray/mist-cooling or blast-chilling/shock-cooling tunnel to cool pigs (see Sections 4.2.2.8.1 and 4.2.2.8.2)
- 16 not shower pigs before they are chilled in a chilling tunnel (see Section 4.2.2.8.3)
- 17 empty stomachs dry (see Section 4.2.2.9.2)
- 18 collect the contents of small intestines dry (see Section 4.2.2.9.3), whether or not they are intended to be used for casings (see Section 4.2.2.9.4)
- 19 regulate and minimise the water consumption during small and large intestine washing (see Section 4.2.2.9.6)
- 20 regulate and minimise the water consumption during rinsing of tongues and hearts (see Section 4.2.2.9.9)
- 21 use a mechanised fat trap for removing fat from water (see Section 4.2.2.9.7)
- 22 according to the current *Reference Document on Best Available Techniques for the Tanning of Hides and Skins* [273, EC, 2001] BAT “is to process fresh hides and skins as far as they are available”.
- 23 when it is impossible to process hides and skins before 8 – 12 hours, with the actual range depending on local conditions, to immediately store hides between 10 and 15 °C (see Section 4.2.2.9.11)
- 24 when it is impossible to process hides before a period of between 8 – 12 hours and 5 – 8 days, with the actual ranges depending on local conditions, to immediately refrigerate hides at 2 °C (see Section 4.2.2.9.15) and
- 25 always immediately drum-salt all hides and skins, if they have to be stored for longer than 8 days, e.g. if they have to be transported overseas (see Section 4.2.2.9.12), combined with the dry collection of salt residues (see Section 4.2.2.9.14).

5.2.2 Additional BAT for the slaughter of poultry

In addition to the general measures in Sections 5.1 and 5.2, for all poultry slaughterhouses, BAT is to do all of the following:

- 1 apply dust abatement at bird reception, unloading and hanging stations (see Sections 4.2.3.1.2, 4.2.3.1.3 and 4.2.3.1.4)
- 2 stun birds in their modules, using inert gases at new installations and when existing stunning equipment and bird delivery vehicles are due for renewal (see Section 4.2.3.2.1)
- 3 reduce water consumption in poultry slaughter, by removing carcase washing equipment from the line except after de-feathering and evisceration (see Section 4.2.1.11)
- 4 steam scald poultry (see Section 4.2.3.3.1)
- 5 insulate scalding tanks in those existing premises where it is not yet economically viable to change to steam scalding (see Section 4.2.3.3.2)
- 6 use nozzles instead of irrigation pipes to shower poultry, during de-feathering (see Section 4.2.3.4.1)
- 7 use recycled water, e.g. from the scalding tank, for the carriage of feathers (see Section 4.2.3.4.2)
- 8 use water efficient shower heads to wash poultry, during evisceration (see Section 4.2.3.5.1) and
- 9 chill poultry by immersion/spin chilling and to control, regulate and minimise the water consumption (see Section 4.2.3.6.2).

5.3 Additional BAT for animal by-products installations

In addition to the general measures in Sections 5.1, for all animal by-products installations, BAT is to do all of the following:

- 1 operate continuous, dry and segregated collection of animal by-products throughout animal by-products treatment (see Section 4.3.1.1)
- 2 use sealed, storage, handling and charging facilities for animal by-products (see Section 4.3.1.3)
- 3 where it is not possible to treat animal by-products before their decomposition starts to cause odour problems and/or quality problems, refrigerate them as quickly as possible and for as short a time as possible (see Section 4.3.1.4) and
- 4 where inherently malodorous substances are used or are produced during the treatment of animal by-products, pass the low intensity/high volume gases through a biofilter (see Section 4.1.33).

5.3.1 Additional BAT for fat melting

For fat melting no additional BAT have been identified in addition to those in Sections 5.1 and 5.3.

5.3.2 Additional BAT for rendering

In addition to the general measures in Sections 5.1 and 5.3, for rendering installations, BAT is to do all of the following:

- 1 totally enclose the rendering line (see Section 4.3.3.1)
- 2 reduce the size of carcasses and parts of animal carcasses before rendering (see Section 4.3.3.2)
- 3 remove water from blood, by steam coagulation, prior to rendering (see Section 4.3.3.4)
- 4 for raw material throughputs less than 50000 t/yr, to use a single effect evaporator to remove water from liquid mixtures (see Section 4.3.3.5) and
- 5 for raw material throughputs greater than, or equal to 50000 t/yr, to use a multiple-effect evaporator to remove water from liquid mixtures (see Section 4.3.1.5).

When it has been impossible to use fresh raw materials and thereby to minimise the production of malodorous substances, BAT is to do either of the following:

- 1 burn the non-condensable gases in an existing boiler (see Section 4.3.3.11) and to pass the low intensity/high volume odours through a biofilter (see Section 4.1.33) or
- 2 to burn the whole vapour gases in a thermal oxidiser (see Section 4.3.3.10) and to pass the low intensity/high volume odours through a biofilter (see Section 4.1.33).

5.3.3 Additional BAT for fish-meal and fish-oil production

In addition to the general measures in Sections 5.1 and 5.3, for fish-meal and fish-oil production installations, BAT is to do all of the following:

- 1 use fresh, (low total volatile nitrogen) feedstock (see Section 4.3.4.1)
- 2 use heat from the vapour evaporated during the drying of fish-meal in a falling film evaporator to concentrate stickwater (see Section 4.3.4.2)
- 3 incinerate malodorous air, with heat recovery (see Section 4.3.4.3) and
- 4 wash air using condensate liquid instead of using clean seawater (see Section 4.3.4.4).

5.3.4 Additional BAT for blood processing

In addition to the general measures in Sections 5.1 and 5.3, for blood processing installations BAT is to do one of the following:

- 1 concentrate plasma, prior to spray drying, using reverse osmosis (see Section 4.3.5.1)
- 2 concentrate plasma, prior to spray drying, using vacuum evaporation (see Section 4.3.5.2) or
- 3 remove water from blood, by steam coagulation, prior to spray drying (see Section 4.3.3.4).

5.3.5 Additional BAT for bone processing

For bone processing, no additional BAT have been identified in addition to those in Sections 5.1 and 5.3.

5.3.6 Additional BAT for gelatine manufacture

In addition to the general measures in Sections 5.1 and 5.3, for gelatine manufacturing installations, BAT is to do the following:

- 1 insulate bone de-fatting equipment (see Section 4.3.7.1).

5.3.7 Additional BAT for the incineration of animal by-products

BAT listed for incineration, apply to those issues related only to the dedicated incineration of animal by-products. BAT for issues related to the incineration of all wastes, come within the scope of the *Reference document on Best Available Techniques in waste incineration* [329, EC, 2003].

In addition to the general measures in Sections 5.1 and 5.3, for the incineration of animal by-products, BAT is to do all of the following:

- 1 enclose buildings used for delivery storage, handling and processing of animal by-products (see Section 4.3.8.1)
- 2 clean and disinfect delivery vehicles and equipment, after each delivery/use (see Section 4.3.8.2)
- 3 carry carcasses (not drag them) (see Section 4.3.8.3)
- 4 reduce in size animal carcasses and parts of animal carcasses, before incineration (see Section 4.3.8.4)
- 5 restrict feedstock to exactly that tested during trials (see Section 4.3.8.5)
- 6 agree the fat:moisture:ash content of animal meal, with the renderer (see Section 4.3.8.6)
- 7 avoid receipt of material for incineration in PVC packaging (see Section 4.3.8.10)
- 8 either auger feed (see Section 4.3.8.11), or pump (see Section 4.3.8.12) parts of carcasses or animal meal to the incinerator
- 9 incinerate incineration waste water (see Section 4.3.8.13), if there is no suitable WWTP on the site
- 10 seal the storage, handling and charging of animal by-products to incinerators (see Section 4.3.8.14)
- 11 duct air from the installation and the pre-combustion equipment to combustion chambers (see Section 4.3.8.15)
- 12 alarm and interlock combustion temperatures to charging mechanisms (see Section 4.3.8.16).

- 13 operate continuous incineration (see Section 4.3.8.20)
- 14 operate an ash burnout chamber (see Section 4.3.8.21), where adequate combustion is not otherwise achievable, e.g. immediately downstream from rotary kilns
- 15 operate automated continuous de-ashing (see Section 4.3.8.22)
- 16 operate a monitoring regime for emissions, including a protocol for monitoring burnout, including biohazard from TSE prions, in ash (see Section 4.3.8.25)
- 17 to achieve emission levels as low as reasonably practicable below those shown in Table 5.2 (see Section 4.3.8.17)

Releases to air		Performance associated with BAT ⁽³⁾	
		Typical	Monitoring
SO ₂	(mg/m ³)	< 30 ⁽²⁾	Continuous
HCl	(mg/m ³)	< 10 ⁽²⁾	Continuous
HF	(mg/m ³)	n/a	
NO _x	(mg/m ³)	< 175 ⁽²⁾	Continuous
CO	(mg/m ³)	< 25 ⁽²⁾	Continuous
VOCs	(mg/m ³)	< 10 ⁽²⁾	Periodic
Dust	(mg/m ³)	< 10 ⁽²⁾	Continuous
Dioxins and furans	(ng/m ³)	< 0.1 ⁽⁴⁾	Periodic
Heavy metals total (Cd, TI)	(mg/m ³)	< 0.05 ⁽⁵⁾	
Heavy metals (Hg)	(mg/m ³)	< 0.05 ⁽⁵⁾	
Heavy metals total (Sb, As, Pb, Cr, Co, Cu, Mn, Ni, V)	(mg/m ³)	< 0.5 ⁽⁵⁾	
NH ₃	(mg/m ³)	< 10	
Residence time	> 850 °C	3.5 s	
Oxygen	(minimum after last injection)	9 %	Continuous
Pressure, Temperature, Water vapour, Volumetric flow			Continuous
Ash - (total carbon)		< 1 % ⁽⁶⁾	Periodic
Ash – (total protein) (Aqueous extract) (mg/100g)		0.3 – 0.6	Periodic
⁽²⁾ Releases control – “95 % percentile <u>hourly</u> average over 24 hours”. Measurements at 273 K (temp.), 101.3 kPa (pressure) and 11 % O ₂ dry gas ⁽³⁾ Actual performance results operating a dry flue gas-cleaning system with bag filters and injected reagents ⁽⁴⁾ Values measured over a sample period of a minimum of 6 hours and a maximum of 8 hours expressed as toxic equivalent in accordance with Annex 1 of the Waste Incineration Directive ⁽⁵⁾ Values measured over a sample period of a minimum of 6 hours and a maximum of 8 hours ⁽⁶⁾ Total organic carbon Note: Protein analysis is not relevant to the dedicated incineration of poultry by-products			

Table 5.2: Emission levels associated with the dedicated incineration of animal by-products in either bubbling fluidised bed, circulating fluidised bed or rotary kiln incinerators

- 18 regularly clean and disinfect installations and equipment (see Section 4.3.8.26)
- 19 operate odour arrestment techniques, when the incinerator is not working (see Section 4.3.8.27), when odour prevention is not reasonably practicable and
- 20 use a carbon filter for odour abatement, when incinerators are not operating (see Section 4.3.8.29) and where odour prevention is not reasonably practicable.

In addition to the general measures in Sections 5.1, 5.3 and those listed above, for the incineration of animal by-products, BAT is to do to do one of the following:

- 1 incinerate animal carcasses, parts of carcasses and animal meal in bubbling fluidised bed incinerators (see Section 4.3.8.17), with suitable flue gas treatment equipment or
- 2 incinerate animal carcasses, parts of carcasses and animal meal in circulating fluidised bed incinerators (see Section 4.3.8.18), with suitable flue gas treatment equipment or
- 3 incinerate animal carcasses, parts of carcasses and animal meal in rotary kiln incinerators (see Section 4.3.8.19), with suitable flue gas treatment equipment.

5.3.8 Additional BAT for biogas production

In addition to the general measures in Sections 5.1 and 5.3, for biogas production, BAT is to do the following:

- 1 re-use heat during biogas production (see Section 4.3.10.3).

5.3.9 Additional BAT for composting

In addition to the general measures in Sections 5.1 and 5.3, for composting, animal by-products, BAT is to do the following:

- 1 provide sufficient drainage capacity for a windrow on a hard standing (see Section 4.3.11.1) constructed from concrete (see Section 4.3.11.2).

6 EMERGING TECHNIQUES

6.1 Bio-refining of animal by-products to produce soil improvers and fertilisers

Description

The technique is a bio-refining treatment of biological waste materials which sterilises pathogenic agents. Animal carcasses and parts of carcasses can be processed with organic fibrous material to produce sterile plant and animal nutrient products, such as fertilisers and soil conditioners.

The organic waste material is mixed with a finely divided organic fibrous material to provide a reaction mixture. The absorbent organic fibrous material is selected from cellulose-containing material and lignin-containing material not exceeding about 40 % moisture by weight, or cellulose packaging materials, straw, hay, moss and mixtures thereof.

Ammonium nitrate, an oxidising agent, is added to give an animal by-product: NH_4NO_3 in a weight ratio of 1:10 - 1:30. The reaction mixture is heated in a hyperbaric reactor vessel at elevated pressure and temperature, for enough time to create saturated steam and to hydrolyse the absorbent organic fibrous material and to produce a substantially denatured product containing inactivated pathogenic agents. The denatured product is dehydrated in a hyperbaric reactor vessel, to produce a free-flowing solid. The moisture content of the solid is approximately 10 %. Controls are provided to prevent malodorous compounds from being released to the atmosphere.

The mixture is maintained at 180 - 200 °C and 1000 – 1380 kPa for 20 – 40 minutes.

The vapour is released from the hyperbaric reactor vessel into a condenser. The denatured vapour can be recovered and condensed for use in crop irrigation or for the production of liquid fertiliser.

Achieved environmental benefits

It has been reported that the technique can inactivate pathogens, including TSE prions. It can also increase opportunities for the recovery and recycling of animal by-products.

Cross-media effects

Energy is consumed during heating and in the generation of high pressure.

Operational data

The construction materials of the equipment are not critical, as long the required operations can be adequately carried out. Any type of size reduction device may be used. The hyperbaric reactor vessel may be of any suitable size and shape as long as the required steam pressure and temperature ranges are maintained.

For example, a site may install a two-vessel system with a capacity to process 20000 t/yr of animal by-products. Multiple systems can be installed at one site to process larger volumes of material.

Applicability

At the time of writing, this technique is not permitted in the EU, due to the fact that in ABP Regulation 1774/2002/EC, it is neither listed, nor has it been approved in accordance with the procedure referred to in Article 33(2) therein, after consultation of the appropriate scientific committee.

Reference literature

[320, Biosphere Refineries Corporation, 2002]

6.2 Biotechnological treatment of animal by-products in order to increase energetic valorisation

Description

Animal meal is sorted by grain size. It is then treated with a liquid containing active micro-organisms (non pathogenic bacteria), a feeding solution and water. The bacterial compound is selected for its ability to degrade animal and vegetable fat, proteins and starch. Approximately 1 litre is required per cubic metre of animal meal.

An enzymatic reaction is activated by the micro-organisms. This substantially reduces the fat content. This causes the calorific value of the material to increase.

Once the process has started, it is assisted by mechanical or manual stirring. The time needed for the process is approximately 15 – 20 days. The reaction conditions are between 20 - 27 °C in semi-darkness.

Achieved environmental benefits

Reduced fat content

Cross-media effects

Mercury and arsenic loss during the process has been reported, but not accounted for.

Applicability

At the time of writing, this technique is not permitted in the EU, due to the fact that in ABP Regulation 1774/2002/EC, it is neither listed, nor has it been approved in accordance with the procedure referred to in Article 33(2) therein, after consultation of the appropriate scientific committee.

It is reported that the simplicity of the treatment could make it possible to apply the process either at the end of the rendering process or before incineration.

Economics

The initial investment would be limited to the purchase of cochlea treatment tanks and stirring blades. The main operational cost would be the purchase of the biotechnological solution.

Driving force for implementation

The application of biotechnical processes for agricultural and environmental emergencies is continuously growing. The operations reportedly prefer the use of natural rather than artificially produced micro-organisms, in order to avoid the risk of genetic pollution which might be difficult to control.

Studies underway show the possibility of achieving a higher net calorific value with one simple treatment.

By the end of 2003, the process could be considered as an industrial technique usable for the treatment and transformation of animal by-products to increase their calorific value.

Example plants

None yet because the technique is still under development.

Reference literature

[326, Italian TWG Members, 2002]

7 CONCLUDING REMARKS

7.1 Timing of the work

The work on this BREF document started with the first plenary meeting of the TWG in October 2000. A first draft was sent out to the TWG for consultation in March 2002. During the preparation of the first draft there was an escalation in the BSE crisis, due to the discovery of cases of BSE in MSs which had previously been free of the disease. The industries concerned and the regulatory authorities worked virtually full-time on dealing with the practical and legal repercussions of this emergency. This was closely followed by the outbreak of foot and mouth disease. The TWG was consequently unable to devote much time to the BREF work during this period.

A second plenary meeting of the TWG was held in April 2002, to discuss the dedicated incineration of animal by-products. A second draft, including the proposed BAT conclusions was sent to the TWG in January 2003. The final plenary meeting of the TWG was held in July 2003. After the final meeting, there were short consultation periods on the revised BAT chapter, the “Concluding remarks” and the “Executive summary”. Following these consultations, the final redrafting took place.

7.2 Information provided

Many reports from industry and MS authorities were used as sources of information in the drafting of this BREF and these were supplemented by information from individuals based on example plants. The reports submitted by Denmark [134, Nordic States, 2001], Germany [163, German TWG Members, 2001] and the UK [12, WS Atkins-EA, 2000, 67, WS Atkins Environment/EA, 2000] can be considered to be the building blocks of the slaughterhouse sections. For rendering, much of the information was received from Germany [49, VDI, 1996, 163, German TWG Members, 2001]. The fish-meal and fish-oil sections are mainly based on information submitted by Denmark [155, Nordic Council of Ministers, 1997]. For blood processing, EAPA provided most of the information [202, APC Europe, 2001] and for gelatine manufacture the GME submitted the majority of the information [249, GME, 2002]. Information about incineration came from a variety of sources including Germany [164, Nottrodt A., 2001], the UK [6, EA, 1997, 65, EA, 1996, 82, EA, 1998] and industry [199, PDM Group and Wykes Engineering (Rushden) Ltd, 2000].

These written reports were supplemented to a great extent by information received during and following site visits to large animal and poultry slaughterhouses and to installations carrying out fat melting, rendering, fish-meal and fish-oil production, blood processing, gelatine manufacture, incineration, tallow burning, biogas production and composting. The site visits were in Belgium, Denmark, Spain, Italy and the UK.

The formal consultations on the draft document also prompted the submission of a huge amount of information, as well as providing the main opportunities for the TWG to verify information already submitted.

Although over 350 items of information were provided, some significant gaps remain. For instance, although energy consumption is a key environmental issue in slaughterhouses, due to chilling and refrigerated storage and in many animal by-products installations, especially during drying, very little data or information about energy saving techniques was submitted. It is, therefore, difficult for the reader to compare the energy implications for the various routes for use and disposal of animal by-products.

Odour is also a key issue. However, there is a lack of consistency in the data on measurement of odour and the identification of the options for keeping odour streams separate for treatment. Prevention of odour is addressed in the BREF, albeit qualitatively.

In general, the consumption and emission data provided were not well explained in terms of operating conditions and analytical methods and their relationship with the techniques described was not always made clear. The TWG attempted to collect data “per tonne of carcase produced” and “per tonne of animal by-product treated” for each unit operation, to allow direct comparisons to be made and to identify the areas with high consumption and emission levels, so that these could be targeted. Large gaps remain in this data.

Operation of abatement/end-of-pipe techniques, such as WWTPs, is often a part of the slaughterhouse or animal by-products installation activity and as such is included in this document. Unfortunately, most of the data received is not sufficiently explained to be able to say in each case what techniques it refers to. This is one of the reasons why there are very few associated BAT levels quoted.

Very little information was received about bone processing, glue manufacture, gasification of meat and bone meal, land spreading/injection, shellfish shell cleaning and the manufacture of fertiliser from animal meal. This may in some cases be due to local legislation prohibiting or restricting the application of animal by-products to land and restrictions under the new ABP Regulation 1774/2002/EC [287, EC, 2002] which has been drafted and brought into force during the course of the BREF preparation.

Other issues about which little or no information was received include, methane emissions from manure and biogas; zinc and copper emissions in waste water from pig slaughterhouse lairages and the ball drying of blood.

7.3 Driving forces

The content of the BREF, as well as its time-scale for preparation has been strongly influenced by issues such as food and feed safety concerns, e.g. arising from BSE, food hygiene and animal welfare. The focus has remained on prevention and control of pollution, but care has been taken to ensure that there is consistency with legislation and good practice associated with these other important drivers. The main legal driver has been the new ABP Regulation 1774/2002/EC [287, EC, 2002]. This Regulation controls the routes allowed for the use and disposal of animal by-products not intended for human consumption and progress with its preparation was followed closely during the drafting process. As it sets some technical conditions, such as temperature and pressure conditions, it imposes consequent energy consumption requirements which cannot be reduced.

Food and veterinary legislation also affects the content of the BREF due to, e.g. requirements for the use of potable water in slaughterhouses and the consequent prohibitions on the re-use of water. Increasing the shelf-life of the final product has been a factor included in the discussion about the BAT conclusions.

Animal welfare requirements have also been taken into consideration. The information exchange has led to the conclusion that good animal welfare conditions minimise injuries, so less waste is produced, so the requirements are complementary.

7.4 Level of consensus

The conclusions of the BREF were agreed at the final TWG meeting and there are no split views. It is worth noting that animal by-products by their very nature are either inherently malodorous or they decompose and become so. This decomposition also reduces their usability and causes additional odour problems during processing and associated waste water treatment. The TWG discussed the cross-media issues and the economics associated with minimising the decomposition of animal by-products destined for use and for those destined for disposal. It was agreed that BAT is to store animal by-products for as short periods as possible and to refrigerate them, but only if necessary to prevent odour problems from arising. The importance of minimising storage times was emphasised.

Storage conditions were also discussed in the context of collaboration with upstream and downstream activities and it was agreed that BAT is to seek collaboration with upstream partners, to create a chain of environmental responsibility, to minimise pollution and to protect the environment as a whole.

The TWG decided not to include information about the provision of storage capacity for an epidemic in the document. The IPPC Directive does not grant any exemptions from its obligations in epidemic crisis periods. Contingency plans established by MSs need to take this into account. This may involve taking into account any excess storage capacity available in already permitted installations. For example, Council Directive 2001/89/EC of 23 October 2001 on Community measures for the control of classical swine fever [357, EC, 2001], Council Directive 85/511/EEC of 18 November 1985 introducing Community measures for the control of foot-and-mouth disease [358, EC, 1985] and Council Directive 2002/60/EC of 27 June 2002 laying down specific provisions for the control of African swine fever and amending Directive 92/119/EEC as regards Teschen disease and African swine fever [359, EC, 2002] contain requirements for action, in the event of an outbreak of any of these diseases.

7.5 Recommendations for future work

The information exchange and preparation of the BREF document has been a positive development in the prevention and control of pollution for the industries concerned. The new intra- and inter-industry information exchange, e.g. between pig slaughterhouses; between pig slaughterhouses and poultry slaughterhouses and between slaughterhouses and rendering plants, has provided an opportunity for discussion and learning which has not existed in the past.

The gaps in the information have highlighted areas where future work could provide results which might assist in the identification of BAT when the BREF is revised. By taking such additional information into consideration, this could help operators and permit writers to protect the environment as a whole.

The lack of data “per tonne of carcase produced” and “per tonne of animal by-product treated”, for each unit operation, could be addressed via the regulatory authorities and the various industry NGOs which represent the slaughterhouses and animal by-products operators. They could encourage and coordinate the increased measurement of consumption and emission levels at unit operation level. To facilitate the identification of consumption and emission levels associated with the use of BAT, the data should be provided together with details on the operating conditions, descriptions of techniques applied, sampling protocols, analytical methods, averaging periods and statistical presentation.

The information about waste water treatment was initially collected separately for slaughterhouses and animal by-products installations, with the intention that techniques which are particularly effective for particular processes would be identified. In fact it was concluded by the TWG that whilst some techniques are particularly effective for the treatment of particular pollutants and loads, most of the techniques described were applicable at both slaughterhouses

and animal by-products installations. When the BREF is revised it may be possible to combine the sections on waste water treatment and highlight any particular advantages that each technique may have for a particular slaughterhouse or animal by-products activity.

The TWG could not reach BAT conclusions on what substances should be used for cleaning slaughterhouses and animal by-products installations, because insufficient information was provided to compare the cleaning properties and methods of use of substances, taking into account other issues such as water consumption, water temperature and use of physical work to remove dirt. This information could be collected before the BREF is revised.

There was a great deal of incomplete information provided about some of the techniques. The TWG decided that although there was insufficient information on some of the techniques to help with the determination of BAT, they should still be included in the document. The incomplete techniques are appended to this chapter. They are included to provoke both the collection and provision of further information, for assessment when this document is revised. The structure of the BREF should be reviewed when the document is revised, taking account of users' comments.

7.6 Suggested topics for future R & D projects

The following topics might be considered for future research and development projects.

Energy consumption associated with chilling and refrigerated storage

The chilling and refrigeration of carcasses accounts for approximately 50 % the total energy consumption of slaughterhouses. Traditionally improvements have focused on food quality issues, with little emphasis on the consumption of energy. Studies could be carried out to look at how the required product qualities can be achieved with minimum energy consumption.

Energy consumption associated with the drying of animal by-products

The energy consumption associated with the drying of animal by-products is significant and can account for about 2/3 of the energy used in a rendering plant. Studies could focus on optimising the energy use and identifying the opportunities for heat recovery.

Use of non-potable water at slaughterhouses

Due to current food and veterinary legislation, slaughterhouses may only use potable water. Studies could identify possibilities for using non-potable water for some unit operations, thereby allowing certain slaughterhouse water to be re-used. This could potentially reduce water consumption and contamination and the associated energy needed to heat water and treat waste water, without affecting hygiene and food safety.

Optimisation of the use of animal by-products

When pigs and cattle are slaughtered approximately 25 % and 50 % respectively, of the live weight of the animal is not used for human consumption. Studies could be carried out to identify how animal by-products can be used, so that they can be collected separately where appropriate, to reduce the amount which ends up being disposed of as waste. This would have to take account of ABP Regulation 1774/2002/EC [287, EC, 2002].

Benchmarking tools

Benchmarking has been recognised as an effective tool for identifying potential environmental improvements. It needs to take into account product range, product quality, size of production plant and degree of automation. The work on the BREF document, whilst highlighting common problems and solutions, has also shown that systems for improving benchmarking could be developed. This could improve the quality of future exchanges of information and revisions of the BREF.

7.7 Techniques not included in Chapter 4, “Techniques to consider in the determination of BAT”, due to lack of sufficient information

7.7.1 General techniques applicable in slaughterhouses and animal by-products installations

7.7.1.1 Hoses can be fitted with flat-jet spray nozzles

Description

Hoses can be fitted with spray nozzles with a pressure of 2.5 – 3 MPa (25 – 30 bar). A spray of up to 60 ° provides wide coverage and a sweeping effect. Dry-cleaning can be undertaken first and drains can be filled with meshes and traps to prevent stray solids from entering the waste water.

Achieved environmental benefits

Reduced water consumption.

Cross-media effects

None.

Reference literature

[167, Greek Ministry for the Environment, 2001]

7.7.1.2 Fat/sludge collector

Description

A concrete pit covered with a lid made from planks or steel plates can be provided to as a collection vessel. The waste water flows in via an antechamber. The waste water stays in the pit for sufficient time to allow heavy particles to sediment and fat to collect on the surface. The outlet is placed midway between the base and top. This method removes significant impurities from the waste water if the retention period is sufficient and the pit is emptied regularly with a sludge suction system.

Achieved environmental benefits

Removal of fat from waste water.

Cross-media effects

If the water often stands in the pit overnight, this can result in anaerobic conditions and both the waste water and the sludge can produce unpleasant odours.

Reference literature

[134, Nordic States, 2001]

7.7.1.3 Fat cleaning

Example plants

Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.1.4 Conductivity controlled blowdown on cooling towers

Description

Blowdown may be controlled by measurement of conductivity to detect when it is required. This can replace either a timed automatic blowdown control, to release water to drain for 2 - 3 minutes every 0.5 - 1 hour each day or a constant flow to drain.

Achieved environmental benefits

Reduced water consumption.

Reference literature

[214, AVEC, 2001]

7.7.1.5 Design of refrigeration space to minimise energy consumption

Description

Dimensions of cold rooms can be designed to prevent unnecessary cooling of empty spaces. When doors are opened the cooled air can be rapidly replaced by warm air and this slows down the carcass cooling process and consumes more energy.

Achieved environmental benefits

Reduced energy consumption

Example plants

At least one cattle/sheep slaughterhouse in the UK.

7.7.1.6 Energy saving motors

Description

An electronic start-up control of the motor prevents the high switch-on current consumption that, depending of the type of burden, can amount to several times the nominal current consumption of the motor.

Achieved environmental benefits

Reduced energy use.

Example plants

A poultry slaughterhouse in the UK. Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.1.7 Heat recovery

Description

Heat can be recovered in rendering plants and used in the rendering process, for other on-site activities or for off-site activities, such as district heating. The recovered heat can be used for space heating, feedstock heating and water heating.

Achieved environmental benefits

Reduced energy use.

Reference literature

[148, Finnish Environment Institute and Finnish Food and Drink Industries' Federation, 2001]

7.7.1.8 Airlock provision between the indoor loading/unloading area and outdoors

Description

A tunnel large enough to accommodate the biggest despatch/delivery vehicle can be constructed. Odours can be contained if the tunnel has doors at either end, which make a good seal with the walls and which can be opened and shut rapidly with minimum effort and inconvenience. If the doors are difficult to operate they may fall into disuse. High-speed plastic roller-shutter doors, which are less susceptible to damage than metal doors, are available. The integrity of the tunnel and the unloading, storage, processing and packing areas should prevent leakage of odours and the use of the tunnel should not compromise the negative pressure maintained in the rest of the installation.

Achieved environmental benefits

Minimisation of emission of odour to the surrounding neighbourhood.

Driving force for implementation

Odour control and hygiene. The significance of hygiene may vary depending on the type of animal by-product and its intended use. For example, the scattering of BSE risk material by birds and rodents and the prevention of contamination of material intended for human consumption will make enclosure important.

Example plants

Six rendering plants in Germany.

Reference literature

[168, Sweeney L., 2001, 244, Germany, 2002]

7.7.1.9 OzoneDescription

Ozone is a powerful oxidising agent and can remove odour in a number of cases. Good results have been reported after tests on air from lairages. Ozone can be produced by a high voltage generator or by using a UV-tube.

Achieved environmental benefits

Reduced odour emission, with a reported efficiency often above 90 %.

Applicability

Ozone odour control systems are less effective when dealing with high humidity air streams, e.g. the vent from a scalding tank room.

7.7.1.10 Use of low rpm fans for air conditioningExample plants

Slaughterhouses in Denmark

7.7.1.11 Separation of metalsExample plants

Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.2 General techniques applicable in slaughterhouses**7.7.2.1 Control of water supply, by, e.g. department or unit operation**Description

The water supply to each part of the machine line can be controlled to switch off, when no carcasses are present.

Achieved environmental benefits

Reduction of water consumption.

Cross-media effects

None.

Applicability

Applicable at all large slaughterhouses.

Economics

Short payback time.

Driving force for implementation

Reduction of water costs.

Reference literature

[134, Nordic States, 2001, 183, Pontoppidan O., 2001]

7.7.2.2 Air-cooling of vacuum pumps instead of water-coolingReference literature

[134, Nordic States, 2001]

7.7.2.3 Once a day knife washing – multiple knife supply at work stationsDescription

Slaughter knives can be washed and sterilised once a day and the number of clean knives required during each shift, brought to each work station in the slaughter-line. For those operations where the knife does not need to be cleaned between each animal, e.g. where there is faecal contamination, a new knife may be selected as and when required. This may be combined with centralised knife sharpening.

Example plants

At least one cattle slaughterhouse in Italy.

Reference literature

[269, Italian TWG Members, 2002]

7.7.2.4 Use of a hot dry airline to sterilise knives

Example plants

UK retail sector.

7.7.2.5 Use of an autoclave to sterilise knives (off-line, e.g. between shifts)

7.7.2.6 Automatic magnetic valve controlled water sprays

Achieved environmental benefits

Water consumption reduced, due to the flow being interrupted when there are no carcasses on the line, such as during lunch breaks.

Reference literature

[134, Nordic States, 2001]

7.7.2.7 Recuperation/recovery of energy

Description

Energy/heat can be regained from refrigeration installations, compressed air, singeing kilns. The recouped energy can be used for heating of water and room heating.

Achieved environmental benefits

In a pig slaughterhouse in Denmark there has been heat recuperation of 39 kWh/t of carcase.

Example plants

At least one pig slaughterhouse in Denmark.

Reference literature

[134, Nordic States, 2001]

7.7.3 Slaughter of large animals

7.7.3.1 Collect water used to clean aprons and boots

Description

The quality of blood intended for human consumption will be reduced if it is diluted by water used to clean aprons and boots.

Cross-media effects

Additional contamination of waste water by blood.

Applicability

Applicable in large animal slaughterhouses.

Reference literature

[346, Belgian TWG member, 2003]

7.7.3.2 Lairage

7.7.3.2.1 Re-use of water to wash vehicles

Description

Cooling water from the refrigeration plant and vacuum pumps can be collected and re-used for washing vehicles. Veterinary approval must be obtained before use. It is also possible to use water from the rinsing of filters in water works, after sedimentation of ochre.

Achieved environmental benefits

Less water consumption.

Applicability

Totally applicable

Reference literature

[63, ETBPP, 2000, 134, Nordic States, 2001]

7.7.3.2.2 Pig delivery planned for times least sensitive for noise

Reference literature

[134, Nordic States, 2001]

7.7.3.2.3 Unloading using unloading bridgesDescription

If unloading bridges are used, a direct connection can be made between the vehicle delivering large animals and the lairage.

Applicability

Applicable in large animal slaughterhouses.

Reference literature

[346, Belgian TWG member, 2003]

7.7.3.2.4 Use of slatted lairage floorsDescription

Slatted concrete floors laid to falls of 1 in 60 with drainage beneath to a slurry tank.

Achieved environmental benefits

Reduced water consumption for wash down and less entrainment of manure and urine in waste water.

7.7.3.2.5 Re-use of water to wash the lairage floor (pigs)Description

Cooling water from the refrigeration plant and vacuum pumps can be collected and re-used for washing vehicles. Veterinary approval must be obtained before use. It is also possible to use water from the rinsing of the filters in water works, after sedimentation of ochre.

Example plants

Three slaughterhouses in Germany.

Reference literature

[134, Nordic States, 2001, 244, Germany, 2002]

7.7.3.2.6 Collection of urine, for use as a fertiliserDescription

Urine can be collected either through slatted or sloping floors.

Achieved environmental benefits

Reduces contamination of waste water by nitrogen from, e.g. ammonia, urea, uric acid and proteins.

Urine can be used as a fertiliser, in suitable land, where the addition of liquid will not lead to ground or surface water contamination.

Reference literature

[134, Nordic States, 2001]

7.7.3.2.7 Washing animals before slaughterDescription

Animals can be washed before slaughter.

Achieved environmental benefits

Reduced water consumption and entrainment of fat, blood and manure, due to the reduced requirement for carcass washing along the slaughter-line and during carcass dressing.

Cross-media effects

Additional water consumption and contamination, between the lairage and the stunning pen.

Reference literature

[288, Durkan J., 2002]

7.7.3.3 Slaughter**7.7.3.3.1 Drive pigs to the stunning pen, as quietly as possible**Description

If pigs are driven to the stunning pen as quietly as is possible, this can reduce squealing and prevent stress to the animals.

Applicability

Applicable in pig slaughterhouses.

Reference literature

[346, Belgian TWG member, 2003]

7.7.3.3.2 Carbon dioxide stunning of pigs

Description

Pigs may be stunned and in some cases killed by exposure to CO₂, prior to bleeding.

Operational data

The pigs are lowered into a chamber containing 85 % CO₂ for 45 seconds. They may be stunned in batches of e.g. 12 at a time or individually in a *pater noster* lift.

Applicability

Applicable in pig slaughterhouses.

7.7.3.4 Hide and skin removal

7.7.3.4.1 Pneumatic removal of hides and skins

Description

The carcass is removed pneumatically after receiving an electric stimulus, to stop the back breaking.

Applicability

Applicable in cattle slaughterhouses.

Example plants

At least one cattle slaughterhouse in Italy.

Reference literature

[269, Italian TWG Members, 2002]

7.7.3.5 Pig scalding

7.7.3.5.1 Design of pig scalding tank, to ease emptying and cleaning

Description

The scalding tank may be designed with good falls to the bottom drain from all positions.

Achieved environmental benefits

The ease of emptying and cleaning of the tank minimises the total water consumption and the discharged waste water volume.

Reference literature

[134, Nordic States, 2001]

7.7.3.5.2 Reducing water carried out of scalding tanks

Description

A flap placed at the exit of the scalding tank can be used to collect and return water dripping from carcasses.

Achieved environmental benefits

Reduced water consumption and energy use to heat the water.

Reference literature

[346, Belgian TWG member, 2003]

7.7.3.5.3 Stopping the water supply to the scalding tank during breaks in production

Operational data

For a slaughterhouse killing 18000 turkeys per day, i.e. 38 birds per minute the reported potential water saving is 3650 m³/yr with a financial saving of GBP 2280/yr. (Costs in 1999)

Reference literature

[214, AVEC, 2001]

7.7.3.5.4 Heat recovery from tank water

Economics

The payback time is considered to be 1 to 3 years.

Reference literature

[57, DoE, 1993]

7.7.3.5.5 Use of a scalding tank with a steep baseDescription

Use of a scalding tank which has a steep gradient towards the outlet can reduce cleaning water consumption.

Achieved environmental benefits

Reduced water consumption during cleaning.

Cross-media effects

The increased volume of the tank required to have a steep base may increase the water consumption required during the use of the tank.

Reference literature

[330, AWARENET, 2002]

7.7.3.6 Pig hair and toenail removal**7.7.3.6.1 Control of the water supply to de-hairing machines**Description

Water supplied to the de-hairing machines can be controlled, to ensure that it is only supplied when there are carcasses in the machine.

Achieved environmental benefits

Reduced water consumption.

Reference literature

[134, Nordic States, 2001]

7.7.3.7 Pig singeing**7.7.3.7.1 Reduce the pig singeing time**Description

The singeing time of a pig can be reduced if it is supplied to the singeing furnace dry.

Achieved environmental benefits

Reduced fuel consumption.

Reference literature

[346, Belgian TWG member, 2003]

7.7.3.7.2 Efficient use and design of singe pipesDescription

Singeing should only be to the extent necessary for the product. Bacon production requires a heavy singe, whereas pig meat destined for ham and other butcher cuts require minimum singeing.

Reference literature

[57, DoE, 1993]

7.7.3.7.3 Install switches which initiate the singeing flame only when a carcass is presentDescription

The flame in the carcass singeing kiln can be ignited only when a carcass is present. A continuous supply of air can be combined with an intermittent supply of gas, to produce a flame, activated by a carcass entering the singeing furnace. It is reported that there are no adverse bacteriological effects. Solenoid switches may be installed which initiate the singeing flame only when a carcass is passing.

Achieved environmental benefits

Reduced gas consumption.

Reference literature

[330, AWARENET, 2002, 346, Belgian TWG member, 2003]

7.7.3.7.4 Insulate the singeing oven

Description

Singeing ovens can be insulated.

Achieved environmental benefits

Reduced energy consumption.

Reference literature

[330, AWARENET, 2002]

7.7.3.8 Evisceration

7.7.3.8.1 Move viscera by conveyor

Description

Viscera may be removed from the slaughter-line by conveyor in individual receptacles.

Reference literature

[269, Italian TWG Members, 2002]

7.7.3.8.2 Use of fat separators

Description

At locations, where it is possible to concentrate volumes of fat, such as evisceration points, where there are high fat emissions, it is possible to reduce the fat content in the production water by using fat separators. They can, e.g. be installed at the discharges from the evisceration units.

Achieved environmental benefits

Reduced BOD in the waste water. The retained fat can be used for the production of technical fats.

Operational data

If the temperature of the effluent exceeds 30 °C, the efficiency of fat separation is significantly reduced.

Reference literature

[244, Germany, 2002]

7.7.3.9 Splitting

7.7.3.9.1 Optimise the use of the carcass splitting saw

Description

If the correct diameter and thickness of saw blade is selected for the carcass-splitting saw and the blade is maintained sharp, then the noise levels will be reduced and less bone dust will end up in the waste water. Bone sawdust can cause a high phosphorus load in the waste water.

Achieved environmental benefits

Reduced noise levels and a lower phosphorus contamination of waste water.

Applicability

Applicable in large animal slaughterhouses.

Reference literature

[346, Belgian TWG member, 2003]

7.7.3.10 Chilling

7.7.3.10.1 Batch chilling

Description

Batch chilling uses a chill room with rails or walking beams as in the processing area. Each batch chill is separate, to prevent air from filtering between operating cells and those out of use. Each cell has a capacity for 2 hours of production. Batch chilling uses air as transport media. A uniform air distribution, e.g. via socks with nozzles, keeps the heat transfer coefficient high. The combination of air velocity and air temperature determines the time it takes to chill a carcass.

Operational data

The advantage by using the batch chilling process is that chilling and equalization of carcasses take place in same room. The process is simple to establish. The chills can be loaded either manually or automatically.

The disadvantage of using batch chilling is that if the air distribution is not uniform, it is impossible to get uniform equalised carcase temperatures. It is very important that there is free space around the carcasses. If, e.g. some carcasses touch each other, this will prevent the heat transfer from the contact points. These will warm up and this may reduce the meat, by damaging the PSE and causing bacterial growth.

7.7.3.11 Downstream activities**7.7.3.11.1 Water control at rumen washing machine**Description

The supply of water at a drum washing machine for washing rumen, can be controlled by a magnetic valve connected to the motor of the drum. This can ensure that water is only used when the drum is operating.

Achieved environmental benefits

Measurements have shown that this can reduce the water consumption by 10 - 30 %.

The washed rumen can be used for pet food or mink feed.

Reference literature

[134, Nordic States, 2001]

7.7.3.11.2 Removal and use/disposal of water from the “dry” intestine contentsDescription

If the intestinal contents are pressed, the liquid has a very high BOD and N content. It may not be sent to the municipal sewer, depending on what the local discharge consents allow. It may be treated in an on-site WWTP.

7.7.3.11.3 Dry removal of gut manureDescription

Compressed air at approximately 100 - 273 kPa (15 - 40 psi) can be used to blow paunch manure to the collection trailer. A piston compactor can be used to reduce the volume.

Achieved environmental benefits

Reduced water contamination.

Reference literature

[63, ETBPP, 2000]

7.7.3.11.4 Re-use of finish water from casing washingDescription

Finish water is the last batch of cold water used for the cleaning of the small intestines. The Danish State Veterinary Services have given approval, under certain conditions, for this water to be used to flush the contents out of large intestines and fat ends.

Achieved environmental benefits

Reduced water consumption.

Applicability

For larger Danish slaughterhouses (with two slaughter-lines), the payback time for the capital cost is 2 to 4 years.

Example plants

Re-use of finish water from cleaning of the small intestines (from pigs) is used at one Danish slaughterhouse, for emptying large casings and fat ends, with the approval of the Danish State Veterinary Services.

Reference literature

[134, Nordic States, 2001, 274, Pontoppidan O., 2002]

7.7.3.11.5 Minimise noise on the intestine mucus machine

Description

A silencer can be provided on pneumatically operated mucus removal machines.

Achieved environmental benefits

Reduced noise levels.

Reference literature

[346, Belgian TWG member, 2003]

7.7.3.11.6 Chilling of red and green offals, using ice

Description

Red and green offals can be chilled using ice instead of running water. The ice is often already required for storage and during transport.

Achieved environmental benefits

Reduced water consumption and consequent reduced volume and BOD loading of waste water.

Reference literature

[134, Nordic States, 2001]

7.7.4 Slaughter of poultry

7.7.4.1 Reception of birds

7.7.4.1.1 Multi-stage crate washing units

Description

Washing units for the racks and boxes used to transport the birds, can be multi-stage installations. The water used for initial rinsing and cleaning is recirculated over, e.g. wedge wire screens and only the last rinse done with clean water. The water from the last rinse can be used to supplement the water for the earlier stages.

Achieved environmental benefits

Reduced water consumption. Reduced use of detergents.

Cross-media effects

None reported.

Reference literature

[134, Nordic States, 2001]

7.7.4.1.2 Collection of materials screened off crate washing machines

Description

Crate-washing units can incorporate a system for collection of solids, to ensure that they are removed from the waste water, before it is sent to either the on-site, or municipal WWTP.

Achieved environmental benefits

Reduced suspended solids and BOD in the waste water.

Reference literature

[134, Nordic States, 2001]

7.7.4.1.3 Sealing of the crate-washing machines

Description

The outer cabinet of the crate-washing machines can be sealed to prevent leakage of water and evaporation.

Achieved environmental benefits

Reduced water consumption and consequently reduced energy consumption, for heating water.

Reference literature

[134, Nordic States, 2001]

7.7.4.2 Poultry scalding

7.7.4.2.1 Limitation of water loss from the scalding tank

Description

The total water loss from the scalding tank can be limited to less than one litre per chicken (714 l/t of chicken carcase). To limit the water loss to this level, drip trays carrying part at the water dripping from scalded chickens back to the tank can be fitted after the tank.

Achieved environmental benefits

Reduced water consumption and consequently reduced energy consumption, to heat water.

Cross-media effects

None.

Reference literature

[134, Nordic States, 2001]

7.7.4.3 De-feathering

7.7.4.3.1 Transport of heads and feet using a vacuum system

Description

Transport of feathers can be done without using water, e.g. with a vacuum system.

Achieved environmental benefits

Reduced water consumption and reduced entrainment of organic matter in water. Reduced energy consumption to remove water from the heads and feet, during rendering or in preparation for landfill.

Cross-media effects

Energy is required to operate the vacuum system.

Reference literature

[134, Nordic States, 2001]

7.7.4.4 Evisceration

7.7.4.4.1 Dual water supply system

Description

The water supply to the slaughter equipment can be separated into two systems, one for “lubricating water”, which is supplied only when the conveyor system is operating and one for “process water”, which is supplied only when there are chickens in the appropriate machine.

Achieved environmental benefits

Reduced water consumption.

Reference literature

[134, Nordic States, 2001]

7.7.4.4.2 Integrated transport and cooling of red offal from poultry slaughter

Description

Hearts, necks, gizzards and livers are transported with iced water to containers for collection, from the slaughter-line for storage and distribution, for either human consumption or pet food, depending on the market prices. This integrated transport and cooling system means that separate chilling of these organs is not required.

Achieved environmental benefits

Reduced energy consumption, i.e. avoiding the need for additional chilling.

Example plants

At least one large Danish poultry slaughterhouse.

Reference literature

[134, Nordic States, 2001]

7.7.4.4.3 Reduce water flow at knife wash points

Operational data

For a slaughterhouse killing 18000 turkeys per day, i.e. 38 birds per minute the reported potential water saving is 12500 m³/yr with a financial saving of GBP 7800/yr. (Costs in 1999)

Reference literature

[214, AVEC, 2001]

7.7.4.4.4 Reduced water flow in mini-chiller

Description

The manual control for the flow of water through the mini-chiller places reliance on the operator to set the flow when the valve is switched on. The flowrate could be permanently set at the minimum required.

Operational data

For a slaughterhouse killing 18000 turkeys per day, i.e. 38 birds minute the reported potential water saving is 1800 m³/yr with a financial saving of GBP 1125/yr. (Costs in 1999)

Reference literature

[214, AVEC, 2001]

7.7.4.5 Slaughterhouse cleaning

7.7.4.5.1 Large tray and box washing units

Description

Large washing units, e.g. for large quantities of trays and boxes, can be designed to optimise washing procedure, with respect to water, detergent and energy consumption. The unit may be designed to soak, pre-wash, wash, drip-off, rinse, disinfect and dry. The water consumption per unit will increase if one or more stages are left out.

Achieved environmental benefits

Reduced consumption of water, detergent and energy to heat water.

Reference literature

[134, Nordic States, 2001]

7.7.4.5.2 High-pressure cleaning

Description

Use of high-pressure cleaning at 8.11 million Pa instead of 1.82 million - 2.03 million Pa has been reported to have resulted in reduced water consumption.

Achieved environmental benefits

Reduced water consumption from approximately 750 litres to 500 litres per tonne of carcase.

Example plants

A small Danish pig slaughterhouse.

Reference literature

[134, Nordic States, 2001]

7.7.4.5.3 Monitor contamination removal

Description

Monitoring the contamination removal can assist in optimising the cleaning process, e.g. by using less water and causing less chemical, physical and/or biological pollution.

Achieved environmental benefits

Reduced water consumption and less chemical, physical and/or biological pollution.

Reference literature

[346, Belgian TWG member, 2003]

7.7.4.6 Waste water treatment

7.7.4.6.1 Trough screen

Description

The waste water is led to a trough shaped vessel where the half cylinder shaped screen is kept clean by brushes rotating from the centre of the cylinder, on arms. The particles are pushed over the edge of the trough and collected in a container. The typical pore size is 2 mm. Figure 7.1 shows a trough screen.




Figure 7.1: Trough screen – cross-section
[134, Nordic States, 2001]

Reference literature

[134, Nordic States, 2001]

7.7.5 Rendering

7.7.5.1 Provide sufficient production capacity

Example plants

Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.5.2 Discontinuous sterilisation using a “strainer basket boiling apparatus”

Description

A strainer basket boiling apparatus is a rotary cylindrical screen of mesh diameter approximately 15 - 18 mm, installed into a horizontal cylindrical cooker. During sterilisation, a pulpy mass is produced, which is pressed out through the rotary screen within the cooker. Foreign matter is trapped inside the rotary screen and can be cleared from time to time.

Operational data

For a load of 8 tonnes, the total sterilisation time is approximately 1.0 - 1.5 hours.

Driving force for implementation

The technique is reported to be easily implemented at small plants.

Reference literature

[244, Germany, 2002]

7.7.5.3 Discontinuous sterilisation using a sieve disc-drier

Description

The sieve disc cooker is horizontally mounted and contains a stirrer. The casing and the stirring device are both heated. During sterilisation, a pulpy mass is produced, which is pressed out through the permanently installed sieve, or a sieve that rotates with the stirring device, within the cooker.

Operational data

The processing time for sterilisation is approximately one hour. The combination of the effects of the intensive mixing and the heated stirring device, enables cookers with capacities of up to 15 tonnes to be used.

Driving force for implementation

The technique is reported to be easily implemented at small plants.

Example plants

Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.5.4 Rendering, with periodic mixing

Description

Continuous driers with and without addition of fat, suspension driers, disc driers and grinder-driers can all be constructed with mixing paddles incorporated which can be operated periodically. For continuous drying, double-wall cylindrical cookers with a built-in stirrer are used. The shaft of the stirrer is heated. The material is removed from the end of the drier using a screw conveyor.

Reference literature

[244, Germany, 2002]

7.7.5.5 Rendering, with a disc drier

Description

The disc drier comprises a horizontal cooker with tightly packed discs, which can be heated and a stirrer.

Operational data

Capacities can be up to 8 tonnes per hour, if the raw material has a high fat content or 4 tonnes per hour if it has a low fat content.

Reference literature

[244, Germany, 2002]

7.7.5.6 Recirculation of solid residues from pre-treatment into the raw material (if there is no feed production)

Example plants

Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.5.7 Recirculation of excess sludge into the raw material (if there is no feed production)

Example plants

Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.5.8 Air-cooling of condensate, instead of water-cooling

Description

The large quantities of vapours produced during cooking and those from meal presses, can be extracted and ducted to air-cooled condensers.

Achieved environmental benefits

Reduced water consumption. Reduced water contamination because the contents of the condensate cannot be transferred into the cooling water.

Example plants

Several rendering plants in Germany.

Reference literature

[163, German TWG Members, 2001, 244, Germany, 2002]

7.7.5.9 Use of a decanter systemDescription

The meal can be dried using a decanter system instead of a drier.

Achieved environmental benefits

The energy consumption can be halved.

Operational data

The energy consumption for drying can be reduced from 700 - 800 kWh per tonne raw materials to 350 - 400 kWh per tonne, depending on the type of drier.

Example plants

Several rendering plants in Germany.

Reference literature

[134, Nordic States, 2001, 244, Germany, 2002]

7.7.5.10 Centrifuge bloodExample plants

Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.5.11 Disinfection chute for vehicles and footwearExample plants

Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.5.12 Sludge traps, settling tanks and oil/petrol separators for waste water from vehicle cleaningExample plants

Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.5.13 Grease traps and oil traps (DIN 4040)Example plants

Several rendering plants in Germany.

Reference literature

[244, Germany, 2002]

7.7.5.14 Cover all tanks to enable air treatmentExample plants

One rendering plant in Germany

Reference literature

[244, Germany, 2002]

7.7.5.15 Enclosure of WWTP balance tanks and ducting air stream to odour treatmentReference literature

[163, German TWG Members, 2001]

7.7.5.16 Dosing of nutrients, acids and alkalis

Example plants

Two rendering plants in Germany

Reference literature

[244, Germany, 2002]

7.7.5.17 Thermal disinfection of cleaning water - dedicated water heating unit

Description

The cleaning water from the raw material delivery storage and handling vehicles and equipment can be thermally disinfected. It is heated to 100 °C, for at least 30 minutes. The thermal treatment is generally done in batches.

Prior to thermal treatment the solids are frequently separated using sedimentation tanks, sieves and fat separators with sludge catchers, or by flotation plants.

Example plants

Several German rendering plants.

Reference literature

[163, German TWG Members, 2001, 244, Germany, 2002]

7.7.5.18 Neutralisation tanks

Description

Neutralisation stages can be provided as part of the waste water treatment process, e.g. when high pH values result from ammonia stripping or extremely low pH values result from ammonia conversion. The case for neutralisation needs to be carefully considered because it causes salinisation, which can be problematic to the WWTP.

Operational data

At an example rendering plant the neutralisation process using 31 % hydrochloric acid leads to an increase in conductivity of 17 to 33 %. The pH value of the effluent was approximately 10 at the inflow and 7.5 at the outflow.

Example plants

Two German rendering plants.

Reference literature

[244, Germany, 2002]

7.7.6 Fish-meal and fish-oil production

7.7.6.1 Vacuum unloading of fish from fishing vessels

Description

Fish can be unloaded using a vacuum instead of air or water.

Achieved environmental benefits

Reduced air and water contamination and odour, all of which have to be treated afterwards.

Applicability

The lay out of the vessels has to be suitable, so it may be difficult to apply where old unsuitable fishing fleets are in use.

7.7.6.2 Product loss audit and control

Description

Reduction of product loss, with a reduction in the emissions from production, demands a knowledge of how and when the product loss occurs and the size of the loss in the different sections of the process. For pollution reduction through investments in cleaner technologies, it is an absolute necessity to relate product loss, and thereby pollution, to the relevant process equipment.

Achieved environmental benefits

Reduced emissions to water.

Reference literature

[155, Nordic Council of Ministers, 1997]

7.7.6.3 Controlled cooking - preventing over-boilingAchieved environmental benefits

Reduced phosphorus emissions.

Reference literature

[155, Nordic Council of Ministers, 1997]

7.7.6.4 Indirect cooling of vapour from production of evaporated stickwater, using seawaterDescription

Instead of following the common practice of spraying seawater into the vapour air mix to cool it, the vapour can be indirectly cooled using seawater. The condensed vapour is then treated in a WWTP and heat is recovered from the seawater.

Achieved environmental benefits

Avoiding contamination of seawater and the subsequent treatment it requires, or pollution it causes.

Cross-media effects

High energy consumption to pump seawater.

7.7.6.5 Vacuum drying at 65 °CAchieved environmental benefits

Re-use of heat from the meal-drying process.

Economics

The fish-meal produced from vacuum drying is of a higher quality than that from traditional drying and it can be sold for 10 % more.

Reference literature

[213, Nielsen E.W., 2001]

7.7.6.6 Drying by heatingDescription

The capacity of traditional drying equipment is greater than that for the equivalent vacuum drying equipment.

7.7.6.7 Stripping plant to remove volatile nitrogen from waterReference literature

[213, Nielsen E.W., 2001]

7.7.6.8 Use of a decanter instead of a press and decanterDescription

A large decanter can be used instead of a press and decanter, to produce the press cake and grax.

7.7.6.9 Control of suction on the drierAchieved environmental benefits

Odour reduction.

Reference literature

[155, Nordic Council of Ministers, 1997]

7.7.6.10 High-pressure removal of burned products instead of using NaOHAchieved environmental benefits

Reduced nitrogen levels in waste water.

Cross-media effects

Increased use of water.

Reference literature

[155, Nordic Council of Ministers, 1997]

7.7.6.11 Waste water treatment of certain fractions of the impure condensate

Achieved environmental benefits

Reduced seawater contamination.

Reference literature

[155, Nordic Council of Ministers, 1997]

7.7.7 Blood processing

7.7.7.1 Back venting of tankers during unloading

Description

An activated charcoal filter can be provided.

Achieved environmental benefits

Odour reduction

7.7.8 Gelatine manufacture

7.7.8.1 Neutralisation of acid waste waters by alkaline waste waters

Description

The washings from liming pits contain lime and can be used to neutralise the acid used in other parts of the process, e.g. during demineralisation.

Achieved environmental benefits

The washings can be used instead of caustic, which would have to be acquired for the purpose.

Economics

An example plant reported a 2 year payback time.

Example plants

A gelatine manufacturing plant in the UK.

7.7.8.2 Re-use of heat from evaporators

Description

Hot water from evaporators in gelatine production can be used to heat driers and the condensate can be used to manufacture steam.

Achieved environmental benefits

Reduced energy use.

Driving force for implementation

Reduced energy consumption and consequent reduced financial cost.

Example plants

A gelatine manufacturing plant.

7.7.9 Incineration

7.7.9.1 Initial cleaning of vehicles and equipment, by dry vacuuming

Applicability

Applicable to animal meal delivery.

Reference literature

[82, EA, 1998]

7.7.9.2 Monitoring amino compounds in salt fractions recovered in wash-water

Reference literature

[164, Nottrodt A., 2001]

7.7.10 Burning of tallow

7.7.10.1 Back venting of tankers during unloading

Achieved environmental benefits

Odour reduction.

7.7.11 Composting

7.7.11.1 In-vessel composting of animal by-products

Description

Achieved environmental benefits

In-vessel systems potentially provide optimal conditions for odour control, as they are enclosed systems and also offer a higher degree of process control than open systems.

Reference literature

[210, Environment Agency, 2001]

7.7.11.2 Use of a high carbon source to prevent pungent ammonia odours

Description

Adding a high carbon source, such as co-composting with a paper sludge can combat any pungent NH_3 odours.

Reference literature

[210, Environment Agency, 2001]

7.7.11.3 Avoiding dusty activities on windy days

Description

Formation or turning of windrows or piles, screening and shredding will cause dust problem if the natural is dry and there are windy weather/climate conditions.

Reference literature

[210, Environment Agency, 2001]

7.7.12 Integrated same-site activities

7.7.12.1 Combining gasification of MBM with thermal oxidation on a rendering site

Achieved environmental benefits

Reduction of odour from the rendering process, including removal of strong odours produced from non-condensable gases and process room odours. Re-use of heat to produce steam for use in the rendering process and the consequent reduction in fossil fuel use. Reduced fossil fuel usage to transport the MBM to another site for destruction. The high gasification temperatures produces a clean dust free fuel, for which passing through a cyclone is sufficient for purification prior to thermal oxidation.

Operational data

The suppliers of gasification equipment report the following efficiency, for a 6 MW thermal gasification plant.

Fuel data

MBM lower heating value 3000 kcal/kg = 12.552 MJ/kg

MBM flowrate 1720 kg/h = 0.478 kg/s

$\text{Power}_{\text{thermal}} = 12.552 \times 0.478 \sim 6000 \text{ kW}$

Syngas data

Syngas lower heating value 1100 kcal/kg = 4.602 MJ/kg

Syngas flowrate 3086 kg/h = 0.857 kg/s

$\text{Power}_{\text{thermal}} = 4.602 \times 0.857 \sim 3944 \text{ kW}$ (3947 kW quoted)

Assuming a thermal efficiency of 92 % an the resultant $\text{Power}_{\text{effective}} = 92 \% \text{ of } 3944 = 3628 \text{ kW}$ (3632 kW quoted)

Boiler data

Assuming a thermal efficiency of 90 % they calculate a $\text{Power}_{\text{thermal global}} = 3268/3944 = 83 \%$.

Reference literature

[196, Therma CCT, 2000]

The EC is launching and supporting, through its RTD programmes, a series of projects dealing with clean technologies, emerging effluent treatment and recycling technologies and management strategies. Potentially these projects could provide a useful contribution to future BREF reviews. Readers are therefore invited to inform the EIPPCB of any research results which are relevant to the scope of this document (see also the preface of this document).

8 REFERENCES

- 3 EPA (1996). "Integrated Pollution Control Licensing Batneec Guidance Note For The Slaughter of Animals", EPA No.LC 17(9/96).
- 4 EPA (1996). "Integrated Pollution Control licensing Batneec Guidance Note For The Rendering of Animal By-products", EPA No.LC 13(10/96).
- 6 EA (1997). "Processes Subject to Integrated Pollution Control Animal Remains Incineration - Amplification note", S2 5.01 Amplification note No. 1.
- 12 WS Atkins-EA (2000). "Model Approach for Producing BAT Guidance for Specific Sub-sectors within the Food and Drink Industry, Red Meat Abattoirs".
- 13 UKRA (undated). "United Kingdom Renderers' Association Q & A The Rendering Industry".
- 17 UKRA (2000). "Understanding rendering What is the UKRA?", Fact sheet 3.
- 18 UKRA (2000). "Understanding rendering Financial aid to the animal by-product industry", Fact sheet 4.
- 19 UKRA (2000). "Understanding rendering The action taken by the renderers since the emergence of BSE, and the impact it had on the industry", Fact sheet 5.
- 20 UKRA (2000). "Understanding rendering The disposal of fallen stock", Fact sheet.
- 21 UKRA (2000). "Understanding rendering The economics of rendering in the UK - compared with our major competitors", Fact sheet 7.
- 22 UKRA (2000). "Understanding rendering Alternative uses of animal by-products which cannot be (for legal reasons) or are not (for commercial reasons) used in animal feedingstuffs", Fact sheet 8.
- 24 EURA (1997). "The animal by-product industry in Europe".
- 27 University of Guelph (undated). "Slaughtering".
- 29 US Environmental Protection Agency, S. C., Department of Health and Environmental Control, (1997). "Air Pollution Control Regulations, Regulation Number 62.1, Definitions, Permit Requirements and Emissions Inventory", Regulation Number 62.1.
- 47 DoE SO and WO (1997). "Secretary of State's Guidance - Fish meal and fish oil processes", PG6/19(97).
- 49 VDI (1996). "Emission Control Plants for the Utilization and Disposal of Animal Carcasses, either Wholly or Partially, and for the Processing of Animal Products (Rendering Plants)", VDI 2590.
- 52 DoE (1994). "Energy Management at a Red Meat Plant", Case Study 225.
- 53 IEA OECD (1996). "Evaporation cooling of pig carcasses", Result 252.
- 56 ETBPP (1997). "Biotechnology tackles abattoir waste", NC 17.
- 57 DoE (1993). "Red meat plants", Guide 32.

References

- 61 ETBPP (1998). "Reducing the cost of cleaning in the food and drink industry", Good Practice Guide GG 154.
- 63 ETBPP (2000). "Reducing water and effluent costs in red meat abattoirs", Good Practice Guide GG 234.
- 65 EA (1996). "Processes subject to Integrated Pollution Control - Waste Incineration", S2 5.01.
- 67 WS Atkins Environment/EA (2000). "BAT Guidance for Specific Sub-sectors within the Food and Drink Industry, Poultry Processors".
- 69 AINIA (2000). "Guías Tecnológicas, Directiva 96/61 relativa a la prevención y control integrados de la contaminación, Epígrafe 6.4.a Mataderos polivalentes".
- 70 AINIA (2000). "Guías Tecnológicas, Directiva 96/61 relativa a la prevención y control integrados de la contaminación, Epígrafe 6.4.a Mataderos avícolas".
- 82 EA (1998). "Processes Subject to Integrated Pollution Control, Combustion of Meat and Bone Meal (MBM)", S2 1.05 Amplification note No. 1.
- 85 EC (1999). "99/724/EC: Commission Decision of 28 October 1999 amending Annex II to Council Directive 92/118/EEC laying down animal health and public health requirements governing trade in and imports into the Community of products not subject to the said requirements laid down in specific Community rules referred to in Annex A (I) to Directive 89/662/EEC and, as regards pathogens, to Directive 90/425/EEC (notified under document number C(1999) 3493) (Text with EEA relevance)".
- 88 EC (2000). "Council Decision of 4 December 2000 concerning certain protection measures with regard to transmissible spongiform encephalopathies and the feeding of animal protein".
- 99 EC (1964). "Council Directive 64/433/EEC of 26 June 1964 on health problems affecting intra-Community trade in fresh meat".
- 111 EC (2001). "Report on Implementation of Latest BSE Control Measures in the Member States Working document",
http://europa.eu.int/comm/dgs/health_consumer/library/press/press104_en.html.
- 113 EC (2000). "2001/2/EC: Commission Decision of 27 December 2000 amending Decision 2000/418/EC regulating the use of material presenting risks as regards transmissible spongiform encephalopathies (Text with EEA relevance) (notified under document number C(2000) 4147)".
- 114 MLC (1999). "A glossary of carcase and meat quality terms", 0 1908 677577.
- 115 EC (1993). "Council Directive 93/119/EC of 22 December 1993 on the protection of animals at the time of slaughter or killing".
- 127 MLC Economics (1999). "The Abattoir and Meat Processing Industry in Great Britain, 1999 edition", 0 904650 75 8.
- 129 McIlwaine N. (2001). "Site info.", personal communication.
- 132 Thy-Christensen (2001). "Data - slaughterhouses and renderers", personal communication.

- 134 Nordic States (2001). "Best Available Techniques (BAT) in Nordic Slaughterhouses".
- 136 Derden A (2001). "info slachthuissector_1_No.s_s'houses sp._weights.xls", personal communication.
- 137 Leoni C. (2001). "Pig slaughterhouses in Italy", personal communication.
- 140 Minck F. (2001). "Fishmeal & oil production process 140601.doc", personal communication.
- 142 Derden A. (2001). "010622_rc-pigs_CE_14_5_011.xls, 010622_rc-cattle_CE_15_5_011.xls, 010622_rc-sheep_CE_16_5_011.xls", personal communication.
- 143 Skodlar M. (2001). "1_No.s_s'houses sp._weights11.xls", personal communication.
- 144 Det Norske Veritas (2001). "Environmental Assessment of Options for the Utilisation or Disposal of Animal By-products for UKRA".
- 145 Filstrup P. (1976). "Handbook for the meat by-products industry".
- 147 DHV (1999). "Moving bed trickling filter: Cost-effective treatment of water, air and air/water mixtures".
- 148 Finnish Environment Institute and Finnish Food and Drink Industries' Federation (2001). "The Finnish Background Report for the EC documentation of the best available techniques for slaughterhouses and installations for the disposal or recycling of animal carcasses and animal waste".
- 152 Danish Institute of Agricultural and Fisheries Economics (1999). "Centralised Biogas Plants - Integrated Energy Production, Waste Treatment and Nutrient Redistribution Facilities".
- 155 Nordic Council of Ministers (1997). "BAT Best Available Technology in the Fishing Industry".
- 159 EC (2001). "(Draft) Common position adopted by the Council with a view to the adoption of a Regulation of the European Parliament and of the Council laying down health rules concerning animal by-products not intended for human consumption".
- 161 Italy (2001). "Best Available Techniques Reference Document on the Slaughterhouses and Animal By-products Industry".
- 163 German TWG Members (2001). "Best available techniques reference document on the "Slaughterhouses and animal by-products industry"".
- 164 Nottrodt A. (2001). "Guideline for Technical Requirements and General Recommendations for the disposal of Meat and Bone Meal and Tallow".
- 166 Nykänen K. (2001). "Measuring results of burning animal fat in heavy oil boiler".
- 167 Greek Ministry for the Environment, P. P. a. P. W., General Direction for the Environment, Air Pollution and Noise Control Directorate, Industrial Pollution Control Division (2001). "Food industry IPPC study".
- 168 Sweeney L. (2001). "Personal communication", personal communication.

References

- 169 EC (1991). "Council Directive 91/497/EEC of 29 July 1991 amending and consolidating Directive 64/433/EEC on health problems affecting intra-Community trade in fresh meat to extend it to the production and marketing of fresh meat".
- 170 ENDS Daily (2001). "Dutch court ruling on phosphate pollution".
- 173 EC (2001). "Regulation (EC) No 999/2001 of the European Parliament and of the Council of 22 May 2001 laying down rules for the prevention, control and eradication of certain transmissible spongiform encephalopathies".
- 174 EC (1980). "Council Directive 80/778/EEC of 15 July 1980 relating to the quality of water intended for human consumption (Will be repealed by 98/83/EC of 3 November 1998 on 3 Nov 2003)".
- 176 The Composting Association (2001). "Large-scale composting - a practical manual for the UK".
- 177 EA SEPA and EHS (2001). "Integrated Pollution Prevention and Control (IPPC) Guidance for the Poultry Processing Sector (draft)", IPPC S6.11.
- 179 EA SEPA & EHS (2001). "Extracts relating to the Landspreading of Waste Food, Drink or Materials used in or resulting from the Preparation of Food or Drink taken from Environment Agency R&D Technical Report P193", Environment Agency R&D Technical Report P193.
- 180 EC (2000). "Directive 2000/60/EC of the European Parliament and of the Council of 23 October 2000 establishing a framework for Community action in the field of water policy".
- 182 Pontoppidan O. (2001). "Pig slaughter data".
- 183 Pontoppidan O. (2001). "Techniques to consider in the determination of BAT - slaughter".
- 184 Pontoppidan O. (2001). "Expected effects of the ongoing automation of pig slaughtering processes."
- 185 Pontoppidan O. (2001). "Cattle slaughter consumption and emission data".
- 186 Pontoppidan O. (2001). "Slaughter - water, energy and by-product info."
- 187 Pontoppidan O. (2001). "Copper and zinc from pig slaughtering".
- 188 Pontoppidan O. (2001). "Poultry slaughter consumption and emission data".
- 189 Pontoppidan O. (2001). "Example of the progress in a matter of noise at a Danish pig slaughterhouse".
- 190 EAPA (2001). "Unit operations consumption and emission data - Blood processing plants".
- 191 Woodgate S. (2001). "Feather processing: One factory processing 90 000 MT pa".
- 192 Woodgate S. (2001). "Rendering: Four factories processing total of 515 000 Mt pa".
- 193 Woodgate S. (2001). "IPPC Data MBM combustion: One factory processing 50 000 mt pa".

- 194 EURA (2000). "Rendering, thermal oxidation and gasification information".
- 195 EC (2000). "Directive 2000/76/EC of the European Parliament and of the Council of 4 December 2000 on the incineration of waste".
- 196 Therma CCT (2000). "Therma CCT".
- 199 PDM Group and Wykes Engineering (Rushden) Ltd (2000). "Recovery of Energy from Waste".
- 200 Widell S. (2001). "Information about odour control at rendering, incineration and biogas production", personal communication.
- 201 APC Europe (2000). "A TSE risk analysis for spray-dried plasma".
- 202 APC Europe (2001). "The safety, in regard to the TSE risk, of non-ruminant blood products intended for consumption by non-ruminant farm animals.....".
- 206 Tritt W. P. and Schuchardt F. (1992). "Materials flow and possibilities of treating liquid and solid wastes from slaughterhouses in Germany - A review", Bioresource technology, pp. 235 - 245.
- 207 Linköping Gas AB (1997). "Waste to fuel".
- 208 Croda Colloids Ltd (undated). "Bone degreasing process".
- 209 The Composting Association (undated). "A guide to in-vessel composting plus a directory of systems", 0 9532546 0 7.
- 210 Environment Agency (2001). "Technical Guidance on Composting Operations - Draft for external consultation".
- 212 Nielsen E.W. (2001). "Information about fish-meal and fish-oil", personal communication.
- 213 Nielsen E.W. (2001). "Fish-meal and fish-oil production - information", personal communication.
- 214 AVEC (2001). "Poultry slaughter information".
- 215 Durkan J. (2001). "Waste water treatment & data for cattle", personal communication.
- 216 Metcalf and Eddy (1991). "Wastewater engineering", 0 07 100824 - 1.
- 217 Brindle J. (2001). "Information about carcase washing in slaughterhouses", personal communication.
- 218 Dansk Biogas A/S (undated). "Smedester biogas plants".
- 219 Skodlar M. (2002). "Letter", personal communication.
- 220 APC Europe (2001). "Personal communication", personal communication.
- 221 Hansen P.I. (2001). "Rendering - energy data", personal communication.
- 222 Gordon W. (2001). "Centralised Biogas Plants, A report for the British Poultry Council".

References

- 223 EC (1992). "Council Directive 92/116/EEC of 17 December 1992 amending and updating Directive 71/118/EEC on health problems affecting trade in fresh poultrymeat".
- 224 German TWG members (2002). "Techniques to consider BAT".
- 227 ADAS (2001). "An assessment of the numbers and types of small carcass incinerators (<50kg/hour) currently in use in the UK".
- 236 ORGALIME (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 237 Italy (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 238 UECBV (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 239 Denmark (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 240 The Netherlands (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 241 UK (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 242 Belgium (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 243 Clitravi - DMRI (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 244 Germany (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 246 AVEC (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 248 Sorlini G. (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 249 GME (2002). "Description of the gelatine manufacturing process".
- 250 James R. (2002). "MBM incinerator information - Fawley UK".
- 253 Raj A. B. M. (2002). "Recent developments in humane slaughter of poultry (1998) updated to include recent commercial developments and changes to the Animal Welfare Regulations (Statutory Instrument No. 3830)", personal communication.
- 260 EAPA (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 262 United Nations Environment Programme (2002). "Promoting Cleaner Production in the Industrial Sector".
- 264 May G. E. (2001). "Personal communication", personal communication.

- 265 EC (2001). "Reference Document on Best Available Techniques in the Glass Manufacturing Industry".
- 266 Tauw (undated). "Description of techniques for reducing emissions to air - Biotrickling".
- 267 IFFO (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 268 Ockerman H. W. and Hansen C. L. (2000). "Animal by-product processing and utilisation", 1-56676-777-6.
- 269 Italian TWG Members (2002). "Information from site visits", personal communication.
- 271 Casanellas J. (2002). "Personal communication", personal communication.
- 272 Woodgate S. (2002). "Personal communication", personal communication.
- 273 EC (2001). "Reference Document on Best Available Techniques for the Tanning of Hides and Skins".
- 274 Pontoppidan O. (2002). "Personal communication", personal communication.
- 276 Anão M. (2002). "Personal communication", personal communication.
- 277 EC (1991). "Council Directive 91/271/EEC of 21 May 1991 concerning urban wastewater treatment", Official Journal L 135 , 30/05/1991 P. 0040 - 0052.
- 278 EC (2002). "Reference Document on The General Principles of Monitoring".
- 279 Leoni C. (1979). "Il problema delle acque nelle industrie alimentari - aggiornamento, utilizzazione e trattamenti depurativi".
- 280 Savini F. (2002). "Heat recovery from singeing", personal communication.
- 281 Savini F. (2002). "Personal communication", personal communication.
- 282 Palomino S. (2002). "Personal communication", personal communication.
- 283 Brindle J. (2002). "Optimising blood collection", personal communication.
- 284 Leoni C. (2002). "Personal communication", personal communication.
- 285 Brindle J. (2001). "Odour - slaughterhouses".
- 286 COTANCE (2002). "Treatment of hides and skins undertaken at slaughterhouses".
- 287 EC (2002). "Regulation (EC) No 1774/2002 of the European Parliament and of the Council of 3 October 2002 laying down health rules concerning animal by-products not intended for human consumption".
- 288 Durkan J. (2002). "Comments on first draft of the "Slaughterhouses and animal by-products BREF"".
- 289 EFRA (2002). "Description of rendering processes".

References

- 291 Rodgers K. (2002). "Re-use of crate washing water".
- 292 ETSU (2000). "Running refrigeration plant efficiently - a cost effective guide for owners", Good practice guide 279.
- 293 Smith T. (2002). "Information supplied following intermediate meeting 23rd, 24th April 2002 to discuss dedicated incineration of animal by-products".
- 294 Waste Reduction Europe Ltd (2002). "Alkaline hydrolysis at elevated temperature process".
- 295 HSE (1998). "The storage of flammable liquids in tanks".
- 296 EA (2002). "Horizontal Guidance for noise - Part 1 Regulation and permitting".
- 297 EA (2002). "Horizontal Guidance for noise - Part 2 Noise assessment and control".
- 298 Widell S. (2002). "Personal communication", personal communication.
- 299 ETSU (1999). "A new refrigeration system in a small coldstore".
- 300 ETSU (1998). "Aspects of energy management - energy management guide".
- 301 German TWG (2002). "Biomembrat[®] process (biology utilising overpressure in conjunction with ultra-filtration)".
- 302 Jimenéz Rodriguez J J. (2002). "Use of SBR in slaughterhouse waste water treatment".
- 303 Minck F. (2002). "Personal communication", personal communication.
- 304 EC (2002). "Reference Document on Best Available Techniques for Intensive Rearing of Poultry and Pigs".
- 305 Porteous A. (2000). "Dictionary of Environmental Science and Technology", 0-471-63470-0.
- 306 Hydrotech Water and Environmental Engineering Ltd (2001). "Englezakis Ostrich Farms Study of the Wastewater Treatment Plant".
- 307 UK (2002). "Supplementary information after first draft".
- 308 Hupkes H. (2002). "Supplementary information after first draft".
- 309 Sweeney L. (2002). "Personal communication", personal communication.
- 310 Oberthur R. (2002). "Personal communication", personal communication.
- 311 CEN (2001). "prEN 13725:2001 - Air quality - Determination of odour concentration by dynamic olfactometry", CEN standard.
- 312 Latvia TWG (2002). "Slaughterhouse ad weight data".
- 314 Viitasaari S. (2002). "Personal communication", personal communication.
- 315 Belgium (2002). "Waste water data from slaughterhouses".
- 316 May G. (2002). "Personal communication", personal communication.

- 317 German TWG (2002). "Personal communication", personal communication.
- 318 EPEA Internationale Umweltforschung GmbH (2000). "Recycling of Nutrients in Modern Livestock Production".
- 319 NL TWG (2002). "Personal communication", personal communication.
- 320 Biosphere Refineries Corporation (2002). "Bio-refining technology that converts organic wastes and by-products into sterile fertilizers and soil amendments".
- 321 RenCare nv (undated). "Information Booklet on the Processing of Animal Waste using a RenCare - AW2 installation".
- 322 Finnish TWG (2002). "Personal communication", personal communication.
- 323 Czech Republic TWG (2002). "Personal communication", personal communication.
- 324 Brough D. (2002). "World meat demand to rise, animal disease fears - FAO".
- 325 Smith T. (2002). "Typical air emissions from a BFB incinerator burning MBM - before and after flue gas treatment", personal communication.
- 326 Italian TWG Members (2002). "Biotechnological treatment of animal by-products in order to increase energetic valorisation".
- 327 EC (2002). "Integrated Pollution Prevention and Control Draft Reference Document on Economics and Cross-Media Effects".
- 328 EC (2003). "Reference Document on Best Available Techniques in the Food, Drink and Milk Industry".
- 329 EC (2003). "Reference Document on Best Available Techniques in Waste Incineration".
- 330 AWARENET (2002). "Tools for the prevention and minimisation of agro-food wastes generation in European industry", Workpackage 3 Deliverable 16.
- 331 Italy (2003). "Comments on second draft of the "Slaughterhouses and animal by-products BREF"".
- 332 COTANCE (2003). "Comments on second draft of the "Slaughterhouses and animal by-products BREF"".
- 333 Netherlands TWG (2003). "Comments on second draft of the "Slaughterhouses and animal by-products BREF"".
- 334 Brunner C. R. (1996). "Incineration systems handbook".
- 336 BPMF (2003). "Basic requirements for bird handling and unloading".
- 341 EC (2002). "Reference Document on Best Available Techniques in Common Waste Water and Waste Gas Treatment / Management Systems in the Chemical Sector".
- 342 Pontoppidan O. (2003). "Data about chilling pigs".
- 344 Brechtelsbauer P. (undated). "Separation of grease, floating and settling material in the food industry".
- 345 GME (2003). "Waste water treatment discharge limits - gelatine".

References

- 346 Belgian TWG member (2003). "Comments on second draft of the "Slaughterhouses and animal by-products BREF"".
- 347 German TWG members (2003). "Comments on second draft of the "Slaughterhouses and animal by-products BREF" and associated e-mails".
- 348 Austrian TWG member (2003). "Comments on second draft of the "Slaughterhouses and animal by-products BREF"".
- 349 GME TWG members (2003). "Comments on second draft of the "Slaughterhouses and animal by-products BREF"".
- 350 EFRA (2003). "Comments on second draft of the "Slaughterhouses and animal by-products BREF"".
- 351 UK TWG Members (2003). "Comments on second draft of the "Slaughterhouses and animal by-products BREF"".
- 352 EC (1999). "Council Directive 1999/31/EC of 26 April 1999 on the landfill of waste".
- 353 Clitavi - DMRI (2003). "Comments on second draft of the "Slaughterhouses and animal by-products BREF"".
- 354 German TWG (2003). "Applied processes and techniques and Current consumption and emission levels information".
- 355 AVEC (2003). "Personal communication".
- 356 EC (2003). "Commission Regulation (EC) No 808/2003 of 12 May 2003 amending Regulation (EC) No 1774/2002 of the European Parliament and of the Council laying down health rules concerning animal by-products not intended for human consumption".
- 357 EC (2001). "Council Directive 2001/89/EC of 23 October 2001 on Community measures for the control of classical swine fever".
- 358 EC (1985). "Council Directive 85/511/EEC of 18 November 1985 introducing Community measures for the control of foot- and-mouth disease".
- 359 EC (2002). "Council Directive 2002/60/EC of 27 June 2002 laying down specific provisions for the control of African swine fever and amending Directive 92/119/EEC as regards Teschen disease and African swine fever".
- 360 German TWG members (2003). "Binary ice cooling".
- 361 Pontoppidan O. (2003). "Binary ice cooling", personal communication.

9 GLOSSARY

1. GENERAL TERMS, ABBREVIATIONS, ACRONYMS AND SUBSTANCES

ABP Regulation 1774/2002/EC	Regulation (EC) No 1774/2002 of the European Parliament and of the Council of 3 October 2002 laying down health rules concerning animal by-products not intended for human consumption
Acid	Proton donor. A substance that, more or less readily, gives off hydrogen ions in a water solution
Activated sludge process	A sewage treatment process by which bacteria that feed on organic wastes are continuously circulated and put in contact with organic waste in the presence of oxygen to increase the rate of decomposition.
Aeration	The act of mixing a liquid with air (oxygen).
Alkali	Proton acceptor. A substance that, more or less readily, takes up hydrogen ions in a water solution
Ammoniacal nitrogen	Nitrogen present as ammonia and ammonium ion in liquid effluents
Anaerobic	A biological process which occurs in the absence of oxygen
Animal meal	See “processed animal proteins”
AOX	Adsorbable organic halogen compounds. The total concentration in milligrams per litre, expressed as chlorine, of all halogen compounds (except fluorine) present in a sample of water that are capable of being adsorbed on activated carbon
Biocoenosis	Association of different organisms forming a closely integrated community; relationship existing between such organisms
BFB	Bubbling fluidised bed
Biochemicals	Chemicals that are either naturally occurring or identical to naturally occurring substances. Examples include hormones, pheromones and enzymes. Biochemicals function as pesticides through non-toxic, non-lethal modes of action, such as disrupting the mating pattern of insects, regulating growth or acting as repellents.
Biodegradable	That can be broken down physically and/or chemically by microorganisms. For example, many chemicals, food scraps, cotton, wool and paper are biodegradable
BOD	Biochemical oxygen demand: the quantity of dissolved oxygen required by micro-organisms in order to decompose organic matter. The unit of measurement is mg O ₂ /l. In Europe, BOD is usually measured after 3 (BOD ₃), 5 (BOD ₅) or 7 (BOD ₇) days.
Bovine	Of or like an ox
Bristles	Hairs [114, MLC, 1999]
BSE	Bovine spongiform encephalopathy
Caprine	Of or like a goat
Casings	The outer layer of meat products such as sausages, i.e. the skin of a sausage, produced from intestines [114, MLC, 1999]
Category 1	See definition in the “Regulation of the European Parliament and of the Council laying down health rules concerning animal by-products not intended for human consumption” Article 4
Category 2	See definition in the “Regulation of the European Parliament and of the Council laying down health rules concerning animal by-products not intended for human consumption” Article 5
Category 3	See definition in the “Regulation of the European Parliament and of the Council laying down health rules concerning animal by-products not intended for human consumption” Article 6

CEN	European Committee for Standardisation
CIP	Cleaning-in-place
CHP	Co-generation of heat and power
Clean whole saleable carcase	(Awaiting definition - see "General information – slaughterhouses section" of BREF)
COD	Chemical oxygen demand: the amount of potassium dichromate, expressed as oxygen, required to chemically oxidise at ca. 150 °C substances contained in waste water.
Cons.	Consumption
CFD	Computerised fluid dynamics
CJD	Creutzfeld - Jacob disease
Cross-media effects	The calculation of the environmental impacts of water/air/soil emissions, energy use, consumption of raw materials, noise and water extraction (i.e. everything required by the IPPC Directive)
DAF	Dissolved air flotation
DEM	German mark
DEFRA	Department for Environment, Food and Rural Affairs (for England and Wales)
Denitrification	Biological process by which nitrate is converted to nitrogen and other gaseous end-products
Directive (the)	Council Directive 96/61/EC of 24 September 1996 concerning integrated pollution prevention and control (IPPC Directive)
DKK	Danish kroner
DL	Detection limit
Dressing	The process of removing various parts of the body of an animal following slaughter
DS	Dry solids (content). The mass of a material remaining after drying by the standard method of test
EA	Environment Agency of England and Wales
EAPA	European Animal Protein Association
EDTA	Ethylene diamine tetraacetic acid
Effluent	Physical fluid (air or water together with contaminants) forming an emission
EIPPCB	European IPPC Bureau
ELV	Emission limit value
Emerging techniques	(Name of a standard chapter in BREFs)
Emis.	Emission
Emission	The direct or indirect release of substances, vibrations, heat or noise from individual or diffuse sources in the installation into the air, water or land
Emission limit values	The mass, expressed in terms of certain specific parameters, concentration and/or level of an emission, which may not be exceeded during one or more periods of time
End-of-pipe technique	A technique that reduces final emissions or consumptions by some additional process but does not change the fundamental operation of the core process. Synonyms: "secondary technique", "abatement technique". Antonyms: "process-integrated technique", "primary technique" (a technique that in some way changes the way in which the core process operates thereby reducing raw emissions or consumptions)
EPA	Environmental Protection Agency
EURA	European Renderers Association (amalgamated with UNEGA in 2001 to form EFPPA)
EVC	Exhaust vapour condensate
Evisceration	The removal of the viscera from the carcase [114, MLC, 1999]
EUR	Euro (currency)

Eutrophication	The pollution of a body of water by sewage, fertilisers washed from the land, and industrial wastes (inorganic nitrates and phosphates). These compounds stimulate the growth of algae, reducing the oxygen content in the water, and so killing animals with a high oxygen requirement.
Existing installation	An installation in operation or, in accordance with legislation existing before the date on which this Directive is brought into effect, an installation authorized or in the view of the competent authority the subject of a full request for authorization, provided that that installation is put into operation no later than one year after the date on which this Directive is brought into effect
FAO	Food and Agricultural Organisation
FFA	Free fatty acid
FGR	Flue gas reduction
Fleshing	Eliminating sub-cutaneous tissue, fat and flesh adhering to the hide or skin, manually or by the mechanical action of a cylinder equipped with cutting blades
FMD	Foot and mouth disease
FOG	Fats, oils and greases
Gambrelling table	A table that is free standing or bolted to the de-hairing machine. It is a substantial rigid table with a self draining top designed to receive the carcass after it is discharged from the de-hairing machine, to enable the operatives to cut the gam (part of the leg of the pig) and insert the "gambrel", prior to the carcass being elevated onto the dressing line.
GB	Great Britain
GBP	Pound sterling
Grax	An intermediate solid phase, with a high water content, produced during rendering and fish-meal manufacture
Greaves	The solid product of fat melting
HCFC	Hydrochlorofluorocarbon
Hollow knife	Knife used to bleed carcasses, with a hollow blade through which blood runs through the handle and a tube to a collection vessel
HPLV	High pressure low volume
HRT	Hydraulic retention time (days) (reactor volume (m ³)/influent flowrate (m ³ /d))
IBC	Intermediate bulk container
ICP/MSA	Inductive coupled plasma/mass spectrometry
Intestine	Lower part of alimentary canal from pyloric end of stomach to anus
IPPC	Integrated Pollution Prevention and Control
Kjeldahl nitrogen	Nitrogen in an organic compound
Lairage	Area of a slaughterhouse where animals are held before slaughter
LAS	Linear alkylbenzene sulphonates
LECA	Light expanded clay aggregate
LPG	Liquefied petroleum gas
LT	Low temperature drier – vacuum drier
M & T	Monitoring and targeting
MAFF	Ministry of Agriculture Fisheries and Food (now DEFRA)
Maturation	The holding of carcasses or standard cuts at refrigerated temperatures (0 - 4 °C) to improve eating quality [114, MLC, 1999]
MBM	Meat and bone meal – an animal meal produced from meat and bones - see “processed animal proteins”
MBTF	Moving bed trickling filter

Mesophilic	Organisms for which the optimum temperature for growth is within the range of 20 – 45 °C
Min	Minute(s)
MLC	Meat and Livestock Commission
MLVSS	Mixed-liquor volatile suspended solids
Monitoring	Process intended to assess or to determine the actual value and the variations of an emission or another parameter, based on procedures of systematic, periodic or spot surveillance, inspection, sampling and measurement or another assessment methods intended to provide information about emitted quantities and/or trends for emitted pollutants
Mpa	Megapascal
MS(s)	Member state(s)
Mucosa	Mucose membrane
N	Normality of solution, i.e. gramme-equivalents of solute per cubic decimetre (see context – fix for final draft)
n/a	Not applicable
N D	Not detectable
Nitrification	Biological process by which ammonia is converted first to nitrite and then to nitrate
Nitrogen (ammoniacal)	Nitrogen present as ammonia and ammonium ion in liquid effluents
Nitrogen (Kjeldahl)	Ammoniacal nitrogen and nitrogen in an organic compound
NLG	Dutch gilder
NOK	Norwegian kroner
Nitrogen (total)	Organic nitrogen, ammonia, nitrite and nitrate
NPE	Nonyl phenol ethoxylate
NTAA	Nitrilo triacetic acid
Odour unit	A consistent term for odour unit has not been agreed, the data reported is as received
Offal	The edible or inedible soft tissues, i.e. excluding bone, of a carcass removed during the dressing of the carcass of an animal killed for food. Green offal is the digestive tract and associated organs and red offal is the more commonly consumed offal from the carcass such as the liver, kidney and heart [114, MLC, 1999]
Operator	Any natural or legal person who operates or controls the installation or, where this is provided for in national legislation, to whom decisive economic power over the technical functioning of the installation has been delegated
OTMS	Over Thirty Months Scheme
OU	Odour unit
Ovine	Of or like a sheep
PAC	Pre-accession countries
Paunch	Stomach contents
Pith	Slaughter or immobilise animal by severing the spinal cord, achieved by pushing a nylon rod through the hole left by the captive bolt.
PLC	Programmable logic control
Pollutant	Individual substance or group of substances which can harm or affect the environment
Prion	Hypothetical proteinaceous infectious particle consisting only of protein, thought to be the cause of diseases such as TSE and scrapie

Processed animal proteins	Meat and bone meal, meat meal, bone meal, blood meal, dried plasma and other blood products, hydrolysed proteins, hoof meal, horn meal, poultry offal meal, feather meal, dry greaves, fish-meal, dicalcium phosphate, gelatine and any other similar products including mixtures, feedingstuffs, feed additives and premixtures, containing these products (from 2000/766/EC Council Decision of 4 December 2000 concerning certain protection measures with regard to transmissible spongiform encephalopathies and the feeding of animal protein [88, EC, 2000])
PSE	Pale, soft and exudative meat
PVC	Polyvinyl chloride
relative density	Specific gravity
SBR	Sequencing batch reactor
Scalding	Either plunging pig or poultry carcasses in a tank of water held at about 60 °C for about 5 minutes or passing them through steam or heated water sprays, so as to soften the skin and bristles or the feathers, in preparation for de-hairing and toenail removal or de-feathering
SCR	Selective catalytic reduction
SCS	selective Cull Scheme
SEC	Specific electricity consumption
SEK	Swedish kroner
SHC	Specific heating fuel consumption
Singeing	The burning off of hairs from a pig carcass [114, MLC, 1999]
SNCR	Selective non-catalytic reduction
Soliped	Solid-hoofed animal
SRM	Specified risk material
SS	Suspended solids (content) (in water) (See also TSS)
Standard cuts	Carcasses, half carcasses, half carcasses cut into no more than three wholesale cuts and quarters
Stunning	Refers to methods used to render an animal insensible to pain, causing unconsciousness, at slaughter [114, MLC, 1999]
SWC	Specific water consumption - the volume of water used to process one tonne of meat
Tallow	Animal fat separated from the solid (protein/meal) and water fractions of animal tissue, by rendering (the term is usually applied to fat which is either inedible or not intended for human consumption)
Therm	A unit of energy, equivalent to 106 MJ
TKN	Total Kjeldahl nitrogen
TMA	Trimethylamine
TN	Total nitrogen
Total nitrogen	Mostly consists of ammonia, nitrate and organic forms of nitrogen
TSE	Transmissible spongiform encephalopathy
TSS	Total suspended solids (content) (in water) (See also SS)
TVN	Total volatile nitrogen
TWG	Technical working group, established for the duration of the work of preparing the BREF
UKRA	United Kingdom Renderers Association
UNEGA	European Animal Fat Processors Association (amalgamated with EURA in 2001 to form EFPPA)
US	United States
USDA	United States Department of Agriculture

Viscera	Offal from the thoracic, abdominal and pelvic cavities, including the trachea and oesophagus (large animals) [169, EC, 1991] or offal from the thoracic, abdominal and pelvic cavities, and also, where appropriate, the trachea, oesophagus and crop (poultry) [223, EC, 1992]
VHR	Volumetric heat release rate
VOC	Volatile organic compound
VTEC	Verocytotoxin-producing <i>Escherichia coli</i>
WWTP	Waste water treatment plant
WID Council Directive 2000/76/EC	Directive 2000/76/EC of the European Parliament and of the Council of 4 December 2000 on the incineration of waste
WHD	Waste heat dewatering

2. COMMON UNITS, MEASUREMENT AND SYMBOLS

bar	bar (1.013 bar = 1 atm)
Bé	(or °B) degree Baumé - a unit of relative density. For liquids lighter than water, the relative density d in °Bé is related to relative density "S" by the formula $d = (144.3/S) - 144.3$ and for heavier liquids the formula is $d = 144.3 - (144.3/S)$
°C	degree Celsius
cm	centimetre
d	day
g	gramme
GJ	gigajoule
h	hour
Hz	Hertz
J	Joule
kg	kilogramme (1 kg = 1000 g)
kPa	kilopascal
kWh	– kilowatt hour (1 kWh = 3600 kJ = 3.6 MJ)
l	litre(s)
m	metre(s)
m ²	square metre
m ³	cubic metre
mg	milligramme (1 mg = 10 ⁻³ gramme)
MJ	megajoule (1 MJ = 1000 kJ = 10 ⁶ J)
MPa	megapascal
N	normality of solution, i.e. gramme-equivalents of solute per cubic decimetre (see context – fix for final draft)
ng	nanogramme (1 ng = 10 ⁻⁹ gramme)
Nm ³	normal cubic metre
OU	odour unit
Pa	pascal
s	second
t	metric tonne
t/d	tonnes per day
t/yr	tonnes per year
Therm	a unit of energy, equivalent to 10 ⁶ MJ
yr	year
µm	micrometre (1 µ = 10 ⁻⁶ m)

3. LIST OF CHEMICAL ELEMENTS AND COMPOUNDS

Al	Aluminium
As	Arsenic
Ba	Barium
C	Carbon
Ca	Calcium
CaCl ₂	Calcium chloride
Ca(H ₂ PO ₄) ₂	Calcium phosphate
Ca ₃ (PO ₄) ₂	Tricalcium phosphate
CaCO ₃	Calcium carbonate
Cd	Cadmium
CH ₄	Methane
Cl	Chlorine
Co	Cobalt
CO	Carbon monoxide
CO ₂	Carbon dioxide
Cr	Chromium
Cu	Copper
F	Fluorine
FeCl ₂	Iron II chloride (ferrous chloride)
HCl	Hydrochloric acid or hydrogen chloride
H ₂ CO ₃	Carbonic acid
Hg	Mercury
H ₂ O	Water
H ₂ S	Hydrogen sulphide
H ₂ SO ₄	Sulphuric acid
K	Potassium
Mg	Magnesium
Mn	Manganese
N	Nitrogen (see context – fix for final draft)
Na	Sodium
NaOH	Sodium hydroxide
NH ₃	Ammonia
Ni	Nickel
NO _x	Oxides of nitrogen
NO ₂	Nitrogen dioxide
N ₂ O	Nitrous oxide
O	Oxygen
P	Phosphorus
Pb	Lead
Si	Silicon
S	Sulphur
SO ₂	Sulphur dioxide
Tl	Thallium
V	Vanadium
Zn	Zinc

10 ANNEXES

10.1 Monitoring protocol - ash and particulate testing methods and frequency (for analysis of carbon, nitrogen and amino acid content)

[6, EA, 1997, 82, EA, 1998]

This protocol from the Environment Agency of England and Wales has been reproduced for consideration as a monitoring technique - see Section 4.3.8.25.

PROCESSES SUBJECT TO INTEGRATED POLLUTION CONTROL - ANIMAL REMAINS INCINERATION, INCLUDING MEAT AND BONE MEAL (MBM)

MONITORING PROTOCOL - ASH AND PARTICULATE TESTING METHODS AND FREQUENCY (FOR ANALYSIS OF CARBON, NITROGEN AND AMINO ACID CONTENT)

Introduction

This protocol is issued to provide additional guidance to inspectors for monitoring levels of carbon, nitrogen and amino acids in residues from sites authorised to incinerate animal remains. It must be read in conjunction with (65, EA, 1997) and (6, EA, 1997) and guidance issued previously on how to take representative samples of ash, as described at the end of this protocol. In the case of burning MBM the relevant documents are *S2.1.05 on the combustion of fuel manufactured from or comprised of solid waste in appliances 3MW(th)* (64, EA, 1995) and (82, EA, 1998).

The Regulator's risk assessment study has shown that risks from burning animal remains in incinerators are negligible. The requirements contained in this protocol are to ensure that those incinerators are operated to acceptable standards. The data generated will allow the Regulator to review the monitoring frequency and authorisation limits on a site-by-site basis.

The protocol is applicable to all new plant and any other existing installations which will burn BSE suspects or cattle from the Over Thirty Month Scheme (OTMS).

Protocol

Sampling for ash should be carried out as detailed below during commissioning for all combustion processes, as soon as the plant has reached an initial steady state operation, and continued, subsequent to the commissioning period following what is described below. The Amplification Note gives guidance on what commissioning trials are to be undertaken.

(1) Initial Sampling:

Daily duplicate samples (minimum of 7 duplicate sets) of incinerator/bottom ash (ie. coarse ash) - These samples should be taken by the operator, with Regulator staff in attendance to observe (either the Site Inspector, Monitoring Liaison Officer, or another designated person), and analysed for total carbon and total nitrogen content, to assess burnout. The Regulator should repeat the analysis of one of the sets of duplicate samples. The preferred method of analysis of these samples is by CHN Elemental Analyser, although other, equivalent, methods may be agreed with the Site Inspector on a site-by-site basis (see note (a) below). The Site Inspector must be assured that the operator will appoint quality contractors who are suitably accredited for carrying out the required sampling and analysis.

The Regulator should take the two sets of duplicate samples with the highest carbon and nitrogen content for analysis of amino acid content (see note (b) below).

3 duplicate samples of baghouse (or other abatement equipment) ash (ie fine ash):

The operator will collect these samples, with Regulator staff in attendance to observe (either the Site Inspector, Monitoring Liaison Officer, or another designated person). Samples will be analysed by the operator (or their contractor) for total carbon and total nitrogen. The Regulator will take a portion of the sample for analysis of amino acid content.

3 particulate stack samples: These samples should be taken by the operator, with Regulator staff in attendance (for at least part of the time) to observe (either the Site Inspector, Monitoring Liaison Officer, or another designated person). Sampling will need to be carried out over an extended period of up to 10 hours to obtain sufficient material for analysis. Samples should be analysed for total nitrogen, total carbon and amino acid content (see note (c) below). If insufficient material (see notes (a) and (b)) has been collected after 10 hours of sampling it will have to be assumed that the results of the bag filter samples are representative of the particulate samples.

At least one of the sets of particulate samples and duplicate sets of fine ash samples should be collected under “normal” plant throughput (agreed on a site-by-site basis with the Site Inspector). One of the remaining sets of samples should be collected during maximum plant throughput (as agreed with the Site Inspector). Care must be taken to ensure that the ash samples taken are representative of the specified loading rate. The Site Inspector should ensure that there is not more than one change of loading rate in any one day of the commissioning period.

All samples should be collected at the burnout rate initially proposed by the operator. If these fail the action levels detailed below then burnout time will need to be amended and sampling, as above, repeated.

Sampling at this level should continue in subsequent weeks until results of the analysis are available and an assessment of the data can be made. Assessments should not be made on anything less than a complete week of data which have been collected as specified above.

(2) The proposed action levels for these samples are:

1 % total carbon

5 mg/100g sample total protein (aqueous extract) - see note (d) below.

Both of these levels should be achievable for all samples although the carbon level is included for guidance only. Sampling frequency will be determined on the total protein levels found in samples collected as part of this protocol.

If the results of the fine and coarse ash samples collected in (1) above are all less than the levels specified for total protein, sampling frequency may be reduced to 1 fine ash duplicate sample and 1 coarse ash duplicate sample per week, for the operator to analyse for total carbon and total nitrogen. Regulator staff will take a portion of the sample for analysis of amino acid content. If any of the samples exceed these levels, sampling frequency should revert to the frequency specified in (1) until the limits are achieved.

(3) If the criteria for total protein in (2) above are met for all samples over 4 consecutive weeks, sampling frequency may be reduced to 1 fine ash and 1 coarse ash sample per month, for analysis of total carbon, total nitrogen and amino acid content, as above.

(4) If the levels for total protein are met for all samples after a period of 6 consecutive months, sampling frequency may be reduced to 1 fine ash and 1 coarse ash per quarter, for the analysis of total carbon, total nitrogen and amino acid content, as above.

(5) If at any time, samples exceed the action levels for total protein in (2) above or if the Site Inspector considers it necessary, sampling frequency should revert back to the previous stage.

(6) Particulate stack samples: With the abated emission it may be difficult to collect sufficient particulate material for analysis. Where it is possible, a further duplicate sample should be collected 3 months after the initial one in (1) above. Thereafter sampling should be on an annual basis for total carbon, total nitrogen and amino acid content of particulate material.

Minimum sampling frequency will be quarterly for coarse and fine ash, and annually for particulate for the analysis of total nitrogen, total carbon and amino acid content.

The onus is on the operator to sample and analyse ash for carbon and nitrogen and this should be clearly stated in the authorisation. The Regulator will carry out a programme of independent check monitoring on approximately 10 % of samples by collecting a portion of a sample (previously taken by the operator) and analysing it for total carbon and nitrogen content by Elemental Analysis. The Site Inspector should ensure that independent samples are collected early on so that problems can be identified sooner rather than later. If at any time the operator's sampling and/or analytical contractor is changed, the Regulator should re-check the accuracy of the new results by further independent tests. Site Inspectors should ensure that operators notify them of any such change.

Regulator policy on charging will apply to all independent samples in that the operator will be recharged. Approximate costs for Regulator samples are currently:

GBP 21.60 per sample for total carbon and total nitrogen content;
GBP 100.00 per sample for amino acid content.

For all operator monitoring (covering any parameters), the Regulator requires at least 2 weeks notice of the proposed date(s) so that the work can be observed by Regulator staff as and when considered appropriate.

Notes

(a) 10g (dry weight) of sample is ideally required for analysis of carbon and nitrogen using elemental analysis.

(b) 1 - 2g (dry weight) of sample is required for amino acid analysis. Samples should be ground by the operator then securely packaged in plastic containers (or a plastic bag), clearly labelled with the site name, incinerator number (if applicable) and the date (of sample collection). Samples should be sent to a designated Monitoring Liaison Officer. They will then be forwarded on a weekly basis to the contract laboratory for analysis. Samples must be with the designated Monitoring Liaison Officer by noon on Thursday each week in order to be sent to the laboratory.

(c) Particulate samples - once collected, the sample should be divided into 2 portions, each clearly labelled with the site name, incinerator number (if applicable) and the date (of sample collection). One portion should be sent to the designated Monitoring Liaison Officer (as above); the other sent to a laboratory for total carbon and total nitrogen analysis.

(d) Carbon and nitrogen data are required to assess burnout. The limit currently proposed for inclusion in authorisations is 100mg/kg of protein in ash as calculated from amino acid analysis.

Stage	Type of Sample	Number of samples	Sampled by	Analysed by	Analysis requirements	Notes
1 (initial sampling)	Incinerator/bottom ash (coarse ash)	7 duplicate samples (i.e. daily)	Operator	Operator	Total carbon and nitrogen	Regulator to repeat the analysis of 1 of the sets of duplicate samples
				Regulator	Amino acid content	Regulator to analyse a portion of the 2 sets of duplicate samples with the highest carbon and nitrogen results
	Baghouse ash (fine ash)	3 duplicate samples	Operator	Operator	Total carbon and nitrogen	
				Regulator	Amino acid content	Regulator to analyse a portion of each of the duplicate samples for amino acid content
	Particulate stack samples	3 single samples	Operator	Operator	Total carbon and nitrogen	
				Regulator	Amino acid content	Regulator to analyse a portion of each sample for amino acid content
2 If at any time samples exceed the action levels for total protein (see (2) on p. 15) or the Site Inspector deems it necessary, sampling should revert back to the previous stage	Incinerator/bottom ash (coarse ash)	1 duplicate sample per week for 4 weeks	Operator	Operator	Total carbon and nitrogen	
				Regulator	Amino acid content	Regulator to analyse a portion of each sample for amino acid content
	Baghouse ash (fine ash)	1 duplicate sample per week for 4 weeks	Operator	Operator	Total carbon and nitrogen	
				Regulator	Amino acid content	Regulator to analyse a portion of each sample for amino acid content

Stage	Type of Sample	Number of samples	Sampled by	Analysed by	Analysis requirements	Notes
3 If at any time samples exceed the action levels for total protein (see (2) on p. 15) or the Site Inspector deems it necessary, sampling should revert back to the previous stage	Incinerator/bottom ash (coarse ash)	1 duplicate sample per month for 6 months	Operator	Operator	Total carbon and nitrogen	
				Regulator	Amino acid content	Regulator to analyse a portion of each sample for amino acid content
	Baghouse ash (fine ash)	1 duplicate sample per month for 6 months	Operator	Operator	Total carbon and nitrogen	
				Regulator	Amino acid content	Regulator to analyse a portion of each sample for amino acid content
4 If at any time samples exceed the action levels for total protein (see (2) on p. 15) or the Site Inspector deems it necessary, sampling should revert back to the previous stage	Incinerator/bottom ash (coarse ash)	1 duplicate sample per quarter	Operator	Operator	Total carbon and nitrogen	
				Regulator	Amino acid content	Regulator to analyse a portion of each sample for amino acid content
	Baghouse ash (fine ash)	1 duplicate sample per quarter	Operator	Operator	Total carbon and nitrogen	
				Regulator	Amino acid content	Regulator to analyse a portion of each sample for amino acid content
6?	Particulate stack samples	1 sample 3 months after the initial test (from stage 1 above); thereafter annual samples	Operator	Operator	Total carbon and nitrogen	
				Regulator	Amino acid content	Regulator to analyse a portion of each sample for amino acid content

REGULATOR - BOVINE TRIALS GROUP

NOTES ON SAMPLING OF ASH

Introduction

The purpose of these guidelines is to ensure that:

- (i) samples of ash are collected in a reasonably consistent manner during trials of incinerating bovine material or whilst a plant is undergoing commissioning,
- (ii) representative samples of ash are obtained as far as is reasonably possible by minimising sampling bias,
- (iii) sample preparation requirements minimise the sampling handling/preparation required by analytical laboratory staff.

They are not necessarily intended for use during full scale plant operation and may not be appropriate for certain types of continuous incinerator. The general principles put forward here may however still apply.

The guidelines given below follow British Standard methods whenever possible; where strict adherence to the standard method is not practical alternative guidelines are given. It is recommended that any deviation from these guidelines, by the operator of the process, should be agreed with Regulator inspectors before sampling is undertaken. It is intended that this method should be employed either by operators or by anyone else taking samples on behalf of the Regulator.

It is envisaged that operators of the incinerator (or power station) will collect the samples with Regulator inspectors observing the collection at least for the first few samples collected and thereafter on a regular (unannounced) basis.

Method

1) Whenever possible, successive samples of ash should represent a similar time period, for example, 24 hours of incineration with samples collected on a daily basis (this may vary depending on the details in the Authorisation). Preferably an empty skip (or other primary ash collector) should be used to collect ash for each successive sample. The smaller the amount of ash present, the easier it will be to collect a representative sample. Depending on the collection process, samples should not exceed a 24 hour burn period.

2) BS3316, Section 4 (4.2) specifies a method for collecting representative samples as follows:

2.1 - Record the mass of residue removed from the incinerator and empty it onto a clean and level floor. Spread the residue and remove all glass, metal and large objects - these materials can be discarded.

2.2 - Collect and mix the remaining residue into a cone-shaped heap using a shovel and flatten the cone until the height of the residue does not exceed 100mm.

2.3 - Place 20 scoopfuls, taken from different parts of the heap of not less than 0.2 kg each into an airtight container and remove to a laboratory (remainder of the heap can be discarded).

2.4 - In the laboratory, crush the sample to 99 % below 1 mm particle size.

2.5 - Divide the sample using a sample division device (see Section 5 of BS1017: Part 1: 1989) until a final sample of 1 ± 0.1 kg remains. Place this sample in an airtight container and send to the laboratory for analysis.

NOTES:

Wherever possible, large aggregates of ash should be broken down into sampleable proportions using a shovel.

20 scoopfuls should be taken at points equally spaced over the heap.

The airtight container should be clearly labelled with site name, date and time of sample collection, skip number (if appropriate), name of person taking the sample and a brief description of the sample.

This method requires a suitable weighing device, a scoop (of at least 0.2kg capacity), a crushing device, a sample division device (see Section 5 of BS1017: part 1: 1989).

In 2.4, “laboratory” means on site laboratory wherever possible; if facilities are not available any crushing will have to be done by the analytical laboratory (who will be undertaking the analysis).

3) Duplicate sampling should be carried out to try to ensure a more representative result is reported. The two samples should be collected simultaneously, with alternate increments being taken for each sample (ie. a total of 40 increments will be taken from the ash heap). Analysis should be carried out on each duplicate and an average result reported.

4) When there is insufficient space at the site to be able to spread the ash according to the standard method, the sample will have to be collected whilst still contained in the skip. Wherever possible, large aggregates of ash should be broken down using a shovel. Increments should be taken from equally spaced points throughout the skip (including close to the sides). The number of increments required should be increased to 35 (as it is more difficult to get a representative sample). Increments may be sampled using either a scoop or an auger (such as illustrated in BS1017: part 1: 1989, Figures 16 and 17). Half the increments should be collected from the bottom of the ash heap by sampling at least 0.3m below the surface (or to half the depth of the ash in the skip whichever is the smaller depth) and taking the increment from the bottom of the hole with a shovel or scoop. An auger can be used to dig down into the ash with the last portion obtained by the auger forming the increment. Once the increments have been collected the duplicate samples are treated as in 2.4 and 2.5 above.

5) If sample dividing devices are not available at the site, the collected sample should be sub-sampled using a smaller scoop - using the same principles (and collecting the same number of increments) as in Section 2 (above) to obtain the 1kg sample required for analysis.